Management Software

AT-S63

Menus User's Guide

For Stand-alone AT-9400 Switches

Version 2.2.0 for AT-9400 Layer 2+ Switches
Version 3.2.0 for AT-9400 Basic Layer 3 Switches

613-001025 Rev. A

Allied Telesis™

Downloaded from www.Manualslib.com manuals search engine

Copyright © 2008 Allied Telesis, Inc.

All rights reserved. No part of this publication may be reproduced without prior written permission from Allied Telesis, Inc.

Microsoft and Internet Explorer are registered trademarks of Microsoft Corporation. Netscape Navigator is a registered trademark of Netscape Communications Corporation. All other product names, company names, logos or other designations mentioned herein are trademarks or registered trademarks of their respective owners.

Allied Telesis, Inc. reserves the right to make changes in specifications and other information contained in this document without prior written notice. The information provided herein is subject to change without notice. In no event shall Allied Telesis, Inc. be liable for any incidental, special, indirect, or consequential damages whatsoever, including but not limited to lost profits, arising out of or related to this manual or the information contained herein, even if Allied Telesis, Inc. has been advised of, known, or should have known, the possibility of such damages.

Downloaded from www.Manualslib.com manuals search engine

Contents

Preface 19
How This Guide is Organized 20
Product Documentation 22
Where to Go First 23
Starting a Management Session 24
Document Conventions 25
Where to Find Web-based Guides 26
Contacting Allied Telesis 27
Online Support 27
Email and Telephone Support 27
Returning Products 27
Sales and Corporate Information 27
Management Software Updates 27

Section I: Basic Operations 29

Chapter 1: Basic Switch Parameters 31
Configuring the Switch's Name, Location, and Contact 32
Changing the Manager and Operator Passwords 35
Changing the Manager or Operator Password 35
Resetting the Manager Password 37
Setting the System Time 38
Setting the System Time Manually 39
Setting the System Time from an SNTP or NTP Server 40
Rebooting the Switch 43
Configuring the Console Startup Mode 45
Configuring the Console Timer 46
Configuring the Telnet Server 47
Setting the Baud Rate of the Serial Terminal Port 48
Pinging a Remote System 49
Returning the AT-S63 Management Software to the Factory Default Values 50
Displaying Hardware and Software Information 52
Displaying System Hardware Information 55
Displaying Uplink Port Information 57

Chapter 2: Port Parameters 61
Displaying Port Status 62
Configuring Port Parameters 65
Configuring Head of Line Blocking 69
Configuring Flow Control and Back Pressure 71
Configuring Port Filtering 73
Setting Up Rate Limiting 75
Resetting a Port 77
Forcing Port Renegotiation 78
Resetting the Port Configuration to the Default Settings 79

Downloaded from www.Manualslib.com manuals search engine

Displaying Port Statistics 80
Clearing Port Statistics 83

Chapter 3: Enhanced Stacking 85
Setting a Switch's Enhanced Stacking Status 86
Selecting a Switch in an Enhanced Stack 88
Returning to the Master Switch 91
Displaying the Enhanced Stacking Status 92

Chapter 4: SNMPv1 and SNMPv2c 93
Enabling or Disabling SNMP Management 94
Setting the Authentication Failure Trap 95
Creating an SNMP Community String 96
Modifying a Community String 99
Deleting a Community String 103
Displaying the SNMP Community Strings 104

Chapter 5: MAC Address Table 105
Displaying the MAC Address Tables 106
Adding Static Unicast and Multicast MAC Addresses 110
Deleting Unicast and Multicast MAC Addresses 112
Deleting All Dynamic MAC Addresses 113
Changing the Aging Time 114

Chapter 6: Static Port Trunks 115
Creating a Static Port Trunk 116
Modifying a Static Port Trunk 120
Deleting a Static Port Trunk 123

Chapter 7: LACP Port Trunks 125
Enabling or Disabling LACP 126
Setting the LACP System Priority 128
Creating an Aggregator 129
Modifying an Aggregator 132
Deleting an Aggregator 134
Displaying LACP Port and Aggregator Status 135

Chapter 8: Port Mirroring 137
Creating a Port Mirror 138
Disabling a Port Mirror 140
Modifying a Port Mirror 141
Displaying the Port Mirror 142

Section II: Advanced Operations 143

Chapter 9: File System 145
Working with Boot Configuration Files 146
Creating a Boot Configuration File 146
Setting the Active Boot Configuration File 149
Viewing a Boot Configuration File 151
Editing a Boot Configuration File 152
Copying a System File 154
Examples 155
Renaming a System File 156
Examples 157
Deleting a System File 158
Displaying System Files 159

Downloaded from www.Manualslib.com manuals search engine

Listing All Files 159
Listing Files on the Compact Flash Card 161
Working with Flash Memory 162
Displaying Information about the Flash Memory 162
Formatting the Flash Memory 163
Working with the Compact Flash Card 164
Displaying Compact Flash Card Information 164
Changing the Current Flash Card Directory 166

Chapter 10: File Downloads and Uploads 167
Downloading the AT-S63 Image File onto a Switch 168
Guidelines 168
Downloading the AT-S63 Image from a Local Management Session 170
Downloading the AT-S63 Image from a Remote Management Session 174
Uploading the AT-S63 Image File Switch to Switch 176
Guidelines 176
Uploading an AT-S63 Configuration File Switch to Switch 179
Guidelines 179
Downloading a System File 182
Guidelines 182
Downloading a System File from a Local Management Session 184
Downloading a System File from a Remote Management Session 187
Uploading a System File 190
Guidelines 190
Uploading a System File from a Local Management Session 191
Uploading a System File from a Remote Management Session 194

Chapter 11: Event Logs and the Syslog Client 197
Working with the Event Logs 198
Enabling or Disabling the Event Logs 198
Displaying an Event Log 199
Modifying the Event Log Full Action 205
Clearing an Event Log 206
Saving an Event Log to a File 206
Configuring Log Outputs 209
Creating a Log Output Definition 210
Modifying a Log Output 215
Deleting a Log Output 216
Displaying the Log Output Definition Details 217

Chapter 12: Classifiers 219
Creating a Classifier 220
Modifying a Classifier 224
Deleting a Classifier 226
Deleting All Classifiers 227
Displaying Classifiers 228

Chapter 13: Access Control Lists 231
Creating an ACL 232
Modifying an ACL 235
Deleting an ACL 237
Deleting All ACLs 239
Displaying ACLs 240

Downloaded from www.Manualslib.com manuals search engine

Chapter 14: Class of Service 243
Configuring CoS 244
Mapping CoS Priorities to Egress Queues 247
Configuring Egress Scheduling 248
Displaying Port CoS Priorities 250

Chapter 15: Quality of Service 251
Managing Flow Groups 252
Creating a Flow Group 252
Modifying a Flow Group 255
Deleting a Flow Group 256
Displaying Flow Groups 257
Managing Traffic Classes 261
Creating a Traffic Class 261
Modifying a Traffic Class 265
Deleting a Traffic Class 267
Displaying Traffic Classes 268
Managing Policies 271
Creating a Policy 271
Modifying a Policy 274
Deleting a Policy 275
Displaying Policies 276

Chapter 16: Denial of Service Defenses 279
Configuring Denial of Service Defense 280

Chapter 17: Power Over Ethernet 283
Setting the PoE Threshold 284
Configuring PoE Port Settings 286
Displaying PoE Status and Settings 288

Section III: IGMP Snooping, MLD Snooping, and RRP Snooping 293

Chapter 18: IGMP Snooping 295
Configuring IGMP Snooping 296
Enabling or Disabling IGMP Snooping 300
Displaying a List of Host Nodes 301
Displaying a List of Multicast Routers 303

Chapter 19: MLD Snooping 305
Configuring MLD Snooping 306
Enabling or Disabling MLD Snooping 309
Displaying a List of Host Nodes 310
Displaying a List of Multicast Routers 312

Chapter 20: RRP Snooping 315
Enabling or Disabling RRP Snooping 316

Section IV: SNMPv3 317

Chapter 21: SNMPv3 319
Configuring SNMPv3 Entities 320
Configuring the SNMPv3 User Table 321
Creating an SNMPv3 User Table Entry 321
Deleting an SNMPv3 User Table Entry 325
Modifying an SNMPv3 User Table Entry 326

Downloaded from www.Manualslib.com manuals search engine

Configuring the SNMPv3 View Table 331
Creating an SNMPv3 View Table Entry 331
Deleting an SNMPv3 View Table Entry 334
Modifying an SNMPv3 View Table Entry 335
Configuring the SNMPv3 Access Table 340
Creating an SNMPv3 Access Table Entry 340
Deleting an SNMPv3 Access Table Entry 344
Modifying an SNMPv3 Access Table Entry 346
Configuring the SNMPv3 SecurityToGroup Table 356
Creating an SNMPv3 SecurityToGroup Table Entry 356
Deleting an SNMPv3 SecurityToGroup Table Entry 359
Modifying an SNMPv3 SecurityToGroup Table Entry 360
Configuring the SNMPv3 Notify Table 364
Creating an SNMPv3 Notify Table Entry 364
Deleting an SNMPv3 Notify Table Entry 366
Modifying an SNMPv3 Notify Table Entry 367
Configuring the SNMPv3 Target Address Table 372
Creating an SNMPv3 Target Address Table Entry 372
Deleting an SNMPv3 Target Address Table Entry 375
Modifying an SNMPv3 Target Address Table Entry 376
Configuring the SNMPv3 Target Parameters Table 385
Creating an SNMPv3 Target Parameters Table Entry 386
Deleting an SNMPv3 Target Parameters Table Entry 389
Modifying an SNMPv3 Target Parameters Table Entry 390
Configuring the SNMPv3 Community Table 398
Creating an SNMPv3 Community Table Entry 399
Deleting an SNMPv3 Community Table Entry 402
Modifying an SNMPv3 Community Table Entry 403
Displaying SNMPv3 Table Menus 408
Displaying the Display SNMPv3 User Table Menu 408
Displaying the Display SNMPv3 View Table Menu 410
Displaying the Display SNMPv3 Access Table Menu 411
Displaying the Display SNMPv3 SecurityToGroup Table Menu 411
Displaying the Display SNMPv3 Notify Table Menu 412
Displaying the Display SNMPv3 Target Address Table Menu 413
Displaying the Display SNMPv3 Target Parameters Table Menu 413
Displaying the Display SNMPv3 Community Table Menu 414

Section V: Spanning Tree Protocols 417

Chapter 22: Spanning Tree and Rapid Spanning Tree Protocols 419
Enabling or Disabling a Spanning Tree Protocol 420
Configuring STP 422
Configuring STP Bridge Settings 422
Configuring STP Port Settings 425
Displaying STP Port Settings 428
Resetting STP to the Default Settings 429
Configuring RSTP 430
Configuring RSTP Bridge Settings 430
Configuring RSTP Port Settings 433
Displaying the RSTP Port Configuration 435
Displaying the RSTP Port State 437
Resetting RSTP to the Default Settings 438

Downloaded from www.Manualslib.com manuals search engine

Chapter 23: Multiple Spanning Tree Protocol 439
Selecting MSTP as the Active Spanning Tree Protocol 440
Configuring MSTP Bridge Settings 441
Configuring the CIST Priority 445
Displaying the CIST Priority 447
Creating, Deleting, and Modifying MSTI IDs 449
Creating an MSTI ID 449
Deleting an MSTI ID 450
Modifying an MSTI ID 450
Adding, Removing, and Modifying VLAN Associations to MSTI IDs 452
Adding or Removing a VLAN from an MSTI ID 452
Associating a VLAN to an MSTI ID 453
Removing a VLAN from an MSTI ID 454
Associating VLANs to an MSTI ID and Deleting All Associated VLANs 455
Clearing VLAN to MSTI Associations 456
Configuring MSTP Port Settings 457
Configuring Generic MSTP Port Settings 457
Configuring MSTI-specific Port Parameters 460
Displaying the MSTP Port Configuration 463
Displaying the MSTP Port State 465
Resetting MSTP to the Defaults 468

Section VI: Virtual LANs 469

Chapter 24: Port-based and Tagged VLANs 471
Creating a Port-based or Tagged VLAN 472
Example of Creating a Port-based VLAN 477
Example of Creating a Tagged VLAN 479
Modifying a Port-based or Tagged VLAN 481
Displaying VLANs 485
Deleting a Port-based or Tagged VLAN 487
Deleting All VLANs 490
Displaying PVIDs 492
Enabling or Disabling Ingress Filtering 493

Chapter 25: GARP VLAN Registration Protocol 495
Configuring GVRP 496
Enabling or Disabling GVRP on a Port 498
Converting a Dynamic GVRP VLAN 500
Displaying the GVRP Port Configuration 501
Displaying GVRP Counters 502
Displaying the GVRP Database 507
Displaying the GIP Connected Ports Ring 509
Displaying the GVRP State Machine 511

Chapter 26: Multiple VLAN Modes 515
Selecting a VLAN Mode 516
Displaying VLAN Information 518

Chapter 27: Protected Ports VLANs 521
Creating a Protected Ports VLAN 522
Modifying a Protected Ports VLAN 525
Displaying a Protected Ports VLAN 528
Deleting a Protected Ports VLAN 530

Downloaded from www.Manualslib.com manuals search engine

Chapter 28: MAC Address-based VLANs 533
Creating a MAC Address-based VLAN 534
Adding and Deleting MAC Addresses 536
Adding and Deleting Egress Ports 538
Deleting a MAC Address-based VLAN 540
Displaying MAC Address-based VLANs 542

Section VII: Internet Protocol Routing 545

Chapter 29: Internet Protocol Version 4 Routing Interfaces 547
Creating a New Routing Interface 548
Modifying a Routing Interface 551
Deleting a Routing Interface 554
Displaying the IP Address of the Local Interface 555
Setting the Default Route or Default Gateway 556
Setting the Local Interface 557
Setting the ARP Cache Timeout 558

Section VIII: Port Security 559

Chapter 30: MAC Address-based Port Security 561
Configuring MAC Address Port Security 562
Displaying Port Security Levels 566

Chapter 31: 802.1x Port-based Network Access Control 569
Setting Port Roles 570
Enabling or Disabling 802.1x Port-based Network Access Control 572
Configuring Authenticator Port Parameters 573
Configuring Supplicant Port Parameters 579
Displaying the Port Access Parameters 582
Configuring RADIUS Accounting 584

Section IX: Management Security 587

Chapter 32: Web Server 589
Configuring the Web Server 590
General Steps for Configuring the Web Server for Encryption 593
General Steps for a Self-signed Certificate 593
General Steps for a Public or Private CA Certificate 593

Chapter 33: Encryption Keys 595
Creating an Encryption Key 596
Deleting an Encryption Key 600
Modifying an Encryption Key 601
Exporting an Encryption Key 602
Importing an Encryption Key 605
Displaying the Encryption Keys 608

Chapter 34: PKI Certificates and SSL 611
Creating a Self-signed Certificate 612
Adding a Certificate to the Database 616
Modifying a Certificate 619
Deleting a Certificate 622
Viewing a Certificate 624
Generating an Enrollment Request 627

Downloaded from www.Manualslib.com manuals search engine

Installing CA Certificates onto a Switch 630
Viewing and Configuring the Maximum Number of Certificates 631
Configuring SSL 632

Chapter 35: Secure Shell (SSH) 633
Configuring SSH 634
Displaying SSH Information 637

Chapter 36: TACACS+ and RADIUS Protocols 639
Enabling or Disabling Server-based Management Authentication 640
Configuring the TACACS+ Client 642
Displaying the TACACS+ Settings 644
Configuring the RADIUS Client 645
Displaying RADIUS Status and Settings 648

Chapter 37: Management Access Control List 651
Enabling or Disabling the Management ACL 652
Creating an ACE 654
Modifying an ACE 656
Deleting an ACE 658
Displaying the ACEs 659

Index 661

Downloaded from www.Manualslib.com manuals search engine

Figures

Figure 1: System Administration Menu 32
Figure 2: System Configuration Menu 33
Figure 3: Authentication Configuration Menu 35
Figure 4: Passwords Configuration Menu 36
Figure 5: Configure System Time Menu 39
Figure 6: System Utilities Menu 43
Figure 7: Console (Serial/Telnet) Configuration Menu 45
Figure 8: System Information Menu 52
Figure 9: System Hardware Information Menu 55
Figure 10: Uplink Information Menu 57
Figure 11: GBIC/SFP Information Menu (Page 1) 58
Figure 12: GBIC/SFP Information Menu (Page 2) 59
Figure 13: Port Configuration Menu 62
Figure 14: Port Status Menu 62
Figure 15: Port Configuration (Port) Menu 65
Figure 16: Head of Line Blocking 69
Figure 17: Flow Control Menu 72
Figure 18: Filtering Menu 73
Figure 19: Rate Limiting Menu 75
Figure 20: Port Statistics Menu 80
Figure 21: Display Port Statistics Menu 81
Figure 22: Enhanced Stacking Menu 86
Figure 23: Stacking Services Menu 88
Figure 24: Stacking Services Menu With List of Switches 89
Figure 25: Enhanced Stacking Menu 92
Figure 26: SNMP Configuration Menu 94
Figure 27: Configure SNMPv1 & SNMPv2c Community Menu 96
Figure 28: Modify SNMP Community Menu 99
Figure 29: Display SNMP Community Menu 104
Figure 30: MAC Address Tables Menu 106
Figure 31: Display Unicast MAC Addresses Menu 106
Figure 32: Display All Menu - Unicast MAC Addresses 107
Figure 33: Display All Menu - Multicast MAC Addresses 108
Figure 34: MAC Addresses Configuration Menu 110
Figure 35: Port Trunking and LACP Menu 116
Figure 36: Static Port Trunking Menu 117
Figure 37: Create Trunk Menu 118
Figure 38: Modify Trunk Menu 121
Figure 39: LACP (IEEE 8023ad) Configuration Menu 126
Figure 40: Create LACP (IEEE 8023ad) Aggregator Menu 130
Figure 41: Modify LACP (IEEE 8023ad) Aggregator Menu 132
Figure 42: LACP (IEEE 802.3ad Port Status Menu 135
Figure 43: LACP (IEEE 802.3ad) Aggregator Status Menu 136
Figure 44: Port Mirroring Menu #1 138
Figure 45: Port Mirroring Menu #2 138
Figure 46: Port Mirroring Menu 142
Figure 47: File Operations Menu 147
Figure 48: View File Menu with Sample Boot Configuration File 152
Figure 49: List Files Menu for Flash Memory and a Compact Flash Card 160
Figure 50: List Files Menu for a Compact Flash Card 161

Downloaded from www.Manualslib.com manuals search engine

Figure 51: Display Flash Information Menu 162
Figure 52: Display Compact Flash Information Menu 164
Figure 53: Set/Change Compact Flash Directory Menu 166
Figure 54: Downloads and Uploads Menu 170
Figure 55: HyperTerminal Window 172
Figure 56: Send File Window 172
Figure 57: XModem File Send Window 173
Figure 58: HyperTerminal Window 186
Figure 59: Send File Window 186
Figure 60: XModem File Send Window 187
Figure 61: HyperTerminal Window 193
Figure 62: Receive File Window 194
Figure 63: Event Log Menu 198
Figure 64: Event Log Example in Normal Mode 203
Figure 65: Event Log Example in Full Mode 204
Figure 66: Sample Log File View 207
Figure 67: Configure Log Outputs Menu 210
Figure 68: Syslog Output Configuration Menu 211
Figure 69: Configure Log Outputs Menu with a Syslog Output Definition 215
Figure 70: Syslog Output Configuration Menu for Selected Output ID 217
Figure 71: Security and Services Menu 220
Figure 72: Classifier Configuration Menu 221
Figure 73: Create Classifier Menu (Page 1) 221
Figure 74: Create Classifier Menu (Page 2) 222
Figure 75: Show Classifiers Menu 228
Figure 76: Display Classifier Details Menu (Page 1) 229
Figure 77: Display Classifier Details Menu (Page 2) 230
Figure 78: Access Control Lists (ACL) Menu 232
Figure 79: Create ACL Menu 233
Figure 80: Modify ACL Menu 235
Figure 81: Destroy ACL Menu 237
Figure 82: Show ACLs Menu 240
Figure 83: Display ACL Details Menu 241
Figure 84: Class of Service (CoS) Menu 244
Figure 85: Configure Port COS Priorities Menu 245
Figure 86: Map CoS Priority to Egress Queue Menu 247
Figure 87: Configure Egress Scheduling Menu 248
Figure 88: Show Port CoS Priorities Menu 250
Figure 89: Quality of Service (QoS) menu 252
Figure 90: Flow Group Configuration Menu 253
Figure 91: Create Flow Group Menu 253
Figure 92: Modify Flow Group Menu 256
Figure 93: Destroy Flow Group Menu 257
Figure 94: Show Flow Groups Menu 258
Figure 95: Display Flow Group Detail Menu 259
Figure 96: Traffic Class Configuration Menu 261
Figure 97: Create Traffic Class Menu 262
Figure 98: Modify Traffic Class Menu 266
Figure 99: Destroy Traffic Class Menu 267
Figure 100: Show Traffic Classes Menu 268
Figure 101: Display Traffic Class Details Menu 269
Figure 102: Policy Configuration Menu 271
Figure 103: Create Policy Menu 272
Figure 104: Modify Policy Menu 274
Figure 105: Show Policies Menu 276
Figure 106: Display Policy Details Menu 277
Figure 107: Denial of Service (DoS) Menu 280
Figure 108: LAN IP Subnet Menu 280
Figure 109: SYN Flood Configuration Menu 282
Figure 110: Power Over Ethernet Configuration Menu 284

Downloaded from www.Manualslib.com manuals search engine

Figure 111: PoE Global Configuration Menu 284
Figure 112: PoE Port Configuration Menu 286
Figure 113: PoE Status Menu 288
Figure 114: PoE Global Status Menu 289
Figure 115: PoE Summary Ports Status Menu 290
Figure 116: PoE Summary Ports Status Menu 291
Figure 117: PoE Device Information 292
Figure 118: Advanced Configuration Menu 296
Figure 119: IGMP Snooping Configuration Menu 297
Figure 120: View IGMP Multicast Hosts List Menu 301
Figure 121: View IGMP Multicast Routers List Menu 303
Figure 122: MLD Snooping Configuration Menu 306
Figure 123: View MLD Multicast Hosts List Menu 310
Figure 124: View MLD Multicast Routers List Menu 312
Figure 125: RRP Snooping Menu 316
Figure 126: Configure SNMPv3 Table Menu 322
Figure 127: Configure SNMPv3 User Table Menu 322
Figure 128: Modify SNMPv3 User Table Menu 326
Figure 129: Configure SNMPv3 View Table Menu 332
Figure 130: Modify SNMPv3 View Table Menu 336
Figure 131: Configure SNMPv3 Access Table Menu 341
Figure 132: Modify SNMPv3 Access Table Menu 347
Figure 133: Configure SNMPv3 SecurityToGroup Table Menu 357
Figure 134: Modify SNMPv3 SecurityToGroup Table Menu 361
Figure 135: Configure SNMPv3 Notify Table Menu 365
Figure 136: Modify SNMPv3 Notify Table Menu 368
Figure 137: Configure SNMPv3 Target Address Table Menu 373
Figure 138: Modify SNMPv3 Target Address Table Menu 377
Figure 139: Configure SNMPv3 Target Parameters Table Menu 386
Figure 140: Modify SNMPv3 Target Parameters Table Menu 391
Figure 141: Configure SNMPv3 Community Table Menu 400
Figure 142: Modify SNMPv3 Community Table Menu 404
Figure 143: Display SNMPv3 Table Menu 409
Figure 144: Display SNMPv3 User Table Menu 409
Figure 145: Display SNMPv3 View Table Menu 410
Figure 146: Display SNMPv3 Access Table Menu 411
Figure 147: Display SNMPv3 SecurityToGroup Table Menu 412
Figure 148: Display SNMPv3 Notify Table Menu 412
Figure 149: Display SNMPv3 Target Address Table Menu 413
Figure 150: Display SNMPv3 Target Parameters Table Menu 414
Figure 151: Display SNMPv3 Community Table Menu 415
Figure 152: Spanning Tree Configuration Menu 420
Figure 153: STP Menu 423
Figure 154: STP Port Parameters Menu 426
Figure 155: Configure STP Port Settings Menu 426
Figure 156: Display STP Port Configuration Menu 428
Figure 157: RSTP Menu 431
Figure 158: RSTP Port Parameters Menu 433
Figure 159: Configure RSTP Port Settings Menu 434
Figure 160: Display RSTP Port Configuration Menu 436
Figure 161: Display RSTP Port State Menu 437
Figure 162: MSTP Configuration Menu 441
Figure 163: CIST Menu 445
Figure 164: MSTI Menu 447
Figure 165: VLAN-MSTI Association Menu 453
Figure 166: MSTP Port Parameters Menu 458
Figure 167: Configure MSTP Port Settings Menu 458
Figure 168: Configure Per Spanning Tree Port Settings Menu 461
Figure 169: Display MSTP Port Configuration Menu 463
Figure 170: Display MSTP Port State Menu 466
Figure 171: VLAN Configuration Menu 472

Downloaded from www.Manualslib.com manuals search engine

Figure 172: Configure VLANs Menu 473
Figure 173: Create VLAN Menu 473
Figure 174: Modify VLAN Menu 481
Figure 175: Expanded Modify VLAN Menu 482
Figure 176: Show VLANs Menu 485
Figure 177: Delete VLAN Menu 487
Figure 178: Expanded Delete VLAN Menu 488
Figure 179: Show PVIDs Menu 492
Figure 180: GARP-GVRP Menu 496
Figure 181: GVRP Port Parameters Menu 498
Figure 182: Configure GVRP Port Settings Menu 499
Figure 183: Display GVRP Port Configuration Menu 501
Figure 184: Other GVRP Parameters Menu 502
Figure 185: GVRP Counters Menu (page 1) 503
Figure 186: GVRP Counters Menu (page 2) 504
Figure 187: GVRP Database Menu 507
Figure 188: GIP Connected Ports Ring Menu 509
Figure 189: GVRP State Machine Menu (page 1) 511
Figure 190: Display GVRP State Machine Menu (page 2) 512
Figure 191: VLAN Configuration Menu (Multiple VLAN Mode) 518
Figure 192: Show VLANs Menu, Multiple VLANS 519
Figure 193: Create VLAN Menu 522
Figure 194: Expanded Modify VLAN Menu 526
Figure 195: Show VLANs Menu 528
Figure 196: Show VLANs Menu 529
Figure 197: Delete VLAN Menu 530
Figure 198: Expanded Delete VLAN Menu 531
Figure 199: MAC Based VLANs Menu 536
Figure 200: Delete VLAN Menu 540
Figure 201: Expanded Delete VLAN Menu 541
Figure 202: Show VLANs Menu with MAC Address-based VLANs 542
Figure 203: Detail Information Display 543
Figure 204: Configure Interface Menu 548
Figure 205: Create Interface Menu 549
Figure 206: Modify Interface Menu 552
Figure 207: Port Security Menu 562
Figure 208: Configure Port Security Menu #1 562
Figure 209: Configure Port Security Menu #2 564
Figure 210: Display Port Security Menu 566
Figure 211: Port Access Control (802.1X) Menu 570
Figure 212: Configure Port Access Role Menu 571
Figure 213: Configure Authenticator Menu 573
Figure 214: Configure Authenticator Port Access Parameters Menu 574
Figure 215: Configure Supplicant Menu 579
Figure 216: Configure Supplicant Port Access Parameters Menu 580
Figure 217: Display Port Access Status Menu 582
Figure 218: Radius Accounting Menu 584
Figure 219: Web Server Configuration Menu 590
Figure 220: Web Server Configuration Menu Configured for HTTPS 591
Figure 221: Keys/Certificate Configuration Menu 596
Figure 222: Key Management Menu 597
Figure 223: Create Key Menu 597
Figure 224: Export Key to File Menu 603
Figure 225: Import Key from File Menu 606
Figure 226: Key Management Menu 608
Figure 227: Public Key Infrastructure (PKI) Configuration Menu 613
Figure 228: X509 Certificate Management Menu 613
Figure 229: Create Self-Signed Certificate Menu 614
Figure 230: Add Certificate Menu 616
Figure 231: Modify Certificate Menu 620

Downloaded from www.Manualslib.com manuals search engine

Figure 232: View Certificate Details Menu (page 1) 625
Figure 233: View Certificate Details Menu (page 2) 626
Figure 234: Generate Enrollment Request Menu 628
Figure 235: Secure Socket Layer (SSL) Menu 632
Figure 236: Secure Shell (SSH) Menu 634
Figure 237: Show Server Information Menu 637
Figure 238: Authentication Configuration Menu 640
Figure 239: TACACS+ Client Configuration Menu 642
Figure 240: TACACS+ Client Configuration Menu 644
Figure 241: RADIUS Client Configuration 645
Figure 242: RADIUS Server Configuration 646
Figure 243: Show Status Menu 648
Figure 244: Management ACL Configuration Menu 652
Figure 245: Modify Management ACL Entry 656
Figure 246: Display All Management ACL Entries Menu 659

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Tables

Table 1: AT-S63 Modules 201
Table 2: Event Severity Levels 203
Table 3: Applicable RFC 3164 Numerical Code and AT-S63 Module Mappings 212
Table 4: Numerical Code and Facility Level Mappings 213
Table 5: Bridge Priority Value Increments 424
Table 6: Port Priority Value Increments 427
Table 7: STP Auto-Detect Port Costs 427
Table 8: STP Auto-Detect Port Trunk Costs 427
Table 9: RSTP Auto-Detect Port Costs 434
Table 10: RSTP Auto-Detect Port Trunk Costs 435
Table 11: Auto External Path Costs 459
Table 12: Auto External Path Trunk Costs 459
Table 13: RSTP Auto-Detect Port Costs 461
Table 14: RSTP Auto-Detect Port Trunk Costs 462
Table 15: GVRP Counters 504
Table 16: GVRP State Machine Parameters 512

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Preface

This guide contains instructions on how to configure the AT-9400 Layer 2+ and Basic Layer 3 Gigabit Ethernet Switches from the menus of the AT-S63 Management Software.

This preface contains the following sections:

- ❒ “How This Guide is Organized” on page 20
- ❒ “Product Documentation” on page 22
- ❒ “Where to Go First” on page 23
- ❒ “Starting a Management Session” on page 24
- ❒ “Document Conventions” on page 25
- ❒ “Where to Find Web-based Guides” on page 26
- ❒ “Contacting Allied Telesis” on page 27

Caution

The software described in this documentation contains certain cryptographic functionality and its export is restricted by U.S. law. As of this writing, it has been submitted for review as a “retail encryption item” in accordance with the Export Administration Regulations, 15 C.F.R. Part 730-772, promulgated by the U.S. Department of Commerce, and conditionally may be exported in accordance with the pertinent terms of License Exception ENC (described in 15 C.F.R. Part 740.17). In no case may it be exported to Cuba, Iran, Iraq, Libya, North Korea, Sudan, or Syria. If you wish to transfer this software outside the United States or Canada, please contact your local Allied Telesis sales representative for current information on this product’s export status.

Downloaded from www.Manualslib.com manuals search engine

How This Guide is Organized

This guide contains the following sections and chapters:

- Section I: Basic Operations

  Chapter 1, “Basic Switch Parameters” on page 31

  Chapter 2, “Port Parameters” on page 61

  Chapter 3, “Enhanced Stacking” on page 85

  Chapter 4, “SNMPv1 and SNMPv2c” on page 93

  Chapter 5, “MAC Address Table” on page 105

  Chapter 6, “Static Port Trunks” on page 115

  Chapter 7, “LACP Port Trunks” on page 125

  Chapter 8, “Port Mirroring” on page 137

- Section II: Advanced Operations

  Chapter 9, “File System” on page 145

  Chapter 10, “File Downloads and Uploads” on page 167

  Chapter 11, “Event Logs and the Syslog Client” on page 197

  Chapter 12, “Classifiers” on page 219

  Chapter 13, “Access Control Lists” on page 231

  Chapter 14, “Class of Service” on page 243

  Chapter 15, “Quality of Service” on page 251

  Chapter 16, “Denial of Service Defenses” on page 279

  Chapter 17, “Power Over Ethernet” on page 283

- Section III: Snooping Protocols

  Chapter 18, “IGMP Snooping” on page 295

  Chapter 19, “MLD Snooping” on page 305

  Chapter 20, “RRP Snooping” on page 315

- Section IV: SNMPv3

  Chapter 21, “SNMPv3” on page 319

Downloaded from www.Manualslib.com manuals search engine

- Section V: Spanning Tree Protocols

  Chapter 22, "Spanning Tree and Rapid Spanning Tree Protocols" on page 419

  Chapter 23, "Multiple Spanning Tree Protocol" on page 439

- Section VI: Virtual LANs

  Chapter 24, "Port-based and Tagged VLANs" on page 471

  Chapter 25, "GARP VLAN Registration Protocol" on page 495

  Chapter 26, "Multiple VLAN Modes" on page 515

  Chapter 27, "Protected Ports VLANs" on page 521

  Chapter 28, "MAC Address-based VLANs" on page 533

- Section VII: Internet Protocol Routing

  Chapter 29, "Internet Protocol Version 4 Routing Interfaces" on page 547

- Section VIII: Port Security

  Chapter 30, "MAC Address-based Port Security" on page 561

  Chapter 31, "802.1x Port-based Network Access Control" on page 569

- Section IX: Management Security

  Chapter 32, "Web Server" on page 589

  Chapter 33, "Encryption Keys" on page 595

  Chapter 34, "PKI Certificates and SSL" on page 611

  Chapter 35, "Secure Shell (SSH)" on page 633

  Chapter 36, "TACACS+ and RADIUS Protocols" on page 639

  Chapter 37, "Management Access Control List" on page 651

Downloaded from www.Manualslib.com manuals search engine

Product Documentation

For overview information on the features of the AT-9400 Switch and the AT-S63 Management Software, refer to:

- AT-S63 Management Software Features Guide (PN 613-001022)

For instructions on starting a local or remote management session on a stand-alone AT-9400 Switch or a stack, refer to:

- Starting an AT-S63 Management Session Guide (PN 613-001023)

For instructions on installing or managing a stand-alone AT-9400 Switch, refer to:

- AT-9400 Gigabit Ethernet Switch Installation Guide (PN 613-000987)
- AT-S63 Management Software Menus User's Guide (PN 613-001025)
- AT-S63 Management Software Command Line User's Guide (PN 613-001024)
- AT-S63 Management Software Web Browser User's Guide (PN 613-001026)

For instructions on installing or managing a stack of AT-9400 Basic Layer 3 Switches, refer to:

- AT-9400 Stack Installation Guide (PN 613-000796)
- AT-S63 Stack Command Line User's Guide (PN 613-001027)
- AT-S63 Stack Web Browser User's Guide (PN 613-001028)

Downloaded from www.Manualslib.com manuals search engine

Where to Go First

Allied Telesis recommends that you read Chapter 1, Overview, in the *AT-S63 Management Software Features Guide* before you begin to manage the switch for the first time. There you will find a variety of basic information about the unit and the management software, like the two levels of manager access levels and the different types of management sessions.

The *AT-S63 Management Software Features Guide* is also your resource for background information on the features of the switch. You can refer there for the relevant concepts and guidelines when you configure a feature for the first time.

Downloaded from www.Manualslib.com manuals search engine

Starting a Management Session

For instructions on how to start a local or remote management session on the AT-9400 Switch, refer to the *Starting an AT-S63 Management Session Guide*.

Downloaded from www.Manualslib.com manuals search engine

Document Conventions

This document uses the following conventions:

Note
Notes provide additional information.

Caution
Cautions inform you that performing or omitting a specific action may result in equipment damage or loss of data.

Warning
Warnings inform you that performing or omitting a specific action may result in bodily injury.

Downloaded from www.Manualslib.com manuals search engine

Where to Find Web-based Guides

The installation and user guides for all Allied Telesis products are available in portable document format (PDF) on our web site at **www.alliedtelesis.com**. You can view the documents online or download them onto a local workstation or server.

Downloaded from www.Manualslib.com manuals search engine

Contacting Allied Telesis

This section provides Allied Telesis contact information for technical support and for sales and corporate information.

Online Support

You can request technical support online from the Allied Telesis Knowledge Base at **www.alliedtelesis.com/support/kb.aspx**. You can submit questions to our technical support staff from the Knowledge Base and review answers to previously asked questions.

Email and Telephone Support

For Technical Support by email or telephone, refer to the Allied Telesis web site at **www.alliedtelesis.com**. Select your country from the list on the web site and then select the appropriate tab.

Returning Products

Products for return or repair must be assigned Return Materials Authorization (RMA) numbers. A product sent to Allied Telesis without an RMA number will be returned to the sender at the sender's expense.

To obtain an RMA number, contact the Allied Telesis Technical Support group at **www.alliedtelesis.com/support/rma.aspx**.

Sales and Corporate Information

You can contact Allied Telesis for sales or corporate information at our web site at **www.alliedtelesis.com**.

Management Software Updates

New releases of the management software for our managed products are available from the following Internet sites:

- Allied Telesis web site: **www.alliedtelesis.com**
- Allied Telesis FTP server: **ftp://ftp.alliedtelesis.com**

If the FTP server prompts you to log on, enter "anonymous" as the user name and your email address as the password.

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Section I

Basic Operations

The chapters in this section provide information and procedures for basic switch setup using the AT-S63 Management Software. The chapters include:

- Chapter 1, ”Basic Switch Parameters” on page 31
- Chapter 2, ”Port Parameters” on page 61
- Chapter 3, ”Enhanced Stacking” on page 85
- Chapter 4, ”SNMPv1 and SNMPv2c” on page 93
- Chapter 5, ”MAC Address Table” on page 105
- Chapter 6, ”Static Port Trunks” on page 115
- Chapter 7, “LACP Port Trunks” on page 125
- Chapter 8, ”Port Mirroring” on page 137

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Chapter 1

Basic Switch Parameters

This chapter contains the following procedures:

- ❒ “Configuring the Switch’s Name, Location, and Contact” on page 32
- ❒ “Changing the Manager and Operator Passwords” on page 35
- ❒ “Setting the System Time” on page 38
- ❒ “Rebooting the Switch” on page 43
- ❒ “Configuring the Console Startup Mode” on page 45
- ❒ “Configuring the Console Timer” on page 46
- ❒ “Configuring the Telnet Server” on page 47
- ❒ “Setting the Baud Rate of the Serial Terminal Port” on page 48
- ❒ “Pinging a Remote System” on page 49
- ❒ “Returning the AT-S63 Management Software to the Factory Default Values” on page 50
- ❒ “Displaying Hardware and Software Information” on page 52
- ❒ “Displaying System Hardware Information” on page 55
- ❒ “Displaying Uplink Port Information” on page 57

Downloaded from www.Manualslib.com manuals search engine

Configuring the Switch's Name, Location, and Contact

This procedure explains how to assign a name to the switch. The name appears at the top of the menus. Names can help you identify your switches when you manage them and help you avoid performing a configuration procedure on the wrong switch. This procedure also assigns the name of the administrator responsible for maintaining the unit and the location of the switch.

To assign a name, location, and contact to a switch, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1.

```
            Allied Telesis AT-9424Ts - AT-S63
                        Marketing
User: Manager                          11:20:02 02-Mar-2005
                    System Administration
1 - System Information
2 - System Configuration
3 - Console (Serial/Telnet) Configuration
4 - Web Server Configuration
5 - SNMP Configuration
6 - Authentication Configuration
7 - Management ACL
8 - Event Log
9 - System Utilities

R - Return to Previous Menu

Enter your selection?
```

Figure 1. System Administration Menu

2. From the System Administration menu, type **2** to select System Configuration.

Downloaded from www.Manualslib.com manuals search engine

The System Configuration menu is shown in Figure 2.

```
            Allied Telesis AT-9424Ts - AT-S63
                        Marketing
User: Manager                            11:20:02 02-Mar-2006
                    System Configuration
 1 - Eth0 Interface.............. vlan2-0
 2 - IP Address ................. 184.35.62.11
 3 - Subnet Mask ................ 255.255.255.0
 4 - Default Gateway ............ 184.35.62.4
 5 - System Name ................
 6 - Location ...................
 7 - Administrator ..............
 8 - ARP Cache Timeout ......... 150 seconds

 T - Configure System Time
 I - Configure Interface
 R - Return to Previous Menu

 Enter your selection?
```

Figure 2. System Configuration Menu

Note
Selections 1 to 4 are described in "Displaying the IP Address of the Local Interface" on page 555. Selection 8, ARP Cache Timeout, is described in "Setting the ARP Cache Timeout" on page 558. Selection T, Configure System Time, is described in "Setting the System Time" on page 38.

3. Adjust options 5 to 7 as necessary.

5 - System Name
This parameter specifies a name for the switch (for example, Sales Ethernet switch). The name is displayed at the top of the management menus and pages. The name can be from 1 to 39 characters. The name can include spaces and special characters, such as exclamation points and asterisks. The default is no name. This parameter is optional.

6 - Location
This parameter specifies the location of the switch, (for example, 4th Floor - rm 402B). The location can be from 1 to 20 characters. The location can include spaces and special characters, such as dashes and asterisks. The default is no location. This parameter is optional.

7 - Administrator
This parameter specifies the name of the network administrator responsible for managing the switch. The name can be from 1 to 20 characters. It can include spaces and special characters, such as

Downloaded from www.Manualslib.com manuals search engine

dashes and asterisks. The default is no name. This parameter is optional.

4. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Changing the Manager and Operator Passwords

There are two levels of management access on the AT-9400 Switch: manager and operator. When you log in as manager, you can view and configure all of a switch's operating parameters. When you log in as an operator, you can only view the operating parameters; you cannot change any values.

You log in as a manager or an operator when you enter the appropriate username and password when you start a management session. The default password for manager access is "friend." The default password for operator access is "operator." Passwords are case sensitive.

This section contains these two procedures:

- "Changing the Manager or Operator Password" on page 35
- "Resetting the Manager Password" on page 37

The first procedure allows you to change the manager or operator password. The second procedure allows you to bypass the manager password in the event you lose or forget it.

Changing the Manager or Operator Password

To change the manager or operator password, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **6** to select Authentication Configuration.

   The Authentication Configuration menu is shown in Figure 3.

```
            Allied Telesis AT-9424Ts - AT-S63
                        Marketing
User: Manager                          11:20:02 02-Mar-2005
                Authentication Configuration

1 - Server-based Authentication ..... Disabled
2 - Authentication Method ........... TACACS+
3 - TACACS+ Configuration
4 - RADIUS Configuration
5 - Passwords Configuration

R - Return to Previous Menu

Enter your selection?
```

Figure 3. Authentication Configuration Menu

Downloaded from www.Manualslib.com manuals search engine

3. From the Authentication Configuration menu, type **5** to select Passwords Configuration.

   The Passwords Configuration menu is shown in Figure 4.

```
            Allied Telesis AT-9424Ts - AT-S63
                        Marketing
User: Manager                          11:20:02 02-Mar-2005
                  Passwords Configuration

1 - Set Manager Password
2 - Set Operator Password

R - Return to Previous Menu

Enter your selection?
```

Figure 4. Passwords Configuration Menu

4. From the Passwords Configuration menu, type **1** to select Set Manager Password.

   The following prompt is displayed:

   ```
   Enter Current Manager Password ->
   ```

5. Type the current manager password (the default is “friend”) and press Return.

   The following prompt is displayed:

   ```
   Enter New Manager Password ->
   ```

6. When prompted, re-enter the new password.

7. Type **2** to select Set Operator Password.

   The following prompt is displayed:

   ```
   Enter New Operator Password ->
   ```

8. Type the current operator password (the default is “friend”) and press Return.

Note
A password can be from 0 to 16 alphanumeric characters. Passwords are case sensitive. You should not use spaces or special characters, such as asterisks (*) or exclamation points (!), in a password if you are managing the switch from a web browser. Many web browsers cannot handle special characters in passwords.

Downloaded from www.Manualslib.com manuals search engine

9. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Resetting the Manager Password

This procedure can be used to bypass the login on the switch in the event you forget the manager password. This procedure must be performed from a local management session.

Caution
With this procedure, any person with physical access to the switch can gain access to the unit's management software without a user name or password. For this reason, all AT-9400 Switches should be maintained in a locked wiring closet or other secure location to prevent unauthorized management access.

Note
This procedure requires rebooting the switch. Some network traffic may be lost.

To reset the manager password, perform the following procedure:

1. Establish a local management session with the switch.
2. Reboot the switch. Refer to "Rebooting the Switch" on page 43 for instructions.
3. When the switch displays "Press <Ctrl> B to go to Boot prompt," type **S** or **s**.

   The switch, without acknowledging the key input, continues with the process of initializing the management software.
4. At the completion of the initialization process, press Return.

   You are automatically logged on with manager privileges. The command line interface is displayed.
5. Change the manager's password from either the command line interface or the menus interface. For instructions on how to change the password from the menus interface, refer to "Changing the Manager or Operator Password" on page 35.

   This completes the procedure for resetting the manager password. You can continue to manage the switch or quit from the management session. You must use the new password the next time you log on to the switch at the start of a management session.

Downloaded from www.Manualslib.com manuals search engine

Setting the System Time

This procedure explains how to set the switch's date and time. Setting the system time is important if you configured the switch to send traps to your management stations. Traps from a switch where the time has not been set do not contain the correct date and time. Therefore, it becomes difficult for you to determine when the events represented by the traps occurred.

It is also important to set the system time if you intend to use the Secure Sockets Layer (SSL) certificate feature described in, Chapter 34, "PKI Certificates and SSL" on page 611. Certificates must contain the date and time when they are created.

There are two ways to set the switch's time. One method is to set it manually. The AT-9400 Switch has an onboard battery that maintains the date and time even when the unit is powered off or reset. For instructions, refer to "Setting the System Time Manually," next.

The second method uses the Simple Network Time Protocol (SNTP). The AT-S63 Management Software is shipped with the client version of this protocol. You can configure the AT-S63 Management Software to obtain the current date and time from an SNTP or Network Time Protocol (NTP) server located on your network or the Internet. For instructions, refer to "Setting the System Time from an SNTP or NTP Server" on page 40.

SNTP is a reduced version of the NTP. However, the SNTP client software in the AT-S63 Management Software is interoperable with NTP servers.

The local subnet on the switch where the SNTP server is a member must have a routing interface. The switch uses the IP address of the routing interface as its source address when communicating with the server. To configure routing interfaces using the menus interface, refer to Chapter 29, "Internet Protocol Version 4 Routing Interfaces" on page 547 in this guide.

Note
Prior to version 2.0.0 of the AT-S63 Management Software, the SNTP server had to be a member of the switch's management VLAN. This restriction no longer applies. The SNTP server can be located on any local subnet of the switch, provided the subnet has a routing interface.

Note
The default system time on the switch is midnight, January 1, 1970.

Downloaded from www.Manualslib.com manuals search engine

Setting the System Time Manually

To set the system time manually, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **2** to select System Configuration.

   The System Configuration menu is shown in Figure 2 on page 33.

3. From the System Configuration menu, type **T** to select Configure System Time.

   The Configure System Time menu is shown in Figure 5.

```
              Allied Telesis AT-9424Ts - AT-S63
                        Marketing
User: Manager                              11:20:02 02-Mar-2005
                     Configure System Time
1 - System Time ................... 00:00:00 on 01-Jan-1970
2 - SNTP Status ................... Disabled
3 - SNTP Server ................... 0.0.0.0
4 - UTC Offset .................... +0
5 - Daylight Savings Time (DST) ... Enabled
6 - Poll Interval ................. 600 seconds
7 - Last Delta .................... +0 seconds

U - Update System Time
R - Return to Previous Menu

Enter your selection?
```

Figure 5. Configure System Time Menu

4. From the Configure System Time menu, type **1** to select System Time. The following prompt is displayed:

   ```
   Enter new system time [hh:mm:ss] ->
   ```

5. Enter a new time for the system in the following format: hours, minutes, and seconds all separated by colons. The following prompt is displayed:

   ```
   Enter new system date [dd-mm-yyyy] ->
   ```

6. Enter a new date for the system. Use two numbers to specify the day and month. Use four numbers to specify the year. Separate the values with hyphens. For example, December 5, 2004 is specified 05-12-2004.

   The new time and date are immediately activated on the switch.

Downloaded from www.Manualslib.com manuals search engine

Setting the System Time from an SNTP or NTP Server

To configure the switch to obtain its date and time from an SNTP or NTP server on your network or the Internet, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **2** to select System Configuration.

   The System Configuration menu is shown in Figure 2 on page 33.

3. From the System Configuration menu, type **8** to select Configure System Time.

   The Configure System Time menu is shown in Figure 5 on page 39.

4. Type **3** to select SNTP Server and enter the IP address of an SNTP or NTP server.

   Note
   If the local interface on the switch is obtaining its IP address and subnet mask from a DHCP server, you can configure the server to provide the interface with an IP address of an NTP or SNTP server. If you configured the server to provide this address, then you do not need to enter it here, and you can skip ahead to step 5.

   The following prompt is displayed:

   ```
   Enter SNTP server IP address ->
   ```

5. Enter an IP address of an SNTP or NTP server.

6. Type **4** to select UTC Offset to specify the difference between the UTC and local time.

   Note
   If the switch is using DHCP, it automatically attempts to determine this value. In this case, you do not need to configure a value for the UTC Offset parameter.

   The following prompt is displayed:

   ```
   Enter UTC Offset [-12 to 12] -> 0
   ```

7. Enter a UTC Offset time.

   The default is 0 hours. The range is -12 to +12 hours.

Downloaded from www.Manualslib.com manuals search engine

8. Type **5** to select Daylight Savings Time (DST) to enable or disable the switch's ability to adjust its system time to daylight savings time. The following prompt is displayed:

   ```
   Adjust for Daylight Savings Time (E - Enabled, D - Disabled) ->
   ```

9. Type **E** to enable daylight savings time and allow the switch to adjust system time to daylight savings time. This is the default value. Type **D** to disable daylight savings time and not allow the switch to adjust system time to daylight savings time.

   Note
   The switch does not set DST automatically. If the switch is in a locale that uses DST, you must remember to enable this in April when DST begins and disable it in October when DST ends. If the switch is in a locale that does not use DST, this option should be set to disabled all the time.

10. Type **6** to select Poll Interval to specify the time interval between queries to the SNTP server.

    The following prompt is displayed:

    ```
    Enter interval to poll SNTP server [60 to 1200] -> 600
    ```

    Note
    Selection 7, Last Delta, reports the last adjustment that had to be applied to the system time; the drift in the system clock between two successive queries to the SNTP server. You cannot change this value.

11. Enter the number of seconds the switch waits between polling the SNTP or NTP server. The default is 600 seconds. The range is from 60 to 1200 seconds.

12. Type **2** to select SNTP Status to enable or disable the SNTP client.

    The following prompt is displayed:

    ```
    SNTP Status (E-Enabled, D-Disabled) ->
    ```

13. Type **E** to enable SNTP client software on the switch or **D** to disable the NTP client software and press Return. The default is disabled.

    After SNTP is enabled, the switch immediately polls the SNTP or NTP server for the current date and time. (The switch also automatically polls the server whenever a change is made to any of the parameters in this menu, so long as SNTP is enabled.)

Downloaded from www.Manualslib.com manuals search engine

The Last Delta option in the menu displays the last adjustment that was applied to system time due to a drift in the system clock between two successive queries to the SNTP server. This is a read only field.

Option U, Update System Time, allows you to prompt the switch to poll the SNTP or NTP server for the current time and date. You can use this selection to update the time and date immediately rather than wait for the switch's next polling period. This selection has no effect if you set the date and time manually.

14. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Rebooting the Switch

This procedure reboots the switch.

Note
Any configuration changes not saved are lost after the switch reboots. To save your configuration changes, return to the Main Menu and type **S** to select Save Configuration Changes.

Caution
The switch does not forward traffic while it initializes its operating software. The process can take from 20 seconds to several minutes to complete, depending on the number and complexity of the commands in its boot configuration file. Some packet traffic may be lost. You must reestablish your management session after the switch finishes reloading its software to continue managing the unit.

To reboot the switch, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **9** to select System Utilities.

   The System Utilities menu is shown in Figure 6.

```
            Allied Telesis AT-9424Ts - AT-S63
                        Marketing
User: Manager                           11:20:02 02-Mar-2005
                     System Utilities

1 - File Operations
2 - Downloads and Uploads
3 - Ping a Remote System
4 - Reset to Factory Defaults
5 - Reboot the Switch

R - Return to Previous Menu

Enter your selection?
```

Figure 6. System Utilities Menu

Downloaded from www.Manualslib.com manuals search engine

Note
Item 1 - File Operations, is described in Chapter 9, ”File System” on page 145. Item 2 - Downloads and Uploads is described in Chapter 10, ”File Downloads and Uploads” on page 167. Ping a Remote System, item 3, is described in “Pinging a Remote System” on page 49. Reset to Factory Defaults, item 4, is described in “Returning the AT-S63 Management Software to the Factory Default Values” on page 50.

3. From the System Utilities menu, type **5** to select Reboot the switch.

   The following prompt is displayed:

   ```
   The switch is about to reboot. Do you want to proceed?
   [Yes/No] ->
   ```

4. Type **Y** to reboot the switch or **N** to cancel the procedure.

Downloaded from www.Manualslib.com manuals search engine

Configuring the Console Startup Mode

With this procedure you can control which management interface, menus or command line, is displayed at the start of your local and remote management sessions. The default is the command line interface.

To change the console startup mode, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **3** to select Console (Serial/Telnet) Configuration.

   The Console (Serial/Telnet) Configuration menu is shown in Figure 7.

```
            Allied Telesis AT-9424Ts - AT-S63
                        Marketing
User: Manager                          11:20:02 02-Mar-2005
          Console (Serial/Telnet) Configuration

1 - Console Startup Mode ............. CLI
2 - Console Disconnect Interval ..... 10 minute(s)
3 - Console Baud Rate ................ 9600
4 - Telnet Server .................... Enabled
5 - Telnet insert NULL ............... OFF

R - Return to Previous Menu

Enter your selection?
```

Figure 7. Console (Serial/Telnet) Configuration Menu

3. Type **1** to toggle Console Startup Mode between Menu and CLI. When the mode is set to Menu, management sessions start with the Main Menu. When the mode is set to CLI, management sessions start with the command line interface prompt. The default is CLI.

4. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

   A change to the console startup mode takes effect the next time you start a local management session.

Downloaded from www.Manualslib.com manuals search engine

Configuring the Console Timer

The AT-S63 Management Software uses the console timer, also referred to as the console disconnect interval, to automatically end inactive local and remote management sessions. The management software automatically ends a local or remote management session if a management session is inactive for the length of time specified by the console timer. For example, if you specify two minutes as the console timer, the AT-S63 Management Software automatically ends a management session if it does not detect any activity from the local or remote management station after two minutes.

This security feature prevents unauthorized individuals from using your management station when you step away from your system while you are configuring a switch. The default for the console timeout value is 10 minutes.

To adjust the console timer, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **3** to select Console (Serial/Telnet) Configuration.

   The Console (Serial/Telnet) Configuration menu is shown in Figure 7 on page 45.

3. From the Console (Serial/Telnet) Configuration menu, type **2** to select Console Disconnect Interval

   The following prompt is displayed:

   ```
   Enter your new value -> [1 to 60]->
   ```

4. Enter a new console timer value. The range is 1 to 60 minutes. The default is 10 minutes.

   A change to the console timer is immediately activated on the switch.

5. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Configuring the Telnet Server

This procedure describes how to enable and disable the Telnet server on the switch. You might disable the server to prevent individuals from managing the switch with a Telnet application or if you intend to use the Secure Shell (SSH) protocol.

This procedure also explains how to toggle the Telnet server on the switch so that is adds a NULL character after each CR. Some Telnet clients require the character in order to correctly display the information from the Telnet server.

To enable or disable the Telnet server or to set the Telnet NULL character parameter, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **3** to select Console (Serial/Telnet) Configuration.

   The Console (Serial/Telnet) Configuration menu is shown in Figure 7 on page 45.

3. To enable or disable the Telnet server, from the Console (Serial/Telnet) Configuration menu type **4** to toggle Telnet Server between Enabled and Disabled. The default is enabled.

   Note
   Disable Telnet access if you are using the SSH (Secure Shell) feature. (The SSH feature is not available in all versions of the AT-S63 Management Software.)

4. To configure the Telnet NULL character parameter, type **5** to toggle Telnet insert NULL between On and Off. When Off, the default setting, the Telnet server does not send a NULL character after each CR. When On, the server does send the character.

   A change to the status of the Telnet server or the Telnet NULL character parameter is immediately implemented on the switch.

5. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Setting the Baud Rate of the Serial Terminal Port

The default baud rate of the RJ-45 type serial terminal port on the switch is 9600 bps.

To change the baud rate, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **3** to select Console (Serial/Telnet) Configuration.

   The Console (Serial/Telnet) Configuration menu is shown in Figure 7 on page 45.

3. From the Console (Serial/Telnet) Configuration menu, type **3** to select Console Baud Rate.

   The following prompt is displayed:

   ```
   Supported baud rates are:
   1200, 2400, 4800, 9600, 19200, 38400, 57600, or 115200
   Enter new baud rate value --> [1200 to 115200]
   ```

4. Type the desired baud rate value and press Return. The default setting is 9600 bps.

   The following message is displayed:

   Baud rate changed to [baud rate you typed] bps.
   Please change your terminal baud rate correspondingly.
   Press <Enter> to continue.

   Note
   If you are running a local management session, be sure to change your terminal's baud rate.

5. Press Return.

Downloaded from www.Manualslib.com manuals search engine

Pinging a Remote System

This procedure instructs the switch to ping a remote device on your network. This can be useful in determining whether a valid link exists between the switch and another network device.

The local subnet on the switch where the device is a member must have a routing interface. The switch uses the IP address of the routing interface as its source address when sending the ping.

> **Note**
> Prior to version 2.0.0 of the AT-S63 Management Software, the switch could ping a device only if the device was a member of the switch's management VLAN. This restriction no longer applies. The switch can ping a device from any local subnet, provided the subnet has a routing interface.

To instruct the switch to ping a network device, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **9** to select System Utilities.

   The System Utilities menu is shown in Figure 6 on page 43.

3. For the System Utilities menu, type **3** to select Ping a Remote System.

   The following prompt is displayed:

   ```
   Please enter an IP address ->
   ```

4. Enter the IP address of the end node you want the switch to ping.

   The results of the ping command are displayed on the screen.

5. To stop the ping, press any key.

Downloaded from www.Manualslib.com manuals search engine

Returning the AT-S63 Management Software to the Factory Default Values

The procedure in this section returns all AT-S63 Management Software parameters to the default values. Please note the following before you perform this procedure:

- Returning all parameter settings to their default values also deletes all routing interfaces as well as all port-based and tagged VLANs on the switch.
- This procedure does not delete files from the AT-S63 file system. To delete files, refer to Chapter 9, ”File System” on page 145.
- This procedure does not delete any encryption keys stored in the key database. To delete encryption keys, refer to “Deleting an Encryption Key” on page 600.
- Returning a switch to its default values does not alter the contents of the active boot configuration file. To reset the file back to the default settings, you must reestablish your management session after the switch reboots and then select Save Configuration changes. Otherwise the switch reverts back to the previous configuration the next time you reset the switch.

Note
The AT-S63 Management Software default values are listed in the *AT-S63 Management Software Features Guide*.

To return the AT-S63 Management Software to the default settings, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **9** to select System Utilities.

   The System Utilities menu is shown in Figure 6 on page 43.

3. From the System Utilities menu, type **4** to select Reset to Factory Defaults.

   The following prompt is displayed:

   ```
   This operation requires a switch reboot? [Yes/No] ->
   ```

4. Type **Y** for yes or **N** to cancel the procedure.

Downloaded from www.Manualslib.com manuals search engine

If you respond with yes, the following prompt is displayed:

```
Do you want to reset the serial port baud rate to 9600
bps? [Yes/No] ->
```

5. To return the baud rate of the terminal port on the switch to 9600 bps, type **Y** for yes. To retain its current speed setting, type **N** for no.

   All of the operating parameters on the switch are automatically returned to their default settings as the unit reboots.

> **Caution**
> The switch does not forward traffic while it initializes its operating software, a process that takes from 20 seconds to several minutes to complete, depending on the number and complexity of commands in the boot configuration file. Some packet traffic may be lost. You must reestablish your management session if you want to continue managing the switch.

To overwrite the settings in the active boot configuration file and return the file to the switch's default settings, perform steps 6 and 7.

6. Reestablish your management session.

7. From the Main Menu, type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Displaying Hardware and Software Information

To display information about the switch hardware and software, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **1** to select System Information.

   The System Information menu is shown in Figure 8.

```
                    Allied Telesis AT-9424T/SP - AT-S63
                                Marketing
User: Manager                                              11:20:02 27-Jun-2006
                                System Information
MAC Address ..... 00:30:84:00:00:00     IP Address ...... 149.35.19.155
Model Name ...... AT-9424T/SP            Subnet Mask ..... 255.255.0.0
Serial Number ... S05525A023600001       Gateway ......... 0.0.0.0
                                         System Up Time .. 30D:12H:56M:14S

Bootloader ...... ATS63_LOADER v1.7.0    Build Date ...... Apr 12 2006 19:32:40
Application ..... ATS63 v2.0.0           Build Date ...... Jun 26 2006 19:32:40

System Name ..... Marketing
Administrator ... Joe
Location ........ 3rd Floor

H - System Hardware Status
U - Uplink Information

R - Return to Previous Menu

Enter your selection?
```

Figure 8. System Information Menu

The System Information menu provides the following information:

MAC Address
The MAC address of the switch. You cannot change this parameter.

Model Name
Model name of the AT-9400 Switch. You cannot change this setting.

Serial Number
Serial number of the switch. You cannot change this setting.

IP Address
IP address of the local interface.

Downloaded from www.Manualslib.com manuals search engine

Subnet Mask
Subnet mask of the local interface.

Gateway
For AT-9400 Switches that support IPv4 routing, such as the AT-9424Ts and AT-9448Ts/XP switches, this field displays the IP address of the next hop of the switch's default route. The switch uses the default route when it receives a network packet for routing, but cannot find a route for it in the routing table. This field will contain 0.0.0.0 if no default route is defined on the switch.

For AT-9400 Switches that do not support IPv4 packet routing, such as the AT-9424T/GB and AT-9424T/SP switches, this field displays the default gateway address. This is the IP address of a router interface on your network. It represents the next hop to reaching a remote network device, such as a remote management workstation or a syslog server, when the switch's local interface and the remote device are on different subnets. The default value is 0.0.0.0.

Note
For instructions on how to configure the routing interfaces on the switch, including the local interface, refer to Chapter 29, "Internet Protocol Version 4 Routing Interfaces" on page 547.

System Up Time
The number of days, hours, minutes, and seconds the switch has been operational. You cannot change this setting.

Bootloader and Build Date
The version of the bootloader software and the date it was built.

Application and Build Date
The version of the AT-S63 Management Software that the switch is currently running and the date it was built.

System Name
The name of the switch.

Administrator
The administrator of the switch.

Location
The location of the switch.

Note
To change the system name, administrator, or location, see "Configuring the Switch's Name, Location, and Contact" on page 32.

For information about selection **H**, System Hardware Status, refer to "Displaying System Hardware Information" on page 55. For

Downloaded from www.Manualslib.com manuals search engine

information about selection **U**, Uplink Information, refer to “Displaying Uplink Port Information” on page 57.

Downloaded from www.Manualslib.com manuals search engine

Displaying System Hardware Information

You can view information about the system hardware, including details about the fans and temperature settings.

To display the system hardware information, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **1** to select System Information

   The System Information menu is shown in Figure 8 on page 52.

3. From the System Information menu, type **H** to select System Hardware Status.

   Note
   Menu selection U, Uplink Information, is described in "Displaying Uplink Port Information" on page 57.

   The information in the System Hardware Status menu varies depending on the model of the switch. The example in Figure 9 is from an AT-9424T/GB switch.

```
          Allied Telesis AT-9424T/GB - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                  System Hardware Status

System 1.25 V Power ............. 1.28V
System 1.8V Power ............... 1.76V
System 2.5V Power ............... 2.48V
System 3.3V Power ............... 3.2V
System 5V Power ................. 5.0V
System 12V Power ................ 11.68V
System Temperature (Celsius) .... 36 C
System Fan Speed ................ 3970 RPM

Main PSU ........................ On
RPS ............................. Not Connected

U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 9. System Hardware Information Menu

Downloaded from www.Manualslib.com manuals search engine

The System Hardware Information menu provides the following information:

System 1.25 V Power
System 1.8V Power
System 2.5 V Power
System 3.3 V Power
System 5 V Power
System 12 V Power
The current voltage of the six power supplies in the switch.

System Temperature (Celsius)
The overall system temperature.

System Fan Speed
The system fan speed.

Main PSU
RPS
The status of the main power supply unit (PSU) and the redundant power supply (RPS).

4. Return to the Main Menu.

Downloaded from www.Manualslib.com manuals search engine

Displaying Uplink Port Information

To display the information about the GBIC or SFP transceivers installed in the uplink ports, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **1** to select System Information

   The System Information menu is shown in Figure 8 on page 52.

3. From the System Information menu, type **U** to select Uplink Information.

   The Uplink Information menu is shown in Figure 10.

```
          Allied Telesis AT-9424T/GB - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                    Uplink Information

 1 - GBIC/SFP 1 ............. Not Present
 2 - GBIC/SFP 2 ............. Present

 R - Return to Previous Menu

 Enter your selection?
```

Figure 10. Uplink Information Menu

The Uplink Information menu displays the status of the GBIC/SFP uplink ports, ports 23 and 24. If a GBIC or an SFP transceiver is installed in one of the slots, the display shows "Present." "Not Present" indicates that no GBIC or SFP transceiver is installed in that slot.

Note
The Uplink Information menu only indicates that a GBIC or an SFP is inserted in the slot. It does not indicate whether or not a fiber optic cable is connected to the GBIC or SFP.

The number of uplink ports shown in the menu varies, depending on the model of the AT-9400 Switch.

Downloaded from www.Manualslib.com manuals search engine

4. Type the number corresponding to the slot where the transceiver is identified as “Present” to view detailed information about that transceiver. The information displayed depends upon the transceiver vendor and whether the slot contains an SFP or a GBIC transceiver.

   The GBIC/SFP Information menu (page 1) is displayed. Figure 11 shows some possible fields for an SFP.

```
                  Allied Telesis AT-9424T/GB - AT-S63
                               Marketing
User: Manager                          11:20:02 02-Mar-2005

                          GBIC/SFP 2 Information

Transceiver Identifier ..................... SFP
Extended Transceiver Identifier ............ Function defined by serial ID
Connector Type ............................. LC
Encoding Algorithm ......................... 8B20B
Nominal Bit Rate ........................... 2100M Bits/sec
Link Length Supported for 9 um Fiber ....... 0m
Link Length Supported for 50 um Fiber ...... 300m
Link Length Supported for 62.5 um Fiber .... 150m
Link Length Supported for Copper ........... 0m

N - Next Page
U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 11. GBIC/SFP Information Menu (Page 1)

5. Type **N** for Next Page to view more information.

Downloaded from www.Manualslib.com manuals search engine

The GBIC/SFP Information menu (page 2) is displayed. Figure 12 shows some possible fields of information.

```
          Allied Telesis AT-9424T/GB - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                   GBIC/SFP 2 Information

Vendor Name ............................ ATI
Vendor OUI ............................. 00-30-d3
Vendor Part Number ..................... AT-MG8SX
Vendor Product Revision ................ 1
Vendor Serial Number ................... A02103E040500070
Upper Bit Rate Margin .................. 0%
Lower Bit Rate Margin .................. 0%
Manufacturing Date Code ................ 040527
Gigabit Ethernet Compliance Code ....... 1000BASE-SX

P - Previous Page
U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 12. GBIC/SFP Information Menu (Page 2)

Note

The information displayed in the menus depends upon whether a GBIC or an SFP transceiver is installed and the transceiver vendor.

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Chapter 2

Port Parameters

This chapter contains the procedures for viewing and changing the parameter settings for the individual ports on a switch, and contains the following procedures:

- ❒ “Displaying Port Status” on page 62
- ❒ “Configuring Port Parameters” on page 65
- ❒ “Configuring Head of Line Blocking” on page 69
- ❒ “Configuring Flow Control and Back Pressure” on page 71
- ❒ “Configuring Port Filtering” on page 73
- ❒ “Setting Up Rate Limiting” on page 75
- ❒ “Resetting a Port” on page 77
- ❒ “Forcing Port Renegotiation” on page 78
- ❒ “Resetting the Port Configuration to the Default Settings” on page 79
- ❒ “Displaying Port Statistics” on page 80
- ❒ “Clearing Port Statistics” on page 83

Downloaded from www.Manualslib.com manuals search engine

Displaying Port Status

To display the current status of the ports on the switch, perform the following procedure:

1. From the Main Menu, type **1** to select Port Configuration.

   The Port Configuration menu is shown in Figure 13.

```
            Allied Telesis AT-9424T/SP - AT-S63
                         Marketing
User: Manager                            11:20:02 02-Mar-2005
                      Port Configuration

1 - Port Configuration
2 - Port Status
3 - Port Statistics
4 - Port Trunking and LACP
5 - Port Security
6 - Port Mirroring

R - Return to Previous Menu

Enter your selection?
```

Figure 13. Port Configuration Menu

2. From the Port Configuration menu, type **2** to select Port Status.

   An example of the Port Status menu is shown in Figure 14.

```
                Allied Telesis AT-9424T/SP - AT-S63
                             Marketing
User: Manager                                      11:20:02 02-Mar-2005
                              Port Status

 Port  Link  Neg   MDIO  Speed  Duplex  PVID   PortType
 ------------------------------------------------------------------
 17    Up    Auto  MDI   1000   Full    12     10/100/1000Base-T
 18    Up    Auto  MDI   100    Full    12     10/100/1000Base-T
 19    Up    Auto  MDI   1000   Full    21     10/100/1000Base-T
 20    Up    Auto  MDI   100    Full    21     10/100/1000Base-T
 21    Up    Auto  MDI   100    Full    21     10/100/1000Base-T
 22    Up    Auto  MDI   1000   Full    4      10/100/1000Base-T
 23    Down  ----  ----  ----   ----    ----   10/100/1000Base-T
 24    Up    Auto  MDI   1000   Full    21     10/100/1000Base-T

 P - Previous Page
 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 14. Port Status Menu

Downloaded from www.Manualslib.com manuals search engine

Note
The speed, duplex mode, and flow control settings are blank for a port that has not established a link to its end node.

The Port Status menu displays a table that contains the following columns of information:

Port
The port number.

Link
The status of the link between the port and the end node connected to the port. The possible settings are:

Up - Indicates that a valid link exists between the port and the end node.

Down - Indicates that the port and the end node have not established a valid link.

Neg
The status of Auto-Negotiation on the port. Possible values are:

Auto - Indicates that the port is using Auto-Negotiation to set operating speed and duplex mode.

Manual - Indicates that the operating speed and duplex mode have been set manually.

MDIO
The operating configuration of the port. Possible values are Auto, MDI, MDI-X. The status Auto indicates that the port automatically determines the appropriate MDI or MDI-X setting.

Speed
The operating speed of the port. Possible values are:

10 - 10 Mbps

100 - 100 Mbps

1000 - 1000 Mbps

Duplex
The duplex mode of the port. Possible values are half-duplex and full-duplex.

PVID
The VLAN identifier (VID) of the VLAN where the port is an untagged member. This column does not include the VIDs of the VLANs where the port is a tagged member.

Downloaded from www.Manualslib.com manuals search engine

Port Type
The port type.

Downloaded from www.Manualslib.com manuals search engine

Configuring Port Parameters

To configure the basic parameter settings for a port, such as speed and duplex mode, perform the following procedure:

1. From the Main Menu, type **1** to select Port Configuration.

   The Port Configuration menu is shown in Figure 13 on page 62.

2. From the Port Configuration menu, type **1** to select Port Configuration.

   The following prompt is displayed:

   ```
   Enter port-list ->
   ```

3. Enter the number of the port to be configured. You can configure more than one port at a time. You can specify the ports individually (for example, 5,7,22), as a range (for example, 18-23), or both (for example 1,5,14-22).

   The Port Configuration menu is shown in Figure 15.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                    Port Configuration
Configuring Port 11

0 - Description ....................... Port_11
1 - Status ............................ Enabled
2 - HOL Blocking Prevention Threshold .. 682 cells
3 - Flow Control
4 - Filtering
5 - Rate Limiting
6 - Negotiation ....................... Auto
X - Reset Port
F - Force Renegotiation
D - Set Port Configuration to Defaults

R - Return to Previous Menu

Enter your selection?
```

Figure 15. Port Configuration (Port) Menu

Note
If you are configuring multiple ports and the ports have different settings, the Port Configuration menu displays the settings of the lowest numbered port. After you have configured the settings of the port, all its settings are copied to the other selected ports.

Downloaded from www.Manualslib.com manuals search engine

4. Adjust the following parameters as necessary.

Note
A change to a parameter is immediately activated on the port.

0 - Description
You use this option to assign a description to a port, from 1 to 15 alphanumeric characters. Spaces are allowed, but you should not use special characters, such as asterisks or exclamation points. (You cannot set a port description if you are configuring more than one port.)

1 - Status
You use this option to enable or disable a port. When disabled, a port does not forward frames to or from the node connected to the port.

You might want to disable a port and prevent packets from being forwarded if a problem occurs with the node or cable connected to the port. After the problem has been fixed, you can enable the port again to resume normal operation.

You might also want to disable a port that is not being used to secure it from unauthorized connections.

Possible settings for this parameter are:

Enabled - The port receives and forwards packets. This is the default setting.

Disabled - The port does not receive or forward packets.

Note
Option 2, HOL Blocking Prevention, is described in “Configuring Head of Line Blocking” on page 69. Option 3, Flow Control, is described in “Configuring Flow Control and Back Pressure” on page 71. Option 4, Filtering, is described in “Configuring Port Filtering” on page 73. Option 5, Rate Limiting, is described in “Setting Up Rate Limiting” on page 75.

6 - Negotiation
You use this option to configure a port for Auto-Negotiation or to manually set a port’s speed and duplex mode. The default is Auto for Auto-Negotiation.

Note
When you set negotiation to Manual, items 7 (Speed), 8 (Duplex), and 9 (MDI Crossover) are displayed.

Downloaded from www.Manualslib.com manuals search engine

If you select Auto for Auto-Negotiation, which is the default setting, the switch sets speed, duplex mode, and MDI crossover for the port automatically. The switch determines the highest possible common speed between the port and its end node and sets the port to that speed. This helps to ensure that the port and the end node are operating at the highest possible common speed.

Note the following items concerning the operation of Auto-Negotiation on a switch port:

- A 10/100/1000Base-T twisted pair port must be set to set to Auto-Negotiation to operate at 1000 Mbps. You cannot manually configure a 10/100/1000Base-T twisted pair port to 1000 Mbps.
- In order for a switch port to successfully autonegotiate its duplex mode with an end node, the end node should also be using Auto-Negotiation. Otherwise, a duplex mode mismatch can occur. A switch port using Auto-Negotiation defaults to half-duplex if it detects that the end node is not using Auto-Negotiation. This can result in a mismatch if the end node is operating at a fixed duplex mode of full-duplex.
- To avoid this problem when connecting an end node with a fixed duplex mode of full-duplex to a switch port, disable Auto-Negotiation on the port and set the port's speed and duplex mode manually.
- When a twisted pair port is set to Auto-Negotiation, the MDI/MDI-X setting for the port is locked at auto-MDI/MDI-X. The switch automatically determines the correct MDI/MDI-X setting. You cannot set MDI/MDI-X manually.
- When Auto-Negotiation is disabled on a twisted pair port, the auto-MDI/MDI-X feature on a port is also disabled, and the port defaults to the MDI-X configuration. Consequently, if you disable Auto-Negotiation and set a port's speed and duplex mode manually, you might also need to set the port's MDI/MDI-X setting as well.
- An SFP or GBIC module uses Auto-Negotiation to set its speed and duplex mode. If the SFP or GBIC is paired with a twisted pair port whose speed and duplex mode were set manually, the speed reverts to Auto-Negotiation when an SFP or GBIC module establishes a link with an end node.

7 - Speed
This item is only available when Negotiation is set to Manual. Type 7 to toggle between the following selections:

10 Mbps

100 Mbps

Downloaded from www.Manualslib.com manuals search engine

1000 Mbps (Applies only to 1000Base SFP and GBIC modules. This selection should not be used. An SFP or GBIC module should use Auto-Negotiation to set its speed and duplex mode.)

8 - Duplex
This item is only available when Negotiation is set to Manual. The possible settings are full-duplex and half-duplex.

9 - MDI Crossover
This item is only available when Negotiation is set to Manual.

This selection sets the wiring configuration of a twisted pair port. The configuration can be MDI or MDI-X.

The twisted pair ports on the switch feature auto-MDI/MDI-X. They configure themselves automatically as MDI or MDI-X when connected to an end node. This allows you to use a straight-through twisted pair cable when connecting any network device to a port on the switch.

When a port is using Auto-Negotiation to set its speed and duplex mode, the only available setting for this item is Auto. The port automatically sets its MDI/MDI-X setting.

If you disable Auto-Negotiation on a port and set a port's speed and duplex mode manually, the auto-MDI/MDI-X feature is also disabled. A port where Auto-Negotiation has been disabled defaults to MDI-X. Disabling Auto-Negotiation may require that you manually configure a port's MDI/MDI-X setting using this option or that you use a crossover cable.

The final three parameters on the Port Configuration menu are:

X - Reset Port
This item resets the selected port. For more information, see "Resetting a Port" on page 77.

F - Force Renegotiation
This item prompts the port to autonegotiate with the end node. For more information, see "Forcing Port Renegotiation" on page 78.

D - Set Port Configuration to Defaults
This item resets all port settings to the default values. For more information, see "Resetting the Port Configuration to the Default Settings" on page 79.

5. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Configuring Head of Line Blocking

Head of line (HOL) blocking is a problem that occurs when a port on a switch becomes oversubscribed. An oversubscribed port is receiving more packets from other switch ports than it can transmit in a timely manner.

An oversubscribed port can prevent other ports from forwarding packets to each other because ingress packets on a port are buffered in a First In, First Out (FIFO) manner. If the head of an ingress queue consists of a packet destined for an oversubscribed port, the ingress queue is not able to forward any of its other packets to the egress queues of other ports.

A simplified version of the problem is illustrated in Figure 16. It shows four ports on a switch. Port D is receiving packets from two ports—50% of the ingress traffic on port A and 100% of the ingress traffic on port B. Not only is port A unable to forward packets to port D because the latter's egress queues are filled with packets from port B, but it is also unable to forward traffic to port C because its ingress queue has frames destined to port D that it is unable to forward.



Figure 16. Head of Line Blocking

The HOL Limit parameter can help prevent this problem from occurring. This parameter sets a threshold on the utilization of a port's egress queue. When the threshold for a port is exceeded, the switch signals other ports to discard packets to the oversubscribed port.

For example, referring to the figure above, when the utilization of the storage capacity of port D exceeds the threshold, the switch signals the

Downloaded from www.Manualslib.com manuals search engine

other ports to discard packets destined for port D. Port A drops the D packets, enabling it to once again forward packets to port C.

The number that you enter for this value represents cells. A cell is 128 bytes. The range is 0 to 8191 cells. The default is 682.

To set up head of line blocking, perform the following procedure:

1. From the Main Menu, type **1** to select Port Configuration.

   The Port Configuration menu is shown in Figure 13 on page 62.

2. From the Port Configuration menu, type **1** to select Port Configuration.

   The following prompt is displayed:

   ```
   Enter port-list ->
   ```

3. Enter the number of the port to be configured. You can configure more than one port at a time. You can specify the ports individually (for example, 5,7,22), as a range (for example, 18-23), or both (for example 1,5,14-22).

   The Port Configuration menu is shown in Figure 15 on page 65.

4. From the Port Configuration menu, type **2** to select HOL BLocking Prevention Threshold.

   The following prompt is displayed:

   ```
   Enter HOL Blocking Prevention Threshold (128 byte cells)
   : [1 to 8191] -> 682
   ```

5. Enter the threshold in cells. A cell equals 128 bytes. The range is 1 to 8191 cells. The default is 682.

6. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Configuring Flow Control and Back Pressure

A switch port uses flow control to control the flow of ingress packets from its end node when operating in full-duplex mode.

A port using *flow control* issues a special frame, referred to as a PAUSE frame, as specified in the IEEE 802.3x standard, to stop the transmission of data from an end node. When a port needs to stop an end node from transmitting data, it issues this frame. The frame instructs the end node to cease transmission. The port continues to issue PAUSE frames until it is again ready to receive data from the end node.

The default setting for flow control on a switch port is disabled.

Back pressure performs much the same function as flow control. Both are used by a port to control the flow of ingress packets. Flow control applies to ports operating in full-duplex; back pressure applies to ports operating in half-duplex mode.

When a twisted pair port on the switch operating in half-duplex mode needs to stop an end node from transmitting data, it forces a collision. A collision on an Ethernet network occurs when two end nodes attempt to transmit data using the same data link at the same time. A collision causes the end nodes to stop sending data.

When a switch port needs to stop a half-duplex end node from transmitting data, it forces a collision on the data link, which stops the end node. After the switch is ready to receive data again, the switch stops forcing collisions. This is called *back pressure*.

The default setting for back pressure on a switch port is disabled.

To set up flow control or back pressure, perform the following procedure:

1. From the Main Menu, type **1** to select Port Configuration.

   The Port Configuration menu is shown in Figure 13 on page 62.

2. From the Port Configuration menu, type **1** to select Port Configuration.

   The following prompt is displayed:

   ```
   Enter port-list ->
   ```

3. Enter the number of the port to be configured. You can configure more than one port at a time. You can specify the ports individually (for example, 5,7,22), as a range (for example, 18-23), or both (for example 1,5,14-22).

   The Port Configuration menu is shown in Figure 15 on page 65.

Downloaded from www.Manualslib.com manuals search engine

4. From the Port Configuration menu, type **3** to select Flow Control.

   The Flow Control menu is shown in Figure 17.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                      Flow Control
Configuring Port 11
1 - Flow Control (Full-Duplex) Status .... Disabled
2 - Flow Control Threshold ............... 7935 cells

3 - Back Pressure (Half-Duplex) Status ... Disabled
4 - Back Pressure Threshold ............... 7935 cells

R - Return to Previous Menu

Enter your selection?
```

Figure 17. Flow Control Menu

5. Type **1** to select FLow Control (Full-Duplex) Status to enable or disable flow control. The possible settings are:

   Disabled -No flow control on the port. This is the default setting.

   Enabled - Flow control is activated. This setting is appropriate only when the end node connected to the port is also using flow control.

   Auto - The port uses flow control only if it detects that the end node is using it.

6. Type **2** to select Flow Control Threshold which specifies the threshold for flow control. The threshold is specified in cells. A cell equals 128 bytes. The range is 1 to 7935. The default is 7935 cells.

7. Type **3** to select Back Pressure (Half-Duplex) Status which enables or disables back pressure on a port. Possible settings are:

   Disabled - The port does not use back pressure. This is the default setting.

   Enabled - The port uses back pressure.

8. Type **4** to select Back Pressure Threshold. This selection specifies the threshold for backpressure. The threshold is specified in cells. A cell equals 128 bytes. The range is 1 to 7935. The default is 7935 cells.

9. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Configuring Port Filtering

If the performance of your network is affected by heavy traffic, you can use these parameters to restrict ingress and egress broadcast packets as well as unknown unicast and multicast packets forwarded by a port. Activating this feature on a port causes the port to discard all packets of the type you specified. For example, you might configure a port to discard all ingress and egress broadcast packet or perhaps just unknown unicast egress packets. The default setting for each filter is disabled.

To set up filtering, perform the following procedure:

1. From the Main Menu, type **1** to select Port Configuration.

   The Port Configuration menu is shown in Figure 13 on page 62.

2. From the Port Configuration menu, type **1** to select Port Configuration.

   The following prompt is displayed:

   ```
   Enter port-list ->
   ```

3. Enter the number of the port to be configured.

   The Port Configuration menu is shown in Figure 15 on page 65.

4. From the Port Configuration menu, type **4** to select Filtering.

   The Filtering menu is shown in Figure 18.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                          11:20:02 02-Mar-2005
                        Filtering
 Configuring Port 11
 1 - Unknown Unicast Ingress Filtering ........... Disabled
 2 - Unknown Unicast Egress Filtering ............ Disabled

 3 - Unknown Multicast Ingress Filtering ......... Disabled
 4 - Unknown Multicast Egress Filtering .......... Disabled

 5 - Broadcast Ingress Filtering ................. Disabled
 6 - Broadcast Egress Filtering .................. Disabled

 R - Return to Previous Menu

 Enter your selection?
```

Figure 18. Filtering Menu

Downloaded from www.Manualslib.com manuals search engine

5. From the Filtering menu, type **1** to toggle Unknown Unicast Ingress Filtering between Disabled and Enabled.

6. Type **2** to toggle Unknown Unicast Egress Filtering between Disabled and Enabled.

7. Type **3** to toggle Unknown Multicast Ingress Filtering between Disabled and Enabled.

8. Type **4** to toggle Unknown Multicast Egress Filtering between Disabled and Enabled.

9. Type **5** to toggle Broadcast Ingress Filtering between Disabled and Enabled.

10. Type **6** to toggle Broadcast Egress Filtering between Disabled and Enabled.

11. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Setting Up Rate Limiting

The rate limiting feature allows you to set the maximum number of ingress packets the port accepts each second. Packets exceeding the threshold are discarded. You can enable rate limiting and set a rate independently for unknown unicast, multicast, and broadcast packets.

To set rate limiting, perform the following procedure:

1. From the Main Menu, type **1** to select Port Configuration.

   The Port Configuration menu is shown in Figure 13 on page 62.

2. From the Port Configuration menu, type **1** to select Port Configuration.

   The following prompt is displayed:

   ```
   Enter port-list ->
   ```

3. Enter the number of the port to be configured.

   The Port Configuration menu is shown in Figure 15 on page 65.

4. From the Port Configuration menu, type **5** to select Rate Limiting.

   The Rate Limiting menu is shown in Figure 19.

```
                Allied Telesis AT-9424T/SP - AT-S63
                           Marketing
User: Manager                                    11:20:02 02-Mar-2005
                            Rate Limiting
Configuring Port 11
1 - Unknown Unicast Rate Limiting Status ... Disabled
2 - Unknown Unicast Rate ................... 262143 packets/second

3 - Multicast Rate Limiting Status ......... Disabled
4 - Multicast Rate ......................... 262143 packets/second

5 - Broadcast Rate Limiting Status ......... Disabled
6 - Broadcast Rate ......................... 262143 packets/second

R - Return to Previous Menu

Enter your selection?
```

Figure 19. Rate Limiting Menu

5. To control unknown unicast packets, do the following:

   a. From the Rate Limiting menu, type **1** to toggle Unknown Unicast Rate Limiting Status between Enabled and Disabled.

Downloaded from www.Manualslib.com manuals search engine

b. If you enabled the feature, type **2** to select Unknown Unicast Rate.

The following prompt is displayed:

```
Enter the Rate Limit (packets/second):[0 to 262143]->
```

c. Enter a number for the rate limit.

6. To control multicast packets, do the following:

a. Type **3** to toggle Multicast Rate Limiting Status between Enabled and Disabled.

b. If you enabled the feature, type **4** to select Multicast Rate.

The following prompt is displayed:

```
Enter the Rate Limit (packets/second):[0 to 262143]->
```

c. Enter a number for the rate limit.

7. To control broadcast packets, do the following:

a. Type **5** to toggle Broadcast Rate Limiting Status between Enabled and Disabled.

b. If you enabled the feature, type **6** to select Broadcast Rate.

The following prompt is displayed:

```
Enter the Rate Limit (packets/second):[0 to 262143]->
```

c. Enter a number for the rate limit.

8. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Resetting a Port

Resetting a port is useful in situations where a port is having problems establishing a valid connection to its end node. Resetting a port does not change any of its parameter settings.

To reset a port, perform the following procedure:

1. From the Main Menu, type **1** to select Port Configuration.

   The Port Configuration menu is shown in Figure 13 on page 62.

2. From the Port Configuration menu, type **1** to select Port Configuration.

   The following prompt is displayed:

   ```
   Enter port-list ->
   ```

3. Enter the number of the port you want to reset. You can reset more than one port at a time. You can specify the ports individually (for example, 5,7,22), as a range (for example, 18-23), or both (for example 1,5,14-22).

   The Port Configuration menu is shown in Figure 15 on page 65.

4. From the Port Configuration menu, type **X** to select Reset Port.

Downloaded from www.Manualslib.com manuals search engine

Forcing Port Renegotiation

Port renegotiation prompts a port operating in Auto-Negotiation to renegotiate its speed and duplex mode with its end node. This option is useful if you believe that a port and end node are not operating at the same speed and duplex mode.

To force port renegotiation, perform the following procedure:

1. From the Main Menu, type **1** to select Port Configuration.

   The Port Configuration menu is shown in Figure 13 on page 62.

2. From the Port Configuration menu, type **1** to select Port Configuration.

   The following prompt is displayed:

   ```
   Enter port-list ->
   ```

3. Enter the number of the port to renegotiate its speed and duplex mode. You can reset more than one port at a time. You can specify the ports individually (for example, 5,7,22), as a range (for example, 18-23), or both (for example 1,5,14-22).

   The Port Configuration menu is shown in Figure 15 on page 65.

4. From the Port Configuration menu, type **F** to select Force Renegotiation.

Downloaded from www.Manualslib.com manuals search engine

Resetting the Port Configuration to the Default Settings

You can return the parameters settings of a port to the default values.

To reset a port's settings to the default settings, perform the following procedure:

1. From the Main Menu, type **1** to select Port Configuration.

   The Port Configuration menu is shown in Figure 13 on page 62.

2. From the Port Configuration menu, type **1** to select Port Configuration.

   The following prompt is displayed:

   ```
   Enter port-list ->
   ```

3. Enter the number of the port to be reset to its default settings. You can reset more than one port at a time. You can specify the ports individually (for example, 5,7,22), as a range (for example, 18-23), or both (for example 1,5,14-22).

   The Port Configuration menu is shown in Figure 15 on page 65.

4. From the Port Configuration menu, type **D** to select Set Port Configuration to Defaults.

Downloaded from www.Manualslib.com manuals search engine

Displaying Port Statistics

To display Ethernet port statistics, perform the following procedure:

1. From the Main Menu, type **1** to select Port Configuration.

   The Port Configuration menu is shown in Figure 13 on page 62.

2. From the Port Configuration menu, type **3** to select Port Statistics.

   The Port Statistics menu is shown in Figure 20.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                          11:20:02 02-Mar-2005
                      Port Statistics

 1 - Display Port Statistics
 2 - Clear Port Statistics

 R - Return to Previous Menu

 Enter your selection?
```

Figure 20. Port Statistics Menu

3. From the Port Statistics menu, type **1** to select Display Port Statistics.

   The following prompt is displayed:

   ```
   Enter port-list:
   ```

4. Enter the port whose statistics you want to view. You can specify more than one port at a time.

Downloaded from www.Manualslib.com manuals search engine

The Display Port Statistics menu is shown in Figure 21.

```
                Allied Telesis AT-9424T/SP - AT-S63
                            Marketing
User: Manager                                   11:20:02 02-Mar-2005
                      Display Port Statistics

 Port 6

 Bytes Rx ......... 983409801      Bytes Tx ......... 965734443
 Frames Rx ........ 815423         Frames Tx ........ 691396
 Bcast Frames Rx... 107774         Bcast Frames Tx .. 1853
 Mcast Frames Rx .. 11429          Mcast Frames Tx .. 0
 Frames 64 ........ 110509         Frames 65-127 .... 15192
 Frames 128-255 ... 1928           Frames 256-511 ... 442
 Frames 512-1023 .. 157796         Frames 1024-1518.. 1221024
 CRC Error ........ 0              Jabber ........... 0
 No. of Rx Errors . 0              No. of Tx Errors . 0
 UnderSize Frames . 0              OverSize Frames .. 0
 Fragments ........ 0              Collision ........ 0
 Frames 1519-1522 . 0              Dropped Frames ... 0

 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 21. Display Port Statistics Menu

The Display Port Statistics menu provides the following information:

Bytes Rx
Number of bytes received by the port.

Bytes Tx
Number of bytes transmitted from the port.

Frames Rx
Number of frames received by the port.

Frames Tx
Number of frames transmitted from the port.

Bcast Frames Rx
Number of broadcast frames received by the port.

Bcast Frames Tx
Number of broadcast frames transmitted from the port.

Mcast Frames Rx
Number of multicast frames received by the port.

Mcast Frames Tx
Number of multicast frames transmitted from the port.

Downloaded from www.Manualslib.com manuals search engine

Frames 64
Frames 65-127
Frames 128-255
Frames 256-511
Frames 512-1023
Frames 1024-1518
Frames 1519-1522
Number of frames transmitted from the port, grouped by size.

CRC Error
Number of frames with a cyclic redundancy check (CRC) error but with the proper length (64-1518 bytes) received on the port.

Jabber
Number of occurrences of corrupted data or useless signals appearing on the port.

No. of Rx Errors
Number of receive errors.

No. of Tx Errors
Number of transmit errors.

Undersize Frames
Number of frames that were less than the minimum length specified by IEEE 802.3 (64 bytes including the CRC) received on the port.

Oversize Frames
Number of frames exceeding the maximum specified by IEEE 802.3 (1518 bytes including the CRC) received on the port.

Fragments
Number of undersized frames, frames with alignment errors, and frames with frame check sequence (FCS) errors (CRC errors) received on the port.

Collision
Number of collisions that have occurred on the port.

Dropped Frames
Number of frames successfully received and buffered by the port, but discarded and not forwarded.

Downloaded from www.Manualslib.com manuals search engine

Clearing Port Statistics

To clear the Ethernet port statistics and reset them to "0", perform the following procedure:

1. From the Main Menu, type **1** to select Port Configuration.

   The Port Configuration menu is shown in Figure 13 on page 62.

2. From the Port Configuration menu, type **3** to select Port Statistics.

   The Port Statistics menu is shown in Figure 20 on page 80.

3. Type **2** to select Clear Statistics.

   The statistics are reset to "0" and the statistics gathering starts again.

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Chapter 3

Enhanced Stacking

This chapter explains the enhanced stacking feature. The sections in this chapter include:

- ❒ “Setting a Switch’s Enhanced Stacking Status” on page 86
- ❒ “Selecting a Switch in an Enhanced Stack” on page 88
- ❒ “Returning to the Master Switch” on page 91
- ❒ “Displaying the Enhanced Stacking Status” on page 92

Downloaded from www.Manualslib.com manuals search engine

Setting a Switch's Enhanced Stacking Status

The enhanced stacking status of the switch can be master, slave, or unavailable. Each status is described below:

- Master switch - The master switch is your entry point for managing the switches of a stack. Starting a local or remote management session on a master switch gives you management access to all the switches in the stack.
- Slave switch - A slave switch can be remotely managed through a master switch or independently, such as through a local session.
- Unavailable - A switch with an unavailable stacking status is not part of an enhanced stack must be managed independently, either locally or remotely.

Note
The default setting for a switch is slave.

Note
You cannot change the stacking status of a switch through enhanced stacking. You must access the switch directly, either through a local or remote session, to change its stacking status.

To adjust a switch's enhanced stacking status, perform the following procedure:

1. From the Main Menu, type **8** to select Enhanced Stacking. The Enhanced Stacking menu is shown in Figure 22.

```
            Allied Telesis AT-9424Ts - AT-S63
                        Marketing
User: Manager                              11:20:02 02-Mar-2005
                     Enhanced Stacking

1 - Switch State-(M)aster/(S)lave/(U)navailable.... Master
2 - Stacking Services

R - Return to Previous Menu

Enter your selection?
```

Figure 22. Enhanced Stacking Menu

The menu displays the current status of the switch at the end of selection "1 - Switch State." For example, the switch's current status in the figure above is master.

Downloaded from www.Manualslib.com manuals search engine

Note
Item 2, Stacking Services, is only displayed on master switches.

2. To change a switch's stacking status, type **1** to select Switch State.

   The following prompt is displayed.

   ```
   Enter new setup (M/S/U) ->
   ```

3. Type **M** to change the switch to a master switch, **S** to make it a slave switch, or **U** to make the switch unavailable. Press Return.

   A change to the status is immediately activated on the switch.

4. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Selecting a Switch in an Enhanced Stack

In order to manage a switch other than the master switch in an enhanced stack, you must instruct the master switch to poll the common VLAN for the other switches and then select the switch. You can manage only one switch at a time

To select a switch in an enhanced stack, perform the following procedure:

1. From the Main Menu, type **8** to select Enhanced Stacking.

   The Enhanced Stacking menu is shown in Figure 22 on page 86.

2. From the Enhanced Stacking menu, type **2** to select Stacking Services.

   Note
   Item 2, Stacking Services, is only displayed on master switches.

   The Stacking Services menu is shown in Figure 23.

```
                  Allied Telesis AT-9424Ts - AT-S63
                              Marketing
User: Manager                                        11:20:02 02-Mar-2005
                           Stacking Services

                              Switch          Software       Switch
Num   MAC Address    Name     Mode            Version        Model
-------------------------------------------------------------------------

1 - Get/Refresh List of Switches
2 - Sort Switches in New Order
3 - Access Switch
4 - Load Image/Bootloader File
5 - Load Configuration File

R - Return to Previous Menu

Enter your selection?
```

Figure 23. Stacking Services Menu

3. From the Stacking Services menu, type **1** to select Get/Refresh List of Switches.

Downloaded from www.Manualslib.com manuals search engine

The master switch polls the common subnet for the slave and master switches that are members of the enhanced stack and displays a list of the switches in the Stacking Services menu. An example is shown in Figure 24.

```
                    Allied Telesis AT-9424Ts - AT-S63
                                Marketing
User: Manager                                          11:20:02 02-Mar-2005
                              Stacking Services

                                                Switch  Software    Switch
Num  MAC Address        Name                   Mode    Version     Model
-------------------------------------------------------------------------
01   00:00:00:12:34:30  Local Users            Slave   S63 v2.0.0  AT-9424T/SP
02   00:30:84:f3:b4:60  Engineering            Slave   S63 v2.0.0  AT-9424T/GB
03   00:30:84:54:02:60  Finance                Slave   S62 v1.0.0  AT-8524M

1 - Get/Refresh List of Switches
2 - Sort Switches in New Order
3 - Access Switch
4 - Load Image/Bootloader File
5 - Load Configuration File

R - Return to Previous Menu

Enter your selection?
```

Figure 24. Stacking Services Menu With List of Switches

The list does not include the master switch where you started the management session, nor any switches with an enhanced stacking status of Unavailable.

By default, the switches are sorted in the menu by MAC address. You can sort the switches by name by selecting option 2, Sort Switches in New Order.

Note
Item 4, Load Image/Bootloader, uploads the AT-S63 image from the master switch to another AT-9400 Switch in the enhanced stack, as explained in "Uploading the AT-S63 Image File Switch to Switch" on page 176. Item 5, Load Configuration File, allows you to upload a configuration file from a master switch to another AT-9400 Switch, as explained in "Uploading an AT-S63 Configuration File Switch to Switch" on page 179.

4. To manage a new switch, type **3** to select Access Switch.

Downloaded from www.Manualslib.com manuals search engine

A prompt similar to the following is displayed:

```
Enter the switch number -> [1 to 24]
```

5. Type the number of the switch in the list you want to manage.
6. Enter the appropriate username and password for the switch.

   The command line interface of the selected switch is displayed. You now can manage the switch. Any management tasks you perform affect only the selected switch.

Downloaded from www.Manualslib.com manuals search engine

Returning to the Master Switch

When you are finished managing a slave switch, return to the Main Menu of the switch and type **Q** for Quit. This returns you to the Stacking Services menu on the master switch where you started the management session. You can either select another switch from the list to manage or, to manage the master switch, type **R** twice to return to the master switch's Main Menu.

Downloaded from www.Manualslib.com manuals search engine

Displaying the Enhanced Stacking Status

To view the stacking status of a switch in a stack, perform the following procedure:

1. From the Main Menu, type **8** to select Enhanced Stacking.

   The Enhanced Stacking menu is shown in Figure 25.

```
            Allied Telesis AT-9424Ts - AT-S63
                        Marketing
User: Manager                            11:20:02 02-Mar-2005
                     Enhanced Stacking
1 - Switch State-(M)aster/(S)lave/(U)navailable.... Slave

R - Return to Previous Menu

Enter your selection?
```

Figure 25. Enhanced Stacking Menu

The menu shows the enhanced stacking status of the switch you selected.

Downloaded from www.Manualslib.com manuals search engine

Chapter 4

SNMPv1 and SNMPv2c

This chapter explains how to activate SNMP management on the switch and how to create, modify, and delete SNMPv1 and SNMPv2c community strings. Sections in the chapter include:

- ❒ “Enabling or Disabling SNMP Management” on page 94
- ❒ “Setting the Authentication Failure Trap” on page 95
- ❒ “Creating an SNMP Community String” on page 96
- ❒ “Modifying a Community String” on page 99
- ❒ “Deleting a Community String” on page 103
- ❒ “Displaying the SNMP Community Strings” on page 104

Downloaded from www.Manualslib.com manuals search engine

Enabling or Disabling SNMP Management

To enable or disable SNMP management for the switch, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **5** to select SNMP Configuration.

   The SNMP Configuration menu is shown in Figure 26.

```
            Allied Telesis AT-9424Ts - AT-S63
                        Marketing
User: Manager                          11:20:02 02-Mar-2005
                     SNMP Configuration
 1 - SNMP Status ....................... Disabled
 2 - Authentication Failure Trap Status ..Disabled
 3 - Configure SNMPv1 & SNMPv2c Community
 4 - Display SNMPv1 & SNMPv2c Community
 5 - Configure SNMPv3 Table
 6 - Display SNMPv3 Table

 R - Return to Previous Menu

 Enter your selection?
```

Figure 26. SNMP Configuration Menu

3. From the SNMP Configuration menu, type **1** to toggle the SNMP Status option between its two settings of Enabled and Disabled. When set to Disabled, the default, you cannot manage the switch using SNMP. When set to Enabled, you can manage the switch using SNMP.

   A change to the SNMP status is immediately activated on the switch.

4. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Setting the Authentication Failure Trap

As mentioned in the SNMP Overview section in this chapter, a trap is a message sent by the switch to a management workstation or server to signal an operating event, such as when the device is reset.

An authentication failure trap is similar to other the traps. It too signals an operating event on the switch. But this trap is somewhat special because it relates to SNMP management. A switch that sends this trap could be indicating an attempt by someone to gain unauthorized management access using an SNMP application program to the switch. There are two events that can cause a switch to send this trap:

- An SNMP management station attempts to access the switch using an incorrect or invalid community name.
- An SNMP management station tried to access a closed access community string, to which its IP address is not assigned.

Given the importance of this trap to the protection of your switch, the management software allows you to disable and enable it separately from the other traps. If you enable it, the switch will send this trap if either of the above events occur. If you disable it, the switch will not send this trap. The default is disabled.

If you enable this trap, be sure to add one or more IP addresses of trap receivers to the community strings so that the switch will know where to send the trap if it needs to.

To enable or disable the authentication trap, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **5** to select SNMP Configuration.

   The SNMP Configuration menu is shown in Figure 26 on page 94.

3. From the SNMP Configuration menu, type **2** to toggle Authentication Failure Trap Status between enabled and disabled. The default is disabled.

4. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Creating an SNMP Community String

To create a new SNMP community string, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **5** to select SNMP Configuration.

   The SNMP Configuration menu is shown in Figure 26 on page 94.

3. From the SNMP Configuration menu, type **3** to select Configure SNMPv1 & SNMPv2c Community.

   The Configure SNMPv1 & SNMPv2c Community menu is shown in Figure 27.

```
                    Allied Telesis AT-9424Ts - AT-S63
                                Marketing
User: Manager                                          11:20:02 02-Mar-2005
                   Configure SNMPv1 & SNMPv2c Community
 Community Name  AccessMode  Status   OpenAcc Manager IP Addr Trap Receiver IP
 ------------------------------------------------------------------------------
 Private         Read|Write  Enabled  Yes
 Public          Read        Enabled  Yes

 1 - Create SNMP Community
 2 - Delete SNMP Community
 3 - Modify SNMP Community

 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 27. Configure SNMPv1 & SNMPv2c Community Menu

The table in the menu lists the current community strings on the switch and their attributes. The columns in the table are defined here:

Community Name
The name of a community string.

Access Mode
The access mode of a community string. A string with a Read Only access mode permits the viewing of the MIB objects on the switch. A string with a Read/Write access mode permits both viewing and changing the SNMP MIB objects.

Downloaded from www.Manualslib.com manuals search engine

Status
The operating status of a community string. Enabled means the string is available for use and Disabled means it is unavailable.

OpenAcc
The access status of a community string. A string with a status of Yes has an open status and can be used by any management workstation. A string with a status of No has a closed status and can only be used by those workstations whose IP addresses are assigned to the string.

Manager IP Addr
The IP addresses of management workstations permitted to use a string with a closed access status.

Trap Receiver IP
The IP addresses of trap receivers to receive traps from the switch.

4. To create a new community string, type **1** to select Create SNMP Community.

   The following prompt is displayed:

   ```
   Enter SNMP Community Name:
   ```

5. Enter the new SNMP community string. The name can be from one to fifteen alphanumeric characters. Spaces are allowed.

   The following prompt is displayed:

   ```
   Enter Access Mode [R-Read Only, W-Read/Write]:
   ```

6. Specify the access mode for the new SNMP community string. If you specify Read, the community string will only allow you to view the MIB objects on the switch. If you specify Read/Write, the community string will allow you to both view and change the SNMP MIB objects on the switch.

   The following prompt is displayed:

   ```
   Enter Open Access Status [Y-Yes, N-No]:
   ```

7. Specify the open access status. If you enter Yes, any network manager who knows the community string can use it. If you respond with No, making it closed access, only those management workstations whose IP addresses you assign to the community string can use it.

   The following prompt is displayed:

   ```
   Enter SNMP Manager IP Addr:
   ```

8. If in Step 7 you responded with No making this a closed community string, specify the IP address of the management workstation that can use the string. A community string can have up to eight IP addresses of

Downloaded from www.Manualslib.com manuals search engine

management workstations. But you can assign only one to it initially with this procedure. To add additional IP addresses, refer to “Modifying a Community String” on page 99.

If you assigned the community string an access status of open, leave this field blank by pressing Return.

The following prompt is displayed:

```
Enter Trap Receiver IP Addr:
```

9. If you want the switch to send traps to a management workstation or server, enter the IP address of the node here. A community string can have up to eight IP addresses of trap receivers. But you can assign only one initially with this procedure. To add additional IP addresses, refer to “Modifying a Community String” on page 99.

   If you do not want to add a IP address of a trap receiver to the community string, leave this field blank by pressing Return.

   The AT-S63 Management Software creates the new community string and adds it to the list in the SNMP Community menu. A new community string is immediately available for use to manage the switch.

10. If desired, repeat this procedure starting with Step 4 to create additional community strings.

11. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Modifying a Community String

To modify a community string, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **5** to select SNMP Configuration.

   The SNMP Configuration menu is shown in Figure 26 on page 94.

3. From the SNMP Configuration menu, type **3** to select Configure SNMPv1 &SNMPv2c Community.

   The Configure SNMPv1 &SNMPv2c Community menu in shown in Figure 27 on page 96.

4. From the Configure SNMPv1 &SNMPv2c Community menu, type **3** to select Modify SNMP Community.

   The Modify SNMP Community menu is shown in Figure 28.

```
                    Allied Telesis AT-9424Ts - AT-S63
                                Marketing
User: Manager                                              11:20:02 02-Mar-2005
                    Modify SNMPv1 & SNMPv2c Community
Community Name   AccessMode  Status   OpenAcc  Manager IP Addr  Trap Rec IP
-------------------------------------------------------------------------------
Private          Read|Write  Enabled  Yes
Public           Read        Enabled  Yes
Private          Read|Write  Enabled  Yes
Public           Read        Enabled  Yes

1 - Add Attributes to Community
2 - Delete Attributes from Community
3 - Set Community Access Mode
4 - Set Community Status
5 - Set Community Open Access

U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 28. Modify SNMP Community Menu

This menu lists the current community strings on the switch and their attributes. For attribute definitions, refer to "Creating an SNMP Community String" on page 96.

Downloaded from www.Manualslib.com manuals search engine

The menu options are described below:

1 - Add Attributes to Community
If a community string has a closed access mode, you can use this selection to add new IP addresses of management workstations that can use the string. You can also use this option to add IP addresses of new trap receivers. To use this option, do the following:

a. From the Modify SNMP Community menu, type **1** to select Add Attributes to Community. The following prompt is displayed:

```
Enter SNMP Community Name:
```

b. Enter the community string you want to modify. Community strings are case sensitive. This prompt is displayed:

```
Enter SNMP Manager IP Addr:
```

c. If you are modifying a community string with a closed access mode and you want to add an IP address of a management workstation to it, enter the workstation's IP address at the prompt. Otherwise, just press Return. A community string can have a maximum of eight IP addresses, but you can add only one at a time with this procedure. This prompt is displayed:

```
Enter Trap Receiver IP Addr:
```

d. If you want the switch to send traps to a trap receiver, enter the IP address of the receiver at this prompt. Otherwise, just press Return.

   The community string is modified and the Modify SNMP Configuration menu is displayed again.

e. Repeat this procedure to modify other community strings.

f. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

2 - Delete Attributes from Community
Use this option to delete an IP address of a management workstation or a trap receiver from a community string. To use this option, do the following:

a. From the Modify SNMP Community menu, type **2** to select Delete Attributes from Community. The following prompt is displayed:

```
Enter SNMP Community Name:
```

b. Enter the community string you want to modify. Community strings are case sensitive. This prompt is displayed:

Downloaded from www.Manualslib.com manuals search engine

```
Enter SNMP Manager IP Addr:
```

c. If you want to remove the IP address of a management workstation from the community string, enter the IP address at the prompt. Otherwise, just press Return. This prompt is displayed:

```
Enter Trap Receiver IP Addr:
```

d. If you want to remove the IP address of a trap receiver from the community string, enter the IP address at the prompt. Otherwise, just press Return.

e. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

3 - Set Community Access Mode
Use this option to change a community string's Read or Read/Write status. To use the selection, do the following:

a. From the Modify SNMP Community menu, type **3** to select Set Community Access Mode. The following prompt is displayed:

```
Enter SNMP Community Name:
```

b. Enter the community string you want to modify. Community strings are case sensitive. The following prompt is displayed:

```
Enter Access Mode [R-Read Only, W-Read/Write]:
```

c. Type **R** to change the string's status to Read only, or **W** for Read/Write. This confirmation prompt is displayed:

```
Do you want to change this Community Access Mode? (Y/
N): [Yes/No] ->
```

d. Type **Y** to change the string's access mode or **N** to cancel the change.

e. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

4 - Set Community Status
Use this option to enable or disable a community string. When disabled, no one can use the community string to access the switch. To use the selection, do the following:

a. From the Modify SNMP Community menu, type **4** to select Set Community Status. The following prompt is displayed:

```
Enter SNMP Community Name:
```

b. Enter the community string you want to modify. Community strings are case sensitive. The following prompt is displayed:

Downloaded from www.Manualslib.com manuals search engine

```
Enter Community Status [E-Enable, D-Disable]:
```

c. Type **E** to enable the community string or **D** to disable it. This confirmation prompt is displayed:

```
Do you want to change Community Status? (Y/N): [Yes/No] ->
```

d. Type **Y** to change the string's status or **N** to cancel the change.

e. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

5 - Set Community Open Status
Use this selection to change a string's open status. A string with an open status can be used by any network administrator. A string with a closed status can only be used from management workstations whose IP addresses are assigned to the community string. To use the option, do the following:

a. From the Modify SNMP Community menu, type **5** to select Set Community Open Status. The following prompt is displayed:

```
Enter SNMP Community Name:
```

b. Enter the community string you want to modify. Community strings are case sensitive. The following prompt is displayed:

```
Enter Open Access Status [Y-Yes, N-No]:
```

c. Type **Y** to assign the string an open status or **N** to assign it a closed status. This confirmation prompt is displayed:

```
Do you want to change Open Access Status? (Y/N): [Yes/No] ->
```

d. Type **Y** to change the string's open status or **N** to cancel the change.

e. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Deleting a Community String

To delete an SNMPv1 or SNMPv2c community string, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **5** to select SNMP Configuration.

   The SNMP Configuration menu is shown in Figure 26 on page 94.

3. From the SNMP Configuration menu, type **3** to select Configure SNMPv1 &SNMPv2c Community.

   The Configure SNMPv1 &SNMPv2c Community menu is shown in Figure 27 on page 96.

4. From the Configure SNMPv1 &SNMPv2c Community menu, type **2** to select Delete SNMP Community. This prompt is displayed:

   ```
   Enter Trap Receiver IP Addr:
   ```

5. Enter the community string to be deleted. Community strings are case sensitive. A confirmation prompt is displayed.

6. Type Y for yes to delete the string or N for no to cancel the procedure.

   If you selected yes, the community string is immediately deleted from the switch.

7. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Displaying the SNMP Community Strings

To display the attributes of all the SNMP community strings on the switch, use the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **5** to select SNMP Configuration.

   The SNMP Configuration menu is shown in Figure 26 on page 94.

3. From the SNMP Configuration menu, type **4** to select Display SNMPv1 & SNMPv2c Community.

   The Display SNMPv1 & SNMPv2c Community menu is shown in Figure 29.

```
                    Allied Telesis AT-9424Ts - AT-S63
                              Marketing
User: Manager                                          11:20:02 02-Mar-2005
                    Display SNMPv1 & SNMPv2c Community

 Community Name Access Mode  Status    OpenAcc  Manager IP Addr  Trap Receiver IP
 ================================================================================
 Private125     Read|Write   Enabled   No       147.41.11.30     147.45.16.70
                                                 147.45.16.80     147.45.16.80
 PublicATI78    Read Only    Enabled   No       147.41.11.12     147.42.22.22
                                                 147.44.16.86     147.45.16.86
                                                 147.45.16.88     147.45.16.88
                                                 147.45.16.90     147.45.16.90
 HighSchool2    Read|Write   Enabled   No       147.45.10.80     147.45.10.80

 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 29. Display SNMP Community Menu

For attribute definitions, refer to “Creating an SNMP Community String” on page 96.

Downloaded from www.Manualslib.com manuals search engine

Chapter 5

MAC Address Table

This chapter contains the procedures for viewing the static and dynamic MAC address table. It also explains how to add static MAC addresses to the table.

This chapter contains the following sections:

- ❒ “Displaying the MAC Address Tables” on page 106
- ❒ “Adding Static Unicast and Multicast MAC Addresses” on page 110
- ❒ “Deleting Unicast and Multicast MAC Addresses” on page 112
- ❒ “Deleting All Dynamic MAC Addresses” on page 113
- ❒ “Changing the Aging Time” on page 114

Downloaded from www.Manualslib.com manuals search engine

Displaying the MAC Address Tables

The AT-S63 Management Software has two menu selections for displaying the MAC addresses of a switch. One selection displays the static and dynamic unicast MAC addresses while the other displays the static and dynamic multicast addresses.

To display the MAC address tables, perform the following procedure:

1. From the Main Menu, type **4** to select MAC Address Tables. The MAC Address Tables menu is shown in Figure 30.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                           11:20:02 02-Mar-2005
                     MAC Address Tables

1 - MAC Address Aging Time ......... 300 second(s)
2 - MAC Addresses Configuration
3 - Display Unicast MAC Addresses
4 - Display Multicast MAC Addresses

R - Return to Previous Menu

Enter your selection?
```

Figure 30. MAC Address Tables Menu

2. From the MAC Address Tables menu, type **3** to select Display Unicast MAC Addresses or **4** to select Display Multicast MAC Addresses. The Display Unicast MAC Addresses menu is shown in Figure 31. The Display Multicast MAC Addresses menu contains the same selections.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                           11:20:02 02-Mar-2005
                Display Unicast MAC Addresses

1 - Display All
2 - Display Static
3 - Display Dynamic
4 - Display by Port
5 - Display Specified MAC
6 - Display by VLAN ID
7 - Display on Base Ports

R - Return to Previous Menu

Enter your selection?
```

Figure 31. Display Unicast MAC Addresses Menu

Downloaded from www.Manualslib.com manuals search engine

Choose one of the following display types.

1 - Display All
This selection displays all dynamic addresses learned on the ports of the switch and all static addresses that have been assigned to the ports. An example of a unicast MAC address table is shown in Figure 32.

```
              Allied Telesis AT-9424T/SP - AT-S63
                          Marketing
User: Manager                                  11:20:02 02-Mar-2005
                            Display All
                              Page 1
 Total Number of MAC Addresses: 121
MAC Address         Port   VLANID   Type
-------------------------------------------------------------
01:80:C1:00:02:01   0      0        Static (fixed, non-aging)
00:a0:d2:18:1a:c8   1      1        Dynamic
00:a0:c4:16:3b:80   2      1        Dynamic
00:a0:12:c2:10:c6   3      1        Dynamic
00:a0:c2:09:10:d8   4      1        Dynamic
00:a0:33:43:a1:87   5      1        Dynamic
00:a0:12:a7:14:68   6      1        Dynamic
00:a0:d2:22:15:10   7      1        Dynamic
00:a0:d4:18:a6:89   8      1        Dynamic

N - Next Page
U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 32. Display All Menu - Unicast MAC Addresses

Note
The first address in the unicast MAC address table is the address of the switch.

A unicast MAC address table contains the following columns of information:

MAC
The static or dynamic unicast MAC address.

Port
The port where the address was learned or assigned. The MAC address with port 0 is the address of the switch.

VLAN ID
The ID number of the VLAN where the port is an untagged member.

Type
The type of the address: static or dynamic.

Downloaded from www.Manualslib.com manuals search engine

An example of a multicast MAC address table is shown in Figure 33.

```
                Allied Telesis AT-9424T/SP - AT-S63
                           Marketing
User: Manager                                      11:20:02 02-Mar-2005
                              Display All
                                Page 1
Total Number of MCAST MAC Addresses: 1
MAC Address         VLANID  Type    Port Maps (U:Untagged T:Tagged)
-------------------------------------------------------------------
01:00:51:00:00:01   1       Static  U:1-4
                                    T:

U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 33. Display All Menu - Multicast MAC Addresses

The multicast MAC address table contains the following columns of information:

MAC Address
The static or dynamic multicast MAC address.

VLAN ID
The ID number of the VLAN where the port is an untagged member.

Type
The type of the address: static or dynamic.

Port Maps
The tagged and untagged ports on the switch that are members of a multicast group. This column is useful in determining which ports belong to different groups.

The other selections on the menu are:

2 - Display Static
This selection displays only the static addresses assigned to the ports on the switch.

3 - Display Dynamic
This selection displays only the dynamic addresses learned on the ports on the switch.

4 - Display by Port
This selection displays the dynamic and static MAC addresses of a particular port. When you select this option, you are prompted for a port number. You can specify more than one port at a time.

Downloaded from www.Manualslib.com manuals search engine

5 - Display Specified MAC
This selection displays the port number on which a MAC address was assigned or learned.

If you want to know on which port a particular MAC address was learned, you can display the MAC address table and scroll through the list looking for the MAC address. But if the switch is part of a large network, finding the address could prove difficult.

When you use the Display Specified MAC selection, you specify the MAC address and the AT-S63 Management Software automatically locates the port on the switch where the device is connected.

6 - Display by VLAN ID
Displays all the static and dynamic addresses learned on the tagged and untagged ports of a specific VLAN. When you select this option, you are prompted for the VLAN ID number of the VLAN. You can specify only one VLAN at a time

7 - Display on Base Ports
This selection displays the static and dynamic MAC addresses learned on the base ports on the AT-9400 Switch. It does not display any addresses assigned or learned on any uplink ports.

Downloaded from www.Manualslib.com manuals search engine

Adding Static Unicast and Multicast MAC Addresses

This section contains the procedure for adding static unicast and multicast MAC addresses to the switch. You can assign up to 255 static addresses per port on the AT-9400 Switch.

To add a static MAC address, perform the following procedure:

1. From the Main Menu, type **4** to select MAC Address Tables.

   The MAC Address Tables menu is shown in Figure 30 on page 106.

2. From the MAC Address Tables menu, type **2** to select MAC Addresses Configuration.

   The MAC Addresses Configuration menu is shown in Figure 34.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                              11:20:02 02-Mar-2005
                MAC Addresses Configuration

1 - Add Static MAC Address
2 - Delete MAC Address
3 - Delete All Dynamic MAC Addresses

R - Return to Previous Menu

Enter your selection?
```

Figure 34. MAC Addresses Configuration Menu

3. From the MAC Addresses Configuration menu, type **1** to select Add static MAC address.

   The following prompt is displayed:

   ```
   Please enter MAC address ->
   ```

4. Enter the static unicast or multicast MAC address in the following format:

   ```
   XXXXXX XXXXXX
   ```

   After you have specified the MAC address, the following prompt is displayed:

   ```
   Enter port-list: [1 to 24] ->
   ```


Downloaded from www.Manualslib.com manuals search engine

5. Enter the number of the port on the switch where you want to assign the static address. If you are adding a static unicast address, you can specify only one port.

   If you are entering a static multicast address, you must specify the port when the multicast application is located as well as the ports where the host nodes are connected. Assigning the address only to the port where the multicast application is located will prevent the forwarding of the multicast packets to the host nodes. You can specify the ports individually (e.g., 1,4,5), as a range (e.g., 11-14) or both (e.g., 15-17,22,24).

   The following prompt is displayed:

   ```
   Please enter VLAN ID: [1 to 4094] -> 1
   ```

6. Enter the VLAN ID where the port is a member.

7. Repeat this procedure starting with Step 3 to enter additional static unicast or multicast MAC addresses.

Downloaded from www.Manualslib.com manuals search engine

Deleting Unicast and Multicast MAC Addresses

To delete a dynamic or static unicast or multicast address from the MAC address table, perform the following procedure:

1. From the Main Menu, type **4** to select MAC Address Tables.

   The MAC Address Tables menu is shown in Figure 30 on page 106.

2. From the MAC Address Tables menu, type **2** to select MAC Addresses Configuration.

   The MAC Addresses Configuration menu is shown in Figure 34 on page 110.

3. From the MAC Addresses Configuration menu, type **2** to select Delete MAC Address.

   The following prompt is displayed:

   ```
   Please enter a MAC address ->
   ```

4. Enter the unicast or multicast MAC address to be deleted in the following format:

   ```
   XXXXXX XXXXXX
   ```

   After you have entered the MAC address, the following prompt is displayed:

   ```
   Please enter VLAN ID -> [1 to 4094] -> 1
   ```

5. Enter the VLAN ID of the port where the address was assigned or learned.

   The MAC address is deleted from the switch's MAC address table.

   Note
   You cannot delete a switch's MAC address, an STP BPDU MAC address, or a broadcast address.

6. Repeat the procedure to delete additional MAC addresses.

7. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Deleting All Dynamic MAC Addresses

To delete all dynamic unicast and multicast MAC address from the MAC address table, perform the following procedure:

1. From the Main Menu, type **4** to select MAC Address Tables.

   The MAC Address Tables menu is shown in Figure 30 on page 106.

2. From the MAC Address Tables menu, type **2** to select MAC Addresses Configuration.

   The MAC Addresses Configuration menu is shown in Figure 34 on page 110.

3. From the MAC Addresses Configuration menu, type **3** to select Delete All Dynamic MAC Addresses.

   The following prompt is displayed:

   ```
   All learned MAC (non-static) addresses will be deleted
   Do you want to continue? [Yes/No] ->
   ```

4. Type **Y** to delete the addresses or **N** to cancel the procedure.

   If you respond with yes, all dynamic unicast and multicast addresses are deleted from the table, and the switch begins to learn new addresses.

Downloaded from www.Manualslib.com manuals search engine

Changing the Aging Time

The switch uses the aging time to delete inactive dynamic MAC addresses from the MAC address table. The switch deletes a MAC address from the table when no packets are sent to or received from the end node of the address for the period of time specified by the aging time. This prevents the table from filling with addresses of nodes that are no longer active. The default setting for the aging time is 300 seconds (5 minutes).

To adjust the aging time, perform the following procedure:

1. From the Main Menu, type **4** to select MAC Address Tables.

   The MAC Address Tables menu is shown in Figure 30 on page 106.

2. From the MAC Address Tables menu, type **1** to select MAC Address Aging Time.

   The following prompt is displayed:

   ```
   Enter MAC address aging time -> [8 to 1048575]
   ```

3. Enter a new value in seconds.

   The range is 0 to 1048575 seconds. The default is 300 seconds (5 minutes). The value 0 disables the aging timer. If the aging timer is disabled, inactive dynamic addresses are not deleted from the table and the switch stops learning new addresses after the table reaches maximum capacity.

   The new value is immediately activated on the switch.

4. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Chapter 6

Static Port Trunks

This chapter contains the procedures for managing static port trunks. Sections in the chapter include:

- ❒ “Creating a Static Port Trunk” on page 116
- ❒ “Modifying a Static Port Trunk” on page 120
- ❒ “Deleting a Static Port Trunk” on page 123

Downloaded from www.Manualslib.com manuals search engine

Creating a Static Port Trunk

This section contains the procedure for creating a static port trunk on a switch.

Caution

Do not connect the cables to the trunk ports on the switches until after you have configured the trunk with the management software. Connecting the cables before configuring the software will create a loop in your network topology. Data loops can result in broadcast storms and poor network performance.

Note

Before creating a port trunk, examine the speed, duplex mode, and flow control settings of the lowest numbered port that will be a part of the trunk. Check to be sure that the settings are correct for the end node to which the trunk will be connected. When you create the trunk, the AT-S63 Management Software copies the settings of the lowest numbered port in the trunk to the other ports so that all the settings are the same.

You should also check to be sure that the ports are untagged members of the same VLAN. You cannot create a trunk of ports that are untagged members of different VLANs.

To create a port trunk, perform the following procedure:

1. From the Main Menu, type **1** to select Port Configuration.
2. From the Port Configuration menu, type **4** to select Port Trunking and LACP. The Port Trunking and LACP menu is shown in Figure 35.

```
          Allied Telesis AT-9448T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005

                  Port Trunking and LACP

1 - Static Port Trunking
2 - LACP Configuration

R - Return to Previous Menu

Enter your selection?
```

Figure 35. Port Trunking and LACP Menu

Downloaded from www.Manualslib.com manuals search engine

3. From the Port Trunking and LACP menu, type **1** to select Static Port Trunking.

   The Static Port Trunking menu is shown in Figure 36.

```
            Allied Telesis AT-9448T/SP - AT-S63
                        Marketing
User: Manager                          11:20:02 02-Mar-2005

                    Static Port Trunking

ID    Name        Ports       Method          Status
-----------------------------------------------------

C - Create Trunk
D - Delete Trunk
M - Modify Trunk

R - Return to Previous Menu

Enter your selection?
```

Figure 36. Static Port Trunking Menu

This menu lists the current trunks on the switch. The information includes the following:

- ID - The ID number of the static port trunk.
- Name - The name of the trunk.
- Ports - The ports of the trunk.
- Method - The load distribution method, which can be one of the following:

SRC MAC	Source MAC address.
DST MAC	Destination MAC address.
SRC/DST MAC	Source address/destination MAC address.
SRC IP	Source IP address.
DST IP	Destination IP address.
SRC/DST IP	Source address/destination IP address.

- Status - The operating status of the trunk. If the trunk has established a link with the other device, the status will be UP. If the trunk has not establish a link or the ports in the trunk are disabled, the status will be DOWN.

4. To create a new trunk, type **C** to select Create Trunk.

Downloaded from www.Manualslib.com manuals search engine

The Create Trunk menu is shown in Figure 37.

```
          Allied Telesis AT-9448T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005

                      Create Trunk

1 - Trunk ID ......... 1
2 - Trunk Name .......
3 - Trunk Method ..... SRC/DST MAC
4 - Trunk Ports ......

C - Create Trunk
R - Return to Previous Menu

Enter your selection?
```

Figure 37. Create Trunk Menu

5. Configure the following parameters as necessary:

   1 - Trunk ID
   Specifies the trunk ID, a value from 1 to 6. You cannot specify a trunk ID. The management software selects it for you. The default value is the next unused ID number.

   2 - Trunk Name
   Specifies the trunk name. Enter a name for the trunk. The name can be up to 16 alphanumeric characters. No spaces or special characters, such as asterisks and exclamation points, are allowed. Each trunk must have a unique name.

   3 - Trunk Method
   Specifies the load distribution method. The possible settings are:

   - SRC MAC - Source MAC address
   - DST MAC - Destination MAC address
   - SRC/DST MAC - Source address /destination MAC address
   - SRC IP - Source IP address trunking
   - DST IP - Destination IP address trunking
   - SRC/DST IP - Source address /destination IP address

   The default is SRC/DST MAC.

   4 - Port Range
   Specifies the ports of the trunk. A trunk can contain up to eight ports. You can identify the ports individually (for example, 3,7,10), as a range (for example, 5-11), or both (for example, 2,4,11-14).

Downloaded from www.Manualslib.com manuals search engine

6. Type **C** to select Create Trunk.

   The port trunk is now active on the switch.

7. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

8. Configure the ports on the remote switch for port trunking.

9. Connect the cables to the ports of the trunk on the switch.

   The port trunk is ready for network operations.

Downloaded from www.Manualslib.com manuals search engine

Modifying a Static Port Trunk

This section contains the procedure for modifying a static port trunk on the switch.

Caution
If you will be adding or removing ports from the trunk, you should disconnect all data cables from the ports of the trunk on the switch before performing the procedure. Adding or removing ports from a static port trunk without first disconnecting the cables may result in loops in your network topology, which can result in broadcast storms and poor network performance.

Note the following before performing this procedure:

- If you are adding a port and the port will be the lowest numbered port in the trunk, its parameter settings will overwrite the settings of the existing ports in the trunk. Therefore, you should check to see if its settings are appropriate prior to adding it.
- If you are adding a port and the port will not be the lowest numbered port in the trunk, its settings will be changed to match the settings of the existing ports in the trunk.
- If you are adding a port to a static trunk, you should check to be sure that the new port is an untagged member of the same VLAN as the other trunk ports. A trunk cannot contain ports that are untagged members of different VLANs.

To modify a port trunk, perform the following procedure:

1. From the Main Menu, type **1** to select Port Configuration.
2. From the Port Configuration menu, type **4** to select Port Trunking and LACP.

   The Port Trunking and LACP menu is shown in Figure 35 on page 116.
3. From the Port Trunking and LACP menu, type **1** to select Static Port Trunking.

   The Static Port Trunking menu is shown in Figure 36 on page 117.
4. Type **M** to select Modify Trunk.

   The following prompt is displayed:

   ```
   Enter Trunk ID: [1 to 6] ->
   ```


Downloaded from www.Manualslib.com manuals search engine

5. Enter the ID number of the trunk you want to modify.

   The Modify Trunk menu is displayed. The menu displays the operating specifications of the selected trunk. An example is shown in Figure 38.

```
            Allied Telesis AT-9448T/SP - AT-S63
                        Marketing
User: Manager                              11:20:02 02-Mar-2005
                          Modify Trunk

1 - Trunk ID ......... 2
2 - Trunk Name ....... Server11
3 - Trunk Method ..... SRC/DST MAC
4 - Trunk Ports ...... 12-16

M - Modify Trunk
R - Return to Previous Menu

Enter your selection?
```

Figure 38. Modify Trunk Menu

Note
You cannot change a trunk's ID number.

2 - Trunk Name
Specifies the trunk name. Enter a name for the trunk. The name can be up to 16 alphanumeric characters. No spaces or special characters, such as asterisks and exclamation points, are allowed. Each trunk must have a unique name.

3 - Trunk Method
Specifies the load distribution method. The possible settings are:

- SRC MAC - Source MAC address
- DST MAC - Destination MAC address
- SRC/DST MAC - Source address /destination MAC address
- SRC IP - Source IP address trunking
- DST IP - Destination IP address trunking
- SRC/DST IP - Source address /destination IP address

The default is SRC/DST MAC.

4 - Port Range
Specifies the ports of the trunk. A trunk can contain up to eight ports. You can identify the ports individually (for example, 3,7,10), as a range (for example, 5-11), or both (for example, 2,4,11-14).

Downloaded from www.Manualslib.com manuals search engine

6. Type **M** to select Modify Trunk.

   The modifications to the port trunk are activated on the switch.

7. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

8. Reconnect the cables to the ports of the trunk on the switch.

   The modified port trunk is ready for network operations.

Downloaded from www.Manualslib.com manuals search engine

Deleting a Static Port Trunk

To delete a static port trunk from the switch, perform the following procedure:

> **Caution**
> Disconnect the cables from the port trunk on the switch before performing the following procedure. Deleting a port trunk without first disconnecting the cables can create loops in your network topology. Data loops can result in broadcast storms and poor network performance.

1. From the Main Menu, type **1** to select Port Configuration.
2. From the Port Menu, type **4** to select Port Trunking and LACP.

   The Port Trunking and LACP menu is shown in Figure 35 on page 116.
3. From the Port Trunking and LACP menu, type **1** to select Static Port Trunking.

   The Static Port Trunking menu is shown in Figure 36 on page 117.
4. Type **D** to select Delete Trunk.

   The following prompt is displayed:

   ```
   Enter Trunk ID: [1 to 6] ->
   ```
5. Enter the ID number of the trunk to be deleted.

   The following prompt is displayed:

   ```
   Are you sure you want to delete this trunk (Y/N) [Yes/No] ->
   ```
6. Type **Y** for yes to delete the port trunk or **N** for no to cancel this procedure.

   The port trunk is deleted from the switch.
7. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Chapter 7

LACP Port Trunks

This chapter contains the procedures for managing LACP port trunks. Sections in the chapter include:

- ❒ “Enabling or Disabling LACP” on page 126
- ❒ “Setting the LACP System Priority” on page 128
- ❒ “Creating an Aggregator” on page 129
- ❒ “Modifying an Aggregator” on page 132
- ❒ “Deleting an Aggregator” on page 134
- ❒ “Displaying LACP Port and Aggregator Status” on page 135

Downloaded from www.Manualslib.com manuals search engine

Enabling or Disabling LACP

This procedure explains how to enable or disable LACP on the switch. When you enable LACP, the switch begins to transmit LACPDU packets from ports assigned to aggregators. If ports in an aggregator receive LACPDU packets from a remote device, the switch creates aggregate trunks. If no aggregators are defined, no LACPDU packets are transmitted. When you disable LACP, any ports in existing aggregators stop sending LACPDU packets and function as regular Fast Ethernet ports.

Caution

Do not disable LACP if there are defined aggregators without first disconnecting all cables connected to the aggregate trunk ports. Otherwise, a network loop might occur, resulting in a broadcast storm and poor network performance.

To enable or disable LACP, perform the following procedure:

1. From the Main Menu, type **1** to select Port Configuration.
2. From the Port Configuration menu, type **4** to select Port Trunking and LACP.

   The Port Trunking and LACP menu is shown in Figure 35 on page 116.
3. Type **2** to select LACP Configuration.

   The LACP (IEEE 8023ad) Configuration menu is shown in Figure 39.

```
            Allied Telesis AT-9448T/SP - AT-S63
                        Marketing
User: Manager                              11:20:02 02-Mar-2005
              LACP (IEEE 802.3ad) Configuration
1 - LACP Status ................. Disabled
2 - Priority ................... 0x0080
3 - Create Aggregator
4 - Modify Aggregator
5 - Delete Aggregator
6 - Show LACP Port Status
7 - Show LACP Aggregator Status

R - Return to Previous Menu

Enter your selection?
```

Figure 39. LACP (IEEE 8023ad) Configuration Menu

Downloaded from www.Manualslib.com manuals search engine

4. Type **1** to toggle LACP Status between Disabled and Enabled. The default is disabled.

5. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Setting the LACP System Priority

This procedure explains how to set the LACP system priority value on a switch. The switch uses this parameter if a conflict occurs when establishing an aggregate trunk with the other device. The LACP settings on the device with the higher priority take precedence over the settings on the other device. The lower the value, the higher the priority. A switch can have only one LACP system priority.

To set the LACP system priority for the switch, perform the following procedure:

1. From the Main Menu, type **1** to select Port Configuration.
2. From the Port Configuration menu, type **4** to select Port Trunking and LACP.

   The Port Trunking and LACP menu is shown in Figure 35 on page 116.
3. Type **2** to select LACP Configuration.

   The LACP (IEEE 8023ad) Configuration menu is shown in Figure 39 on page 126.
4. Type **2** to select Priority.

   The following prompt is displayed:

   ```
   Enter Priority [0x1 - 0xFFFF]: [0x1 to 0xffff] -> 0x
   ```
5. Enter the new value is hexadecimal. The range is 1 to FFFF. The lower the value, the higher the priority. The prefix “0x” indicates that the number is hexadecimal.

   The new priority value takes effect immediately on the switch.
6. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Creating an Aggregator

To create an aggregator, perform the following procedure:

Caution
Do not connect the cables to the ports of the aggregator on the switch until after you have configured the aggregator with the management software and enabled LACP. Connecting the cables before configuring the software and activating the protocol will create a loop in your network topology. Data loops can result in broadcast storms and poor network performance.

Note
Before creating an aggregator, verify that the ports that will be members of the aggregator are set to Auto-Negotiation or 1000 Mbps, full-duplex. Aggregate trunks do not support half-duplex mode.

1. From the Main Menu, type **1** to select Port Configuration.
2. From the Port Configuration menu, type **4** to select Port Trunking and LACP.

   The Port Trunking and LACP menu is shown in Figure 35 on page 116.
3. Type **2** to select LACP Configuration.

   The LACP (IEEE 8023ad) Configuration menu is shown in Figure 39 on page 126.
4. Type **3** to select Create Aggregator.

Downloaded from www.Manualslib.com manuals search engine

The Create LACP (IEEE 8023ad) Aggregator menu is shown in Figure 40.

```
          Allied Telesis AT-9448T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005

          Create LACP (IEEE 802.3ad) Aggregator

1 - Aggregator ..................
2 - Adminkey ..................... 0x0000
3 - Distribution Mode ............ SRC/DST MAC
4 - Port Range ..................
C - Create Aggregator

R - Return to Previous Menu

Enter your selection?
```

Figure 40. Create LACP (IEEE 8023ad) Aggregator Menu

5. Configure the following parameters as necessary:

   1 - Aggregator
   Specifies a name for the aggregator. The name can be up to 20 alphanumeric characters. Spaces are allowed, but special characters, such as asterisks and exclamation points, are not. Each aggregator must have a unique name.

   2 - Adminkey
   Specifies a unique adminkey value for the aggregator. The value is entered in hexadecimal. The range is 1 to FFFF.

   Note
   When you create a new aggregator you can specify either the aggregator's name or adminkey, but not both. If you specify a name, the adminkey is based on the operator key of the lowest numbered port in the aggregator.

   If you specify an adminkey, the default name is DEFAULT_AGG followed by the port number of the lowest numbered port in the aggregator. For example, an aggregator of ports 12 to 16 is given the default name DEFAULT_AGG12.

Downloaded from www.Manualslib.com manuals search engine

3 - Distribution Mode
Sets the load distribution method. Possible settings are:

- SRC MAC - Source MAC address
- DST MAC - Destination MAC address
- SRC/DST MAC - Source address /destination MAC address
- SRC IP - Source IP address trunking
- DST IP - Destination IP address trunking
- SRC/DST IP - Source address /destination IP address

The default is SRC/DST MAC.

4 - Port Range
Specifies the aggregator ports. An aggregator can contain any number of ports on the switch. You can identify the ports individually (for example, 3,7,10), as a range (for example, 5-11), or both (for example, 2,4,11-14).

6. After you configure the parameters, type **C** to select Create Aggregator.

   The aggregator is created on the switch.

7. If LACP is not enabled on the switch, perform the procedure "Enabling or Disabling LACP" on page 126 and activate the protocol.

8. Configure LACP on the other network device.

9. Connect the cables to the ports of the aggregator on both the switch and the other network device.

   The aggregator and its aggregate trunk(s) are now ready for network operations.

Caution
Do not connect the cables to the ports of the aggregator on the switch until after you have enabled LACP. Connecting the cables before activating the protocol will create a loop in your network topology. Data loops can result in broadcast storms and poor network performance.

10. Repeat this procedure to create additional aggregators, if needed.

11. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Modifying an Aggregator

This procedure explains how to modify an aggregator. You can use this procedure to change the load distribution method of an aggregator or to add or remove ports. To modify an aggregator, you need to know its name. To view the names of the existing aggregators, refer to “Displaying LACP Port and Aggregator Status” on page 135.

Caution

If you will be adding or removing ports from the aggregator, you should disconnect all network cables from the ports of the aggregator on the switch before performing the procedure. Adding or removing ports without first disconnecting the cables can result in loops in your network topology, which can result in broadcast storms and poor network performance.

To modify an aggregator, perform the following procedure:

1. From the Main Menu, type **1** to select Port Configuration.
2. From the Port Configuration menu, type **4** to select Port Trunking and LACP. The Port Trunking and LACP menu is shown in Figure 35 on page 116.
3. Type **2** to select LACP Configuration. The LACP (IEEE 8023ad) Configuration menu is shown in Figure 39 on page 126.
4. Type **4** to select Modify Aggregator.

   The Modify LACP (IEEE 8023ad) Aggregator menu is shown in Figure 41.

```
          Allied Telesis AT-9448T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005

          Modify LACP (IEEE 802.3ad) Aggregator

1 - Aggregator ..................
2 - Adminkey ..................... 0x0000
3 - Distribution Mode ........... SRC/DST MAC
4 - Port Range ..................
M - Modify Aggregator

R - Return to Previous Menu

Enter your selection?
```

Figure 41. Modify LACP (IEEE 8023ad) Aggregator Menu

Downloaded from www.Manualslib.com manuals search engine

5. Type **1** to select Aggregator and, when prompted, enter the name of the aggregator to be modified. The name is case-sensitive. (To display the names of the aggregators on a switch, refer to "Displaying LACP Port and Aggregator Status" on page 135)

   After you enter the aggregator's name, the specifications of the aggregator are displayed in the menu.

6. Configure the following parameters as necessary:

   Note
   You cannot modify the name or adminkey of an aggregator. If you need to change an aggregator's name or adminkey, you must delete the aggregator and recreate it.

   3 - Distribution Mode
   Sets the load distribution method. Possible settings are:

   - SRC MAC - Source MAC address
   - DST MAC - Destination MAC address
   - SRC/DST MAC - Source address /destination MAC address
   - SRC IP - Source IP address trunking
   - DST IP - Destination IP address trunking
   - SRC/DST IP - Source address /destination IP address

   The default is SRC/DST MAC.

   4 - Port Range
   Specifies the aggregator ports. An aggregator can contain any number of ports on the switch. You can identify the ports individually (for example, 3,7,10), as a range (for example, 5-11), or both (for example, 2,4,11-14).

7. After configuring the parameters, type **M** to select Modify Aggregator.

   The aggregator is modified on the switch.

8. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

9. Reconnect the cables to the ports of the aggregator.

   The modified aggregator is now ready for network operations.

Downloaded from www.Manualslib.com manuals search engine

Deleting an Aggregator

This procedure deletes an aggregator from the switch. The ports that are members of the aggregator stop transmitting LACPDU packets after the aggregator is deleted.

Caution
Disconnect the cables from the ports of the aggregator before performing the following procedure. Deleting an aggregator without first disconnecting the cables can create loops in your network topology. Data loops can result in broadcast storms and poor network performance.

To delete an aggregator, perform the following procedure:

1. From the Main Menu, type **1** to select Port Configuration.
2. From the Port Configuration menu, type **4** to select Port Trunking and LACP.

   The Port Trunking and LACP menu is shown in Figure 35 on page 116.
3. Type **2** to select LACP Configuration.

   The LACP (IEEE 8023ad) Configuration menu is shown in Figure 39 on page 126.
4. Type **5** to select Delete Aggregator.

   The following prompt is displayed:

   ```
   Enter Aggregator Name [Max up to 20 alphanumeric
   characters]:
   ```
5. Enter the name of the aggregator you want to delete. The name is case-sensitive. You can delete only one aggregator at a time.

   The following prompt is displayed:

   ```
   Are you sure you want to delete this aggregator (Y/N) [Yes/No]
   ->
   ```
6. Type **Y** to delete the aggregator or **N** to cancel the procedure.

   If you entered Yes, the aggregator is deleted.
7. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Displaying LACP Port and Aggregator Status

To display LACP port and aggregator status, perform the following procedure:

1. From the Main Menu, type **1** to select Port Configuration.
2. From the Port Configuration menu, type **4** to select Port Trunking and LACP. The Port Trunking and LACP menu is shown in Figure 35 on page 116.
3. Type **2** to select LACP Configuration. The LACP (IEEE 8023ad) Configuration menu is shown in Figure 39 on page 126.
4. To view port status, type **6** to select Show LACP Port Status. To view aggregator status, type **7** to select Show LACP Aggregator Status. Figure 42 is an example of the LACP (IEEE 802.3ad) Port Status menu. The information in this window is for viewing purposes only. For definitions, refer to the IEEE 802.3ad standard.

```
                    Allied Telesis AT-9448T/SP - AT-S63
                                Marketing
User: Manager                                          11:20:02 02-Mar-2005

                      LACP (IEEE 802.3ad) Port Status


Port ............. 01
Aggregator ....... Sales server

ACTOR                                 PARTNER
=====================================+++++++============================
Actor Port ............. 06          Partner Port ......... 00
Selected ............... SELECTED    Partner System ....... 00-30-84-00-00-02
Oper Key ............... 0x0050      Oper Key  ............ 0x0004
Oper Port Priority  .... 0x0006      Oper Port Priority ... 0x0007
Individual ............. NO          Individual ........... NO
Synchronized............ YES         Synchronized.......... YES
Collecting  ............ YES         Collecting ........... YES
Distributing ........... YES         Distributing ......... NO
Defaulted .............. NO          Defaulted ............ NO
Expired ................ NO          Expired .............. NO
Actor Churn ............ YES         Partner Churn ........ YES

N - Next Page
U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 42. LACP (IEEE 802.3ad Port Status Menu

Downloaded from www.Manualslib.com manuals search engine

Figure 43 is an example of the LACP (IEEE 802.3ad) Aggregator Status menu. The information is for viewing purposes only.

```
                    Allied Telesis AT-9448T/SP - AT-S63
                                 Marketing
User: Manager                                              11:20:02 02-Mar-2005

                   LACP (IEEE 802.3ad) Aggregator Status

Aggregator #1 ................. Sales server
Adminkey ...................... 0x0050
Oper Key....................... 0x1405
Speed ......................... 100 Mbps
Distribution Mode ............. SRC/DST MAC
Ports configured .............. 5-8
Ports in LAGID ................ 5-8
Aggregated Port ............... 5-8

R - Return to Previous Menu

Enter your selection?
```

Figure 43. LACP (IEEE 802.3ad) Aggregator Status Menu

Downloaded from www.Manualslib.com manuals search engine

Chapter 8

Port Mirroring

This chapter contains the procedures for creating and deleting a port mirror. Sections in the chapter include:

- ❒ “Creating a Port Mirror” on page 138
- ❒ “Disabling a Port Mirror” on page 140
- ❒ “Modifying a Port Mirror” on page 141
- ❒ “Displaying the Port Mirror” on page 142

Downloaded from www.Manualslib.com manuals search engine

Creating a Port Mirror

To create a port mirror, perform the following procedure:

1. From the Main Menu, type **1** to select Port Configuration.
2. From the Port Configuration menu, type **6** to select Port Mirroring.

   The Port Mirroring menu is shown in Figure 44.

```
          Allied Telesis AT-9448T/SP - AT-S63
                       Marketing
User: Manager                            11:20:02 02-Mar-2005
                     Port Mirroring
1 - Enable/Disable ..................... Disabled

R - Return to Previous Menu

Enter your selection?
```

Figure 44. Port Mirroring Menu #1

3. From the Port Mirroring menu, type **1** to select Enable/Disable.

   The following prompt is displayed.

   ```
   Enter Enable(E)/Disable(D):
   ```

4. Type **E** to enable the feature.

   New options are added to the Port Mirroring menu, as shown in Figure 45.

```
          Allied Telesis AT-9448T/SP - AT-S63
                       Marketing
User: Manager                            11:20:02 02-Mar-2005
                     Port Mirroring
1 - Enable/Disable ....................... Enabled
2 - Mirror-To (Destination) Port ........ None
3 - Ingress (Rx) Mirror (Source) Ports .. None
4 - Egress (Tx) Mirror (Source) Ports ... None

R - Return to Previous Menu

Enter your selection?
```

Figure 45. Port Mirroring Menu #2

5. Type **2** to select Mirror-To (Destination) Port.

Downloaded from www.Manualslib.com manuals search engine

The following prompt is displayed:

```
Mirror-To Port (0-24):
```

6. Enter the number of the port to function as the destination port. This is the port where the traffic from the source ports will be copied to and where the network analyzer will be located. You can specify only one destination port.

7. To mirror the ingress (received) traffic on one or more ports, do the following:

   a. Type **3** to select Ingress (Rx) Mirror (Source Ports.

      The following prompt is displayed:

      ```
      Ingress Mirror Ports (1-24) (or None):
      ```

   b. Enter the ports. You can identify the ports individually (for example, 3,7,10), as a range (for example, 5-11), or both (for example, 2,4,11-14). Entering "none" removes all ingress source ports.

8. To mirror the egress (transmitted) traffic from one or more ports, do the following:

   a. Type **4** to select Egress Mirror Port.

      The following prompt is displayed:

      ```
      Egress Mirror Ports (1-24) (or None):
      ```

   b. Enter the ports. Entering "none" removes all egress source ports.

   Note
   To monitor the ingress and egress traffic of a port, the port must be specified in both selections 3 and 4.

   The port mirror is now functional. Attach a network analyzer to the destination port to monitor the traffic on the source ports.

9. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Disabling a Port Mirror

To delete a port mirror, perform the following procedure:

1. From the Main Menu, type **1** to select Port Configuration.
2. From the Port Configuration menu, type **6** to select Port Mirroring.

   The Port Mirroring menu is shown in Figure 45 on page 138.
3. From the Port Mirroring Menu, type **1** to select Enable/Disable.

   The following prompt is displayed.

   ```
   Enter Enable(E)/Disable(D):
   ```
4. Type **D** to disable the feature.

   Port mirroring on the switch is now disabled. You can disconnect the network analyzer from the destination port and use the port for normal network operations.
5. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Modifying a Port Mirror

To modify the port mirror, perform the following procedure:

1. From the Main Menu, type **1** to select Port Configuration.
2. From the Port Configuration menu, type **6** to select Port Mirroring.

   The Port Mirroring menu is shown in Figure 45 on page 138.
3. Type **2** to select Mirror-To (Destination) Port.

   The following prompt is displayed:

   ```
   Mirror-To Port (01-24):
   ```
4. Enter the number of the port that will function as the destination port. This is the port where the traffic from the source ports will be copied to and where the network analyzer will be located. You can specify only one destination port.
5. If you want to mirror the ingress (received) traffic on one or more ports, type **3** to select Ingress(Rx) Mirror (Source) Ports.

   The following prompt is displayed:

   ```
   Ingress Mirror Ports (1-24) (or None):
   ```
6. Enter the ports. You can identify the ports individually (for example, 3,7,10), as a range (for example, 5-11), or both (for example, 2,4,11-14). Entering "none" removes all ingress source ports.
7. If you want to mirror the egress (transmitted) traffic from one or more ports, type **4** to select Egress Mirror Port.

   The following prompt is displayed:

   ```
   Egress Mirror Ports (1-24) (or None):
   ```
8. Enter the ports. Entering "none" removes all egress source ports.
9. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Displaying the Port Mirror

To display the port mirror, perform the following procedure:

1. From the Main Menu, type **1** to select Port Configuration.
2. From the Port Configuration menu, type **6** to select Port Mirroring.

   The Port Mirroring menu is shown in Figure 46.

```
            Allied Telesis AT-9448T/SP - AT-S63
                          Marketing
User: Manager                              11:20:02 02-Mar-2005
                        Port Mirroring
1 - Enable/Disable ....................... Enabled
2 - Mirror-To (Destination) Port ........ 22
3 - Ingress (Rx) Mirror (Source) Ports .. 1,3
4 - Egress (Tx) Mirror (Source) Ports ... 1,3,11-13

R - Return to Previous Menu

Enter your selection?
```

Figure 46. Port Mirroring Menu

The Port Mirroring menu provides the following information about the port mirror:

Enable/Disable
The port mirroring status, Enabled or Disabled.

Mirror-To (Destination) Port
The port that functions as the destination port.

Ingress (Rx) Mirror (Source) Port
The port(s) whose ingress (received) traffic is mirrored.

Egress (Tx) Mirror (Source) Port
The port(s) whose egress (transmitted) traffic is mirrored.

Downloaded from www.Manualslib.com manuals search engine

Section II

Advanced Operations

The chapters in this section contain overview information on some of the advanced features of the AT-9400 Switch. The chapters also contain procedures for configuring these features using the AT-S63 Management Software. The chapters include:

- Chapter 9, ”File System” on page 145
- Chapter 10, ”File Downloads and Uploads” on page 167
- Chapter 11, ”Event Logs and the Syslog Client” on page 197
- Chapter 12, ”Classifiers” on page 219
- Chapter 13, ”Access Control Lists” on page 231
- Chapter 14, “Class of Service” on page 243
- Chapter 15, ”Quality of Service” on page 251
- Chapter 16, ”Denial of Service Defenses” on page 279
- Chapter 17, “Power Over Ethernet” on page 283

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Chapter 9

File System

The chapter describes the AT-S63 file system, and how you can copy, rename, and delete system files from the file system or from a compact flash card. This chapter also explains how you can use the file system to select which boot configuration file you want the switch to use the next time the device is reset or power cycled.

This chapter contains the following sections:

- ❒ “Working with Boot Configuration Files” on page 146
- ❒ “Copying a System File” on page 154
- ❒ “Renaming a System File” on page 156
- ❒ “Deleting a System File” on page 158
- ❒ “Displaying System Files” on page 159
- ❒ “Working with Flash Memory” on page 162
- ❒ “Working with the Compact Flash Card” on page 164

Downloaded from www.Manualslib.com manuals search engine

Working with Boot Configuration Files

A boot configuration file contains the series of commands that recreate the current or a specific configuration of the switch when the unit is power cycled or reset. The commands in the file recreate all the VLANs, port settings, spanning tree settings, port trunks, port mirrors, and so forth.

A switch can contain multiple boot configuration files, but only one can be active on a switch at a time. The active boot file is the file that is updated whenever you select the Save Configuration Changes option from the Main Menu.

You can create different boot configuration files and store them in the switch's file system. For example, you might create a backup of a boot configuration file to protect against the loss of the file, or you might create different boot configuration files to see which works best on the switch and for your network. You can also copy boot configuration files onto different switches to save yourself the trouble of having to manually configure AT-9400 Switches that are to have similar configurations. One way to do this with switches that support compact flash cards is to copy the configuration file from flash memory on the master switch onto the compact flash card. Then take the compact flash card to other switches and copy the configuration file from the compact flash card into the switch's flash memory.

The procedures in this section explain how to create a boot configuration file, set the active boot configuration file, view the contents of a boot configuration file, and edit a file. The procedures are:

- "Creating a Boot Configuration File" on page 146
- "Setting the Active Boot Configuration File" on page 149
- "Viewing a Boot Configuration File" on page 151
- "Editing a Boot Configuration File" on page 152

To display a list of the boot configuration files that exist on the switch, see "Displaying System Files" on page 159.

Creating a Boot Configuration File

This section explains how to create a new boot configuration file on the switch. You might want to create a boot configuration file to download it onto another switch. Or, you might want to create a backup of your current configuration.

This process involves three procedures:

- "Creating a Boot Configuration File" on page 147
- "Configuring the Switch's Parameter Settings" on page 148

Downloaded from www.Manualslib.com manuals search engine

- "Selecting the Active Boot Configuration File for the Switch" on page 149

Creating a Boot Configuration File

To create a boot configuration file that contains the switch's current configuration, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.
2. From the System Administration menu, type **9** to select System Utilities.
3. From the System Utilities menu, type **1** to select File Operations.

   The File Operations menu is shown in Figure 47.

```
            Allied Telesis AT-9424T/SP - AT-S63
                         Marketing
User: Manager                            11:20:02 02-Mar-2005
                       File Operations

 1 - Boot Configuration File ......... boot.cfg (Exists)
 2 - Current Configuration ........... boot.cfg
 3 - Create Configuration File
 4 - Copy File
 5 - Rename File
 6 - Delete File
 7 - View File
 8 - List Files
 9 - Format Flash Drive
 F - Display Flash Information
 C - Display Compact Flash Information
 D - Set/Change Compact Flash Directory

 R - Return to Previous Menu

 Enter your selection?
```

Figure 47. File Operations Menu

Note
Item 9, Format Flash Drive, and item F, Display Flash Information, are described in "Working with Flash Memory" on page 162. Item C, Display Compact Flash Information and item D, Compact Flash Directory Configuration are described in "Working with the Compact Flash Card" on page 164.

Downloaded from www.Manualslib.com manuals search engine

4. From the File Operations menu, type **3** to select Create Configuration File.

   The following prompt is displayed:

   ```
   Enter the file name:
   ```

5. Enter a file name for the new boot configuration file. When entering a file name, observe the following:

   - Be sure to include the ".cfg" extension.
   - The file name can be up to 16 alphanumeric characters. Spaces are allowed.
   - To store the file on a flash memory card in the switch, precede the name with "cflash:".
   - If a filename already exists, the system displays a message asking if you want to overwrite the existing file name.
   - You cannot name a boot configuration file "default.cfg." This file name is reserved by the switch.

   After you enter the file name, the switch creates the file. The file contains the switch's current configuration.

6. Type **1** to select Boot Configuration File.

   The following prompt is displayed:

   ```
   Enter the file name:
   ```

7. Enter the same file name you entered in Step 5.

   This makes your new boot configuration file the active file on the switch. Any changes you now make to the switch's parameter settings are saved to this file.

   The file name is now displayed following selection 1 in the File Operations menu. The file name should be followed by "Exist", meaning that the file exists in the switch's file system. If "Not Found" is displayed instead, you probably entered the name incorrectly. If necessary, repeat steps 6 and 7 and reenter the file name.

Configuring the Switch's Parameter Settings

After you create the boot configuration file and designate it as the active boot configuration file on the switch, you can configure the switch's parameter settings by making those changes that you want the new boot configuration file to contain. Then, save your changes to the boot configuration file by returning to the Main Menu and typing **S** to select Save Configuration Changes. Failure to save your changes means that the boot configuration file will not contain the new parameter settings.

Downloaded from www.Manualslib.com manuals search engine

Note
Only the active boot configuration file is changed when you select the Save Configuration Changes option in the Main Menu. No other boot configuration files stored on the switch are altered.

Selecting the Active Boot Configuration File for the Switch

You have now created the boot configuration file, made the necessary changes to the switch's parameter settings, and saved the changes. If you want the switch to use this new boot configuration file the next time you reset or power cycle the switch, no further steps are necessary. The new boot configuration file is already the active boot file on the device.

But if you want the switch to use a different file as the active boot configuration file, then perform the procedure in "Setting the Active Boot Configuration File" on page 149.

Setting the Active Boot Configuration File

This procedure selects the active boot configuration file for the switch. The switch uses the active boot configuration file to set its parameter settings when you reset or power cycle the unit. It also updates the active configuration boot file whenever you select Save Configuration Changes from the Main Menu.

Note the following before performing this procedure:

- To view the name of the currently active configuration file, display the File Operations menu. The name of the file is displayed in option 1 Boot Configuration File in the menu.
- The file to be selected as the new active configuration file must already exist in the switch's file system or on a flash memory card, for those switches that support a flash card. To view the switch's configuration files, see "Displaying System Files" on page 159. Configuration files have a ".cfg" extension.
- To create an entirely new configuration file, refer to "Creating a Boot Configuration File" on page 146.
- Specifying a new active boot configuration file does not change the current operating configuration of the switch. If you want the switch to reconfigure itself according to the configuration in the newly assigned active boot configuration file, reset or power cycle the switch at the end of the procedure.
- Selecting Save Configuration Changes from the Main Menu after changing the active configuration file without resetting the switch overwrites the settings in the file with the current operating settings of the switch.
- For those systems that support a flash memory card, you can specify a configuration file on a flash card as the active boot configuration file for a switch. However, the configuration file is not copied to the switch's

Downloaded from www.Manualslib.com manuals search engine

file system, but is instead used and updated directly from the card. If you remove the card and reset the switch, the management software uses its default settings.

- If the file is on a flash memory card, you must change to the directory where the file is stored before performing this command. The command does not accept a directory path. To change directories on a flash card, see “Changing the Current Flash Card Directory” on page 166. The default location is the root of the flash card.
- This procedure features a NONE option that does the following:
  - It removes the currently active configuration file without assigning a new one.
  - The switch continues to operate with its existing configuration settings.
  - You may make further parameter changes, but you cannot save them.
  - If you reset the switch, it uses the BOOT.CFG file to configure its settings.
  - To be able to save configuration changes again, you must assign a new active boot configuration file.

To select the active boot configuration file for the switch, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.
2. From the System Administration menu, type **9** to select System Utilities.
3. From the System Utilities menu, type **1** to select File Operations.

   The File Operations menu is shown in Figure 47 on page 147.
4. From the File Operations menu, type **1** to select Boot Configuration File. The following prompt is displayed:

   ```
   Enter the file name (or None):
   ```
5. Enter the name of the file of the switch’s new active boot configuration file. When entering the name, note the following:
   - Be sure to include the “.cfg” extension.
   - If the file is stored on a flash card in the switch, precede the name with “cflash:”.
   - To remove the currently assigned active boot configuration file without assigning a new one, enter “none”.

Downloaded from www.Manualslib.com manuals search engine

The name of the file should now appear following selection 1 in the File Operations menu. The file name should be followed by "Exist", which means that the file exists in the switch's file system.

If the management software is unable to find the file, it displays:

```
The specified file was not found on the system.
```

Check to be sure you entered the name of the file correctly. If necessary, performing "Listing All Files" on page 159 to verify the name of the file.

6. Do one of the following:

   - To reconfigure the switch using the parameter settings in the selected active boot configuration file, reset or power cycle the switch. For instructions, refer to "Rebooting the Switch" on page 43.
   - To overwrite the settings in the configuration file with the switch's current settings, return to the Main Menu and type **S** to select Save Configuration Changes.

Viewing a Boot Configuration File

Use the following procedure to view the contents of a boot configuration file. (To display the names of the boot configuration files on the switch, see "Displaying System Files" on page 159.)

To view the contents of a boot configuration file, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.
2. From the System Administration menu, type **9** to select System Utilities.
3. From the System Utilities menu, type **1** to select File Operations.

   The File Operations menu is shown in Figure 47 on page 147.
4. From the File Operations menu, type **7** to select View File.

   The following prompt is displayed:

   ```
   Enter file name:
   ```
5. Enter the name of the boot configuration file you want to view.

Downloaded from www.Manualslib.com manuals search engine

The contents of the boot configuration file are displayed in the View File menu. An example is shown in Figure 48.

```
                Allied Telesis AT-9424T/SP - AT-S63
                             Marketing
User: Manager                                        11:20:02 02-Mar-2005
                             View File

Viewing file “mydefault.cfg”:
-------------------------------------------------------------------------

 #
 # System Configuration
 #
 set system name="Switch12a"
 set system contact="Jane Smith"
 set system location="Building 5"

 N - Next Page
 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 48. View File Menu with Sample Boot Configuration File

A boot configuration file contains those switch settings that differ from the AT-S63 default values. The parameter settings are shown in their command line equivalents. The switch executes the commands in the boot configuration file to configure its settings when it is reset or power cycled. For information on command line commands, refer to the *AT-S63 Management Software Command Line Interface User’s Guide*. The information in this menu is for viewing purposes only.

6. Type **N** for Next Page and **P** for Previous Page to scroll through the file.

Editing a Boot Configuration File

You can edit a boot configuration file using a text editor on your management station. To edit the file, you must first upload it from the switch to your management station. You cannot edit a boot configuration file directly on the switch. After you edit the file, you can download it to the switch and make it the active boot configuration file.

For instructions on how to upload a boot configuration file from a switch to your management station, refer to “Uploading a System File” on page 190. For instructions on how to download a boot configuration file from your management station back to the switch, refer to “Downloading a System File” on page 182. For instructions on how to designate an active boot configuration file, refer to “Setting the Active Boot Configuration File” on page 149.

Downloaded from www.Manualslib.com manuals search engine

The following are several guidelines for editing a boot configuration file:

- The text editor must be able to store the file as ASCII text. Do not use special formatting codes, such as boldface or italics.
- The boot configuration file must contain AT-S63 command line commands. You enter the commands you want the switch to perform when reset or power cycled. For a description of the commands, refer to the *AT-S63 Management Software Command Line Interface User's Guide*.
- A boot configuration file is divided into sections with each section devoted to the commands for a particular function. For example, the VLAN Configuration section should only contain commands for creating VLANs or for setting the VLAN mode.
- Each command must start flush left.
- To comment out a command so that the switch does not perform it, precede the command with the pound symbol (#).
- You should test the commands manually by entering them at a command line prompt before inserting them into a boot configuration file. This is to ensure that you understand the syntax and parameters of the commands and that the commands produce the desired results.
- To troubleshoot a boot configuration file, start a local management session with the switch and reset the device. Messages displayed on the screen during the boot up and boot configuration process indicate the line in the boot configuration file that contains the error.

Downloaded from www.Manualslib.com manuals search engine

Copying a System File

This procedure is used to create copies of files stored in a switch's file system or on a flash memory card. For instance, you might perform this procedure to create a copy of a configuration file so that you have a backup copy.

You can also use this procedure is to copy files between a switch's file system and a flash memory card. For example, you might want to copy a configuration file from a flash card to a switch's file system, or perhaps copy an SSL enrollment request from the switch to a compact flash card.

Before performing the procedure, note the following:

- To copy a file on a compact flash card, you must first change to the directory where the file is stored or, if you are copying a file to the card from the switch's file system, where you want to store the file. This is explained in "Changing the Current Flash Card Directory" on page 166. The following procedure does not allow you to specify a directory path. The default location is the root of the flash card.
- Files with the extension UKF are encryption key pairs. These files cannot be copied, renamed, or deleted from the file system.

To copy a system file, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.
2. From the System Administration menu, type **9** to select System Utilities.
3. From the System Utilities menu, type **1** to select File Operations.

   The File Operations menu is shown in Figure 47 on page 147.
4. From the File Operations menu, type **4** to select Copy File.

   Note
   Selecting Copy File does not allow you to overwrite files.

   The following prompt is displayed:

   ```
   Enter the source file name:
   ```
5. Enter the name of the file to be copied. If the file is located on a compact flash card, precede the filename with "cflash:"

   The following prompt is displayed:

   ```
   Enter the destination file name:
   ```


Downloaded from www.Manualslib.com manuals search engine

6. Enter the new file name. The file name can be up to 16 alphanumeric characters, followed by a 3 letter extension. You must keep the same extension as the original file. To store the file on a compact flash card, precede the filename with "cflash:"

   The following message is displayed:

   ```
   Please wait...
   Press any key ...
   ```

7. Press any key to return to the File Operations menu.

Examples

The following examples illustrate how to create copies of files as well as transfer files between a switch's flash memory and a compact flash card.

This example creates a backup copy of a configuration file called "switch12.cfg" located in the switch's file system and assigns the new copy the name "switch12_backup.cfg":

```
Enter the source file name: switch12.cfg
Enter the destination file name: switch12_backup.cfg
```

This example creates a copy of a configuration file called "sw24.cfg" located on a flash memory card and assigns it the name "sw24_bk.cfg":

```
Enter the source file name: cflash:sw24.cfg
Enter the destination file name: cflash:sw24_bk.cfg
```

This example copies the configuration file "sw_sales.cfg" from the switch's file system to a flash memory card, without changing the name.

```
Enter the source file name: sw_sales.cfg
Enter the destination file name: cflash:sw_sales.cfg
```

This example copies an event log file called "sw14_apr12.log" from the switch's file system to a flash memory card, and assigns it the name "sw14.log" on the card:

```
Enter the source file name: sw14_apr12.log
Enter the destination file name: cflash:sw14.log
```

This example copies the configuration file "pdr_new.cfg" from a flash memory card to the switch's file system and assigns it the name "pdr.cfg":

```
Enter the source file name: cflash:pdr_new.cfg
Enter the destination file name: pdr.cfg
```


Downloaded from www.Manualslib.com manuals search engine

Renaming a System File

This procedure is used to rename files in a system's file system or a compact flash card. Before renaming a file, note the following:

- To rename a file on a compact flash card, you must first change to the directory where the file is stored. This procedure does not allow you to specify a directory path. For instructions, refer to "Changing the Current Flash Card Directory" on page 166.
- Files with the extension UKF are encryption key pairs. These files cannot be copied, renamed, or deleted from the file system.
- Renaming the active boot configuration file and then resetting the switch returns the unit to its default parameter settings, unless you save the current configuration or select another active boot configuration file. For instructions on how to change the active boot configuration file, see "Setting the Active Boot Configuration File" on page 149.

To rename a system file, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.
2. From the System Administration menu, type **9** to select System Utilities.
3. From the System Utilities menu, type **1** to select File Operations.

   The File Operations menu is shown in Figure 47 on page 147.
4. From the File Operations menu, type **5** to select Rename File.

   The following prompt is displayed:

   ```
   Enter the source file name:
   ```
5. Enter the name of the file you want to rename. If the file is located on a compact flash card, precede the filename with "cflash:".

   The following prompt is displayed:

   ```
   Enter the destination file name:
   ```

   Note
   The source and destinations must be on the same device, either flash memory or a compact flash card.
6. Enter the new name for the file.

Downloaded from www.Manualslib.com manuals search engine

You can enter a file name of up to 16 alphanumeric characters, followed by a 3 letter extension. You must keep the same extension. If the file is located on a compact flash card, precede the filename with "cflash:"

The following message is displayed:

```
Please wait...
Press any key ...
```

Press any key to return to the File Operations menu.

Examples

The following examples illustrate how to rename files in a switch's flash memory and on a compact flash card.

This example renames the file "eventlog11.log" in the switch's flash memory to 'apr12_events.log":

```
Enter the source file name: eventlog11.log
Enter the destination file name: apr12_events.log
```

This example renames the file "sw24.cfg" located on a flash memory card to "sw24_bk.cfg":

```
Enter the source file name: cflash:sw24.cfg
Enter the destination file name: cflash:sw24_bk.cfg
```


Downloaded from www.Manualslib.com manuals search engine

Deleting a System File

This procedure is used to delete files from a system's flash memory or a compact flash card. Before deleting a file, note the following:

- Deleting the active boot configuration file and then resetting the switch returns the unit to its default parameter settings, unless you save the current configuration or select another active boot configuration file. For instructions on how to change the active boot configuration file, see "Setting the Active Boot Configuration File" on page 149.
- To delete a file on a compact flash card, you must first change to the directory where the file is stored. This procedure does not allow you to specify a directory path. For instructions, refer to "Changing the Current Flash Card Directory" on page 166.
- Files with the extension UKF are encryption key pairs. These files cannot be copied, renamed, or deleted from the file system. To delete a key pair from the switch, refer to "Deleting an Encryption Key" on page 600.

To delete a system file, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.
2. From the System Administration menu, type **9** to select System Utilities.
3. From the System Utilities menu, type **1** to select File Operations.

   The File Operations menu is shown in Figure 47 on page 147.
4. From the File Operations menu, type **6** to select Delete File.

   The following prompt is displayed:

   ```
   Enter file name to be deleted:
   ```
5. Enter the name of the file you want to delete. If the file is located on a compact flash card, precede the filename with "cflash:".

   The following prompt is displayed:

   ```
   Please wait...
   Press any key ...
   ```
6. Press any key to return to the File Operations menu.

Downloaded from www.Manualslib.com manuals search engine

Displaying System Files

Use this procedure to display a list of the system files currently stored either in the flash memory of the switch or on a compact flash card.

Listing All Files

To display a list of the system files stored in flash memory as well as on a compact flash card (if the switch supports this and a compact flash card is inserted in the slot), perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.
2. From the System Administration menu, type **9** to select System Utilities.
3. From the System Utilities menu, type **1** to select File Operations.

   The File Operations menu is shown in Figure 47 on page 147.
4. From the File Operations Menu, type **8** to select List Files.

   The following prompt is displayed:

   ```
   Enter file name pattern to list:
   ```
5. Enter a boot configuration file name or pattern using the wildcard "*". Below are examples of how to use the wildcard to display different files.

   To display a list of all the files stored both in flash memory and on a compact flash card in the same switch, enter:

   ```
   *.*
   ```

   To display a list of the certificate files, enter:

   ```
   *.cer
   ```

   To display a list of the boot configuration files, enter:

   ```
   *.cfg
   ```

   To display a list of the key files, enter:

   ```
   *.key
   ```

   To display a list of the files that begin with the letter t, enter:

   ```
   t*.*
   ```


Downloaded from www.Manualslib.com manuals search engine

An example of this display is shown in Figure 49.

```
              Allied Telesis AT-9424T/SP - AT-S63
                          Marketing
User: Manager                                  11:20:02 02-Mar-2005
                           List Files

 File Name          Device   Size (Bytes)  Last Modified
 ------------------------------------------------------------------
 default.cfg        flash    805           01/10/2002 12:01:16
 boot.cfg           flash    1249          10/24/2003 16:50:40
 newcfg.cg          flash    1082          07/12/2003 16:59:06
 serverkey150.key   flash    768           11/30/2003 19:17:35
 ProdSw.cer         flash    1024          11/30/2003 20:38:20
 ProdSw2.cer        flash    560           12/11/2003 20:56:13

 Compact Flash Current Directory is: \
 dcim               cflash   <dir>         12/17/2004 12:51:44

 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 49. List Files Menu for Flash Memory and a Compact Flash Card

Note
If the switch does not support a compact flash card, only the files in flash memory are displayed. To display only the files in flash memory, precede the file name with “flash:”.

The columns in the List Files table are described below. This information is for viewing purposes only.

File Name
Name of the system file.

Device
The device type, either “flash” for flash memory or “cflash” for compact flash card.

Size
Size of the file, in bytes.

Last Modified
The time the file was created or last modified, in the following date and time format: month/day/year hours:minutes:seconds.

Downloaded from www.Manualslib.com manuals search engine

Listing Files on the Compact Flash Card

To view the files on the compact flash card, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.
2. From the System Administration menu, type **9** to select System Utilities.
3. From the System Utilities menu, type **1** to select File Operations.

   The File Operations menu is shown in Figure 47 on page 147.
4. From the File Operations Menu, type **8** to select List Files.

   The following prompt is displayed:

   ```
   Enter file name pattern to list:
   ```
5. To list only the files on the compact flash card, enter:

   cflash:*.*

   The system displays files on the compact flash card, as shown in Figure 50.

```
              Allied Telesis AT-9424T/SP - AT-S63
                           Marketing
User: Manager                              11:20:02 02-Mar-2005
                           List Files

 File Name          Device   Size (Bytes)  Last Modified
 ------------------------------------------------------------
 dcim\              cflash   <dir>         01/10/2005 12:01:16
 boot.cfg           cflash   1249          10/24/2005 16:50:40
 newcfg.cg          cflash   1082          07/12/2005 16:59:06
 serverkey150.key   cflash   768           11/30/2005 19:17:35
 ProdSw.cer         cflash   1024          11/30/2005 20:38:20
 ProdSw2.cer        cflash   560           12/11/2005 20:56:13

 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 50. List Files Menu for a Compact Flash Card

Downloaded from www.Manualslib.com manuals search engine

Working with Flash Memory

The flash memory in the AT-9400 Switch stores the file system and the permanent event log.

Displaying Information about the Flash Memory

To display information about the flash memory, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.
2. From the System Administration menu, type **9** to select System Utilities.
3. From the System Utilities menu, type **1** to select File Operations.

   The FIle Operations menu is shown in Figure 47 on page 147.
4. From the File Operations menu, type **F** to select Display Flash Information.

   The Display Flash Information menu is shown in Figure 51.

```
            Allied Telesis AT-9424T/SP - AT-S63
                          Marketing
User: Manager                              11:20:02 02-Mar-2005
                  Display Flash Information

 Flash:
 ------------------------------------------------------

   Files          4096  bytes (2 files)
   Free        8219648  bytes
   Total       8223744  bytes

U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 51. Display Flash Information Menu

Downloaded from www.Manualslib.com manuals search engine

Formatting the Flash Memory

The procedure formats the flash memory in the switch.

Caution

Formatting the flash memory deletes ALL files on the switch, *including* the active configuration file, encryption keys, and certificates. Only the AT-S63 image file in the application block is retained. To remove selected files, refer to "Deleting a System File" on page 158.

Caution

This procedure causes a system reset. Some network traffic may be lost while the switch initializes the AT-S63 Management Software.

To format the flash memory, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.
2. From the System Administration menu, type **9** to select System Utilities.
3. From the System Utilities menu, type **1** to select File Operations.

   The FIle Operations menu is shown in Figure 47 on page 147.
4. From the File Operations menu, type **9** to select Format Flash Drive.

   The following prompt is displayed:

   ```
   This command will format the flash drive and requires a
   switch reboot.
   Do you want to continue? [Yes/No] ->
   ```
5. To continue, type **Y** for Yes; to stop the formatting, type **N** for No.

   If you choose Y, the flash memory is formatted and the switch reboots.

Downloaded from www.Manualslib.com manuals search engine

Working with the Compact Flash Card

Some of the AT-9400 Switches have a slot for a compact flash card. Compact flash cards can be used for transferring files between switches, such as configuration files, and storing backup copies of files.

Displaying Compact Flash Card Information

To display information about the compact flash card, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.
2. From the System Administration menu, type **9** to select System Utilities.
3. From the System Utilities menu, type **1** to select File Operations.

   The FIle Operations menu is shown in Figure 47 on page 147.
4. From the File Operations menu, type **C** to select Display Compact Flash Information.

   The Display Compact Flash Information menu is shown in Figure 52.

```
            Allied Telesis AT-9424T/SP - AT-S63
                         Marketing
User: Manager                              11:20:02 02-Mar-2005
              Display Compact Flash Information

 Compact Flash:
 ------------------------------------------------------

    Current Directory: \
          Number of files ......... 0
          Number of directories ... 1
          Bytes used .............. 0

    Card Information:
          Hardware detected ....... Yes
          Serial Number ........... F000530211
          Size .................... 124666 KB
          Used .....................      4 KB (2 files)
          Free .................... 124662 KB

 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 52. Display Compact Flash Information Menu

Downloaded from www.Manualslib.com manuals search engine

The Display Compact Flash Information menu provides the following information:

Current Directory
The currently selected directory. To change the directory, see "Changing the Current Flash Card Directory" on page 166.

Number of files
The number of files in the current directory.

Number of directories
The number of directories on the compact flash card.

Bytes used
The number of bytes used in the current directory.

The Card Information section contains the following information:

Hardware detected
Whether or not a compact flash card is inserted in the slot.

Serial Number
The serial number of the compact flash card.

Downloaded from www.Manualslib.com manuals search engine

Size
The size in KB of the compact flash card.

Used
The amount of space that is currently used.

Free
The amount of space that is free.

Changing the Current Flash Card Directory

To change the current directory on a compact flash card, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.
2. From the System Administration menu, type **9** to select System Utilities.
3. From the System Utilities menu, type **1** to select File Operations.

   The FIle Operations menu is shown in Figure 47 on page 147.
4. From the File Operations menu, type **D** to select Set/Change Compact Flash Directory.

   The Set/Change Compact Flash Directory menu is shown in Figure 53.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                              11:20:02 02-Mar-2005
             Set/Change Compact Flash Directory

1 - Current Directory: ...\

R - Return to Previous Menu

Enter your selection?
```

Figure 53. Set/Change Compact Flash Directory Menu

5. From the Set/Change Compact Flash Directory menu, type **1** to select Current Directory.

   The following prompt is displayed:

   ```
   Enter the directory name to change to:
   ```
6. Type the directory name and press Enter.

Downloaded from www.Manualslib.com manuals search engine

Chapter 10

File Downloads and Uploads

This chapter contains the procedures for downloading a new AT-S63 image file onto the switch. This chapter also contains the procedures for uploading and downloading system files, such as a boot configuration file, from the file system in the switch. The procedures in this chapter are:

- ❒ “Downloading the AT-S63 Image File onto a Switch” on page 168
- ❒ “Uploading the AT-S63 Image File Switch to Switch” on page 176
- ❒ “Uploading an AT-S63 Configuration File Switch to Switch” on page 179
- ❒ “Downloading a System File” on page 182
- ❒ “Uploading a System File” on page 190

Note
For instructions on how to obtain the latest version of the AT-S63 Management Software, refer to “Management Software Updates” on page 27.

Downloaded from www.Manualslib.com manuals search engine

Downloading the AT-S63 Image File onto a Switch

This section contains the following two procedures:

- “Downloading the AT-S63 Image from a Local Management Session” on page 170
- “Downloading the AT-S63 Image from a Remote Management Session” on page 174

These procedures explain how to download a new version of the AT-S63 image file onto a switch from a local management session using either Xmodem or TFTP, or from a remote management session (i.e, Telnet or SSH) using TFTP. If the switches are part of an enhanced stack, you can simplify the procedure by updating the master switch first by performing one of the procedures in this section. You can then instruct the master switch to upload its image file to the other switches in the enhanced stack, as explained in “Uploading the AT-S63 Image File Switch to Switch” on page 176.

Caution
The switch stops forwarding Ethernet traffic after it has downloaded the image file and begun to initialize the software. Some network traffic may be lost.

Guidelines

The following guidelines apply to both Xmodem and TFTP downloads:

- These procedures download a new AT-S63 image file into the application block portion of the switch’s flash memory. The application block is the area of flash memory reserved for the active AT-S63 image file on a switch and is separate from the file system.
- Alternatively, you can download the image file into the switch’s file system and later copy it into the application block using the LOAD command in the command line interface. To download an image file into the file system rather than the application block, refer to “Downloading a System File” on page 182.
- All models of the AT-9400 Switch use the same AT-S63 Management Software image.
- The current configuration of a switch is retained when a new AT-S63 software image is installed. To return a switch to its default configuration values, refer to “Returning the AT-S63 Management Software to the Factory Default Values” on page 50.
- If you are upgrading the AT-9400 Switch from AT-S63 version 1.3.0 or earlier and the switch has an IP address, the upgrade process automatically creates a routing interface on the switch to preserve the device’s IP configuration. If the switch has a static address, the

Downloaded from www.Manualslib.com manuals search engine

interface is assigned the same address. If the unit obtained its IP configuration from a DHCP or BOOTP server, the interface is created with the DHCP or BOOTP client activated. The interface is given the interface number 0 and assigned to the preexisting management VLAN. Furthermore, the interface is designated as the local interface on the switch.

For example, if the switch has the static IP address 149.44.44.44 and the management VLAN has a VID of 12, the upgrade process automatically creates a routing interface with the same IP address and names it VLAN12-0. It assigns the interface to the VLAN with the VID of 12 and designates it as the switch's local interface.

- The AT-S63 image file also contains the bootloader for the switch. You cannot load the image file and bootloader separately.

The following guidelines apply to an Xmodem download:

- Xmodem can only download the image file onto the switch where you started the local management session. You cannot use Xmodem to download a new image file to a switch accessed through enhanced stacking.
- The new AT-S63 image file must be stored on the computer or terminal connected to the RS232 terminal port on the switch.

The following guidelines apply to a TFTP download:

- The switch must have a routing interface on the local subnet from where it reaches the TFTP server. The switch uses the IP address of the interface as its source address when sending packets to the TFTP server. This rule applies to both master and slave switches of an enhanced stack. If the switch does not have any interfaces, you can perform the download from a local management session of the switch using Xmodem or, alternatively, switch to switch, as explained in "Uploading the AT-S63 Image File Switch to Switch" on page 176.
- Your network must have a node with TFTP server software.
- You must store the new AT-S63 image file on the server.
- You should start the TFTP server software before you begin the download procedure.

The following procedures assume that you have already obtained the new software from Allied Telesis and have stored it on your management station or on the TFTP server.

Downloaded from www.Manualslib.com manuals search engine

Downloading the AT-S63 Image from a Local Management Session

Review "Guidelines" on page 168 before performing the following download procedure.

To download a new AT-S63 software image into the application block portion of the switch's flash memory, making it the active image file on the switch, from a local management session using Xmodem or TFTP, perform the following procedure:

1. Establish a local management session on the switch where you want to download the new management software.
2. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.
3. From the System Administration menu, type **9** to select System Utilities.

   The System Utilities menu is shown in Figure 6 on page 43.
4. From the System Utilities menu, type **2** to select Downloads and Uploads.

   The Downloads and Uploads menu is shown in Figure 54.

```
              Allied Telesis AT-9424T/SP - AT-S63
                             Marketing
User: Manager                              11:20:02 02-Mar-2005
                      Downloads and Uploads
 1 - Download Application Image/BootLoader
 2 - Upload Application Image/BootLoader

 3 - Download a File
 4 - Upload a File

 R - Return to Previous Menu

 Enter your selection?
```

Figure 54. Downloads and Uploads Menu

5. From the Downloads and Uploads menu, type **1** to select Download Application Image/Bootloader.

   The following prompt is displayed:

   ```
   Download Method/Protocol [X-Xmodem, T-TFTP]:
   ```
6. To download the AT-S63 image file using Xmodem, go to Step 7. To download the file using TFTP, do the following:

   a. Type **T**.

Downloaded from www.Manualslib.com manuals search engine

The following prompt is displayed:

```
TFTP Server IP address:
```

b. Enter the IP address of the TFTP server.

The following prompt is displayed:

```
Remote File Name:
```

c. Enter the file name of the AT-S63 image file stored on the TFTP server.

The following message is displayed:

```
Getting the file from Remote TFTP Server - Please wait
...
```

d. If you have not already done so, start the TFTP server software.

After the switch has downloaded the image file, the following message is displayed:

```
File received successfully!
```

After receiving the file, the switch compares the version number of the new image file that you just downloaded against the file already in the application block on the switch. If the new image file has an earlier or the same version number as the file in the switch's application block, it cancels the update process. If the new image file has a newer version number, the switch writes the file to the application block portion of flash memory and then resets.

Caution

The switch does not forward any network traffic while writing the image to flash and during the reset process. This can take several minutes to complete. Some network traffic may be lost.

This completes the procedure for downloading a new AT-S63 image file to a switch from a local management session using TFTP.

7. To download a file using Xmodem, type **X** at the prompt in Step 5.

The following prompt is displayed:

```
You are going to invoke the Xmodem download utility.
Do you wish to continue? [Yes/No]

Note: Please select 1K Xmodem protocol for faster
download.
```


Downloaded from www.Manualslib.com manuals search engine

Note
The transfer protocol must be Xmodem or 1K Xmodem.

8. Type **Y** for Yes.

   The prompt “Downloading” is displayed.

9. Begin the file transfer.

   Steps 10 through 13 illustrate how you download a file using the Hilgraeve HyperTerminal program.

10. From the HyperTerminal main window, select **Send File** from the **Transfer** menu, as shown in Figure 55.



Figure 55. HyperTerminal Window

The Send File window is shown in Figure 56.



Figure 56. Send File Window

11. Click **Browse** and specify the location and file to be downloaded onto the switch.

12. Click in the Protocol field and select as the transfer protocol either Xmodem or, for a faster download, 1K Xmodem.

Downloaded from www.Manualslib.com manuals search engine

13. Click **Send**.

The software immediately begins downloading onto the switch. The Xmodem File Send window in Figure 57 displays the current status of the software download. The download process takes several minutes to complete.



Figure 57. XModem File Send Window

After receiving the file, the switch compares the version number of the new image file that you just downloaded against the file already in the application block on the switch. If the new image file has an earlier or the same version number as the file in the switch's application block, it cancels the update process. If the new image file has a newer version number, the switch writes the file to the application block portion of flash memory and then resets.

Caution

The switch does not forward network traffic while writing the image to flash and during the reset process. This can take several minutes to complete. Some network traffic may be lost.

This completes the procedure for downloading a new AT-S63 image file onto a switch from a local management session using Xmodem.

Downloaded from www.Manualslib.com manuals search engine

Downloading the AT-S63 Image from a Remote Management Session

Review “Guidelines” on page 168 before performing the following download procedure.

To download a new AT-S62 image file into the application block portion of the switch’s flash memory, making it the active image file on the switch, from a remote management session (i.e, Telnet or SSH) using TFTP, perform the following procedure:

1. Establish a remote management session on the switch where you intend to download the new management software. Alternatively, you can access the switch through enhanced stacking.

2. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

3. From the System Administration menu, type **9** to select System Utilities.

   The System Utilities menu is shown in Figure 6 on page 43.

4. From the System Utilities menu, type **2** to select Downloads and Uploads.

   The Downloads and Uploads menu is shown in Figure 54 on page 170.

5. From the Downloads and Uploads menu, type **1** to select Download Application Image/Bootloader.

   The following prompt is displayed:

   ```
   Only TFTP downloads are available for a Telnet access

   TFTP Server IP address:
   ```

6. Enter the IP address of the TFTP server.

   The following prompt is displayed:

   ```
   Remote File Name:
   ```

7. Enter the file name of the image file on the TFTP server that you want to download.

   The following message is displayed:

   ```
   Getting the file from Remote TFTP Server - Please wait
   ...
   ```

8. If you have not already done so, start the TFTP server software.

Downloaded from www.Manualslib.com manuals search engine

After the switch has downloaded the image file, the following message is displayed:

```
File received successfully!
```

After receiving the file, the switch compares the version number of the new image file that you just downloaded against the file already in the application block on the switch. If the new image file has an earlier or the same version number as the file in the switch's application block, it cancels the update process. If the new image file has a newer version number, the switch writes the file to the application block portion of flash memory and then resets.

Caution

The switch does not forward any network traffic while writing the image to flash and during the reset process. This can take several minutes to complete. Some network traffic may be lost.

This completes the procedure for downloading a new AT-S63 image file onto a switch from a remote management session.

Downloaded from www.Manualslib.com manuals search engine

Uploading the AT-S63 Image File Switch to Switch

The procedure in this section uploads the AT-S63 software image from a master AT-9400 Switch to another AT-9400 Switch in an enhanced switch. This procedure is useful in networks that contain a large number of AT-9400 Switches. After updating the software on the master switch, you can use the procedure in this section to instruct the master switch to automatically upgrade the other AT-9400 Switches in the enhanced stack. (For instructions on how to update the AT-S63 image on a master switch, refer to “Downloading the AT-S63 Image File onto a Switch” on page 168.

Caution

This procedure causes the switch receiving the new image file to reset. Some network traffic may be lost.

Guidelines

Please review the following guidelines before performing the procedure:

- You can perform this procedure from a local or remote management session.
- This procedure uploads the active AT-S63 image file on the master switch to the application block in another switch’s flash memory. The application block is the area of memory reserved for the active AT-S63 image file on a switch and is separate from the file system.
- Alternatively, if you prefer to store the image file in the switch’s file system, with plans to transfer it to the application block at a later time, refer to “Downloading a System File” on page 182. To transfer an image file from the file system to the application block, use the LOAD command in the command line interface.
- The current configuration of a switch is retained when a new AT-S63 software image is installed. To return a switch to its default configuration values, refer to “Returning the AT-S63 Management Software to the Factory Default Values” on page 50.
- The AT-S63 image file contains the bootloader for the switch. You cannot load the image file and bootloader separately.
- If you are upgrading the AT-9400 Switch from AT-S63 version 1.3.0 or earlier and the switch has an IP address, the upgrade process automatically creates a routing interface on the switch to preserve the device’s IP configuration. If the switch has a static address, the interface is assigned the same address. If the unit obtained its IP configuration from a DHCP or BOOTP server, the interface is created with its DHCP or BOOTP client activated. The interface is given the interface number 0 and assigned to the preexisting management VLAN. Furthermore, the interface is designated as the local interface on the switch.

Downloaded from www.Manualslib.com manuals search engine

For example, if the switch has the static IP address 149.44.44.44 and the management VLAN has a VID of 12, the upgrade process automatically creates a routing interface with the same IP address and names it VLAN12-0. It assigns the interface to the VLAN with the VID of 12 and designates it as the switch's local interface.

To upload the AT-S63 management software image from a master switch to other switches in the same enhanced stack, perform the following procedure:

1. From the Main Menu, type **8** to select Enhanced Stacking.

   The Enhanced Stacking menu is shown in Figure 22 on page 86.

2. From the Enhanced Stacking menu, type **2** to select Stacking Services.

   Note
   The "2 - Stacking Services" selection is only available on a master switch.

   The Stacking Services menu is shown in Figure 23 on page 88.

3. From the Stacking Services menu, type **1** to select Get/Refresh List of Switches. The master switch polls the subnet for other enhanced stacking switches in the same enhanced stack and displays the switches in the Stacking Services menu.

4. Type **4** to select Download Image/Bootloader File.

   The following prompt is displayed:

   ```
   Remote switches will reboot after load is complete.

   Enter the list of switches ->
   ```

5. Enter the number (Num column in the menu) of the AT-9400 Switch whose software you want to update. You can specify more than one switch at a time (for example, 2,4,5).

   Note
   The AT-S63 software is only supported on the AT-9400 Switches.

   The following prompt is displayed:

   ```
   Do you want to show remote switch burning flash -> [Yes/
   No]
   ```

6. You can respond with Yes or No to this prompt. It does not affect the download.

Downloaded from www.Manualslib.com manuals search engine

The following prompt is displayed:

```
Do you want confirmation before downloading each switch -
> [Yes/No]
```

7. If you answer Yes to this prompt, the management software prompts you with a confirmation message before upgrading a switch. If you answer No, the management software does not display a confirmation prompt before uploading the image file.

   The management software begins the upload. The management software notifies you when the upload is complete.

   After receiving the file, a switch compares the version numbers of the new and existing image files. If the new image file has the same or an earlier version number as the file in the application block, it cancels the update process. If the new image file has a newer version number, the switch writes the file to the application block portion of flash memory and then resets.

   Caution
   The switch does not forward network traffic while writing the image to flash and during the reset process. This can take several minutes to complete. Some network traffic may be lost.

   This completes the procedure for uploading the AT-S63 image file from a master switch to other switches in an enhanced stack.

Downloaded from www.Manualslib.com manuals search engine

Uploading an AT-S63 Configuration File Switch to Switch

This procedure explains how to upload a boot configuration file on a master AT-9400 Switch to another AT-9400 Switch in an enhanced stack. This procedure provides you with an easy way of distributing a configuration file to different switches that are to share a similar configuration. For an explanation of the boot configuration file, refer to "Working with Boot Configuration Files" on page 146.

Note
You can perform this procedure from a local or remote management session.

Guidelines

Please review the following guidelines before performing the procedure:

- This procedure gives you the choice of uploading the master switch's active boot configuration file or another configuration file in the switch's file system. If you upload the master switch's active boot configuration file, the entire file and all of its commands are uploaded to the other switch, with the exception of routing interface commands. This is to prevent different switches from having the same IP addresses on their routing interfaces. Any routing interfaces already defined on the switch that receives the configuration file from the master switch are not retained.
- If you choose to upload another configuration file from the master switch's file system, the entire file without any modification is transferred to the other switch. This type of upload should be performed with care. If a configuration file contains commands that create routing interfaces with static IP addresses, uploading it onto more than one switch can create an IP address conflict between the switches.
- After the upload is complete, the switch receiving the configuration file marks it as its active boot configuration file and resets. Some network traffic may be lost while the switch reloads its operating software. After the reset is complete, the switch operates with the parameter settings contained in the uploaded configuration file.
- A configuration file should only be uploaded onto the same model of switch as the switch where it was created (for example, AT-9408LC/SP to AT-9408LC/SP). Allied Telesis does not recommend uploading a configuration file onto a switch of a different model (for example, AT-9408LC/SP to AT-9424T/SP). Undesirable switch behavior may result.

Downloaded from www.Manualslib.com manuals search engine

Caution
This procedure causes the switch to reset. Some network traffic may be lost.

To upload a boot configuration file on the master switch to another switch in an enhanced stack, perform the following procedure:

1. From the Main Menu, type **8** to select Enhanced Stacking.

   The Enhanced Stacking menu is shown in Figure 22 on page 86.

2. From the Enhanced Stacking menu, type **2** to select Stacking Services.

   Note
   The "2 - Stacking Services" selection is available only on master switches.

   The Stacking Services menu is shown in Figure 23 on page 88.

3. From the Stacking Services menu, type **1** to select Get/Refresh List of Switches. The master switch polls the subnet for other enhanced stacking switches in the same enhanced stack and displays the switches in the Stacking Services menu.

4. Type **5** to select Load Configuration File.

   The following prompt is displayed:

   ```
   Remote switches will reboot after load is complete

   Do you want to load the last saved master configuration?
   [Yes/No] ->
   ```

5. If you want to upload the master switch's active boot configuration file onto the other switch, type **Y** for yes and go to step 7. If you want to upload a different configuration file from the master switch, type **N** for no.

   The following prompt is displayed:

   ```
   Enter the configuration file name ->
   ```

6. Enter the name of the configuration file stored in the master switch's file system you want to upload. The name must include the suffix ".cfg". (To view the names of the configuration files, refer to "Displaying System Files" on page 159.)

Downloaded from www.Manualslib.com manuals search engine

After you have entered a name, the following prompt is displayed:

```
Enter the list of switches ->
```

7. Enter the number (Num column in the menu) of the AT-9400 Switch to receive the configuration file. You can specify more than one switch at a time (for example, 2,4,5).

Note
Do not upload a configuration file from the AT-9400 Switch onto any other type of switch.

The following prompt is displayed:

```
Do you want confirmation before downloading each switch -
> [Yes/No]
```

8. If you answer Yes to this prompt, the management software prompts you with a confirmation message before uploading the file to a switch. If you answer No, the management software does not display a confirmation prompt.

   The management software begins the upload. A switch, after receiving the configuration file, automatically designates it as its new active boot configuration file and resets. After the reset is complete, the switch operates with the parameter settings in its new configuration file.

Caution
The switch does not forward network traffic during the reset. Some network traffic may be lost.

Downloaded from www.Manualslib.com manuals search engine

Downloading a System File

This section contains the following two procedures:

- “Downloading a System File from a Local Management Session” on page 184
- “Downloading a System File from a Remote Management Session” on page 187

Both procedures are used to download files into a switch’s file system. One procedure downloads files from a local management using either Xmodem or TFTP, and the other explains how to do it from a remote management session using TFTP.

There are only two files that you are ever likely to download into a switch’s file system:

- Boot configuration file
- CA certificate

You might have edited a boot configuration file at your management workstation and want to download it onto a switch prior to designating it as the active boot configuration file. Or, you might have obtained a CA certificate for the switch so that you can add encryption to your web browser management sessions.

Note that you can also use these procedures to store an AT-S63 image file in the switch’s file system. However, placing an image file in the file system does not make it the active image file on the switch, and it will take up a large portion of the file system. To be active, the file must be stored in the switch’s application block, which is a separate part of flash memory from the file system. To download an AT-S63 image file directly to a switch’s application block so that it functions as the active image file on the unit, see “Downloading the AT-S63 Image File onto a Switch” on page 168 or “Uploading the AT-S63 Image File Switch to Switch” on page 176. If you do load the image file into a switch’s file system, the only means of transferring it into the application block is with the LOAD command in the command line interface. An image file is about 2MB; it will take up approximately a quarter of the 8MB of storage capacity of the switch’s file system.

Guidelines

This section contains guidelines for downloading a file to the switch’s file system.

These guidelines apply to both Xmodem and TFTP downloads.

- You can use either Xmodem or TFTP to download files from a local management session.

Downloaded from www.Manualslib.com manuals search engine

- You must use TFTP to download files from a remote management session.
- If the switch supports a flash memory card, you can use these procedures to download a file to the card rather than the switch's file system. To download a file to a flash memory card, you should first change to the directory where you want to store the file on the card. This procedure does not accept a directory path. For instructions on to change to a different directory on a memory card, refer to "Changing the Current Flash Card Directory" on page 166.
- Downloading the same configuration file onto multiple switches can create IP address conflicts among the devices if the file contains commands for creating routing interfaces with static IP addresses. This may require adjusting the IP addresses of the routing interfaces after a configuration file is uploaded onto a switch.
- A configuration file should only be downloaded onto the same model of switch as the switch where it was created (for example, AT-9408LC/SP to AT-9408LC/SP). Allied Telesis does not recommend uploading a configuration file onto a switch of a different model (for example, AT-9408LC/SP to AT-9424T/SP). Undesirable switch behavior may result.
- You cannot download a private encryption key onto a switch, but you can download a public key. However, because the switch can only use those encryption keys that it has generated itself, Allied Telesis recommends against downloading any keys onto the switch.

These guidelines apply to an Xmodem download:

- Xmodem can only download a file onto the switch where you started the local management session. You cannot use Xmodem to download a file onto a switch accessed through enhanced stacking.
- The file to be downloaded must be stored on the computer or terminal connected to the RS232 terminal port on the switch.

These guidelines apply to a TFTP download:

- The switch must have a routing interface on the local subnet from where it reaches the TFTP server. The switch uses the IP address of the interface as its source address when sending packets to the TFTP server. For switches without an IP address, such as slave switches, you can download the file from a local management session of the switch using Xmodem.
- Your network must have a node with TFTP server software.
- The file to be downloaded must be stored on the TFTP server.
- You should start the TFTP server software before you begin the download procedure.

Downloaded from www.Manualslib.com manuals search engine

Downloading a System File from a Local Management Session

Review “Guidelines” on page 182 before performing this procedure.

To download a system file onto a switch from a local management session using Xmodem or TFTP, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **9** to select System Utilities.

   The System Utilities menu is shown in Figure 6 on page 43.

3. From the System Utilities menu, type **2** to select Downloads and Uploads.

   The Downloads and Uploads menu is shown in Figure 54 on page 170.

4. From the Downloads and Uploads menu, type **3** to select Download a File.

   The following prompt is displayed:

   ```
   Download Method/Protocol [X-Xmodem, T-TFTP]:
   ```

5. To download a system file using Xmodem, go to Step 6. To download a file using TFTP, do the following:

   a. Type **T**.

      The following prompt is displayed:

      ```
      TFTP Server IP address:
      ```

   b. Enter the IP address of the TFTP server.

      The following prompt is displayed:

      ```
      Remote File Name:
      ```

   c. Enter the name of the file on the TFTP server you want to download to the switch’s file system. You can specify only one system file.

      The following prompt is displayed:

      ```
      Local File Name:
      ```


Downloaded from www.Manualslib.com manuals search engine

d. Enter a name for the system file. This is the name that the switch will store the file as in its file system. To store the file on a flash memory card in the switch rather than the file system, precede the name with "cflash:".

   The following message is displayed:

   ```
   Getting the file from Remote TFTP Server - Please wait
   ...
   ```

e. If you have not already done so, start the TFTP server software.

   After the switch has downloaded the system file, the following message is displayed:

   ```
   File received successfully!
   ```

f. If you downloaded a configuration file and want to make it the active boot file on the switch, refer to "Setting the Active Boot Configuration File" on page 149. If you downloaded a CA certificate, refer to "Adding a Certificate to the Database" on page 616.

   This completes the procedure for downloading a file into the switch's file system or flash memory card from a local management session using TFTP.

6. To download a file using Xmodem, type **X** at the prompt displayed in Step 5.

   The following prompt is displayed:

   ```
   Local File Name:
   ```

7. Enter a name for the system file. This is the name that the switch will store the file as in its file system. To store the file on a flash memory card in the switch rather than the file system, precede the name with "cflash:".

   The following prompt is displayed:

   ```
   You are going to invoke the Xmodem download utility.
   Do you wish to continue? [Yes/No]

   Note: Please select 1K Xmodem protocol for faster
   download.
   ```

   Note
   The transfer protocol must be Xmodem or 1K Xmodem.

8. Type **Y** for Yes.

Downloaded from www.Manualslib.com manuals search engine

The prompt “Downloading” is displayed.

9. Begin the file transfer of the system file using the terminal emulator program.

   Steps 10 through 14 illustrate how to download a system file using the Hilgraeve HyperTerminal program.

10. From the HyperTerminal main window, select **Send File** from the **Transfer** menu, as shown in Figure 58.



Figure 58. HyperTerminal Window

The Send File window is shown in Figure 59.



Figure 59. Send File Window

11. Click **Browse** and specify the location and system file to be downloaded onto the switch.

12. Click in the Protocol field and select as the transfer protocol either Xmodem or, for a faster download, 1K XModem.

13. Click **Send**.

Downloaded from www.Manualslib.com manuals search engine

The file immediately begins downloading onto the switch. The Xmodem File Send window in Figure 60 displays the current status of the download.



Figure 60. XModem File Send Window

The download is complete when the Downloads and Uploads menu is redisplayed.

14. If you downloaded a configuration file and want to make it the active boot file on the switch, refer to "Setting the Active Boot Configuration File" on page 149. If you downloaded a CA certificate, refer to "Adding a Certificate to the Database" on page 616.

    This completes the procedure for downloading a file into the switch's file system or flash memory card from a local management session using Xmodem.

Downloading a System File from a Remote Management Session

Review "Guidelines" on page 182 before performing this procedure.

To download a system file onto a switch from a remote management session using TFTP, perform the following procedure:

1. Establish a remote management session on the switch where you intend to download the new file.

2. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

3. From the System Administration menu, type **9** to select System Utilities.

Downloaded from www.Manualslib.com manuals search engine

The System Utilities menu is shown in Figure 6 on page 43.

4. From the System Utilities menu, type **2** to select Downloads and Uploads.

   The Downloads and Uploads menu is shown in Figure 54 on page 170.

5. From the Downloads and Uploads menu, type **3** to select Download a File.

   The following prompt is displayed:

   ```
   Only TFTP downloads are available for a Telnet access

   TFTP Server IP address:
   ```

6. Enter the IP address of the TFTP server.

   The following prompt is displayed:

   ```
   Remote File Name:
   ```

7. Enter the name of the file on the TFTP server you want to download into the switch's file system.

   The following prompt is displayed:

   ```
   Local File Name:
   ```

8. Enter a name for the system file. This is the name that the switch will store the file as in its file system. To store the file on a flash memory card in the switch rather than the file system, precede the name with "cflash:".

   The following message is displayed:

   ```
   Getting the file from Remote TFTP Server - Please wait
   ...
   ```

9. If you have not already done so, start the TFTP server software.

   After the switch has downloaded the system file, the following message is displayed:

   ```
   File received successfully!
   ```

10. If you downloaded a configuration file and want to make it the active boot file on the switch, refer to "Setting the Active Boot Configuration File" on page 149. If you downloaded a CA certificate, refer to "Adding a Certificate to the Database" on page 616.

Downloaded from www.Manualslib.com manuals search engine

This completes the procedure for downloading a file into the switch's file system or flash memory card from a remote management session using TFTP.

Downloaded from www.Manualslib.com manuals search engine

Uploading a System File

This section contains the following two procedures:

- “Uploading a System File from a Local Management Session” on page 191
- “Uploading a System File from a Remote Management Session” on page 194

These procedures explain how to upload files from a switch’s file system to your management workstation or a TFTP server. One procedure explains how to perform the upload from a local management using either Xmodem or TFTP. The other explains how to upload a file from a remote management session, which only supports TFTP.

Here are the system files you are most likely to upload from a switch:

- Boot configuration file
- Certificate enrollment request
- Public encryption key

You might, for instance, upload a switch’s configuration file so that you can modify it with a text editor at your management workstation. Or, you might have created a CA certificate enrollment request on the switch and need to upload it prior to submitting it to a CA.

Note
The certificate enrollment request and the public encryption key are supported only on the version of AT-S63 management software that features SSL and PKI security.

Guidelines

This section contains guidelines for uploading a file from the switch’s file system.

These guidelines apply to both Xmodem and TFTP uploads.

- You can use either Xmodem or TFTP when uploading files from a local management session.
- You must use TFTP when uploading files from a remote management session.
- If the switch supports a flash memory card, you can use these procedures to upload a file from the card rather than the switch’s file system. To upload a file from a flash memory card, you must first change to the directory where the file is stored on the card. For instructions, refer to “Changing the Current Flash Card Directory” on page 166.

Downloaded from www.Manualslib.com manuals search engine

- To upload a public key, you must first export it from the key database into the switch's file system. For instructions, refer to "Exporting an Encryption Key" on page 602. Public keys have the file name extension ".key."
- You cannot upload an encryption key pair. Key pairs have the file name extension ".ukf." (The prohibition against uploading an encryption key pair is to prevent an unauthorized individual from obtaining the private key.)

This guideline applies only to an Xmodem upload:

- Xmodem can upload a file only from the switch where you started the local management session. You cannot use Xmodem to upload a file from a switch accessed through enhanced stacking.

These guidelines apply only to a TFTP upload:

- Your network must have a node with the TFTP server software.
- You should start the TFTP server software before beginning the download procedure.
- The switch must have a routing interface on the local subnet from where it reaches the TFTP server. The switch uses the IP address of the interface as its source address when sending packets to the TFTP server. For switches without a routing interface, you can download the file from a local management session of the switch using Xmodem.

Uploading a System File from a Local Management Session

Review "Guidelines" on page 190 before performing this procedure.

To upload a file from the switch's file system to a workstation or TFTP server from a local management session using Xmodem or TFTP, perform the following procedure:

1. Establish a local management session on the switch where you want to upload the system file.
2. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.
3. From the System Administration menu, type **9** to select System Utilities.

   The System Utilities menu is shown in Figure 6 on page 43.
4. From the System Utilities menu, type **2** to select Downloads and Uploads.

   The Downloads and Uploads menu is shown in Figure 54 on page 170.

Downloaded from www.Manualslib.com manuals search engine

5. From the Downloads and Uploads menu, type **4** to select Upload a File.

   The following prompt is displayed:

   ```
   Upload Method/Protocol [X-Xmodem, T-TFTP]:
   ```

6. To upload a system file using Xmodem, go to Step 7. To upload a file using TFTP, do the following:

   a. Type **T**.

      The following prompt is displayed:

      ```
      TFTP Server IP address:
      ```

   b. Enter the IP address of the TFTP server.

      The following prompt is displayed:

      ```
      Remote File Name:
      ```

   c. Enter a name for the file for when it is stored on the TFTP server.

      The following message is displayed:

      ```
      Local File Name:
      ```

   d. Enter the name of the system file in the switch's file system that you want to upload to the TFTP server. You can specify only one file. You cannot use wildcards in the file name. If the file is stored on a flash memory card, precede the name with "cflash:".

      The following message is displayed:

      ```
      Sending the file to Remote TFTP Server - Please wait
      ...
      ```

      After the switch has uploaded the system file, the following message is displayed:

      ```
      File sent successfully!
      ```

      The file is now stored on the TFTP server. This completes the procedure for uploading a file using TFTP from a local management session.

7. To upload a file using Xmodem, type **X** at the prompt displayed in Step 5.

   The following message is displayed:

   ```
   Local File Name:
   ```


Downloaded from www.Manualslib.com manuals search engine

8. Enter the name of the system file on the switch that you want to upload to your computer. You can specify only one file. You cannot use wildcards in the file name. If the file is stored on a flash memory card, precede the name with "cflash:".

   The following prompt is displayed:

   ```
   You are going to invoke the Xmodem download utility.
   Do you wish to continue? [Yes/No]

   Note: Please select 1K Xmodem protocol for faster
   download.
   ```

   Note
   The transfer protocol must be Xmodem or 1K Xmodem.

9. Type **Y** for Yes.

   The following message is displayed:

   ```
   Use Hyper Terminal's 'Transfer/Receive File' option to
   select Protocol

   Note: Please select '1K Xmodem' protocol for faster
   upload...
   ```

10. Begin the file transfer.

    Steps 11 through 14 illustrate how you would upload a file using the Hilgraeve HyperTerminal program.

11. From the HyperTerminal main window, select **Receive File** from the **Transfer** menu, as shown in Figure 61.



Figure 61. HyperTerminal Window

Downloaded from www.Manualslib.com manuals search engine

The Receive File window is shown in Figure 62.



Figure 62. Receive File Window

12. Click **Browse** and specify the location on your computer where you want the system file stored.

13. Click in the Protocol field and select as the transfer protocol either Xmodem or, for a faster download, 1K XModem.

14. Click **Receive**.

15. When prompted, enter a name for the file. This is the name given the file when it is stored on your workstation. When naming a file, be sure to give it the same extension as the original file name (for example, ".cfg" for a configuration file and ".csr" for an CA certificate enrollment request.)

    The switch uploads the file from the switch to your computer. This completes the procedure for uploading a file from the switch from a local management session using Xmodem.

Uploading a System File from a Remote Management Session

Review "Guidelines" on page 190 before performing this procedure.

To upload a system file from the switch using a remote management session and TFTP, perform the following procedure:

1. Establish a remote management session on the switch containing the system file you want to upload to the TFTP server.

2. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

3. From the System Administration menu, type **9** to select System Utilities.

   The System Utilities menu is shown in Figure 6 on page 43.

Downloaded from www.Manualslib.com manuals search engine

4. From the System Utilities menu, type **2** to select Downloads and Uploads.

   The Downloads and Uploads menu is shown in Figure 54 on page 170.

5. From the Downloads and Uploads menu, type **4** to select Upload a File.

   The following prompt is displayed:

   ```
   Only TFTP uploads are available for a Telnet access

   TFTP Server IP address:
   ```

6. Enter the IP address of the TFTP server.

   The following prompt is displayed:

   ```
   Remote File Name:
   ```

7. Enter a name for the file for when it is stored on the TFTP server. When naming a file, be sure to give it the same extension as the original file name (for example, ".cfg" for a configuration file and ".csr" for an CA certificate enrollment request.)

   The following message is displayed:

   ```
   Local File Name:
   ```

8. Enter the name of the system file on the switch that you want to upload to the TFTP server. You can specify only one file. You cannot use wildcards in the file name. If the file is stored on a flash memory card in the switch, precede the filename with "cflash:".

   The following message is displayed:

   ```
   Sending the file to Remote TFTP Server - Please wait ...
   ```

   After the switch has uploaded the system file, the following message is displayed:

   ```
   File sent successfully!
   ```

   The file is now stored on the TFTP server. This completes the procedure for uploading a file from a remote management session using TFTP.

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Chapter 11

Event Logs and the Syslog Client

This chapter describes how to monitor the activity of a switch by viewing the event messages in the event logs and sending the messages to a syslog server. Sections in the chapter include:

- “Working with the Event Logs” on page 198
- “Configuring Log Outputs” on page 209

Downloaded from www.Manualslib.com manuals search engine

Working with the Event Logs

This section contains the following procedures:

- ❒ “Enabling or Disabling the Event Logs,” next
- ❒ “Displaying an Event Log” on page 199
- ❒ “Modifying the Event Log Full Action” on page 205
- ❒ “Clearing an Event Log” on page 206
- ❒ “Saving an Event Log to a File” on page 206

Enabling or Disabling the Event Logs

This procedure explains how to enable or disable the event logs on the switch. If you disable the logs, the AT-S63 Management Software does not store events in its logs and does not send events to any syslog servers. The default setting for the event logs is enabled.

> **Note**
> Allied Telesis recommends setting the switch’s date and time if you enable the event logs. Otherwise, event messages will not have the correct time and date. For instructions, refer to “Setting the System Time” on page 38.

To enable or disable the event logs, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.
2. From the System Administration menu, type **8** to select Event Log. The Event Log menu is shown in Figure 63.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                        Event Log

 1 - Event Logging .......... Enabled
 2 - Display Output ......... Temporary (Memory)
 3 - Display Order .......... Chronological
 4 - Display Mode ........... Normal
 5 - Display Severity ....... E, W, I
 6 - Display Module ......... All

 C - Clear Log
 L - Configure Log Outputs
 S - Save Log to File
 V - View Log
 R - Return to Previous Menu

 Enter your selection?
```

Figure 63. Event Log Menu

Downloaded from www.Manualslib.com manuals search engine

3. To enable or disable event logging, type **1** to toggle Event Logging between the two options:

   Enabled
   The switch immediately begins to add events to the logs and send events to any defined syslog servers. This is the default.

   Disabled
   The switch does not store events in the logs and does not send events to any syslog servers.

   Note
   You cannot individually disable or enable the temporary and permanent event logs.

   Note
   When the event log feature is disabled and the switch is rebooted, initialization events are still stored in the logs.

4. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

   To display the events in a log, go to the next procedure.

Displaying an Event Log

To view the events in an event log, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.
2. From the System Administration menu, type **8** to select Event Log.

   The Event Log menu is shown in Figure 63 on page 198.

3. To specify the event log whose events you want to view, type **2** to select Display Output and toggle between these two options:

   Temporary (Memory)
   Displays the events stored in temporary memory. This selection stores approximately 4,000 events. If the switch has been running for some time without a reset or power cycle, select Temporary. This is the default.

   Permanent (NVS)
   Displays events stored in nonvolatile memory, which stores no more than 2,000 events. If the switch was recently reset or power cycled and you want to view the events that occurred prior to the reset, select Permanent.

Downloaded from www.Manualslib.com manuals search engine

4. To select the order of the events in the event log, type **3** to select Display Order and toggle between these two options:

   Chronological
   Displays the events in the order from the oldest event to the most recent event. This is the default.

   Reverse Chronological
   Displays the events from the most recent event to the oldest event.

5. To select the format of the event log, type **4** to select Display Mode and toggle between these two options:

   Normal
   Displays the time, module, severity, and description for each event. This is the default. An example of Normal mode is shown in Figure 64 on page 203.

   Full
   Displays the same information as Normal, plus the file name, line number, and event ID. An example of Full mode is shown in Figure 65 on page 204.

6. To display events of a selected severity, type **5** to select Display Severity.

   The following prompt is displayed:

   ```
   Enter Severity levels to display (ALL, E - Error, W -
   Warning, I - Information, D - Debug) ->
   ```

   The possible options are:

   ALL
   All messages of the following types are displayed. This is the default.

   E - Error
   Only error messages are displayed. Error messages indicate that the switch operation is severely impaired.

   W - Warning
   Only warning messages are displayed. These messages indicate that an issue may require manager attention.

   I - Information
   Only informational messages are displayed. Informational messages display useful information that you can ignore during normal operation.

   D - Debug
   Debug messages provide detailed high-volume information that is intended only for technical support personnel.

   You can select more than one severity at a time, separated by a comma, for example, E,W.

Downloaded from www.Manualslib.com manuals search engine

7. To view the events of a particular AT-S63 software module, type **7** to select Event Module and enter the module. To specify more than one module, separate them by a comma—for example, "system, stp, ptrunk." The default is ALL, which displays the events of all the modules.

   The AT-S63 Management Software consists of modules, each responsible for a different part of switch operation. You can instruct the switch to display only those events that were generated by specific modules. Table 1 lists of modules.

Table 1. AT-S63 Modules

Module Name	Description
ALL	All modules
ACL	Access control list
CFG	Switch configuration
CLASSIFIER	Classifiers used by ACL and QoS
CLI	Command line interface commands
DOS	Denial of service defense
ENCO	Encryption keys
ESTACK	Enhanced stacking
EVTLOG	Event logs
FILE	File system
GARP	GARP GVRP
HTTP	Web server
IGMPSNOOP	IGMP snooping
IP	System IP configuration
LACP	Link Aggregation Control Protocol
MAC	MAC address table
MGMTACL	Management access control list
MLDSNOOP	MLD snooping
PACCESS	802.1x port-based access control
PCFG	Port configuration
PKI	Public Key Infrastructure
PMIRR	Port mirroring

Downloaded from www.Manualslib.com manuals search engine

Table 1. AT-S63 Modules (Continued)

Module Name	Description
PSEC	MAC address-based port security
PTRUNK	Static port trunking
QOS	Quality of Service
RADIUS	RADIUS authentication protocol
RPS	Redundant power supply
RRP	RRP snooping
RTC	Real time clock
SNMP	SNMP
SSH	Secure Shell protocol
SSL	Secure Sockets Layer protocol
STP	Spanning Tree, Rapid Spanning, and Multiple Spanning Tree protocols
SYSTEM	Hardware status; manager and operator log in and log off events.
TACACS	TACACS+ authentication protocol
TELNET	Telnet
TFTP	TFTP
TIME	System time and SNTP
VLAN	Port-based and tagged VLANs, and multiple VLAN modes
WATCHDOG	Watchdog timer

Downloaded from www.Manualslib.com manuals search engine

8. To display the event messages of the log and settings you have chosen, type **V** to select View Log.

   Figure 64 shows an example of an event log in Normal mode.

```
                  Allied Telesis AT-9424T/SP - AT-S63
                              Marketing
User: Manager                                          11:20:02 02-Mar-2005
                              Event Log

 S   Date      Time       Event
 ---------------------------------------------------------------------
 I   02/24/04  12:31:02   ssh: SSH server disabled
 I   02/24/04  12:31:02   garp: GARP initialized
 I   02/24/04  12:31:02   ptrunk: Trunk initialization succeeded

 Temporary (Memory) Log Events 1 - 10 of 340

 P - Previous Page  N - Next Page  F - First Page  L - Last Page
 R - Return to Previous Menu

 Enter your selection?
```

Figure 64. Event Log Example in Normal Mode

The events are displayed in a table. The columns in the table shown in normal display mode are described below:

S (Severity)
The event's severity. The severity codes and their corresponding severity level and description are shown in Table 2.

Table 2. Event Severity Levels

Severity Code	Severity Level	Description
E	Error	Switch operation is severely impaired.
W	Warning	An issue that may require network manager attention.
I	Information	Useful information that can be ignored during normal operation.
D	Debug	Messages intended for technical support and software development.

Date/Time
The date and time the event occurred.

Event
This item contains two parts. The first part is the name of the module

Downloaded from www.Manualslib.com manuals search engine

within the AT-S63 Management Software that generated the event. The second part is a description of the event.

When you display the events in full mode, more information is included. Figure 65 shows the same portion of the event log in Figure 64 on page 203 but displayed in full mode.

```
                    Allied Telesis AT-9424T/SP - AT-S63
                                Marketing
User: Manager                                              11:20:02 02-Mar-2005
                                Event Log

 S  Date      Time       EventID  Source File:Line Number
                         Event
 ------------------------------------------------------------------------------
 I  02/24/04  12:31:02   323003   atissh.c:518
                         ssh: SSH server disabled
 I  02/24/04  12:31:02   073001   garpmain.c:259
                         garp: GARP initialized
 I  02/24/04  12:31:02   103001   trunkapp.c:220
                         ptrunk: Trunk initialization succeeded

 Temporary (Memory) Log Events 1 - 10 of 340

 P - Previous Page  N - Next Page   F - First Page   L - Last Page
 R - Return to Previous Menu

 Enter your selection?
```

Figure 65. Event Log Example in Full Mode

In addition to the information displayed in Normal mode, the Full mode also displays additional columns in the table, as described below:

Event ID
A unique, random number assigned to each event.

Source File:Line Number
The AT-S63 software source file name and the line number in that source file that produced the event.

9. Type the following to scroll through the event log:

   - **P** - Previous page
   - **N** - Next page
   - **F** - First page
   - **L** - Last page

   To clear the events in a log, go to “Clearing an Event Log” on page 206.

Downloaded from www.Manualslib.com manuals search engine

Modifying the Event Log Full Action

This procedure explains how to control the action of the logs when they reach the maximum capacity of 4,000 events for the temporary log and 2,000 events for the permanent log. A log can either delete the oldest entries as it adds new entries or stop adding entries, so as to preserve the existing log contents. You can set the action independently for the two logs.

The log full action does not apply to syslog servers. The switch continues to send events to the servers even when the event logs are full.

To modify the action taken when an event log becomes full, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.
2. From the System Administration menu, type **8** to select Event Log.

   The Event Log menu is shown in Figure 63 on page 198.
3. From the Event Log menu, type **L** to select Configure Log Outputs.

   The Configure Log Outputs menu is shown in Figure 67 on page 210.
4. From the Configure Log Outputs menu, type **2** to select Modify Log Output.

   The following prompt is displayed:

   ```
   Enter output ID to modify [0 to 20] ->
   ```
5. Type **0** to select the permanent log, or **1** to select the temporary log.

   The following prompt is displayed:

   ```
   Enter new log full action (1-Wrap on Full, 2-Halt on
   Full) ->
   ```
6. Make a selection from the following options:

   1 - Wrap on Full
   When the event log reaches maximum capacity, oldest entries are deleted as new entries are added. This is the default.

   2- Halt on Full
   When the event log reaches maximum capacity, the log stops adding new entries.
7. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Clearing an Event Log

To clear all events from an event log, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.
2. From the System Administration menu, type **8** to select Event Log.

   The Event Log menu is shown in Figure 63 on page 198.
3. From the Event Log menu, type **C** to select Clear Log.

   The following prompt is displayed:

   ```
   Enter output to clear (T=Temporary, P=Permanent) ->
   ```
4. To clear the temporary event log, type **T**. To clear the permanent event log, type **P**.

Saving an Event Log to a File

You can save an event log as a file in a file system to review later or to upload to your management workstation. The file is saved as an ASCII file.

To save the event log as a file in the file system, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.
2. From the System Administration menu, type **8** to select Event Log.

   The Event Log menu is shown in Figure 63 on page 198.
3. Configure options 2 to 6 in the Event Log menu to specify which log and entries you want saved to the file. For instructions, refer to “Displaying an Event Log” on page 199.
4. From the Event Log menu, type **S** to select Save Log to File.

   A confirmation prompt is displayed.
5. To save the log file, type **Y** for Yes or, to cancel the process, type **N** for No.

   If you type Y, the following prompt is displayed:

   ```
   Enter file name (*.log) ->
   ```
6. Type a name for the file with a `.log` file name extension.

   The following message is displayed:

   ```
   Saving log to file.
   ```


Downloaded from www.Manualslib.com manuals search engine

When the save process is complete, the word "Complete" is displayed, followed by another prompt:

```
Press any key to continue.
```

7. Press any key.

   The log file is saved in the switch's file system as an ASCII file.

8. To view the log file, type **R** to return to the System Administration menu.

9. From the System Administration menu, type **9** to select System Utilities.

   The System Utilities menu is displayed, as shown in Figure 6 on page 43.

10. From the System Utilities menu, type **1** to select File Operations.

    The File Operations menu is displayed, as shown in Figure 47 on page 147.

11. From the File Operations menu, type **7** to select View File.

    The following prompt is displayed:

    ```
    Enter file name to view:
    ```

12. Type the file name with the `.log` file name extension and press Return. A sample log file saved in full mode is shown in Figure 66.

```
                  Allied Telesis AT-9424T/SP - AT-S63
                               Marketing
User: Manager                                        11:20:02 02-Mar-2005
                               View File

Viewing file "second.log"
-------------------------------------------------------------
I     02/24/04    12:31:02    323003         atissh.c:518
                              ssh: SSH server disabled
I     02/24/04    12:31:02    073001         garpmain.c:259
                              garp: GARP initialized
I     02/24/04    12:31:02    103001         trunkapp.c:220
                              ptrunk: Trunk initialization succeeded
-------------------------------------------------------------
N - Next Page
P - Previous Page
U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 66. Sample Log File View

Downloaded from www.Manualslib.com manuals search engine

13. To upload the file to your management station, refer to “Uploading a System File” on page 190.

Downloaded from www.Manualslib.com manuals search engine

Configuring Log Outputs

There are two methods for viewing the events generated by the switch. One approach is to display one of the switch's event logs. The drawback to this method is that you must establish a management session with the switch before you can view the logs and you can view the log of only one switch at a time.

The other way to view events is to configure the switch to send its event messages to a syslog server. A syslog server can store the events of many network devices simultaneously, making it easier for you to view the event messages because they are all stored in one location.

Configuring the switch to send its events to a syslog server involves creating a log output definition. The log output contains the IP address of the syslog server along with other information such as what types of messages you want the switch to send.

Observe the following guidelines when using this feature:

- You can define up to 19 log output definitions.
- The event log feature on the switch must be enabled in order for the switch to send events to a syslog server. For instructions, refer to "Enabling or Disabling the Event Logs" on page 198.
- The local subnet on the switch where the syslog server is a member must have a routing interface. The switch uses the IP address of the routing interface as its source address when communicating with the server. To configure routing interfaces using the menus interface, refer to Chapter 29, "Internet Protocol Version 4 Routing Interfaces" on page 547 in this guide.

Note
Prior to version 2.0.0 of the AT-S63 Management Software, a syslog server had to be a member of the switch's management VLAN. This restriction no longer applies. The server can be located on any local subnet of the switch that has a routing interface.

This section contains the following procedures:

- "Creating a Log Output Definition" on page 210
- "Modifying a Log Output" on page 215
- "Deleting a Log Output" on page 216
- "Displaying the Log Output Definition Details" on page 217

Downloaded from www.Manualslib.com manuals search engine

Creating a Log Output Definition

To create a log output definition, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.
2. From the System Administration menu, type **8** to select Event Log.

   The Event Log menu is shown in Figure 63 on page 198.

3. From the Event Log menu, type **L** to select Configure Log Outputs.

   The Configure Log Outputs menu, with a list of any log outputs that have already been created, is shown in Figure 67.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                  Configure Log Outputs

 OutputID  Type       Status   Details
 ------------------------------------------------------
 0         Permanent  Enabled  Wrap on Full
 1         Temporary  Enabled  Wrap on Full

 1 - Create Log Output
 2 - Modify Log Output
 3 - Delete Log Output
 4 - View Log Output Details

 R - Return to Previous Menu

 Enter your selection?
```

Figure 67. Configure Log Outputs Menu

   Output 0 is the event log in permanent memory and Output 1 is the log in temporary memory.

4. From the Configure Log Outputs menu, type **1** to select Create Log Output.

   The following prompt is displayed:

   ```
   Enter output type (1-SYSLOG) ->
   ```

5. Enter **1** for Syslog, the only available selection.

Downloaded from www.Manualslib.com manuals search engine

The Syslog Output Configuration menu is displayed, as shown in Figure 68.

```
          Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                          11:20:02 02-Mar-2005
                Syslog Output Configuration

 1 - Output ID ................. <not defined>
 2 - Server IP Address ........ 0.0.0.0
 3 - Output Status ............ Disabled
 4 - Message Format ........... Extended
 5 - Facility Level ........... DEFAULT
 6 - Event Severity ........... E,W,I
 7 - Event Module ............. All

 C - Create Log Output
 R - Return to Previous Menu

 Enter your selection?
```

Figure 68. Syslog Output Configuration Menu

6. From the Syslog Output Configuration menu, type **1** to select Output ID.

   The following prompt is displayed:

   ```
   Enter new output ID [2 to 20] ->2
   ```

7. Type a number between 2 and 20 and press Enter. The output definition is identified in the Configure Log Outputs menu by this number. The default is the next available number. You cannot use a number that is already assigned.

8. Type **2** to select Server IP Address.

   The following prompt is displayed:

   ```
   Enter server IP address:
   ```

9. Type the IP address of the syslog server.

10. Type **3** to toggle Output Status between the following options:

    Enabled
    Enables the syslog output definition. When enabled, the switch sends events to the specified syslog server.

    Disabled
    Disables the syslog output definition. When disabled, which is the default, the switch does not send events to the syslog server.

Downloaded from www.Manualslib.com manuals search engine

11. Type **4** to toggle Message Format between the following options:

    Normal
    Sends the severity, module, and description for each event.

    Extended
    Sends the same information as Normal along with the date, time, and switch's IP address. This is the default.

12. Type **5** to select Facility Level.

    The following prompt is displayed:

    ```
    Enter Facility level (0-DEFAULT, 1-LOCAL1, 2-LOCAL2, 3-
    LOCAL3, 4-LOCAL4, 5-LOCAL 5, 6-LOCAL6, 7-LOCAL7) ->  [0
    to 7] ->
    ```

    This parameter adds a facility level to the entries when they are sent to the syslog server. The facility level is a numerical code that you can use to help group entries on the syslog server according to the module or switch that produced them. This grouping can help you determine which events belong to which device when a syslog server is collecting events from several network devices. You can specify only one facility level.

    There are two approaches to using this parameter. The first is to use the 0-DEFAULT setting which is based on the functional groupings as defined in the RFC 3164 standard. The numerical codes applicable to the AT-S63 Management Software and its modules are shown in Table 3.

Table 3. Applicable RFC 3164 Numerical Code and AT-S63 Module Mappings

Numerical Code	RFC 3164 Facility	AT-S63 Module
4	Security and authorization messages	Security modules: - PSEC - PACCESS - ENCO - PKI - SSH - SSL - MGMTACL - DOS Authentication modules: - SYSTEM - RADIUS - TACACS+

Downloaded from www.Manualslib.com manuals search engine

Table 3. Applicable RFC 3164 Numerical Code and AT-S63 Module Mappings (Continued)

Numerical Code	RFC 3164 Facility	AT-S63 Module
9	Clock daemon	Time- based modules: - TIME (system time and SNTP) - RTC
22	Local use 6	Physical interface and data link modules: - PCFG - PMIRR - PTRUNK - STP - VLAN
23	Local use 7	SYSTEM events related to major exceptions.
16	Local use 0	All other modules and events.

For example, the setting of DEFAULT assigns all port mirroring events a code of 22 and all encryption key events a code of 4.

Your other option is to assign the same numerical code to all events from a switch using one of the following facility level settings:

- 1 - LOCAL1
- 2 - LOCAL2
- 3 - LOCAL3
- 4 - LOCAL4
- 5 - LOCAL5
- 6 - LOCAL6
- 7 - LOCAL7

Each setting represents a predefined RFC 3164 numerical code. The code mappings are listed in Table 4.

Table 4. Numerical Code and Facility Level Mappings

Numerical Code	Facility Level Setting
17	LOCAL1
18	LOCAL2
19	LOCAL3

Downloaded from www.Manualslib.com manuals search engine

Table 4. Numerical Code and Facility Level Mappings (Continued)

Numerical Code	Facility Level Setting
20	LOCAL4
21	LOCAL5
22	LOCAL6
23	LOCAL7

For example, selecting LOCAL2 as the facility level assigns the numerical code of 18 to all events sent by the switch to the syslog server.

13. To include events of a selected severity, type **6** to select Event Severity.

    The following prompt is displayed:

    ```
    Enter Severity levels to display (ALL, E - Error, W -
    Warning, I - Information, D - Debug) ->
    ```

    The possible options are:

    ALL
    All messages of the following types are displayed. This is the default.

    E - Error
    Only error messages are displayed. Error messages indicate that the switch operation is severely impaired.

    W - Warning
    Only warning messages are displayed. These messages indicate that an issue may require manager attention.

    I - Information
    Only informational messages are displayed. Informational messages display useful information that you can ignore during normal operation.

    D - Debug
    Debug messages provide detailed high-volume information that is intended only for technical support personnel.

    You can select more than one severity at a time, separated by a comma, for example, E,W.

14. To send events generated by a particular AT-S63 software module, type **7** to select Event Module.

    The list of modules is displayed, as shown in Table 1, “AT-S63 Modules” on page 201. The default is All.

Downloaded from www.Manualslib.com manuals search engine

15. Enter a list of modules separated by a comma—for example, "system, stp, ptrunk."

16. Type **C** to create the log output.

    The switch adds the new syslog server definition to the Configure Log Outputs menu and begins to send events to the sever, if you enabled the definition when you created it. An example of the menu with a new syslog server definition is shown in Figure 69.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                   Configure Log Outputs

 OutputID  Type       Status   Details
 ------------------------------------------------------
 0         Permanent  Enabled  Wrap on Full
 1         Temporary  Enabled  Wrap on Full
 2         Syslog     Enabled  149.44.44.44

 1 - Create Log Output
 2 - Modify Log Output
 3 - Delete Log Output
 4 - View Log Output Details

 R - Return to Previous Menu

 Enter your selection?
```

Figure 69. Configure Log Outputs Menu with a Syslog Output Definition

17. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Modifying a Log Output

To modify an log output definition, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

2. From the System Administration menu, type **8** to select Event Log.

   The Event Log menu is shown in Figure 63 on page 198.

3. From the Event Log menu, type **L** to select Configure Log Outputs.

   The Configure Log Outputs menu is shown in Figure 67 on page 210.

4. From the Configure Log Outputs menu, type **2** to select Modify Log Output.

   The following prompt is displayed:

   ```
   Enter output ID to modify [0 to 20] ->
   ```


Downloaded from www.Manualslib.com manuals search engine

5. Enter the number of the log output that you want to modify.

   The Syslog Output Configuration menu is displayed, as shown in Figure 68 on page 211.

6. Refer to “Creating a Log Output Definition” on page 210 for information about the menu selections.

7. When you complete the modifications, type **M** to select Modify Log Output.

   The Configure Log Outputs menu as shown in Figure 67 on page 210 is redisplayed.

8. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Deleting a Log Output

To delete a log output definition, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

2. From the System Administration menu, type **8** to select Event Log.

   The Event Log menu is shown in Figure 63 on page 198.

3. From the Event Log menu, type **L** to select Configure Log Outputs.

   The Configure Log Outputs menu is shown in Figure 67 on page 210.

4. From the Configure Log Outputs menu, type **3** to select Modify Log Output.

   The following prompt is displayed:

   ```
   Enter output ID to delete [2 to 20] ->
   ```

5. Enter the number of the log output that you want to delete.

   The following prompt is displayed:

   ```
   Are you sure you want to delete output ID x? [Yes/No] ->
   ```

6. Enter **Y** for Yes or **N** for No and press Enter.

   If you enter Y, the output ID you selected is deleted.

7. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Displaying the Log Output Definition Details

To view the settings of a log output definition, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.
2. From the System Administration menu, type **8** to select Event Log.

   The Event Log menu is shown in Figure 63 on page 198.
3. From the Event Log menu, type L to select Configure Log Outputs.

   The Configure Log Outputs menu is shown in Figure 67 on page 210.
4. From the Configure Log Outputs menu, type **4** to select View Log Output Details.

   The following prompt is displayed:

   ```
   Enter output ID to view [0 to 20] ->
   ```
5. Enter the number of the log output that you want to view.

   The Syslog Output Configuration menu for the selected output is displayed. An example is shown in Figure 70.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
               Syslog Output Configuration

 1 - Output ID ................ 3
 2 - Server IP Address ........ 149.35.87.45
 3 - Output Status ............ Enabled
 4 - Message Format ........... Extended
 5 - Facility Level ........... DEFAULT
 6 - Event Severity ........... E,W,I
 7 - Event Module ............. All

 R - Return to Previous Menu

 Enter your selection?
```

Figure 70. Syslog Output Configuration Menu for Selected Output ID

   To modify the log output configuration, refer to "Modifying a Log Output" on page 215.
6. Return to the Main Menu.

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Chapter 12

Classifiers

This chapter explains classifiers and how you can create classifiers to define traffic flows. The sections in this chapter include:

- “Creating a Classifier” on page 220
- “Modifying a Classifier” on page 224
- “Deleting a Classifier” on page 226
- “Deleting All Classifiers” on page 227
- “Displaying Classifiers” on page 228

Downloaded from www.Manualslib.com manuals search engine

Creating a Classifier

This section contains the procedure for creating a classifier. A classifier contains a series of variables that define a traffic flow. This same procedure is used whether the classifier is intended for an ACL or a QoS policy.

To create a classifier, perform the following procedure

1. From the Main Menu, type **7** to select Security and Services.

   The Security and Services menu is shown in Figure 71.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                           11:20:02 02-Mar-2005
                    Security and Services
1 - Classifier Configuration
2 - Port Access Control (802.1x)
3 - Denial of Service (DoS)
4 - Access Control Lists (ACL)
5 - Class of Service (CoS)
6 - Quality of Service (QoS)
7 - Keys/Certificates Configuration
8 - Secure Shell (SSH)
9 - Secure Socket Layer (SSL)

R - Return to Previous Menu

Enter your selection?
```

Figure 71. Security and Services Menu

2. From the Security and Services menu, type **1** to select Classifier Configuration.

Downloaded from www.Manualslib.com manuals search engine

The Classifier Configuration menu is shown in Figure 72.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                  Classifier Configuration
1 - Create Classifier
2 - Modify Classifier
3 - Destroy Classifier
4 - Show Classifiers

P - Purge Classifiers
R - Return to Previous Menu

Enter your selection?
```

Figure 72. Classifier Configuration Menu

3. From the Classifier Configuration menu, type **1** to select Create Classifier.

   The Create Classifier menu (page 1) is shown in Figure 73.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                    Create Classifier
01 - Classifier ID: . 2
02 - Description: ...
03 - Dst MAC: .......
04 - Src MAC: .......
05 - Eth Format .....
06 - Priority: ......
07 - VLAN ID: .......
08 - Protocol: ......
09 - IP ToS: ........
10 - IP DSCP: .......

E - Edit Parameters
C - Create Classifier
N - Next Page
U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 73. Create Classifier Menu (Page 1)

Downloaded from www.Manualslib.com manuals search engine

This is the first page of the classifier variables. To view the remaining variables, type **N** to select Next Page. The Create Classifier menu (page 2) is shown in Figure 74.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                           11:20:02 02-Mar-2005
                     Create Classifier
11 - IP Protocol: ...
12 - Src IP Addr: ...
13 - Src IP Mask: ...
14 - Dst IP Addr: ...
15 - Dst IP Mask: ...
16 - TCP Src Port: ..
17 - TCP Dst Port: ..
18 - UDP Src Port: ..
19 - UDP Dst Port: ..
20 - TCP Flags: .....

E - Edit Parameters
C - Create Classifier
P - Previous Page
U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 74. Create Classifier Menu (Page 2)

4. To set a variable, type **E** to select Edit Parameters.

   The following prompt is displayed.

   ```
   Enter parameter ID to edit: [1 to 19] ->1
   ```

5. Enter the number of the variable to be configured. You can configure only one parameter at a time.

   Note
   Item 1 allows you to assign the classifier an ID number. Each classifier must have a unique number. The range is 1 to 9999. The default is the lowest available number.

   Item 2 allows you to assign a description to a classifier. You should assign a description to each classifier. A description helps you identify the different classifiers on the switch. A description can be up to fifteen alphanumeric characters, including spaces. An example of a description is “IP traffic flow”.

6. Adjust the new value for the variable.

Downloaded from www.Manualslib.com manuals search engine

7. Repeat steps 5 and 6 to adjust any other variables necessary to define the traffic flow for this classifier.

8. After configuring the necessary variables, type **C** to select Create Classifier.

   The switch creates the classifier. If any of the settings are incompatible, the system displays an error message.

9. To create more classifiers, repeat this procedure starting with step 3.

10. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

11. To add classifiers to an ACL, refer to "Creating an ACL" on page 232. To add classifiers to a QoS policy, refer to "Managing Flow Groups" on page 252.

Downloaded from www.Manualslib.com manuals search engine

Modifying a Classifier

In order to modify a classifier, you need to know its ID number. If you are unsure of the ID number of the classifier you want to modify, refer to “Displaying Classifiers” on page 228.

You cannot modify a classifier if it belongs to an ACL or QoS policy that is assigned to a port. You must first remove the port assignments from the ACL or policy before you can modify the classifier.

To modify a classifier, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.

   The Security and Services menu is shown in Figure 71 on page 220.

2. From the Security and Services menu, type **1** to select Classifier Configuration.

   The Classifier Configuration menu is shown in Figure 72 on page 221.

3. From the Classifier Configuration menu, type **2** to select Modify Classifier.

   The prompt similar to the following is displayed:

   ```
   Available Classifier(s): 1-12
   Enter Classifier ID :  [1 to 9999] -> 1
   ```

4. Enter the ID number of the classifier you want to modify.

   The Modify Classifier window is displayed. This window is identical to the Create Classifier menus, shown in Figure 73 on page 221 and Figure 74 on page 222.

5. Edit the variables as needed.

   When modifying a classifier, note the following:

   - ❒ You cannot change a classifier’s ID number.
   - ❒ To delete a value from a variable so as to leave it blank, select the criterion and then use the backspace key to delete its default value.

6. Once you have adjusted the variables, type **M** to select Modify Classifier.

   A change to a classifier is immediately activated. If any of the settings are incompatible, the system displays an error message.

Downloaded from www.Manualslib.com manuals search engine

7. To modify other classifiers, repeat this process starting with step 3.

8. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

9. To add the modified classifier to an ACL, refer to "Creating an ACL" on page 232 or "Modifying an ACL" on page 235. To add it to a QoS policy, refer to "Managing Flow Groups" on page 252.

Downloaded from www.Manualslib.com manuals search engine

Deleting a Classifier

This procedure deletes a classifier from the switch. To delete a classifier, you need to know its ID number. If you are unsure of the ID number of the classifier you want to delete, refer to “Displaying Classifiers” on page 228.

Note
You cannot delete a classifier if it belongs to an ACL or QoS policy.You must first remove the classifier from its ACL or policy assignments before you can delete it.

To delete a classifier, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.

   The Security and Services menu is shown in Figure 71 on page 220.

2. From the Security and Services menu, type **1** to select Classifier Configuration.

   The Classifier Configuration menu is shown in Figure 72 on page 221.

3. From the Classifier Configuration menu, type **3** to select Destroy Classifier.

   The following prompt is displayed:

   ```
   Enter Classifier ID :  [1 to 9999] -> 1
   ```

4. Enter the ID number of the classifier you want to delete.

   The details of the specified classifier are displayed. Use this window to verify that you are deleting the correct classifier.

5. If this is the correct classifier, type **D** to select Destroy Classifier.

   The classifier is deleted from the switch.

6. To delete additional classifiers, repeat this procedure starting with step 3.

7. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Deleting All Classifiers

This procedure deletes all classifiers from the switch. To delete individual classifiers, refer to "Deleting a Classifier" on page 226.

Note
You cannot delete all classifiers if any of them belong to an ACL or QoS policy.You must first remove all classifiers from their ACL and policy assignments before performing this procedure.

To delete all classifiers from the switch, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.

   The Security and Services menu is shown in Figure 71 on page 220.

2. From the Security and Services menu, type **1** to select Classifier Configuration.

   The Classifier Configuration menu is shown in Figure 72 on page 221.

3. From the Classifier Configuration menu, type **P** to select Purge Classifiers.

Caution
No confirmation prompt is displayed. All classifiers are immediately deleted from the switch.

4. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Displaying Classifiers

To display the classifiers on a switch, do the following:

1. From the Main Menu, type **7** to select Security and Services.

   The Security and Services menu is shown in Figure 71 on page 220.

2. From the Security and Services menu, type **1** to select Classifier Configuration.

   The Classifier Configuration menu is shown in Figure 72 on page 221.

3. From the Classifier Configuration menu, type **4** to select Show Classifiers.

   An example of the Show Classifiers menu is shown in Figure 75.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                            11:20:02 02-Mar-2005
                      Show Classifiers
Number of classifiers: 5

ID    Description       Number of     Number of
                        References    Active Associations
-------------------------------------------------------
1     IP flow           4             3
2     Dst149.11.11.0    1             1
3     TCP flow          1             0
4     Src149.22.22.49   1             1
5     ToS 6             2             2

D - Detail Classifier Display
U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 75. Show Classifiers Menu

The Show Classifiers menu displays the current classifiers in a table with the following columns of information:

ID
The classifier's ID number.

Description
The description of the classifier.

Downloaded from www.Manualslib.com manuals search engine

Number of References
The number of active and inactive ACL and QoS policy assignments for the classifier. An active ACL or QoS policy has been assigned to a switch port while an inactive ACL or policy has not been assigned to a port. If this number is 0 (zero), the classifier has not been assigned to any ACLs or policies.

Number of Active Associations
The number of active ACLs and QoS policy assignments for the classifier. An active ACL or policy has been assigned to a switch port.

You can use this number together with the Number of References to determine the number of inactive ACLs and policies for a classifier. For example, if Number of References for a classifier is 5 and the Number of Active Associations is 3, two of the ACL or QoS policy assignments for the classifier have not been assigned to a switch port.

4. To view the details of a classifier, type **D** to select Detail Classifier Display.

   The following prompt is displayed:

   ```
   Enter Classifier ID :  [1 to 9999] -> 1
   ```

5. Enter the ID number of the classifier you want to display.

   The first page of the Display Classifier Details menu is shown in Figure 76.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                Display Classifier Details
01 - Classifier ID: . 1
02 - Description: ... IP flow
03 - Dst MAC: .......
04 - Src MAC: .......
05 - Priority: ......
06 - VLAN ID: .......
07 - Protocol: ...... 0x800 (IP)
08 - IP ToS: ........
09 - IP DSCP: .......
10 - IP Protocol: ...

N - Next Page
U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 76. Display Classifier Details Menu (Page 1)

Downloaded from www.Manualslib.com manuals search engine

The second page of the Display Classifier Details menu is shown in Figure 77.

```
            Allied Telesis AT-9424T/SP - AT-S63
                         Marketing
User: Manager                            11:20:02 02-Mar-2005
                  Display Classifier Details
11 - Src IP Addr: ...
12 - Src IP Mask: ...
13 - Dst IP Addr: ...
14 - Dst IP Mask: ...
15 - TCP Src Port: ..
16 - TCP Dst Port: ..
17 - UDP Src Port: ..
18 - UDP Dst Port: ..
19 - TCP Flags: .....

P - Previous Page
U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 77. Display Classifier Details Menu (Page 2)

Downloaded from www.Manualslib.com manuals search engine

Chapter 13

Access Control Lists

This chapter explains how to manage access control lists (ACL). This chapter contains the following sections:

- ❒ “Creating an ACL” on page 232
- ❒ “Modifying an ACL” on page 235
- ❒ “Deleting an ACL” on page 237
- ❒ “Deleting All ACLs” on page 239
- ❒ “Displaying ACLs” on page 240

Downloaded from www.Manualslib.com manuals search engine

Creating an ACL

This procedure explains how to create an ACL. In order to perform this procedure, you need to know the ID numbers of the classifiers to be assigned to the ACL. To view classifier ID numbers, refer to “Displaying Classifiers” on page 228.

To create an ACL, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.
2. From the Security and Services menu, type **4** to select Access Control Lists.

   The Access Control Lists (ACL) menu is shown in Figure 78.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                          11:20:02 02-Mar-2005
                Access Control Lists (ACL)

1 - Create ACL
2 - Modify ACL
3 - Destroy ACL
4 - Show ACL

P - Purge ACL
R - Return to Previous Menu

Enter your selection?
```

Figure 78. Access Control Lists (ACL) Menu

3. From the Access Control Lists (ACL) menu, type **1** to select Create ACL.

Downloaded from www.Manualslib.com manuals search engine

The Create ACL menu is shown in Figure 79.

```
            Allied Telesis AT-9424T/SP - AT-S63
                          Marketing
User: Manager                              11:20:02 02-Mar-2005
                          Create ACL

1 - ACL ID ........... 0
2 - Description .......
3 - Action ............ Deny
4 - Classifier List ...
5 - Port List .........

C - Create ACL
R - Return to Previous Menu

Enter your selection?
```

Figure 79. Create ACL Menu

4. Type **1** to select ACL ID and, when prompted, enter an ID number for the ACL. Every ACL on the switch must have a unique ID number. The range is 0 to 255. The default is the lowest unused number. This parameter is required.

5. Type **2** to select Description and enter a description for the ACL. A description can be up to 31 alphanumeric characters. Spaces are allowed. This parameter is optional, though recommended. Assigning the ACLs different names will make it easier for you to identify them.

6. Type **3** to select Action.

   The following prompt is displayed:

   ```
   Enter Value [0 - Deny, 1 - Permit] : [0 to 1] -> 0
   ```

7. Type **0** if you want the ACL to discard ingress packets that meet the criteria in the classifiers to be assigned to the ACL or **1** if the packets are to be accepted. The default setting is Deny.

8. Type **4** to select Classifier List from the Create ACL menu and, when prompted, enter the classifiers to be assigned to the ACL. The prompt includes the ID numbers of the classifiers on the switch. You can assign more than one classifier to an ACL. Separate multiple classifiers with a comma (for example, 4,7,2). The order in which you specify the classifiers is not important.

   When entering classifiers, keep in mind the action that you specified for this ACL in step 7. The action and the traffic flows defined by the classifiers should correspond. For instance, an ACL with an action of permit should be assigned those classifiers that define the traffic flow you want the ports to accept.

Downloaded from www.Manualslib.com manuals search engine

9. Type **5** to select Port List and, when prompted, enter the ports where you want to assign the ACL. You can assign an ACL to just one port or to more than one port. When entering multiple ports, you can list the ports individually (e.g., 2,5,7), as a range (e.g., 8-12) or both (e.g., 1-4,6,8).

10. Type **C** to select Create ACL.

    The ACL is created on the switch and immediately activated on the specified ports.

11. To create additional ACLs, repeat this procedure starting with step 3.

12. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Modifying an ACL

This procedure explains how to modify an ACL. In order to perform this procedure, you need to know the ID number of the ACL. To display ACL ID numbers, refer to "Displaying ACLs" on page 240. If you plan to add classifiers to the ACL, you also need to know the ID numbers of the classifiers. To view classifier ID numbers, refer to "Displaying Classifiers" on page 228.

To modify an ACL, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.
2. From the Security and Services menu, type **4** to select Access Control Lists.

   The Access Control Lists (ACL) menu is shown in Figure 78 on page 232.
3. From the Access Control Lists (ACL) menu, type **2** to selection Modify ACL.

   The following prompt is displayed:

   ```
   Available ACL(s): 0-15
   Enter ACL ID :  [0 to 255] -> 0
   ```
4. Enter the ID number of the ACL you want to modify. You can modify only one ACL at a time.

   The Modify ACL window is displayed with the specifications of the selected ACL. An example of the window is shown in Figure 80.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                            11:20:02 02-Mar-2005
                        Modify ACL

1 - ACL ID ............ 12
2 - Description ....... HTTP - permit
3 - Action ............ Permit
4 - Classifier List ... 18,22
5 - Port List ......... 7,10-14

M - Modify ACL
R - Return to Previous Menu

Enter your selection?
```

Figure 80. Modify ACL Menu

   You cannot change an ACL's ID number.

Downloaded from www.Manualslib.com manuals search engine

5. To change the description of the ACL, type **2** to select Description and enter a new description for the ACL. The description can be up to 31 alphanumeric characters. Spaces are allowed. This parameter is optional, though recommended. Assigning each ACL a name will make it easier for you to identify them.

6. To change the ACL's action, type **3** to select Action.

   The following prompt is displayed:

   ```
   Enter Value [0-Deny, 1-Permit] : [0 to 1] -> 0
   ```

7. Type **0** if you want the ACL to discard ingress packets that meet the criteria in the classifiers to be assigned to the ACL or **1** if the packets are to be accepted. The default setting is Deny.

8. To change the classifiers assigned to the ACL, type **4** to select Classifier List and, when prompted, enter the classifiers. The prompt includes the ID numbers of the classifiers on the switch. You can assign more than one classifier to an ACL. Separate multiple classifiers with a comma (for example, 2,4,7). The order in which you specify the classifiers is not important.

   When entering classifiers, keep in mind the action you specified for this ACL in step 7. The action and the traffic flows defined by the classifiers should correspond. For instance, an ACL with an action of permit should be assigned those classifiers that define the traffic flow you want ports to accept.

9. To change the ports to which the ACL is assigned, type **5** to select Port List and, when prompted, enter the ports where you want to assign the ACL. You can assign an ACL to more than one port. Ports can be listed individually (e.g., 2,5,7), as a range (e.g., 8-12) or both (e.g., 1-4,6,8).

10. Type **M** to select Modify ACL.

    The ACL is modified on the switch. Modifications take affect immediately.

11. To modify additional ACLs, repeat this procedure starting with step 3.

12. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Deleting an ACL

This procedure deletes an ACL from the switch. To perform this procedure, you need to know the ID number of the ACL. To display ACL ID numbers, refer to "Displaying ACLs" on page 240.

To delete an ACL, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.
2. From the Security and Services menu, type **4** to select Access Control Lists.

   The Access Control Lists (ACL) menu is shown in Figure 78 on page 232.
3. From the Access Control Lists (ACL) menu, type **3** to selection Destroy ACL.

   The following prompt is displayed:

   ```
   Available ACL(s): 0-15
   Enter ACL ID :  [0 to 255] -> 0
   ```
4. Enter the ID number of the ACL you want to modify. You can modify only one ACL at a time.

   The Destroy ACL window is displayed with the specifications of the selected ACL. You can use this window to confirm that you are deleting the correct ACL. An example of the window is shown in Figure 81.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                      Destroy ACL

1 - ACL ID ............ 25
2 - Description ....... UDP-deny
3 - Action ............ Deny
4 - Classifier List ... 32
5 - Port List ......... 15,22

D - Destroy ACL
R - Return to Previous Menu

Enter your selection?
```

Figure 81. Destroy ACL Menu

5. To delete the ACL, type **D** to select Destroy ACL. To cancel the procedure, type **R** to select Return to Previous Menu.

Downloaded from www.Manualslib.com manuals search engine

A deleted ACL is immediately removed from the switch.

6. To delete additional ACLs, repeat this procedure starting with step 3.
7. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Deleting All ACLs

This procedure deletes all ACLs from the switch.

To delete all ACLs, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.
2. From the Security and Services menu, type **4** to select Access Control Lists.

   The Access Control Lists (ACL) menu is shown in Figure 78 on page 232.
3. From the Access Control Lists (ACL) menu, type **P** to selection Purge ACLs.

   Caution
   No confirmation prompt is displayed. All ACLs are immediately deleted from the switch.
4. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Displaying ACLs

To display the ACLs on a switch, perform this procedure:

1. From the Main Menu, type **7** to select Security and Services.
2. From the Security and Services menu, type **4** to select Access Control Lists.

   The Access Control Lists (ACL) menu is shown in Figure 78 on page 232.

1. From the Access Control Lists (ACL) menu, type **4** to selection Show ACLs.

   An example of the Show ACLs window is illustrated in Figure 82.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                       Show ACLs

Number of ACLs: 12
ID  Description              Active
-------------------------------------------------------
1   IP - deny                Yes
2   HTTP - permit            Yes
3   TCP - deny               No
4   Src22.49 - deny          Yes
5   P-149.22.22.22           Yes
6   Dst22.50                 Yes
7   ARP packets - deny       No

D - Detail ACL Display
N - Next Page
U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 82. Show ACLs Menu

This menu is for viewing purposes only. To modify an ACL, refer to “Modifying an ACL” on page 235. The columns in the display are explained here:

- ACL ID - The ACL’s ID number.
- Description - The description of the ACL.
- Active - The status of the ACL. An ACL is deemed active if it is assigned to at least one port. An ACL is deemed inactive if it is not assigned to any ports.

Downloaded from www.Manualslib.com manuals search engine

2. To view the details of a ACL, type **D** to select Detail Classifier Display.

   The following prompt is displayed:

   ```
   Enter ACL ID :  [0 to 250] -> 0
   ```

3. Enter the ID number of the ACL you want to display. The details of the selected ACL are displayed.

   An example of the Display ACL Details window is illustrated in Figure 83.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                   Display ACL Details


1 - ACL ID ............... 1
2 - Description ......... IP - Deny
3 - Action ............... Deny
4 - Classifier List ..... 1
5 - Port List ........... 2-4

U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 83. Display ACL Details Menu

This menu is for viewing purposes only. To modify an ACL, refer to "Modifying an ACL" on page 235. The information in the menu is described here:

- ACL ID - The ACL's ID number.
- Description - The description of the ACL.
- Action - The action of the ACL. An active of Permit means that the port(s) where the ACL is assigned accepts those packets that meet the criteria of the ACL's classifiers. An action of Deny means that the port(s) discards the packets provided that the packets do not also meet the criteria of a classifier of a Permit ACL assigned to the same port.
- Classifier List - The classifiers assigned to the ACL. An ACL can have more than one classifier.
- Port List - The ports where the ACL is assigned. An ACL can be assigned to more than one port.

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Chapter 14

Class of Service

This chapter contains the procedures for configuring Class of Service (CoS). Sections in the chapter include:

- ❒ “Configuring CoS” on page 244
- ❒ “Mapping CoS Priorities to Egress Queues” on page 247
- ❒ “Configuring Egress Scheduling” on page 248
- ❒ “Displaying Port CoS Priorities” on page 250

Downloaded from www.Manualslib.com manuals search engine

Configuring CoS

A packet received on a port is placed it into one of eight priority queues on the egress port according to the switch's mapping of 802.1p priority levels to egress priority queues. You can override the mappings at the port level by assigning the packets a temporary priority level. Note that this assignment is made when a packet is received on the ingress port and before the frame is forwarded to the egress port. Consequently, you need to configure this feature on the ingress port.

For example, you can configure a switch port so that all ingress frames are assigned a temporary priority level of 5, regardless of the actual priority levels that might be in the frames themselves, as found in tagged frames.

A temporary priority level applies only while a frame traverses the switching matrix. Tagged frames, which can contain a priority level, leave the switch with the same priority level they had when they entered the switch.

To configure CoS for a port, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.
2. From the Security and Services menu, type **5** to select Class of Service (CoS).

   The Class of Service (CoS) menu is shown in Figure 84.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                 Class of Service (CoS)

Number of CoS Queues: 8
1 - Configure Port CoS Priorities
2 - Map CoS Priority to Egress Queue
3 - Configure Egress Scheduling
4 - Show Port CoS Priorities

R - Return to Previous Menu
Enter your selection?
```

Figure 84. Class of Service (CoS) Menu

The "Number of CoS Queues" line indicates the number of egress queues on each port. The AT-9400 Switch has eight queues per port. This value cannot be changed.

Downloaded from www.Manualslib.com manuals search engine

3. From the Class of Service menu, type **1** to select Configure Port CoS Priorities.

   The following prompt is displayed:

   ```
   Enter port number -> [1 to 24] ->
   ```

4. Enter the number of the port on the switch where you want to configure CoS. You can specify only one port at a time.

   The Configure Port COS Priorities menu is shown in Figure 85.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                              11:20:02 02-Mar-2005
                Configure Port CoS Priorities

1 - Port Number ..................... 1
2 - Priority (0-7) 0=Low 7=High ... 0
3 - Override Priority (Y/N) ....... N

C - Configure Port COS Priorities
R - Return to Previous Menu

Enter your selection?
```

Figure 85. Configure Port COS Priorities Menu

   Menu option 1 cannot be changed.

5. Type **2** to select Priority (0 - 7). The following prompt is displayed:

   ```
   Enter new value -> [0 to 7]
   ```

6. Enter a new temporary priority value of 0 to 7 for the untagged frames received on the port. For example, to assign a temporary priority level of 4 to the ingress untagged packets, enter 4. The default is 0. (If you perform Step 7 and override the priority level in ingress tagged packets, this temporary priority value will also apply to those packets as well.)

7. If you are configuring a tagged port and you want the switch to ignore the priority tag in ingress tagged frames, type **3** to select Override Priority and type **Y**.

   All ingress tagged frames use the temporary priority level specified in Step 6.

Downloaded from www.Manualslib.com manuals search engine

Note
CoS does not change the tagged information in a frame. A tagged frame leaves a switch with the same priority level that it had when it entered.

The default for this parameter is No, meaning that the priority level of tagged frames is determined by the priority level specified in the frames themselves.

8. Type **C** to select Configure Port COS Priorities.

   A change to a port CoS setting is immediately activated on the port.

9. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Mapping CoS Priorities to Egress Queues

This procedure explains how to change the default mappings of CoS priorities to egress priority queues. This is set at the switch level. You cannot set this at the per-port level.

To change the mappings, perform the following procedure.

1. From the Main Menu, type **7** to select Security and Services.
2. From the Security and Services menu, type **5** to select Class of Service (CoS). The Class of Service (CoS) menu is shown in Figure 84 on page 244.
3. From the Class of Service (CoS) menu, type **2** to select Map CoS Priority to Egress Queue.

   The Map CoS Priority to Egress Queue menu is shown in Figure 86.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
             Map CoS Priority to Egress Queue

1 - CoS 0 Priority Queue ..... Q1
2 - CoS 1 Priority Queue ..... Q0
3 - CoS 2 Priority Queue ..... Q2
4 - CoS 3 Priority Queue ..... Q3
5 - CoS 4 Priority Queue ..... Q4
6 - CoS 5 Priority Queue ..... Q5
7 - CoS 6 Priority Queue ..... Q6
8 - CoS 7 Priority Queue ..... Q7

R - Return to Previous Menu
Enter your selection?
```

Figure 86. Map CoS Priority to Egress Queue Menu

4. Type the number of the CoS priority whose queue assignment you want to change. This toggles the queue value through the possible queue settings.

   For example, to direct all tagged packets with a CoS priority of 5 to egress queue Q3, you would toggle 6 until the CoS 5 Priority Queue value reads Q3.
5. If desired, repeat Step 3 to change the queue assignments of other CoS priorities.
6. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Configuring Egress Scheduling

This procedure explains how to select and configure a scheduling method for Class of Service. Scheduling determines the order in which the ports handle packets in their egress queues. Scheduling is set at the switch level. You cannot set this on a per-port basis.

1. From the Main Menu, type **7** to select Security and Services.
2. From the Security and Services menu, type **5** to select Class of Service (CoS).

   The Class of Service (CoS) menu is shown in Figure 84 on page 244.
3. From the Class of Service (CoS) menu, type **3** to select Configure Egress Scheduling.

   The Configure Egress Scheduling menu is shown in Figure 87.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
               Configure Egress Scheduling

1 - Scheduling Mode ............ Strict Priority
2 - Queue 0 Weight ............. 0
3 - Queue 1 Weight ............. 0
4 - Queue 2 Weight ............. 0
5 - Queue 3 Weight ............. 0
6 - Queue 4 Weight ............. 0
7 - Queue 5 Weight ............. 0
8 - Queue 6 Weight ............. 0
9 - Queue 7 Weight ............. 0

R - Return to Previous Menu
Enter your selection?
```

Figure 87. Configure Egress Scheduling Menu

4. Type **1** to toggle Scheduling Mode between its two possible settings. The default setting is Strict Priority.

   If you select Strict Priority, skip the next step. Options 2 through 9 in the menu do not apply to Strict Priority scheduling.
5. If you select Weighted Round Robin Priority as the scheduling method, select menu options 2 through 9 and specify the maximum number of packets a port can transmit from a queue before moving to the next queue. The range for Q0 to Q6 is 1 to 15. The range for Q7 is 0 to 15.

Downloaded from www.Manualslib.com manuals search engine

The default value of 1 for each queue gives all egress queues the same weight.

6. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Displaying Port CoS Priorities

The following procedure displays a menu that lists the current CoS priority level for each port.

1. From the Main Menu, type **7** to select Security and Services.
2. From the Security and Services menu, type **5** to select Class of Service (CoS).

   The Class of Service (CoS) menu is shown in Figure 84 on page 244.
3. From the Class of Service (CoS) menu, type **4** to select Show Port CoS Priorities.

   The Show Port CoS Priorities menu is shown in Figure 88.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                 Show Port CoS Priorities

Port    PVID     Priority   Override Priority
-------------------------------------------

01      1        0          No
02      1        0          No
03      1        0          No
04      1        0          No
05      1        0          No
06      1        0          No
07      1        0          No

N - Next Page
U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 88. Show Port CoS Priorities Menu

The PVID column displays the identifier of the VLAN where the port is an untagged member.

The Priority column displays the temporary priority level assigned to ingress untagged packets on the port.

The Override Priority column indicates whether the priority level in ingress tagged frames is being used or not. If No, the override is deactivated and the port is using the priority levels contained within the frames. If Yes, the override is activated and the tagged packets are assigned the temporary priority level shown in the Priority column.

Downloaded from www.Manualslib.com manuals search engine

Chapter 15

Quality of Service

This chapter describes Quality of Service (QoS). Sections in the chapter include:

- ❒ “Managing Flow Groups” on page 252
- ❒ “Managing Traffic Classes” on page 261
- ❒ “Managing Policies” on page 271

Downloaded from www.Manualslib.com manuals search engine

Managing Flow Groups

This section contains the following procedures:

- ❒ “Creating a Flow Group,” next
- ❒ “Modifying a Flow Group” on page 255
- ❒ “Deleting a Flow Group” on page 256
- ❒ “Displaying Flow Groups” on page 257

Creating a Flow Group

To create a flow group, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.
2. From the Security and Services menu, type **6** to select Quality of Service.

   The Quality of Service (QoS) menu is shown in Figure 89.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                           11:20:02 02-Mar-2005
                  Quality of Service (QoS)

1 - Flow Group Configuration
2 - Traffic Class Configuration
3 - Policy Configuration

R - Return to Previous Menu

Enter your selection?
```

Figure 89. Quality of Service (QoS) menu

3. From the Quality of Service (QoS) menu, type **1** to select Flow Group Configuration.

Downloaded from www.Manualslib.com manuals search engine

The Flow Group Configuration menu is shown in Figure 90.

```
          Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                           11:20:02 02-Mar-2005
                  Flow Group Configuration

1 - Create Flow Group
2 - Modify Flow Group
3 - Destroy Flow Group
4 - Show Flow Groups

R - Return to Previous Menu

Enter your selection?
```

Figure 90. Flow Group Configuration Menu

4. From the Flow Group Configuration menu, type **1** to select Create Flow Group.

   The Create Flow Group menu is shown in Figure 91.

```
          Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                           11:20:02 02-Mar-2005
                     Create Flow Group

1 - Flow Group ID ..............
2 - Description ................
3 - DSCP value .................
4 - Priority ...................
5 - Remark Priority ............
6 - ToS ........................
7 - Move ToS to Priority ...... No
8 - Move Priority to ToS ...... No
9 - Classifier List ............

C - Create Flow Group
R - Return to Previous Menu

Enter your selection?
```

Figure 91. Create Flow Group Menu

5. Configure the following parameters as desired:

   1 - Flow Group ID
   Specifies an ID number for the flow group. Each flow group on the switch must have a unique number. The range is 0 to 1023. The default is 0. This parameter is required.

Downloaded from www.Manualslib.com manuals search engine

2 - Description
Specifies a description for the flow group. The description can be from 1 to 15 alphanumeric characters including spaces. This parameter is optional, but recommended. Names can help you identify the groups on the switch.

3 - DSCP value
Specifies a replacement value to write into the DSCP (TOS) field of the packets. The range is 0 to 63.

A new DSCP value can be set at all three levels: flow group, traffic class, and policy. A DSCP value specified in a flow group overrides a DSCP value specified at the traffic class or policy level.

4 - Priority
Specifies a new user priority value for the packets. The range is 0 to 7. If you specify a new user priority value here and in Traffic Class, the value here overrides the value in Traffic Class. If you want the packets to retain the new value when they exit the switch, change option 5, Remark Priority, to Yes.

5 - Remark Priority
If set to Yes, replaces the user priority value in the packets with the new value specified in option 4, Priority. If set to No, which is the default, the packets retain their preexisting priority level.

6 - ToS
Specifies a replacement value to write into the Type of Service (ToS) field of IPv4 packets. The range is 0 to 7.

A new ToS value can be set at all three levels: flow group, traffic class, and policy. A ToS value specified in a flow group overrides a ToS value specified at the traffic class or policy level.

7 - Move ToS to Priority
If set to Yes, replaces the value in the 802.1p priority field with the value in the ToS priority field on IPv4 packets. If set to No, which is the default, the packets retain their preexisting 802.1p priority level.

8 - Move Priority to ToS
If set to Yes, replaces the value in the ToS priority field with the value in the 802.1p priority field on IPv4 packets. If set to No, which is the default, the packets retain their preexisting ToS priority level.

9 - Classifier List
Specifies the classifiers to be assigned to the policy. The specified classifiers must already exist. Separate multiple classifier IDs with commas (e.g., 4,11,13).

6. After configuring the parameters, type **C** to select Create Flow Group.

Downloaded from www.Manualslib.com manuals search engine

7. To create another flow group, repeat this procedure starting with step 4. To assign the flow group to a traffic class, go to "Managing Traffic Classes" on page 261.

8. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Modifying a Flow Group

To modify a flow group, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.

2. From the Security and Services menu, type **6** to select Quality of Service.

   The Quality of Service (QoS) menu is shown in Figure 89 on page 252.

3. From the Quality of Service (QoS) menu, type **1** to select Flow Group Configuration.

   The Flow Group Configuration menu is shown in Figure 90 on page 253.

4. From the Flow Group Configuration menu, type **2** to select Modify Flow Group.

   The following prompt is displayed:

   ```
   Available Flow Group(s): 0-10
   Enter Flow Group ID :  [0 to 1023] -> 0
   ```

5. Enter the ID number of the flow group you want to modify. You can modify only one flow group at a time.

   The selected flow group is displayed in the Modify Flow Group menu. You can use the menu to verify that you are modifying the correct group. An example is shown in Figure 92.

Downloaded from www.Manualslib.com manuals search engine

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                    Modify Flow Group

1 - Flow Group ID ..............  2
2 - Description ................  Video1
3 - DSCP value .................  0
4 - Priority ...................  6
5 - Remark Priority ............  No
6 - ToS ........................
7 - Move ToS to Priority .......  No
8 - Move Priority to ToS .......  No
9 - Classifier List ............  11

M - Modify Flow Group
R - Return to Previous Menu
```

Figure 92. Modify Flow Group Menu

6. Modify the settings as needed.

   When you modify a flow group, note the following:

   - ❒ You cannot change the flow group ID number.
   - ❒ To delete a value from a variable so as to leave it blank, select the variable and then use the backspace key to delete its default value.
   - ❒ Specifying an invalid value for a parameter that already has a value causes the parameter to revert to its default value.

7. Type **M** to select Modify Flow Group.

8. To modify another flow group, repeat this procedure starting with step 4. To assign the flow group to a traffic class, go to “Managing Traffic Classes” on page 261.

9. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Deleting a Flow Group

To delete a flow group, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.

2. From the Security and Services menu, type **6** to select Quality of Service.

   The Quality of Service (QoS) menu is shown in Figure 89 on page 252.

3. From the Quality of Service (QoS) menu, type **1** to select Flow Group Configuration.

Downloaded from www.Manualslib.com manuals search engine

The Flow Group Configuration menu is shown in Figure 90 on page 253.

4. From the Flow Group Configuration menu, type **3** to select Destroy Flow Group.

   The following prompt is displayed:

   ```
   Available Flow Group(s): 0-10
   Enter Flow Group ID :  [0 to 1023] -> 0
   ```

5. Enter the ID number of the flow group you want to delete. You can delete only one flow group at a time.

   The selected flow group is displayed in the Destroy Flow Group menu. You can use the menu to verify that you are deleting the correct group. An example is shown in Figure 93.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                    Destroy Flow Group

1 - Flow Group ID ..............  2
2 - Description ................  Video1
3 - DSCP value .................  0
4 - Priority ...................  6
5 - Remark Priority ............  No
6 - ToS ........................
7 - Move ToS to Priority .......  No
8 - Move Priority to ToS .......  No
9 - Classifier List ............  11

D - Destroy Flow Group
R - Return to Previous Menu

Enter your selection?
```

Figure 93. Destroy Flow Group Menu

6. Type **D** to delete the flow group.

   The flow group is deleted from the switch. The group is removed from any traffic classes to which it is assigned.

7. To delete another flow group, repeat this procedure starting with step 4.

8. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Displaying Flow Groups

To display flow groups, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.

Downloaded from www.Manualslib.com manuals search engine

2. From the Security and Services menu, type **6** to select Quality of Service.

   The Quality of Service (QoS) menu is shown in Figure 89 on page 252.

3. From the Quality of Service (QoS) menu, type **1** to select Flow Group Configuration.

   The Flow Group Configuration menu is shown in Figure 90 on page 253.

4. From the Flow Group Configuration menu, type **4** to select Show Flow Groups.

   The Show Flow Groups menu is shown in Figure 94.

```
                Allied Telesis AT-9424T/SP - AT-S63
                            Marketing
User: Manager                            11:20:02 02-Mar-2005
                          Show Flow Groups
Number of Flow Groups: 5
                                    Parent
ID    Description                   Traffic Class ID     Active
-------------------------------------------------------------
0     Dev database                  22                   Yes
1     Inv database                  5                    No
2     Video1                        14                   Yes
3     Video2                        2                    Yes
4     Demo dev                      1                    Yes

D - Display Flow Group Details
U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 94. Show Flow Groups Menu

The Show Flow Groups menu provides the following information:

ID
The flow group's ID number.

Description
A description of the flow group.

Parent Traffic Class ID
The ID number of the traffic class to which the flow group is assigned. A flow group can belong to only one traffic class at a time.

Active
The status of the flow group. If the flow group is part of a QoS policy that is assigned to one or more ports, the flow group is deemed active. If the flow group has not been assigned to a policy or if the policy has not been assigned to any ports, the flow group is deemed inactive.

Downloaded from www.Manualslib.com manuals search engine

5. To display the specifics of a flow group, type **D** to select Display Flow Group Details.

   The following prompt is displayed:

   ```
   Available Flow Group(s): 0-10
   Enter Flow Group ID :  [0 to 1023] -> 0
   ```

6. Enter the ID number of the flow group you want to view. You can display only one flow group at a time.

   The specifications of the selected flow group are displayed in the Display Flow Group Details menu. An example is shown in Figure 95.

```
            Allied Telesis AT-9424T/SP - AT-S63
                         Marketing
User: Manager                            11:20:02 02-Mar-2005
                  Display Flow Group Details

1 - Flow Group ID ............... 2
2 - Description ................. Video1
3 - DSCP value .................. 0
4 - Priority .................... 6
5 - Remark Priority ............. No
6 - ToS ......................
7 - Move ToS to Priority ....... No
8 - Move Priority to ToS ....... No
9 - Classifier List ............. 11

U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 95. Display Flow Group Detail Menu

The Display Flow Group Details menu provides the following information:

Flow Group ID
The flow group's ID number.

Description
The flow group's description.

DSCP value
The replacement value to write into the DSCP (TOS) field of the packets.

Priority
The new user priority value for the packets.

Remark Priority
Replaces the user priority value in the packets with the Priority value.

Downloaded from www.Manualslib.com manuals search engine

ToS
Specifies a replacement value to write into the Type of Service (ToS) field of IPv4 packets. The range is 1 to 7.

Move ToS to Priority
If set to Yes, replaces the value in the 802.1p priority field with the value in the ToS priority field on IPv4 packets. If set to No, which is the default, the packets retain their preexisting 802.1p priority level.

Move Priority to ToS
If set to Yes, replaces the value in the ToS priority field with the value in the 802.1p priority field on IPv4 packets. If set to No, which is the default, the packets retain their preexisting ToS priority level.

Classifier List
The classifiers assigned to the flow group.

Downloaded from www.Manualslib.com manuals search engine

Managing Traffic Classes

This section contains the following procedures:

- "Creating a Traffic Class," next
- "Modifying a Traffic Class" on page 265
- "Deleting a Traffic Class" on page 267
- "Displaying Traffic Classes" on page 268

Creating a Traffic Class

To create a traffic class, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.
2. From the Security and Services menu, type **6** to select Quality of Service.

   The Quality of Service (QoS) menu is shown in Figure 89 on page 252.
3. From the Quality of Service (QoS) menu, type **2** to select Traffic Class Configuration.

   The Traffic Class Configuration menu is shown in Figure 96.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                              11:20:02 02-Mar-2005
                  Traffic Class Configuration

1 - Create Traffic Class
2 - Modify Traffic Class
3 - Destroy Traffic Class
4 - Show Traffic Classes

R - Return to Previous Menu

Enter your selection?
```

Figure 96. Traffic Class Configuration Menu

4. From the Traffic Class Configuration menu, type **1** to select Create Traffic Class.

Downloaded from www.Manualslib.com manuals search engine

The Create Traffic Class menu is shown in Figure 97.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                   Create Traffic Class

1 - Traffic Class ID ..... 0
2 - Description ..............
3 - Exceed Action ............. Drop
4 - Exceed Remark Value ....... 0
5 - DSCP value ...............
6 - Max bandwidth ............
7 - Burst Size ...............
8 - Priority .................
9 - Remark Priority ........... No
A - ToS ......................
B - Move ToS to Priority ...... No
D - Move Priority to ToS ...... No
E - Flow Group List ...........

C - Create Traffic Class
R - Return to Previous Menu

Enter your selection?
```

Figure 97. Create Traffic Class Menu

5. Configure the following parameters as desired:

   1 - Traffic Class ID
   Specifies an ID number for the traffic class. Each traffic class on the switch must be assigned a unique number. The range is 0 to 511. The default is 0. This parameter is required.

   2 - Description
   Specifies a description for the traffic class. The description can be from 1 to 15 alphanumeric characters. Spaces are allowed. This parameter is optional, but recommended. Names can help you identify the traffic classes on the switch.

   3 - Exceed Action
   Specifies the action to be taken if the traffic of the traffic class exceeds the maximum bandwidth, specified in option 6. There are two possible exceed actions, drop and remark. If drop is selected, traffic exceeding the bandwidth is discarded. If remark is selected, the packets are forwarded after replacing the DSCP value with the new value specified in option 4, Exceed Remark Value. The default is drop.

   4 - Exceed Remark Value
   Specifies the DSCP replacement value for traffic that exceeds the maximum bandwidth. This value takes precedence over the DSCP value set with option 5, DSCP Value. The default is 0.

Downloaded from www.Manualslib.com manuals search engine

5 - DSCP value
Specifies a replacement value to write into the DSCP (TOS) field of the packets. The range is 0 to 63.

A new DSCP value can be set at all three levels: flow group, traffic class, and policy. A DSCP value specified in a flow group overrides a DSCP value specified at the traffic class or policy level. A DSCP value specified at the traffic class level is used only if no value has been specified at the flow group level. It will override any value set at the policy level.

6 - Max Bandwidth
Specifies the maximum bandwidth available to the traffic class. This parameter determines the maximum rate at which the ingress port accepts data belonging to this traffic class before either dropping or remarking occurs, depending on option 3, Exceed Action. If the sum of the maximum bandwidth for all traffic classes on a policy exceeds the (ingress) bandwidth of the port to which the policy is assigned, the bandwidth for the port takes precedence and the port discards packets before they can be classified. The range is 0 to 1016 Mbps.

The value for this parameter is rounded up to the nearest Mbps value when this traffic class is assigned to a policy on a 10/100 port, and up to the nearest 8 Mbps value when assigned to a policy on a gigabit port (for example, on a gigabit port, 1 Mbps is rounded to 8 Mbps, and 9 is rounded to 16).

Note
If this option is set to 0 (zero), all traffic that matches that traffic class is dropped. However, an access control list can be created to match the traffic that is marked for dropping, or a subset of it, and given an action of permit, to override this. This functionality can be used to discard all but a certain type of traffic. For more information about configuring access control lists, see Chapter 13, "Access Control Lists" on page 231.

7 - Burst Size
Specifies the size of a token bucket for the traffic class. The token bucket is used in situations where you have set a maximum bandwidth for a class, but where traffic activity may periodically exceed the maximum. A token bucket can provide a buffer for those periods where the maximum bandwidth is exceeded.

Tokens are added to the bucket at the same rate as the traffic class' maximum bandwidth, set with option 6, Max Bandwidth. For example, a maximum bandwidth of 50 Mbps adds tokens to the bucket at that rate.

If the amount of traffic flow matches the maximum bandwidth, no traffic is dropped because the number of tokens added to the bucket

Downloaded from www.Manualslib.com manuals search engine

matches the number being used by the traffic. However, no unused tokens will accumulate in the bucket. If the traffic increases, the excess traffic will be discarded since no tokens are available for handling the increase.

If the traffic is below the maximum bandwidth, unused tokens will accumulate in the bucket since the actual bandwidth falls below the specified maximum. The unused tokens will be available for handling excess traffic should the traffic exceed the maximum bandwidth. Should an increase in traffic continue to the point where all the unused tokens are used up, packets will be discarded.

Unused tokens accumulate in the bucket until the bucket reaches maximum capacity, set by this parameter. When the maximum capacity of the bucket is reached, no extra tokens are added. The range is 4 to 512 Kbps.

Note
To use this parameter you must specify a maximum bandwidth using item 6 - Max Bandwidth. Specifying a token bucket size without also specifying a maximum bandwidth serves no function.

8 - Priority
Specifies the priority value in the IEEE 802.1p tag control field that traffic belonging to this traffic class is assigned. Priority values range from 0 to 7 with 0 being the lowest priority and 7 being the highest priority. Incoming frames are mapped into one of eight Class of Service (CoS) queues based on the priority value.

If you want the packets to retain the new value when they exit the switch, change option 9, Remark Priority, to Yes.

If you specify a new user priority value here and in Flow Group, the value in Flow Group overwrites the value here.

9 - Remark Priority
Replaces the user priority value in the packets with the new value specified in option 4, Priority, if set to Yes. If set to No, which is the default, the packets retain their preexisting priority level when they leave the switch.

A - ToS
Specifies a replacement value to write into the Type of Service (ToS) field of IPv4 packets. The range is 0 to 7.

If you specify a new ToS value here and in Flow Group, the value in Flow Group overwrites the value here.

B - Move ToS to Priority
If set to yes, replaces the value in the 802.1p priority field with the

Downloaded from www.Manualslib.com manuals search engine

value in the ToS priority field for IPv4 packet. If set to No, which is the default, the packets retain their preexisting 802.1p priority level.

D - Move Priority to ToS
If set to yes, replaces the value in the ToS priority field with the value in the 802.1p priority field on IPv4 packets. If set to No, which is the default, the packets retain their preexisting ToS priority level.

E- Flow Group List
Specifies the flow groups to be assigned to the traffic class. The specified flow groups must already exist. Separate multiple IDs with commas (e.g., 4,11,13).

6. After configuring the parameters, type **C** to select Create Traffic Class.

7. To create another traffic class, repeat this procedure starting with step 3. To assign the traffic class to a policy, go to "Managing Policies" on page 271.

8. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Modifying a Traffic Class

To modify a traffic class, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.

2. From the Security and Services menu, type **6** to select Quality of Service.

   The Quality of Service (QoS) menu is shown in Figure 89 on page 252.

3. From the Quality of Service (QoS) menu, type **2** to select Traffic Class Configuration.

   The Traffic Class Configuration menu is shown in Figure 96 on page 261.

4. From the Traffic Class Configuration menu, type **2** to select Modify Traffic Class.

   The following prompt is displayed:

   ```
   Available Traffic Class(es): 0-7
   Enter Traffic Class ID :  [0 to 511] -> 0
   ```

5. Enter the ID number of the traffic class you want to modify. You can modify only one traffic class at a time.

Downloaded from www.Manualslib.com manuals search engine

The selected traffic class is displayed in the Modify Traffic Class menu. An example is shown in Figure 98.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                   Modify Traffic Class

1 - Traffic Class ID ..... 11
2 - Description ............... Video2
3 - Exceed Action ............. Drop
4 - Exceed Remark Value ....... 0
5 - DSCP value ................ 0
6 - Max bandwidth ............. 0
7 - Burst Size ................ 0
8 - Priority .................. 0
9 - Remark Priority ........... No
A - ToS .......................
B - Move ToS to Priority ...... No
D - Move Priority to ToS ...... No
E - Flow Group List ........... 6

M - Modify Traffic Class
R - Return to Previous Menu

Enter your selection?
```

Figure 98. Modify Traffic Class Menu

6. Modify the settings as needed. For parameter definitions, refer to “Creating a Traffic Class” on page 261.

   When you modify a traffic class, note the following:

   - ❒ You cannot change the traffic class ID number.
   - ❒ To delete a value from a variable so as to leave it blank, select the variable and then use the backspace key to delete its default value.
   - ❒ Specifying an invalid value for a parameter that already has a value causes the parameter to revert to its default value.

7. Type **M** to select Modify Traffic Class.

8. To modify another traffic class, repeat this procedure starting with step 4. To assign the traffic class to a policy, go to “Managing Policies” on page 271.

9. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Deleting a Traffic Class

To delete a traffic class, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.
2. From the Security and Services menu, type **6** to select Quality of Service.

   The Quality of Service (QoS) menu is shown in Figure 89 on page 252.
3. From the Quality of Service (QoS) menu, type **2** to select Traffic Class Configuration.

   The Traffic Class Configuration menu is shown in Figure 96 on page 261.
4. From the Traffic Class Configuration menu, type **3** to select Destroy Traffic Class. The following prompt is displayed:

```
Available Traffic Class(es): 0-7
Enter Traffic Class ID :  [0 to 511] -> 0
```

5. Enter the ID number of the traffic class you want to delete. You can delete only one traffic class at a time. The selected traffic class is displayed in the Destroy Traffic Class menu. An example is shown in Figure 99. You can use the menu to verify that you are deleting the correct traffic class.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                            11:20:02 02-Mar-2005
                    Destroy Traffic Class

1 - Traffic Class ID .......... 11
2 - Description ............... Video2
3 - Exceed Action ............. Drop
4 - Exceed Remark Value ....... 0
5 - DSCP value ................ 0
6 - Max bandwidth ............. 0
7 - Burst Size ................ 0
8 - Priority .................. 0
9 - Remark Priority ........... No
A - ToS ........................
B - Move ToS to Priority ...... No
D - Move Priority to ToS ...... No
E - Flow Group List ........... 6

D - Destroy Traffic Class
R - Return to Previous Menu

Enter your selection?
```

Figure 99. Destroy Traffic Class Menu

6. Type **D** to delete the traffic class.

Downloaded from www.Manualslib.com manuals search engine

The traffic class is deleted from the switch. The class is removed from any policies to which it is assigned.

7. To delete another traffic class, repeat this procedure starting with step 4.

8. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Displaying Traffic Classes

To display the traffic classes, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.

2. From the Security and Services menu, type **6** to select Quality of Service.

   The Quality of Service (QoS) menu is shown in Figure 89 on page 252.

3. From the Quality of Service (QoS) menu, type **2** to select Traffic Class Configuration.

   The Traffic Class Configuration menu is shown in Figure 96 on page 261.

4. From the Traffic Class Configuration menu, type **4** to select Show Traffic Classes.

   The Show Traffic Classes menu is shown in Figure 100.

```
                Allied Telesis AT-9424T/SP - AT-S63
                             Marketing
User: Manager                          11:20:02 02-Mar-2005
                        Show Traffic Classes

Number of Traffic Classes: 5
                                 Parent
ID   Description                 Policy ID         Active
-------------------------------------------------------------
0    Dev database                6                 Yes
1    Inv database                12                No
2    Video1                      4                 Yes
3    Video2                      5                 Yes
4    Demo dev                    2                 Yes

D - Display Traffic Class Details
U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 100. Show Traffic Classes Menu

Downloaded from www.Manualslib.com manuals search engine

The Show Traffic Classes menu provides the following information:

ID
The traffic class' ID number.

Description
A description of the traffic class.

Parent Policy ID
The ID number of the policy where the traffic class is assigned. A traffic class can belong to only one policy at a time.

Active
The status of the traffic class. If the traffic class is part of a QoS policy that is assigned to one or more ports, the traffic class is deemed active. If the traffic class has not been assigned to a policy or if the policy has not been assigned to any ports, the traffic class is deemed inactive.

5. To display the specifics of a traffic class, type **D** to select Display Traffic Class Details.

6. When prompted, enter the ID number of the traffic class you want to view. You can display only one traffic class at a time.

   An example of the Display Traffic Class Details menu is shown in Figure 101.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
              Display Traffic Class Details

1 - Traffic Class ID ......... 0
2 - Description ............... Dev Database
3 - Exceed Action ............. Drop
4 - Exceed Remark Value ....... 0
5 - DSCP value ................ 0
6 - Max bandwidth ............. 50
7 - Burst Size ................ 0
8 - Priority .................. 0
9 - Remark Priority ........... No
A - ToS .......................
B - Move ToS to Priority ...... No
D - Move Priority to ToS ...... No
E - Flow Group List ........... 11

U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 101. Display Traffic Class Details Menu

Downloaded from www.Manualslib.com manuals search engine

The Display Traffic Class Details menu provides the following information:

Traffic Class ID
The traffic class ID number.

Description
The description of the traffic class.

Exceed Action
The action taken if the traffic of the traffic class exceeds the maximum bandwidth.

Exceed Remark Value
The DSCP replacement value for traffic that exceeds the maximum bandwidth.

DSCP value
The replacement value to write into the DSCP (TOS) field of the packets.

Max Bandwidth
The maximum bandwidth available to the traffic class.

Burst Size
The size of a token bucket for the traffic class.

Priority
The priority value in the IEEE 802.1p tag control field that traffic belonging to this traffic class is assigned.

Remark Priority
Replaces the user priority value in the packets with the Priority value.

ToS
Specifies a replacement value to write into the Type of Service (ToS) field of IPv4 packets. The range is 1 to 7.

Move ToS to Priority
If set to yes, replaces the value in the 802.1p priority field with the value in the ToS priority field on IPv4 packets. If set to No, which is the default, the packets retain their preexisting 802.1p priority level.

Move Priority to ToS
If set to yes, replaces the value in the ToS priority field with the value in the 802.1p priority field on IPv4 packets. If set to No, which is the default, the packets retain their preexisting ToS priority level.

Flow Group List
The flow groups assigned to the traffic class.

Downloaded from www.Manualslib.com manuals search engine

Managing Policies

This section contains the following procedures:

- "Creating a Policy," next
- "Modifying a Policy" on page 274
- "Deleting a Policy" on page 275
- "Displaying Policies" on page 276

Creating a Policy

To create a policy, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.
2. From the Security and Services menu, type **6** to select Quality of Service.

   The Quality of Service (QoS) menu is shown in Figure 89 on page 252.
3. From the Quality of Service (QoS) menu, type **3** to select Policy Configuration.

   The Policy Configuration menu is shown in Figure 102.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                              11:20:02 02-Mar-2005
                     Policy Configuration

1 - Create Policy
2 - Modify Policy
3 - Destroy Policy
4 - Show Policies

R - Return to Previous Menu

Enter your selection?
```

Figure 102. Policy Configuration Menu

4. From the Policy Configuration menu, type **1** to select Create Policy.

Downloaded from www.Manualslib.com manuals search engine

The Create Policy menu is shown in Figure 103.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                     Create Policy
1 - Policy ID ................. 0
2 - Description ...............
3 - Remark DSCP ............... None
4 - DSCP value ................
5 - ToS .......................
6 - Move ToS to Priority ..... No
7 - Move Priority to ToS ..... No
8 - Send to Mirror Port ...... No
9 - Traffic Class List .......
A - Redirect Port .............
B - Ingress Port List ........
D - Egress Port ..............

C - Create Policy
R - Return to Previous Menu

Enter your selection?
```

Figure 103. Create Policy Menu

5. Configure the following parameters as needed:

   1 - Policy ID
   Specifies an ID number for the policy. Each policy on the switch must be assigned a unique number. The range is 0 to 255. The default is 0. This parameter is required.

   2 - Description
   Specifies a description for the policy. The description can be from 1 to 15 alphanumeric characters. Spaces are allowed. This parameter is optional, but recommended. Names can help you identify the policies on the switch.

   3- Remark DSCP
   Specifies whether the ingress DSCP value is overwritten. If All is specified, all packets are remarked. If None is specified, the function is disabled. The default is None.

   4 - DSCP value
   Specifies a replacement value to write into the DSCP (TOS) field of the packets. The range is 0 to 63.

   A new DSCP value can be set at all three levels: flow group, traffic class, and policy. A DSCP value specified in a flow group overrides a DSCP value specified at the traffic class or policy level. A DSCP value specified at the policy level is used only if no value has been specified at the flow group and traffic class levels.

Downloaded from www.Manualslib.com manuals search engine

5 - ToS
Specifies a replacement value to write into the Type of Service (ToS) field of IPv4 packets. The range is 0 to 7. A ToS value specified at the policy level is used only if no value has been specified at the flow group and traffic class levels.

6 - Move ToS to Priority
If set to yes, replaces the value in the 802.1p priority field with the value in the ToS priority field on IPv4 packets. If set to No, which is the default, the packets retain their preexisting 802.1p priority level.

7 - Move Priority to ToS
If set to yes, replaces the value in the ToS priority field with the value in the 802.1p priority field on IPv4 packets. If set to No, which is the default, the packets retain their preexisting ToS priority level.

8 - Send to Mirror Port
Copies the traffic that meets the criteria of the classifiers to a destination mirror port. If you set this to yes, you must specify the destination port by creating a port mirror, as explained in Chapter 8, "Port Mirroring" on page 137.

9 - Traffic Class List
Specifies the traffic classes to be assigned to the policy. The specified traffic classes must already exist. Separate multiple IDs with commas (e.g., 4,11,13).

A - Redirect Port
Specifies the port where the classified traffic from the ingress port is redirected.

B - Ingress Port List
Specifies the ingress ports to which the policy is to be assigned. Ports can be identified individually (for example, 5,7,22), as a range (for example, 18-23), or both (for example, 1,5,14-22).

A port can be an ingress port of only one policy at a time. If a port is already an ingress port of a policy, you must remove the port from its current policy assignment before adding it to another policy.

D - Egress Port
Specifies the egress port to which the policy is to be assigned. You can specify only one egress port.

A port can be an egress port of only one policy at a time. If a port is already an egress port of a policy, you must remove the port from its current policy assignment before adding it to another policy.

6. After configuring the parameters, type **C** to select Create Policy.

   The new policy is immediately activated on the specified ports.

7. To create another policy, repeat this procedure starting with step 3.

Downloaded from www.Manualslib.com manuals search engine

8. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Modifying a Policy

To modify a policy, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.
2. From the Security and Services menu, type **6** to select Quality of Service.

   The Quality of Service (QoS) menu is shown in Figure 89 on page 252.
3. From the Quality of Service (QoS) menu, type **3** to select Policy Configuration.

   The Policy Configuration menu is shown in Figure 102 on page 271.
4. From the Policy Configuration menu, type **2** to select Modify Policy. The following prompt is displayed:

```
Available Policy(ies): 0-4
Enter Policy ID :  [0 to 255] -> 0
```

5. Enter the ID number of the policy you want to modify. You can modify only one policy at a time.

   The selected policy is displayed in the Modify Policy menu. An example is shown in Figure 104.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                     Modify Policy
1 - Policy ID ................ 4
2 - Description ............... Video
3 - Remark DSCP ............... None
4 - DSCP value ................
5 - ToS .......................
6 - Move ToS to Priority ..... No
7 - Move Priority to ToS ..... No
8 - Send to Mirror Port ...... No
9 - Traffic Class List .......
A - Redirect Port ............
B - Ingress Port List ........ 7
D - Egress Port .............. 8

M - Modify Policy
R - Return to Previous Menu

Enter your selection?
```

Figure 104. Modify Policy Menu

6. Modify the settings as needed. For parameter definitions, refer to “Creating a Policy” on page 271.

Downloaded from www.Manualslib.com manuals search engine

When you modify a policy, note the following:

- ❒ You cannot change the traffic class ID number.
- ❒ To delete a value from a variable so as to leave it blank, select the variable and then use the backspace key to delete its default value.
- ❒ Specifying an invalid value for a parameter that already has a value causes the parameter to revert to its default value.

7. Type **M** to select Modify Policy.

   Modifications to a policy are immediately activated on the ports where the policy is assigned.

8. To modify another policy, repeat this procedure starting with step 4.

9. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Deleting a Policy

To delete a policy, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.

2. From the Security and Services menu, type **6** to select Quality of Service.

   The Quality of Service (QoS) menu is shown in Figure 89 on page 252.

3. From the Quality of Service (QoS) menu, type **3** to select Policy Configuration.

   The Policy Configuration menu is shown in Figure 102 on page 271.

4. From the Policy Configuration menu, type, type **3** to select Destroy Policy.

   The following prompt is displayed:

   ```
   Available Policy(ies): 0-4
   Enter Policy ID :  [0 to 255] -> 0
   ```

5. Enter the ID number of the policy you want to delete. You can delete only one policy at a time.

6. Type **D** to delete the policy.

   The policy is deleted from the switch.

7. To delete another policy, repeat this procedure starting with step 4.

8. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Displaying Policies

To display policies, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.
2. From the Security and Services menu, type **6** to select Quality of Service.

   The Quality of Service (QoS) menu is shown in Figure 89 on page 252.
3. From the Quality of Service (QoS) menu, type **3** to select Policy Configuration.

   The Policy Configuration menu is shown in Figure 102 on page 271.
4. From the Policy Configuration menu, type **4** to select Show Policies.

   The Show Policies menu is shown in Figure 105.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                           11:20:02 02-Mar-2005
                       Show Policies

Number of Policies: 4
ID    Description             Active
-----------------------------------------------
0     P1-4 database           No
1     Main video              Yes
2     Dev eng                 Yes
3     Alt video               Yes

D - Display Policy Details
U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 105. Show Policies Menu

The Show Policies menu provides the following information:

ID
The policy's ID number.

Description
A description of the policy.

Active
The status of the policy. A policy that is assigned to one or more ports is deemed active while a policy that is not assigned to any ports is deemed inactive.

Downloaded from www.Manualslib.com manuals search engine

5. To display the specifics of a policy, type **D** to select Display Policy Details.

   The following prompt is displayed:

```
Available Policy(ies): 0-4
Enter Policy ID :  [0 to 255] -> 0
```

6. Enter the ID number of the policy you want to view. You can display only one policy at a time.

   The Display Policy Details menu is shown in Figure 106.

```
           Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                            11:20:02 02-Mar-2005
                  Display Policy Details

1 - Policy ID ................ 11
2 - Description ............... policy_ca2
3 - Remark DSCP ............... None
4 - DSCP value ................ 42
5 - ToS .......................
6 - Move ToS to Priority ..... No
7 - Move Priority to ToS ..... No
8 - Send to Mirror Port ...... No
9 - Traffic Class List .......
A - Redirect Port .............
B - Ingress Port List ........ 15
D - Egress Port ..............

U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 106. Display Policy Details Menu

The Display Policy Details menu provides the following information:

Policy ID
The policy ID number.

Description
The policy description.

Remark DSCP
Whether the ingress DSCP value is overwritten. If All is specified, all packets are remarked. If None is specified, the function is disabled. The default is None.

DSCP value
The replacement value to write into the DSCP (TOS) field of the packets.

Downloaded from www.Manualslib.com manuals search engine

ToS
Specifies a replacement value to write into the Type of Service (ToS) field of IPv4 packets. The range is 1 to 7. A ToS value specified at the policy level is used only if no value has been specified at the flow group and traffic class levels.

Move ToS to Priority
If set to yes, replaces the value in the 802.1p priority field with the value in the ToS priority field on IPv4 packets. If set to No, which is the default, the packets retain their preexisting 802.1p priority level.

Move Priority to ToS
If set to yes, replaces the value in the ToS priority field with the value in the 802.1p priority field on IPv4 packets. If set to No, which is the default, the packets retain their preexisting ToS priority level.

Send to Mirror Port
Copies the traffic that meets the criteria of the classifiers to a destination mirror port. If you set this to yes, you must specify the destination port by creating a port mirror, as explained in Chapter 8, “Port Mirroring” on page 137.

Traffic Class List
The traffic classes assigned to the policy.

Redirect Port
The port to which the classified traffic from the ingress port is assigned.

Ingress Port List
The ingress ports where the policy is assigned.

Egress Port
The egress port where the policy is assigned.

Downloaded from www.Manualslib.com manuals search engine

Chapter 16

Denial of Service Defenses

This chapter contains the procedure for configuring the switch's defense mechanisms against denial of service (DoS) attacks:

- "Configuring Denial of Service Defense" on page 280

Downloaded from www.Manualslib.com manuals search engine

Configuring Denial of Service Defense

To configure DoS defense, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.
2. From the Security Configuration menu, type **3** to select Denial of Service (DoS).

   The Denial of Service (DoS) menu is shown in Figure 107.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                            11:20:02 02-Mar-2005
                  Denial of Service (DoS)

 1 - LAN IP Subnet
 2 - SYN Flood Configuration
 3 - Smurf Configuration
 4 - Land Configuration
 5 - Teardrop Configuration
 6 - Ping of Death Configuration
 7 - IP Option Configuration

 R - Return to Previous Menu

 Enter your selection?
```

Figure 107. Denial of Service (DoS) Menu

3. If you are implementing the Smurf or Land defense, you must provide the IP address of a node connected to the switch and a subnet mask. For the Land defense, you must also specify an uplink port. To do this, complete the following steps. Otherwise, go to step 4.

   a. Type **1** to select LAN IP Subnet. The LAN IP Subnet menu is shown in Figure 108.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                            11:20:02 02-Mar-2005
                      LAN IP Subnet

 1 - IP Address ................. 0.0.0.0
 2 - Subnet Mask ................ 0.0.0.0
 3 - Uplink Port ................ 24

 R - Return to Previous Menu

 Enter your selection?
```

Figure 108. LAN IP Subnet Menu

Downloaded from www.Manualslib.com manuals search engine

b. Type **1** to select IP Address.

   The following prompt is displayed:

   ```
   Enter the IP Address for the LAN:
   ```

   Enter the IP address of one of the devices connected to the switch, preferably the lowest IP address.

c. Type **2** to select Subnet Mask.

   The following prompt is displayed:

   ```
   Enter the Subnet Mask for the LAN:
   ```

   Enter the subnet mask for your network. For example, the subnet mask for a network with the IP address range 149.11.11.1 to 149.11.11.50 is 255.255.255.192.

d. If you are activating the Land defense, type **3** to select Uplink Port.

   The following prompt is displayed:

   ```
   Enter the Uplink Port for the LAN [0 to 24]:
   ```

   Enter the number of the port connected to the device (e.g., DSL router) that leads outside your network. You can specify only one uplink port.

e. Type **R** to return to the Denial of Service (DoS) Configuration menu and continue with the next step.

4. Type the number of the DoS attack that you want to protect against.

   The following prompt is displayed:

   ```
   Enter port-list:
   ```

5. Enter the port(s) where you want to activate or deactivate the defense.

Note
If you plan to use the Teardrop defense, Allied Telesis recommends activating it on only the uplink port and one other port. The defense is CPU intensive and can overwhelm the switch's CPU.

Downloaded from www.Manualslib.com manuals search engine

A menu is displayed containing either one or two options, depending on the DoS defense you selected. An example of the menu is shown in Figure 109.

```
          Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                          11:20:02 02-Mar-2005
                  SYN Flood Configuration

 Configuring DoS for Port 2
 1 - Attack Detection ................. Disabled

 R - Return to Previous Menu

 Enter your selection?
```

Figure 109. SYN Flood Configuration Menu

6. Adjust the following parameters as necessary.

   1 - Attack Detection
   Enables and disables the selected DoS defense on the selected ports. The default is disabled.

   2 - Mirroring Attack Pkt
   This option is displayed for the Land, Tear Drop, Ping of Death, and IP options defense mechanisms. You can use this option to mirror the traffic examined by a defense mechanism to another port on the switch. To use this feature, you must activate port mirroring on the switch and specify a destination mirror port, as explained in “Creating a Port Mirror” on page 138. Mirroring traffic is not required.

7. Repeat this procedure starting with Step 3 to configure other DoS defenses.

8. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Chapter 17

Power Over Ethernet

This chapter contains the procedures for configuring Power over Ethernet (PoE) on the AT-924T/POE Switch. Sections in the chapter include:

- ❒ “Setting the PoE Threshold” on page 284
- ❒ “Configuring PoE Port Settings” on page 286
- ❒ “Displaying PoE Status and Settings” on page 288

Note
This chapter applies only to the AT-924T/POE Switch.

Downloaded from www.Manualslib.com manuals search engine

Setting the PoE Threshold

This procedure lets you specify a power threshold for the powered devices that are connected to the switch. If the total power requirements of the devices exceed the threshold, the switch enters an event in the event log and sends an SNMP trap to your management workstation. The threshold is entered as a percentage of the total amount of power on the switch for the powered devices. At the default setting of 95%, the threshold is 361 W, which is 95% of 380 W, the maximum power on the AT-924T/POE Switch for the powered devices.

To configure the PoE threshold, perform the following procedure:

1. From the Main Menu, type **6** to select Advanced Configuration.
2. From the Advanced Configuration menu, type **4** to select Power Over Ethernet (PoE) Configuration menu. The Power Over Ethernet Configuration menu is shown in Figure 110.

```
          Allied Telesis AT-924T/POE - AT-S63
                   Production Switch
User: Manager                          11:20:02 02-Jan-2008
         Power Over Ethernet (PoE) Configuration
1 - PoE Global Configuration
2 - PoE Port Configuration
3 - PoE Status

R - Return to Previous Menu

Enter your selection?
```

Figure 110. Power Over Ethernet Configuration Menu

3. From the Power Over Ethernet Configuration menu, type **1** to select PoE Global Configuration. The PoE Global Configuration menu is shown in Figure 111.

```
          Allied Telesis AT-924T/POE - AT-S63
                   Production Switch
User: Manager                        11:20:02 02-Jan-2008
                PoE Global Configuration
1 - Power Threshold ................. 95 percent
2 - Maximum Available Power ........ 380W

R - Return to Previous Menu

Enter your selection?
```

Figure 111. PoE Global Configuration Menu

Downloaded from www.Manualslib.com manuals search engine

Options 2, Maximum Available Power, displays the maximum amount of PoE supplied by the switch. For the AT-924T/POE switch, this value is 380W. This value cannot be changed.

4. From the PoE Global Configuration menu, type **1** to select Power Threshold.

   The following prompt is displayed:

   ```
   Enter percentage of power limit threshold : [1 to 100] -
   > 95
   ```

   Enter the new threshold as a percentage of the total available PoE power on the switch. The new threshold is immediately activated on the switch.

5. After making the change, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Configuring PoE Port Settings

This procedure enables and disables PoE on a port. This procedure also sets a port's priority level and its maximum power usage.

To configure PoE port settings, do the following:

1. From the Main Menu, type **6** to select Advanced Configuration.
2. From the Advanced Configuration menu, type **4** to select Power Over Ethernet (PoE) Configuration menu.

   The Power Over Ethernet Configuration menu is shown in Figure 110 on page 284.
3. From the Power Over Ethernet Configuration menu, type **2** to select PoE Port Configuration.

   The following prompt is displayed:

   ```
   Enter port-list:
   ```
4. Enter the port you want to configure. You can specify more than one port at a time.

   The PoE Port Configuration menu is shown in Figure 112.

```
          Allied Telesis AT-924T/POE - AT-S63
                  Production Switch
User: Manager                      11:20:02 02-Jan-2008
                PoE Port Configuration
Configuring PoE Port 4
1 - PoE Function ....... ENABLED
2 - Power Priority ..... LOW
3 - Power Limit ........ 15,400 mW

R - Return to Previous Menu

Enter your selection?
```

Figure 112. PoE Port Configuration Menu

   If you are configuring multiple ports, the management software displays the settings of the lowest numbered port.
5. To enable or disable PoE on the port, type **1** to select PoE Function and, when prompted, type **E** to enable PoE or **D** to disable it. The default is Enabled.

Downloaded from www.Manualslib.com manuals search engine

6. To change the port's priority, type **2** to select Power Priority and, when prompted, type **C** for Critical, **H** for High, or **L** for Low. A port can belong to only one priority level at a time. The default is Low.

7. To change the maximum amount of power the port can supply to the device, type **3** to select Power Limit and enter a new value in milliwatts. The default value is 15,400 mW.

   A change to a parameter value is immediately activated on the switch.

8. After making your changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Displaying PoE Status and Settings

Use this procedure to display PoE status and settings at the switch or port level.

To display PoE information, do the following:

1. From the Main Menu, type **6** to select Advanced Configuration.
2. From the Advanced Configuration menu, type **4** to select Power Over Ethernet (PoE) Configuration menu.

   The Power Over Ethernet Configuration menu is shown in Figure 110 on page 284.
3. From the Power Over Ethernet Configuration menu, type **3** to select PoE Status.

   The PoE Status menu is shown in Figure 113.

```
          Allied Telesis AT-924T/POE - AT-S63
                   Production Switch
User: Manager                    11:20:02 02-Jan-2008
                        PoE Status

1 - PoE Global Status
2 - PoE Summary Ports Status
3 - PoE Detailed Ports Status
4 - PoE Device Information

R - Return to Previous Menu

Enter your selection?
```

Figure 113. PoE Status Menu

The selections are defined below.

Downloaded from www.Manualslib.com manuals search engine

1 - PoE Global Status Menu

This selection displays the following window:

```
 Allied Telesis Ethernet Switch AT-924T/POE - AT-S63
                  Production Switch
User: Manager                    11:20:02 02-Jan-2008
                  PoE Global Status
Max Available Power ..... 380 W
Consumed Power ........... 25 W
Available Power .......... 375W
Power Usage .............. 6.25 percent
Min Shutdown Voltage ..... 44.0 V
Max Shutdown Voltage ..... 57.0 V

U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 114. PoE Global Status Menu

The selections in this window are for viewing purposes only. These parameters are not adjustable. The selections are described below.

Max Available Power
The total available power for PoE supplied by the switch. This value is 380 W for the AT-924T/POE switch.

Consumed Power
The amount of power being used by the powered devices.

Available Power
The amount of unused power available for additional powered devices.

Power Usage
The amount of power currently consumed by the powered devices connected to the switch. The value is give as a percentage of the total amount of power available, which for the AT-924T/POE switch is 380 W.

Min Shutdown Voltage
The minimum threshold voltage at which the switch shuts down PoE. If the power supply in the switch experiences a problem and the output voltage drops below this value, the switch shuts down PoE on all ports. This value is not adjustable.

Max Shutdown Voltage
The maximum threshold voltage at which the switch shuts down PoE. If the power supply in the switch experiences a problem and the output voltage exceeds this value, the switch shuts down PoE on all ports. This value is not adjustable.

Downloaded from www.Manualslib.com manuals search engine

2 - Summary All Ports Status Menu

This selection display an abbreviated status report of PoE on the individual switch ports. For more detailed information, refer to selection 3.

This selection displays the following window:

```
                  Allied Telesis AT-924T/POE - AT-S63
                           Production Switch
User: Manager                                        11:20:02 02-Jan-2008
                        PoE Summary Ports Status
Port PoE Function    Consumed Power (mW)    Power Status
-------------------------------------------------------------------------
1    ENABLED         1,900                  ON - Valid PD detected
2    ENABLED         1,900                  ON - Valid PD detected
3    ENABLED         1,900                  ON - Valid PD detected
4    ENABLED         0                      OFF - Detection in process
5    ENABLED         0                      OFF - Detection in process

N - Next Page
U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 115. PoE Summary Ports Status Menu

The selections in this window are for viewing purposes only. Each column is described below.

Port
Port number.

PoE Function
Whether PoE is enabled or disabled on the port. The default setting is enabled. To enable or disable PoE on a port, refer to “Configuring PoE Port Settings” on page 286.

Consumed Power
The amount of power in milliwatts currently consumed by the powered device connected to the port. If the port is not connected to a powered device, this value will be 0 (zero).

Power Status
Whether power is being supplied to the device. ON means that the port is providing power to a powered device. OFF means the device is not a powered device or PoE has been disabled on the port.

Downloaded from www.Manualslib.com manuals search engine

3 - Detailed Ports Status Menu

When you select this option, you are prompted to enter the port(s) you want to view. You can specify more than one port at a time. Once you have specified the port, the selection displays the following window:

```
            Allied Telesis AT-924T/POE - AT-S63
                     Production Switch
User: Manager                          11:20:02 02-Jan-2008
                   PoE Detailed Port Status
Port: 4
PoE Function ........... ENABLED
Power Status ........... ON - Valid PD detected
Power Consumed ......... 1,900 mW
Power Limit ............ 15,400 mW
Power Priority ......... Low
Power Class ............ 1
Voltage ................ 48.6V
Current ................ 40 mA

U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 116. PoE Summary Ports Status Menu

The selections in this window are for viewing purposes only. Each selection is described below.

Port
Port number.

PoE Function
Whether PoE is enabled or disabled on the port. The default setting is enabled. To enable or disable PoE on a port, refer to "Configuring PoE Port Settings" on page 286.

Power Status
Whether power is being supplied to the device. ON means that the port is providing power to a powered device. OFF means the device is not a powered device, PoE has been disabled on the port, or no device is connected to the port.

Power Consumed
The amount of power in milliwatts currently consumed by the powered device connected to the port. If the port is not connected to a powered device, this value will be 0 (zero).

Power Limit
The maximum amount of power allowed by the port for the device. The default is 15,400 milliwatts (15.4 W). To adjust this value for a port, refer to "Configuring PoE Port Settings" on page 286.

Downloaded from www.Manualslib.com manuals search engine

Power Priority
The port priority. This can be Critical, High, or Low. To adjust this value, refer to “Configuring PoE Port Settings” on page 286.

Power Class
The IEEE 802.3af class of the device. This parameter cannot be changed.

Voltage
The voltage being delivered to the powered device

Current
The current drawn by the powered device.

4 - PoE Device Information

This selection displays the hardware and firmware version numbers of the PoE chipset used in the switch. This selection is intended for troubleshooting purposes and displays the following window:

```
          Allied Telesis AT-924T/POE - AT-S63
                   Production Switch
User: Manager                       11:20:02 02-Jan-2008

                 PoE Device Information

MCU Device Info:
Hardware Version ......... 0
Firmware Version ......... 0290

PSE Devices Info:
Device 0 Hardware Version .... 1
Device 1 Hardware Version .... 1

R - Return to Previous Menu

Enter your selection?
```

Figure 117. PoE Device Information

Downloaded from www.Manualslib.com manuals search engine

Section III

IGMP Snooping, MLD Snooping, and RRP Snooping

The chapters in this section contain overview information on IGMP snooping, MLD snooping, and RRP snooping. The chapters also explain how to configure these features from the menus interface of the AT-S63 Management Software. The chapters include:

- Chapter 18, ”IGMP Snooping” on page 295
- Chapter 19, “MLD Snooping” on page 305
- Chapter 20, ”RRP Snooping” on page 315

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Chapter 18

IGMP Snooping

This chapter explains how to activate and configure the Internet Group Management Protocol (IGMP) snooping feature on the switch. Sections in the chapter include:

- ❒ “Configuring IGMP Snooping” on page 296
- ❒ “Enabling or Disabling IGMP Snooping” on page 300
- ❒ “Displaying a List of Host Nodes” on page 301
- ❒ “Displaying a List of Multicast Routers” on page 303

Downloaded from www.Manualslib.com manuals search engine

Configuring IGMP Snooping

To configure IGMP snooping on the switch, perform the following procedure:

1. From the Main Menu, type **6** to select Advanced Configuration.

   The Advanced Configuration menu is shown in Figure 118.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                              11:20:02 02-Mar-2005
                    Advanced Configuration

 1 - RRP Snooping Configuration
 2 - IGMP Snooping Configuration
 3 - MLD Snooping Configuration
 4 - Power Over Ethernet (PoE) Configuration

 R - Return to Previous Menu

 Enter your selection?
```

Figure 118. Advanced Configuration Menu

2. From the Advanced Configuration menu, type **2** to select IGMP Snooping Configuration.

Note
For information on option 1, RRP Snooping Configuration, refer to Chapter 20, “RRP Snooping” on page 315. For information on option 3, MLD Snooping Configuration, refer to Chapter 19, “MLD Snooping” on page 305. For information on option 4, Power Over Ethernet (PoE) Configuration, refer to Chapter 17, ”Power Over Ethernet” on page 283.

Downloaded from www.Manualslib.com manuals search engine

The IGMP Snooping Configuration menu is shown in Figure 119.

```
              Allied Telesis AT-9424T/SP - AT-S63
                          Marketing
User: Manager                                11:20:02 02-Mar-2005
                    IGMP Snooping Configuration

 1 - IGMP Snooping Status ........... Disabled
 2 - Host Topology .................. Single-Host/Port (Edge)
 3 - Host/Router Timeout Interval ... 260 seconds
 4 - Maximum IGMP Multicast Groups .. 64
 5 - Router Port(s) .................. Auto Detect
 6 - View IGMP Multicast Hosts List
 7 - View IGMP Multicast Routers List

 R - Return to Previous Menu

 Enter your selection?
```

Figure 119. IGMP Snooping Configuration Menu

3. Adjust the following parameters as necessary:

   1 - IGMP Snooping Status
   Enables or disables IGMP snooping on the switch. The default setting is disabled.

   2 - Host Topology
   Defines whether there is only one host node per switch port or multiple host nodes per port. The possible settings are:

   Single-Host/Port (Edge)
   The Single-Host/Port setting is appropriate when there is only one host node connected to each port on the switch. This setting causes the switch to immediately stop sending multicast packets out a switch port when a host node signals its desire to leave a multicast group by sending a leave request or when the host node stops sending reports. The switch responds by immediately ceasing the transmission of additional multicast packets out the port where the host node is connected.

   Multiple Host/Ports (Intermediate)
   The Multi-Host setting is appropriate if there is more than one host node connected to a switch port, such as when a port is connected to an Ethernet hub to which multiple host nodes are connected. With this setting selected the switch continues sending multicast packets out a port even after it receives a leave request from a host node on the port. This ensures that the remaining active host nodes on the port continue to receive the multicast packets. Only after all the host nodes connected to a switch port have transmitted leave requests or have timed out does the switch stop sending multicast packets out the port.

Downloaded from www.Manualslib.com manuals search engine

If a switch has a mixture of host nodes, that is, some connected directly to the switch and others through an Ethernet hub, you should select the Multi-Host Port (Intermediate) selection.

3 - Host/Router Timeout Interval
Specifies the time period in seconds at which the switch determines that a host node is inactive. An inactive host node is a node that has not sent an IGMP report during the specified time interval. The range is from 0 second to 86,400 seconds (24 hours). The default is 260 seconds. If you set the timeout to zero (0), the timer never times out, and the timeout interval is essentially disabled.

This parameter also controls the time interval used by the switch in determining whether a multicast router is still active. The switch makes the determination by watching for queries from the router. If the switch does not detect any queries from a multicast router during the specified time interval, the router is assumed to be no longer active on the port.

The actual timeout may be ten seconds less that the specified value. For example, a setting of 25 seconds can result in the switch classifying a host node or multicast router as being inactive after just 15 seconds. A setting of 10 seconds or less can result in the immediate timeout of an inactive host node or router.

4 - Maximum IGMP Multicast Groups
This parameter specifies the maximum number of IGMP multicast groups the switch can learn. This parameter is useful with networks that contain a large number of multicast groups. The range is 0 to 255 groups. The default is 64 multicast groups.

Note
The combined number of multicast address groups for IGMP and MLD snooping cannot exceed 255.

5 - Router Port(s)
Specifies the port on the switch where a multicast router is detected. You can let the switch determine this automatically by selecting Auto Detect, or you can specify the port yourself by entering a port number. You can specify more than one port. To specify all ports, enter ALL. To specify no ports, enter NONE, To select Auto Detect, enter AUTO.

Note
A change to any parameter in this menu is immediately activated on the switch.

Downloaded from www.Manualslib.com manuals search engine

Note
Selection 6, View IGMP Multicast Hosts List, is described in "Displaying a List of Host Nodes" on page 301. Selection 7, View IGMP Multicast Routers List, is described in "Displaying a List of Multicast Routers" on page 303.

4. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Enabling or Disabling IGMP Snooping

To activate or deactivate IGMP snooping on the switch, perform the following procedure:

1. From the Main Menu, type **6** to select Advanced Configuration.

   The Advanced Configuration menu is shown in Figure 118 on page 296.

2. From the Advanced Configuration menu, type **2** to select IGMP Snooping Configuration.

   The IGMP Snooping Configuration menu is shown in Figure 119 on page 297.

3. From the IGMP Snooping Configuration menu, type **1** to select IGMP Snooping Status.

   The following prompt is displayed:

   ```
   IGMP Snooping Status (E-Enabled, D-Disabled) :
   ```

4. Type **E** to enable IGMP or **D** to disable it. The default setting is disabled.

   A change to the status of IGMP snooping is immediately implemented on the switch:

5. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Displaying a List of Host Nodes

You can use the AT-S63 Management Software to display a list of the multicast groups on a switch, as well as the host nodes. To display the list, perform the following procedure:

1. From the Main Menu, type **6** to select Advanced Configuration.

   The Advanced Configuration menu is shown in Figure 118 on page 296

2. From the Advanced Configuration menu, type **2** to select IGMP Snooping Configuration.

   The IGMP Snooping Configuration menu is shown in Figure 119 on page 297.

3. From the IGMP Snooping Configuration menu, type **6** to select View IGMP Multicast Hosts List.

   The View IGMP Multicast Host List menu is shown in Figure 120.

```
                Allied Telesis AT-9424T/SP - AT-S63
                             Marketing
User: Manager                                    11:20:02 02-Mar-2005
                   View IGMP Multicast Hosts List

Number of IGMP Multicast Groups: 4
                      VLAN  Port/                    IGMP   Exp.
MulticastGroup        ID    TrunkID  HostIP          Ver    Time
-------------------------------------------------------------------
01:00:5E:00:01:01     1     6/-      172.16.10.51    v2     21
01:00:5E:7F:FF:FA     1     5/-      149.35.200.75   v2     11
                                     149.35.200.65   v2     65
01:00:5E:00:00:02     1     17/-     149.35.200.69   v2     34
01:00:5E:00:00:09     1     14/-     172.16.10.51    v2     32

U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 120. View IGMP Multicast Hosts List Menu

The View IGMP Multicast Hosts List menu displays a table with the following columns of information:

Multicast Group
The multicast address of the group.

Downloaded from www.Manualslib.com manuals search engine

VLAN
The VID of the VLAN where the port is an untagged member.

Port/Trunk
The port on the switch where the host node is connected. If the host node is connected to the switch through a trunk, the trunk ID number, not the port number, is displayed.

HostIP
The IP address of the host node connected to the port.

IGMP Ver.
The version of IGMP used by the host.

Exp. Time
The number of seconds remaining before the host is timed out if no further IGMP reports are received from it.

Downloaded from www.Manualslib.com manuals search engine

Displaying a List of Multicast Routers

A multicast router is a router that is receiving multicast packets from a multicast application and transmitting the packets to host nodes. You can use the AT-S63 Management Software to display a list of the multicast routers that are connected to the switch.

To display a list of the multicast routers, perform the following procedure:

1. From the Main Menu, type **6** to select Advanced Configuration.

   The Advanced Configuration menu is shown in Figure 118 on page 296.

2. From the Advanced Configuration menu, type **2** to select IGMP Snooping Configuration.

   The IGMP Snooping Configuration menu is shown in Figure 119 on page 297.

3. From the IGMP Snooping Configuration menu, type **7** to select View IGMP Multicast Routers List.

   The View IGMP Multicast Routers List menu is shown in Figure 121.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                            11:20:02 02-Mar-2005
             View IGMP Multicast Routers List


VLAN  Port/Trunk ID   RouterIP
-------------------------------------------------
1     14/-            172.16.01.1

U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 121. View IGMP Multicast Routers List Menu

The View IGMP Multicast Routers List menu displays a table that contains the following columns of information:

VLAN
The VID of the VLAN in which the port is an untagged member.

Port/Trunk ID
The port on the switch where the multicast router is connected. If the

Downloaded from www.Manualslib.com manuals search engine

switch learned the router on a port trunk, the trunk ID number, not the port number, is displayed.

Router IP
The IP address of the multicast router.

Downloaded from www.Manualslib.com manuals search engine

Chapter 19

MLD Snooping

This chapter explains how to activate and configure Multicast Listener Discovery (MLD) snooping on the switch. Sections in the chapter include:

- ❒ “Configuring MLD Snooping” on page 306
- ❒ “Enabling or Disabling MLD Snooping” on page 309
- ❒ “Displaying a List of Host Nodes” on page 310
- ❒ “Displaying a List of Multicast Routers” on page 312

Downloaded from www.Manualslib.com manuals search engine

Configuring MLD Snooping

To configure MLD snooping on the switch, perform the following procedure:

1. From the Main Menu, type **6** to select Advanced Configuration.

   The Advanced Configuration menu is shown in Figure 118 on page 296.

2. From the Advanced Configuration menu, type **3** to select MLD Snooping Configuration.

   The MLD Snooping Configuration menu is shown in Figure 122.

```
              Allied Telesis AT-9424T/SP - AT-S63
                          Marketing
User: Manager                              11:20:02 02-Mar-2005
                    MLD Snooping Configuration

 1 - MLD Snooping Status ............. Disabled
 2 - Host Topology ................... Single-Host/Port (Edge)
 3 - Host/Router Timeout Interval .... 260 seconds
 4 - Maximum MLD Multicast Groups .... 64
 5 - Router Port(s) .................. Auto Detect
 6 - View MLD Multicast Hosts List
 7 - View MLD Multicast Routers List

 R - Return to Previous Menu

 Enter your selection?
```

Figure 122. MLD Snooping Configuration Menu

3. Adjust the following parameters as necessary:

   1 - MLD Snooping Status
   Enables or disables MLD snooping on the switch. The default setting is disabled.

   2 - Host Topology
   Defines whether there is only one host node per switch port or multiple host nodes per port. The possible settings are:

   Single-Host/Port (Edge)
   The Single-Host/Port setting is appropriate when there is only one host node connected to each port on the switch. This setting causes the switch to immediately stop sending multicast packets out a switch port when a host node signals its desire to leave a multicast group by sending a leave request or when the host node stops sending reports. The switch responds by immediately ceasing the transmission of

Downloaded from www.Manualslib.com manuals search engine

additional multicast packets out the port where the host node is connected.

Multiple Host/Ports (Intermediate)
The Multi-Host setting is appropriate if there is more than one host node connected to a switch port, such as when a port is connected to an Ethernet hub to which multiple host nodes are connected. With this setting selected the switch continues sending multicast packets out a port even after it receives a leave request from a host node on the port. This ensures that the remaining active host nodes on the port continue to receive the multicast packets. Only after all the host nodes connected to a switch port have transmitted leave requests or have timed out does the switch stop sending multicast packets out the port.

If a switch has a mixture of host nodes, that is, some connected directly to the switch and others through an Ethernet hub, you should select the Multi-Host Port (Intermediate) selection.

3 - Host/Router Timeout Interval
Specifies the time period in seconds at which the switch determines that a host node has become inactive. An inactive host node is a node that has not sent an MLD report during the specified time interval. The range is from 0 second to 86,400 seconds (24 hours). The default is 260 seconds. If you set the timeout to zero (0), the host never times out, and the timeout interval is essentially disabled.

This parameter also specifies the time interval used by the switch in determining whether a multicast router is still active. The switch makes the determination by watching for queries from the router. If the switch does not detect any queries from a multicast router during the specified time interval, it assumes that the router is no longer active on the port.

4 - Maximum MLD Multicast Groups
This parameter specifies the maximum number of MLD multicast groups the switch can learn. This parameter is useful with networks that contain a large number of multicast groups. The range is 0 to 256 groups. The default is 64 multicast groups.

Note
The combined number of multicast address groups for IGMP and MLD snooping cannot exceed 256.

5 - Router Port(s)
Specifies the port on the switch where a multicast router is located. You can let the switch determine this automatically by selecting Auto Detect, the default setting, or you can specify the port yourself by entering a port number. You can specify more than one port. To specify all ports, enter ALL. To specify no ports, enter NONE, To select Auto Detect, enter AUTO.

Downloaded from www.Manualslib.com manuals search engine

Note
A change to any parameter in this menu is immediately activated on the switch.

Note
Selection 6, View MLD Multicast Hosts List, is described in “Displaying a List of Host Nodes” on page 310. Selection 7, View MLD Multicast Routers List, is described in “Displaying a List of Multicast Routers” on page 312.

4. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

   Your changes are activated immediately on the switch.

Downloaded from www.Manualslib.com manuals search engine

Enabling or Disabling MLD Snooping

To activate or deactivate MLD snooping on the switch, perform the following procedure:

1. From the Main Menu, type **6** to select Advanced Configuration.

   The Advanced Configuration menu is shown in Figure 118 on page 296.

2. From the Advanced Configuration menu, type **3** to select MLD Snooping Configuration.

   The MLD Snooping Configuration menu is shown in Figure 122 on page 306.

3. From the MLD Snooping Configuration menu, type **1** to select MLD Snooping Status.

   The following prompt is displayed:

   ```
   MLD Snooping Status (E-Enabled, D-Disabled) :
   ```

4. Type **E** to enable MLD or **D** to disable it. The default setting is disabled.

   A change to the status of MLD snooping is immediately implemented on the switch:

5. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Displaying a List of Host Nodes

You can use the AT-S63 Management Software to display a list of the multicast groups on a switch, as well as the host nodes. To display the list, perform the following procedure:

1. From the Main Menu, type **6** to select Advanced Configuration.

   The Advanced Configuration menu is shown in Figure 118 on page 296

2. From the Advanced Configuration menu, type **3** to select MLD Snooping Configuration.

   The MLD Snooping Configuration menu is shown in Figure 122 on page 306.

3. From the MLD Snooping Configuration menu, type **6** to select View MLD Multicast Hosts List.

   The View MLD Multicast Host List menu is shown in Figure 123.

```
                          Allied Telesis AT-9424T/SP - AT-S63
                                    Marketing
User: Manager                                          11:20:02 02-Mar-2005
                             View MLD Multicast Hosts List


Number of MLD Multicast Groups: 1
                       VLAN    Port/                                                 Exp.
MulticastGroup         ID      TrunkID    HostIP                                     Time
-------------------------------------------------------------------------------------------
33:33:00:00:00:ab      1       6          fe80:0000:0000:0000:0208:74ff:feff:bf08    21



U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 123. View MLD Multicast Hosts List Menu

The View MLD Multicast Hosts List menu displays a table with the following columns of information:

Multicast Group
The multicast address of the group.

VLAN
The VID of the VLAN where the port is an untagged member.

Port/Trunk
The port on the switch where the host node is connected. If the host

Downloaded from www.Manualslib.com manuals search engine

node is connected to the switch through a trunk, the trunk ID number, not the port number, is displayed.

HostIP
The IP address of the host node connected to the port.

Exp. Time
The number of seconds remaining before the host is timed out if no further MLD reports are received from it.

Downloaded from www.Manualslib.com manuals search engine

Displaying a List of Multicast Routers

A multicast router is a router that is receiving multicast packets from a multicast application and transmitting the packets to host nodes. You can use the AT-S63 Management Software to display a list of the multicast routers that are connected to the switch.

To display a list of the multicast routers, perform the following procedure:

1. From the Main Menu, type **6** to select Advanced Configuration.

   The Advanced Configuration menu is shown in Figure 118 on page 296.

2. From the Advanced Configuration menu, type **3** to select MLD Snooping Configuration.

   The MLD Snooping Configuration menu is shown in Figure 122 on page 306.

3. From the MLD Snooping Configuration menu, type **7** to select View MLD Multicast Routers List.

   The View MLD Multicast Routers List menu is shown in Figure 124.

```
              Allied Telesis AT-9424T/SP - AT-S63
                          Marketing
User: Manager                            11:20:02 02-Mar-2005
                 View MLD Multicast Routers List

VLAN  Port/Trunk ID   RouterIP
-------------------------------------------------------------
1     14              fe80:0000:0000:0000:0200:cdff:fe12:bf08

U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 124. View MLD Multicast Routers List Menu

The View MLD Multicast Routers List menu displays a table that contains the following columns of information:

VLAN
The VID of the VLAN in which the port is an untagged member.

Downloaded from www.Manualslib.com manuals search engine

Port/Trunk ID
The port on the switch where the multicast router is connected. If the switch learned the router on a port trunk, the trunk ID number, not the port number, is displayed.

Router IP
The IP address of the multicast router.

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Chapter 20

RRP Snooping

The section in this chapter explains how to configure RRP snooping:

❒ “Enabling or Disabling RRP Snooping” on page 316

Downloaded from www.Manualslib.com manuals search engine

Enabling or Disabling RRP Snooping

To enable or disable RRP snooping on a switch, perform the following procedure:

1. From the Main Menu, type **6** to select Advanced Configuration.
2. From the Advanced Configuration menu, type **1** to select RRP Snooping Configuration.

   The RRP Snooping Configuration menu is shown in Figure 125.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
               RRP Snooping Configuration

 1 - RRP Snooping Status ............ Disabled

 R - Return to Previous Menu

 Enter your selection?
```

Figure 125. RRP Snooping Menu

3. From the RRP Snooping Configuration menu, type **1** to toggle the setting between Enabled and Disabled. The default setting is disabled.

   A change to the status of RRP snooping is immediately activated on the switch. If you activate the feature, the switch flushes all dynamic MAC addresses from the MAC address table and immediately begins to relearn the addresses as it receives packets from the end nodes.
4. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Section IV

SNMPv3

The chapter in this section contains overview information on SNMPv3. The chapter also explains how to configure this feature from the menus interface of the AT-S63 Management Software. The chapter is:

❒ Chapter 21, ”SNMPv3” on page 319

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Chapter 21
SNMPv3

This chapter provides a description of the AT-S63 implementation of the SNMPv3 protocol. In addition, the chapter contains procedures that allow you to create and modify SNMPv3 entities. The following sections are provided:

- “Configuring SNMPv3 Entities” on page 320
- “Configuring the SNMPv3 User Table” on page 321
- “Configuring the SNMPv3 View Table” on page 331
- “Configuring the SNMPv3 Access Table” on page 340
- “Configuring the SNMPv3 SecurityToGroup Table” on page 356
- “Configuring the SNMPv3 Notify Table” on page 364
- “Configuring the SNMPv3 Target Address Table” on page 372
- “Configuring the SNMPv3 Target Parameters Table” on page 385
- “Configuring the SNMPv3 Community Table” on page 398
- “Displaying SNMPv3 Table Menus” on page 408

Downloaded from www.Manualslib.com manuals search engine

Configuring SNMPv3 Entities

This section describes how to configure SNMPv3 entities using the SNMPv3 Tables. To successfully configure this protocol, you must perform the procedures in the order given.

The following SNMPv3 tables are described:

- “Configuring the SNMPv3 User Table,” next
- “Configuring the SNMPv3 View Table” on page 331
- “Configuring the SNMPv3 Access Table” on page 340
- “Configuring the SNMPv3 SecurityToGroup Table” on page 356
- “Configuring the SNMPv3 Notify Table” on page 364
- “Configuring the SNMPv3 Target Address Table” on page 372
- “Configuring the SNMPv3 Target Parameters Table” on page 385
- “Configuring the SNMPv3 Community Table” on page 398

The SNMPv3 User, View, Access, and SecurityToGroup tables are concerned with setting up a user, determining authentication and privacy, and associating a user to a security group. The SNMPv3 Notify, Target Address, and Target Parameters tables are concerned with message notification. You use the SNMPv3 Community Table to configure SNMPv1 and SNMPv2 communities.

Due to the complexity of the SNMPv3 configuration, Allied Telesis recommends that you configure the SNMPv3 protocol with the procedures listed above, in the order they are listed. However, you can configure the SNMPv3 protocol using the above procedures in any order.

Downloaded from www.Manualslib.com manuals search engine

Configuring the SNMPv3 User Table

This section contains a description of the SNMPv3 User Table and how to create, delete, and modify table entries. Configure the SNMPv3 User Table first. Creating this table, allows you to create an entry in an SNMPv3 User Table for a User Name. In addition, this table allows you to associate a User Name with the following parameters:

- Authentication protocol
- Authentication password
- Privacy protocol
- Privacy password

There are three functions you can perform with the SNMPv3 User Table.

- "Creating an SNMPv3 User Table Entry," next
- "Deleting an SNMPv3 User Table Entry" on page 325
- "Modifying an SNMPv3 User Table Entry" on page 326

Creating an SNMPv3 User Table Entry

To create an entry in the SNMPv3 User Table, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **5** to select SNMP Configuration.

   The SNMP Configuration menu is shown in Figure 26 on page 94.

3. From the SNMP Configuration menu, type **5** to select Configure SNMPv3 Table.

Downloaded from www.Manualslib.com manuals search engine

The Configure SNMPv3 Table menu is shown in Figure 126.

```
              Allied Telesis AT-9424T/SP - AT-S63
                           Marketing
User: Manager                                  11:20:02 02-Mar-2005
                      Configure SNMPv3 Table
 1 - SNMP Engine.............80:00:00:CF:31:00:30:84:FD:57:DA
 2 - Configure SNMPv3 User Table
 3 - Configure SNMPv3 View Table
 4 - Configure SNMPv3 Access Table
 5 - Configure SNMPv3 SecurityToGroup Table
 6 - Configure SNMPv3 Notify Table
 7 - Configure SNMPv3 Target Address Table
 8 - Configure SNMPv3 Target Parameters Table
 9 - Configure SNMPv3 Community Table

 R - Return to Previous Menu

 Enter your selection?
```

Figure 126. Configure SNMPv3 Table Menu

Note
The SNMP Engine field is a read-only field. You cannot change the setting. The field displays the SNMP engine identifier that is assigned automatically to the switch.

4. From the Configure SNMPv3 Table menu, type **2** to select Configure SNMPv3 User Table.

   The Configure SNMPv3 User Table menu is shown in Figure 127.

```
              Allied Telesis AT-9424T/SP - AT-S63
                           Marketing
User: Manager                                  11:20:02 02-Mar-2005
                   Configure SNMPv3 User Table
 Engine ID ................. 80:00:00:CF:03:00:30:84:FD:57:DA
 User Name ................. jenny
 Authentication Protocol ... MD5
 Privacy Protocol .......... DES
 Storage Type .............. NonVolatile
 Row Status ................ Active
 1 - Create SNMPv3 Table Entry
 2 - Delete SNMPv3 Table Entry
 3 - Modify SNMPv3 Table Entry

 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 127. Configure SNMPv3 User Table Menu

Downloaded from www.Manualslib.com manuals search engine

5. To create a new user table, type **1** to select Create SNMPv3 Table Entry.

   The following prompt is displayed:

   ```
   Enter User (Security) Name:
   ```

6. Enter a descriptive name of the user.

   You can enter a name that consists of up to 32 alphanumeric characters.

   The following prompt is displayed:

   ```
   Enter Authentication Protocol [M-MD5, S-SHA, N-None]:
   ```

7. Enter one of the following:

   M-MD5
   This value represents the MD5 authentication protocol. With this selection, users (SNMP entities) are authenticated with the MD5 authentication protocol after a message is received. This algorithm generates the message digest. The user is authenticated when the authentication protocol checks the message digest. With the MD5 selection, you can configure a Privacy Protocol.

   S-SHA
   This value represents the SHA authentication protocol. With this selection, users are authenticated with the SHA authentication protocol after a message is received. This algorithm generates the message digest. The user is authenticated when the authentication protocol checks the message digest. With the SHA selection, you can configure a Privacy Protocol.

   N-None
   This value represents no authentication protocol. When messages are received, users are not authenticated. With the None selection, you cannot configure a Privacy Protocol.

   Note
   You may want to assign NONE to a super user.

   If you select NONE, you are prompted for the Storage Type. Go to Step 13.

   If you select MD5 or SHA, the following prompt is displayed:

   ```
   Enter Authentication Password:
   ```

8. Enter an authentication password of up to 32 alphanumeric characters and press Return.

Downloaded from www.Manualslib.com manuals search engine

You are prompted to re-enter the password.

The following prompt is displayed:

```
Enter Privacy Protocol [D-DES, N-None]:
```

Note
You can only configure the Privacy Protocol if you have configured the Authentication Protocol with the MD5 or SHA values.

9. Select one of the following options:

   D -DES
   Select this value to make the DES privacy (or encryption) protocol the privacy protocol for this User Table entry. With this selection, messages transmitted between the host and the switch are encrypted with the DES protocol.

   N -None
   Select this value if you do not want a privacy protocol for this User Table entry. With this selection, messages transmitted between the host and the switch are not encrypted.

   If you select NONE, you are prompted for the Storage Type. Go to Step 13.

   If you select DES, the following prompt is displayed:

   ```
   Enter Privacy Password:
   ```

10. Enter a privacy password of up to 32 alphanumeric characters.

    You are prompted to re-enter the password.

    The following prompt is displayed:

    ```
    Enter Storage Type [V-Volatile, N-NonVolatile]:
    ```

11. Select one of the following storage types for this table entry:

    V - Volatile
    Select this storage type if you do not want the ability to save an entry in the SNMPv3 User Table to nonvolatile memory. After making changes to an SNMPv3 User Table entry with a Volatile storage type, the **S** - Save Configuration Changes option does not appear on the Main Menu.

    N-NonVolatile
    Select this storage type if you want the ability to save an entry in the SNMPv3 User Table to nonvolatile memory. After making changes to an SNMPv3 User Table entry with a NonVolatile storage type, the **S** - Save Configuration Changes option appears on the Main Menu,

Downloaded from www.Manualslib.com manuals search engine

allowing you to save your changes. Allied Telesis recommends this storage type.

Note
The Row Status parameter is a read-only field. The Active value indicates the SNMPv3 User Table entry takes effect immediately.

12. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Deleting an SNMPv3 User Table Entry

You may want to delete an entry from the SNMPv3 User Table. When you delete an entry in the SNMPv3 User Table, there is no way to undelete, or recover the entry.

To delete an entry in the SNMPv3 User Table, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in "Configuring the SNMPv3 User Table" on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **2** to select Configure SNMPv3 User Table.

   The SNMPv3 User Table is shown in Figure 127 on page 322.

3. From the SNMPv3 User Table, type **2** to select Delete SNMPv3 Table Entry.

   The following prompt is displayed:

   ```
   Enter User (Security) Name:
   ```

4. Enter the User Name of the User Table entry you want to delete.

   The following prompt is displayed:

   ```
   Do you want to delete this table entry? (Y/N):[Yes/No]->
   ```

5. Enter **Y** to delete the user or **N** to save the user.

6. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Modifying an SNMPv3 User Table Entry

This section describes how to modify parameters in an SNMPv3 Notify Table entry. See the following procedures:

- “Modifying the Authentication Protocol and Password” on page 326
- “Modifying the Privacy Protocol and Password” on page 328
- “Modifying the Storage Type” on page 329

Modifying the Authentication Protocol and Password

To modify the Authentication Protocol and Password in an SNMPv3 User Table entry, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in “Configuring the SNMPv3 User Table” on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **2** to select Configure SNMPv3 User Table.

   The SNMPv3 User Table is shown in Figure 127 on page 322.

3. From the SNMPv3 User Table, type **3** to select Modify SNMPv3 Table Entry.

   The Modify SNMPv3 User Table is shown in Figure 128.

```
              Allied Telesis AT-9424T/SP - AT-S63
                           Marketing
User: Manager                                  11:20:02 02-Mar-2005
                     Modify SNMPv3 User Table
 Engine ID ................. 80:00:00:CF:03:00:30:84:FD:57:DA
 User Name ................. wilson
 Authentication Protocol ... SHA
 Privacy Protocol .......... DES
 Storage Type .............. NonVolatile
 Row Status ................ Active

 1 - Set Authentication Protocol & Password
 2 - Set Privacy Protocol & Password
 3 - Set Storage Type

 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 128. Modify SNMPv3 User Table Menu

Downloaded from www.Manualslib.com manuals search engine

4. To change the authentication protocol and password, type **1** to select Set Authentication Protocol & Password.

   The following prompt is displayed:

   ```
   Enter User Name:
   ```

5. Enter the User Name of the User Table you want to modify.

   The following prompt is displayed:

   ```
   Enter Authentication Protocol [M-MD5, S-SHA, N-None]:
   ```

6. Enter one of the following:

   M-MD5
   This value represents the MD5 authentication protocol. With this selection, users (SNMP entities) are authenticated with the MD5 authentication protocol after a message is received. This algorithm generates the message digest. The user is authenticated when the authentication protocol checks the message digest. With the MD5 selection, you can configure a Privacy Protocol.

   S-SHA
   This value represents the SHA authentication protocol. With this selection, users are authenticated with the SHA authentication protocol after a message is received. This algorithm generates the message digest. The user is authenticated when the authentication protocol checks the message digest. With the SHA selection, you can configure a Privacy Protocol.

   N-None
   This value represents no authentication protocol. When messages are received, users are not authenticated. With the None selection, you cannot configure a Privacy Protocol.

   If you select None, go to step 9.

   If you select MD5 or SHA, the following prompt is displayed:

   ```
   Enter Authentication Password:
   ```

7. Enter an authentication password of up to 32 alphanumeric characters.

   The following prompt is displayed:

   ```
   Re-enter Authentication password:
   ```

8. Re-enter the password.

   The following message is displayed:

   ```
   Authentication protocol algorithm has been changed.
   ```


Downloaded from www.Manualslib.com manuals search engine

The following prompt is displayed:

```
Please enter privacy password to regenerate privacy key.
```

9. Enter the Privacy Password for this User Name.

   The following prompt is displayed:

   ```
   Re-enter Privacy password:
   ```

10. Re-enter the password.

11. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Modifying the Privacy Protocol and Password

To modify the Privacy Protocol and Password in an SNMPv3 User Table entry, perform the following procedure.

> **Note**
> You can only configure the Privacy Protocol if you have configured the Authentication Protocol with the MD5 or SHA values.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in “Configuring the SNMPv3 User Table” on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **2** to select Configure SNMPv3 User Table.

   The SNMPv3 User Table is shown in Figure 127 on page 322.

3. From the SNMPv3 User Table, type **3** to select Modify SNMPv3 Table Entry.

   The Modify SNMPv3 Table menu is shown in Figure 128 on page 326.

4. Type **2** to select Privacy Protocol & Password.

   The following prompt is displayed:

   ```
   Enter User (Security) Name:
   ```

5. Enter the User Name.

   The following prompt is displayed:

   ```
   Enter Privacy Protocol [D-DES, N-None]:
   ```


Downloaded from www.Manualslib.com manuals search engine

6. Choose one of the following Privacy Protocols:

   D -DES
   Select this value to make the DES privacy (or encryption) protocol the privacy protocol for this User Table entry. With this selection, messages transmitted between the host and the switch are encrypted with the DES protocol.

   N -None
   Select this value if you do not want a privacy protocol for this User Table entry. With this selection, messages transmitted between the host and the switch are not encrypted.

   If you select None, proceed to step 9.

   If you select DES, the following prompt is displayed:

   ```
   Enter Privacy Password:
   ```

7. Enter a privacy password of up to 32 alphanumeric characters.

   The following prompt is displayed:

   ```
   Re-enter Authentication password:
   ```

8. Re-enter the password.

9. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Modifying the Storage Type

To modify the Storage Type in an SNMPv3 User Table entry, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in "Configuring the SNMPv3 User Table" on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **2** to select Configure SNMPv3 User Table.

   The SNMPv3 User Table is shown in Figure 127 on page 322.

3. From the SNMPv3 User Table, type **3** to select Modify SNMPv3 Table Entry.

   The Modify SNMPv3 Table menu is shown in Figure 128 on page 326.

4. To change the storage type, type **3** to select Set Storage Type.

Downloaded from www.Manualslib.com manuals search engine

The following prompt is displayed:

```
Enter User (Security) Name:
```

5. Enter the User Name.

   The following prompt is displayed:

   ```
   Enter Storage Type [V-Volatile, N-NonVolatile]:
   ```

6. Select one of the following storage types for this table entry:

   V - Volatile
   Select this storage type if you do not want the ability to save an entry in the SNMPv3 User Table to nonvolatile memory. After making changes to an SNMPv3 User Table entry with a Volatile storage type, the **S** - Save Configuration Changes option does not appear on the Main Menu.

   N-NonVolatile
   Select this storage type if you want the ability to save an entry in the SNMPv3 User Table to nonvolatile memory. After making changes to an SNMPv3 User Table entry with a NonVolatile storage type, the **S** - Save Configuration Changes option appears on the Main Menu, allowing you to save your changes. Allied Telesis recommends this storage type.

7. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Configuring the SNMPv3 View Table

This section contains a description of the SNMPv3 View Table and how to create, delete, and modify table entries. Creating this table, allows you to specify a view using the following parameters:

- Subtree OID
- Subtree Mask
- MIB OID Table View

To configure the SNMPv3 View Table, you need to be very familiar with the OID table. You can be very specific about the view a user can or cannot access—down to a column or row of the table. AT-S63 supports the Internet subtree of the OID table.

There are three functions you can perform with the SNMPv3 User Table:

- "Creating an SNMPv3 View Table Entry," next
- "Deleting an SNMPv3 View Table Entry" on page 334
- "Modifying an SNMPv3 View Table Entry" on page 335

Creating an SNMPv3 View Table Entry

To create an entry in the SNMPv3 View Table, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in "Configuring the SNMPv3 User Table" on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **3** to select Configure SNMPv3 View Table.

Downloaded from www.Manualslib.com manuals search engine

The Configure SNMPv3 View Table menu is shown in Figure 129.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                              11:20:02 02-Mar-2005
                 Configure SNMPv3 View Table
 View Name ................. internet
 Subtree OID ............... 1.3.6.1
 Subtree Mask ..............
 View Type ................. Included
 Storage Type .............. NonVolatile
 Row Status ................ Active

 1 - Create SNMPv3 Table Entry
 2 - Delete SNMPv3 Table Entry
 3 - Modify SNMPv3 Table Entry

 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 129. Configure SNMPv3 View Table Menu

3. From the Configure SNMPv3 View Table menu, type **1** to select Create SNMPv3 Table Entry.

   The following prompt is displayed:

   ```
   Enter View Name:
   ```

4. Enter a descriptive name of this View.

   Enter a unique name of up to 32 alphanumeric characters.

   Note
   The “defaultViewAll” value is the default entry for the SNMPv1 and SNMPv2c configuration. You cannot use the default value for an SNMPv3 View Table entry.

   The following prompt is displayed:

   ```
   Enter View Subtree (OID format/Text Name):
   ```

5. Enter the subtree that this view will or will not be permitted to display.

   You can enter either a numeric value in hex format or the equivalent text name. For example, the OID hex format for TCP/IP is:

   ```
   1.3.6.1.2.1.6
   ```

   The text format is for TCP/IP is:

Downloaded from www.Manualslib.com manuals search engine

```
tcp
```

The following prompt is displayed:

```
Enter Subtree Mask (Hex format):
```

6. Enter a subtree mask in hexadecimal format.

   This is an optional parameter that is used to further refine the value in the View Subtree parameter. This parameter is in binary format.

   The relationship between a subtree mask and a subtree is similar to the relationship between an IP address and a subnet mask. The subnet mask further refines the IP address. In the same way, the OID table entry defines a MIB View and the subtree mask further restricts a user's view to a specific the column and row of the MIB View. The value of the Subnet Mask parameter is dependent on the subtree you select. For example, if you configure the View Subtree parameter as MIB, ifEntry.0.3 has the following value:

   ```
   1.3.6.1.2.1.2.2.1.0.3
   ```

   To restrict the user's view to the third row (all columns) of the ifEntry MIB, enter the following value for the Subtree Mask parameter

   ```
   ff:bf
   ```

   The following prompt is displayed:

   ```
   Enter View Type [I-Included, E-Excluded]:
   ```

7. Enter one of the following view types:

   I - Included
   Enter this value to permit the View Name to see the subtree specified above.

   E - Excluded
   Enter this value to not permit the View Name to see the subtree specified above.

   The following prompt is displayed:

   ```
   Enter Storage Type [V-Volatile, N-NonVolatile]:
   ```

8. Select one of the following storage types for this table entry:

   V - Volatile
   Select this storage type if you do not want the ability to save an entry in the SNMPv3 View Table to the configuration file. After making changes to an SNMPv3 View Table entry with a Volatile storage type, the **S** - Save Configuration Changes option does not appear on the Main Menu.

Downloaded from www.Manualslib.com manuals search engine

N-NonVolatile
Select this storage type if you want the ability to save an entry in the SNMPv3 View Table to the configuration file. After making changes to an SNMPv3 View Table entry with a NonVolatile storage type, the **S** - Save Configuration Changes option appears on the Main Menu, allowing you to save your changes. Allied Telesis recommends this storage type.

Note
The Row Status parameter is a read-only field. The Active value indicates the SNMPv3 View Table entry takes effect immediately.

9. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Deleting an SNMPv3 View Table Entry

You may want to delete an entry from the SNMPv3 View Table. After you delete an SNMPv3 View Table entry, there is no way to undelete, or recover the entry.

To delete an entry in the SNMPv3 View Table, perform the following procedure:

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in “Configuring the SNMPv3 User Table” on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **3** to select Configure SNMPv3 View Table.

   The SNMPv3 View Table is shown in Figure 129 on page 332.

3. From the SNMPv3 View Table, type **2** to select Delete SNMPv3 Table Entry.

   The following prompt is displayed:

   ```
   Enter View Name:
   ```

4. Enter the View Name of the View Table entry you want to delete.

   The following prompt is displayed:

   ```
   Enter View Subtree (OID format/Text Name):
   ```

5. Enter the subtree for this view.

   ```
   Do you want to delete this table entry? (Y/N):[Yes/No]->
   ```


Downloaded from www.Manualslib.com manuals search engine

6. Enter **Y** to delete the view or **N** to save the view.

7. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Modifying an SNMPv3 View Table Entry

This section describes how to modify parameters in an SNMPv3 Notify Table entry. See the following procedures:

- "Modifying a Subtree Mask" on page 335
- "Modifying a View Type" on page 337
- "Modifying a Storage Type" on page 338

Modifying a Subtree Mask

To modify the Subtree Mask parameter in an SNMPv3 View Table entry, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in "Configuring the SNMPv3 User Table" on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **3** to select Configure SNMPv3 View Table.

   The Configure SNMPv3 View Table menu is shown in Figure 129 on page 332.

3. From the Configure SNMPv3 View Table menu, type **3** to select Modify SNMPv3 Table Entry.

Downloaded from www.Manualslib.com manuals search engine

The Modify SNMPv3 View Table menu is shown in Figure 130.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                              11:20:02 02-Mar-2005
                  Modify SNMPv3 View Table

 View Name ................. tcp
 Subtree OID ............... 1.3.6.1.2.1.6
 Subtree Mask .............. ff:ff
 View Type ................. Included
 Storage Type .............. NonVolatile
 Row Status ................ Active

 1 - Set Subtree Mask
 2 - Set View Type
 3 - Set Storage Type

 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 130. Modify SNMPv3 View Table Menu

4. To modify the Subtree Mask for this view, type **1** to select Set Subtree Mask.

   The following prompt is displayed:

   ```
   Enter View Name:
   ```

5. Enter an existing View Name.

   The following prompt is displayed:

   ```
   Enter View Subtree (OID format/Text Name):
   ```

6. Enter Subtree that this view will or will not be permitted to display.

   You can enter either a numeric value in hex format or the equivalent text name. For example, the OID hex format for TCP/IP is:

   ```
   1.3.6.1.2.1.6
   ```

   The text format is for TCP/IP is:

   ```
   tcp
   ```

   The following prompt is displayed:

   ```
   Enter Subtree Mask (Hex format):
   ```

7. Enter a Subtree Mask in hexadecimal format.

Downloaded from www.Manualslib.com manuals search engine

This is an optional parameter that is used to further refine the value in the View Subtree parameter. This parameter is in binary format.

A subtree mask and a subtree have a similar relationship as an IP address and a subnet mask. The subnet mask further refines the IP address. In the same way, the OID table entry defines a MIB View and the subtree mask further restricts a user's view to a specific the column and row of the MIB View. The value of the Subnet Mask parameter is dependent on the subtree you select. For example, if you configure the View Subtree parameter as MIB, ifEntry.0.3 has the following value:

```
1.3.6.1.2.1.2.2.1.0.3
```

To restrict the user's view to the third row (all columns) of the ifEntry MIB, enter the following value for the Subtree Mask parameter:

```
ff:bf
```

8. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Modifying a View Type

To modify the View Type parameter in an SNMPv3 View Table entry, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in "Configuring the SNMPv3 User Table" on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **3** to select Configure SNMPv3 View Table.

   The Configure SNMPv3 View Table menu is shown in Figure 129 on page 332.

3. From the Configure SNMPv3 View Table menu, type **3** to select Modify SNMPv3 Table Entry.

   The Modify SNMPv3 Table menu is shown in Figure 130 on page 336.

4. To modify the View Type, type **2** to select Set View Type.

   The following prompt is displayed:

   ```
   Enter View Name:
   ```

5. Enter a View Name that was previously configured.

Downloaded from www.Manualslib.com manuals search engine

The following prompt is displayed:

```
Enter View Subtree (OID format/Text Name):
```

6. Enter the View Subtree value for this View Name.

   You can enter either a numeric value in hex format or the equivalent text name. For example, the OID hex format for TCP/IP is:

   ```
   1.3.6.1.2.1.6
   ```

   The text format is for TCP/IP is:

   ```
   tcp
   ```

   The following prompt is displayed:

   ```
   Enter View Type [I-Included, E-Excluded]:
   ```

7. Choose one of the following view types:

   I - Included
   Enter this value to permit the View Name to see the subtree specified above.

   E - Excluded
   Enter this value to not permit the View Name to see the subtree specified above.

8. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Modifying a Storage Type

To modify the Storage Type parameter in an SNMPv3 View Table entry, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in “Configuring the SNMPv3 User Table” on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **3** to select Configure SNMPv3 View Table.

   The Configure SNMPv3 View Table menu is shown in Figure 129 on page 332.

3. From the Configure SNMPv3 View Table menu, type **3** to select Modify SNMPv3 Table Entry.

Downloaded from www.Manualslib.com manuals search engine

The Modify SNMPv3 Table menu is shown in Figure 130 on page 336.

4. To modify the storage type, type **3** to select Set Storage Type.

   The following prompt is displayed:

   ```
   Enter View Name:
   ```

5. Enter the View Name you want to modify.

   The following prompt is displayed:

   ```
   Enter View Subtree (OID format/Text Name):
   ```

6. Enter the View Subtree for this View Name.

   The following prompt is displayed:

   ```
   Enter Storage Type [V-Volatile, N-Nonvolatile]:
   ```

7. Select one of the following storage types for this table entry:

   V - Volatile
   Select this storage type if you do not want the ability to save an entry in the SNMPv3 View Table to the configuration file. After making changes to an SNMPv3 View Table entry with a Volatile storage type, the **S** - Save Configuration Changes option does not appear on the Main Menu.

   N-NonVolatile
   Select this storage type if you want the ability to save an entry in the SNMPv3 View Table to the configuration file. After making changes to an SNMPv3 View Table entry with a NonVolatile storage type, the **S** - Save Configuration Changes option appears on the Main Menu, allowing you to save your changes. Allied Telesis recommends this storage type.

8. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Configuring the SNMPv3 Access Table

This section contains a description of the SNMPv3 Access Table and how to create, delete, and modify table entries. The SNMPv3 Access Table allows you to configure a security group. Each user must belong to a security group. After you have configured a security group, use the SecurityToGroup Table to assign users to security groups. See “Creating an SNMPv3 SecurityToGroup Table Entry” on page 356.

For each security group, you can assign the following attributes:

- a Security Model (SNMPv1, SNMPv2c, SNMPv3)
- Read, write, and notify views
- A security level
- A storage type

Before you begin this procedure, you will need to configure entries in the View Table. These values are used to configure the Read, Write, and Notify View parameters in this procedure. See “Configuring the SNMPv3 View Table” on page 331.

There are three functions you can perform with the SNMPv3 Access Table.

- “Creating an SNMPv3 Access Table Entry,” next
- “Deleting an SNMPv3 Access Table Entry” on page 344
- “Modifying an SNMPv3 Access Table Entry” on page 346

Creating an SNMPv3 Access Table Entry

To create an entry in the SNMPv3 Access Table, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in “Configuring the SNMPv3 User Table” on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **4** to select Configure SNMPv3 Access Table.

Downloaded from www.Manualslib.com manuals search engine

The Configure SNMPv3 Access Table menu is shown in Figure 131.

```
                Allied Telesis AT-9424T/SP - AT-S63
                             Marketing
User: Manager                                        11:20:02 02-Mar-2005
                    Configure SNMPv3 Access Table
 Group Name .... softwareengineering   Security Model . v3
 Context Prefix.                       Security Level . AuthPriv
 Read View...... internet              Context Match .. Exact
 Write View .... tcp                   Storage Type ... NonVolatile
 Notify View ... tcp                   Row Status ..... Active

 1 - Create SNMPv3 Table Entry
 2 - Delete SNMPv3 Table Entry
 3 - Modify SNMPv3 Table Entry

 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 131. Configure SNMPv3 Access Table Menu

3. To create a group in the SNMPv3 Access Table, type **1** to select Create SNMPv3 Table Entry.

   The following prompt is displayed:

   ```
   Enter Group Name:
   ```

4. Enter a descriptive name of the group. The Group Name can consist of up to 32 alphanumeric characters.

   The Group Name can consist of up to 32 alphanumeric characters.

   You are not required to enter a unique value here because the SNMPv3 Access Table entry is index with the Group Name, Security Model, and Security Level parameter values. However, unique group names allow you to more easily distinguish the groups.

   There are four default values for this field:

   - defaultV1GroupReadOnly
   - defaultV1GroupReadWrite
   - defaultV2cGroupReadOnly
   - defaultV2cGroupReadWrite

   These values are reserved for SNMPv1 and SNMPv2c implementations.

Downloaded from www.Manualslib.com manuals search engine

Note
The Context Prefix and the Context Match fields are a read only fields. The Context Prefix field is always set to null. The Context Match field is always set to exact.

The following prompt is displayed:

```
Enter Security Model [1-v1, 2-v2c, 3-v3]:
```

5. Select one of the following SNMP protocols as the Security Model for this Group Name.

   1-v1
   Select this value to associate the Group Name with the SNMPv1 protocol.

   2-v2c
   Select this value to associate the Group Name with the SNMPv2c protocol.

   3-v3
   Select this value to associate the Group Name with the SNMPv3 protocol. The SNMPv3 protocol allows you to configure the group to authenticate SNMPv3 entities (users) and encrypt messages.

   The following prompt is displayed:

   ```
   Enter Security Level [N-NoAuthNoPriv, A-AuthNoPriv,
   P-AuthPriv]:
   ```

6. Select one of the following security levels:

   N-NoAuthNoPriv
   This option represents no authentication and no privacy protocol. Select this security level if you do not want to authenticate SNMP entities and you do not want to encrypt messages using a privacy protocol. This security level provides the least security.

   Note
   If you have selected SNMPv1 or SNMPv2c, N-NoAuthNoPriv is the only security level you can select.

   A-AuthNoPriv
   This option represents authentication, but no privacy protocol. Select this security level if you want to authenticate SNMP users, but you do not want to encrypt messages using a privacy protocol.You can select this value if you configured the Security Model parameter with the SNMPv3 protocol.

Downloaded from www.Manualslib.com manuals search engine

P-AuthPriv
This option represents authentication and the privacy protocol. Select this security level to encrypt messages using a privacy protocol and authenticate SNMP entities. This level provides the greatest level of security. You can select this value if you configured the Security Model parameter with the SNMPv3 protocol.

The following prompt is displayed:

```
Enter Read View Name:
```

7. Enter a value that you configured with the View Name parameter in the SNMPv3 View Table.

   A Read View Name allows the users assigned to this Group Name to view the information specified by the View Table entry. This value does not need to be unique.

   The following prompt is displayed:

   ```
   Enter Write View Name:
   ```

8. Enter a value that you configured with the View Name parameter in the SNMPv3 View Table.

   A Write View Name allows the users assigned to this Security Group to write, or modify, the information in the specified View Table. This value does not need to be unique.

   The following prompt is displayed:

   ```
   Enter Notify View Name:
   ```

9. Enter a value that you configured with the View Name parameter in the SNMPv3 View Table.

   A Notify View Name allows the users assigned to this Group Name to send traps permitted in the specified View. This value does not need to be unique.

   The following prompt is displayed:

   ```
   Enter Storage Type [V-Volatile, N-NonVolatile]:
   ```

10. Select one of the following storage types for this table entry:

    V - Volatile
    Select this storage type if you do not want the ability to save an entry in the SNMPv3 Access Table to the configuration file. After making changes to an SNMPv3 Access Table entry with a Volatile storage type, the
    S - Save Configuration Changes option does not appear on the Main Menu.

Downloaded from www.Manualslib.com manuals search engine

N-NonVolatile
Select this storage type if you want the ability to save an entry in the SNMPv3 Access Table to the configuration file. After making changes to an SNMPv3 Access Table entry with a NonVolatile storage type, the **S** - Save Configuration Changes option appears on the Main Menu, allowing you to save your changes. Allied Telesis recommends this storage type.

Note
The Row Status parameter is a read-only field. The Active value indicates the SNMPv3 Access Table entry will take effect immediately.

11. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Deleting an SNMPv3 Access Table Entry

You may want to delete an entry from the SNMPv3 Access Table. After you delete an SNMPv3 Access Table, there is no way to undelete, or recover, the entry.

To delete an entry in the SNMPv3 Access Table, perform the following procedure:

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in “Configuring the SNMPv3 User Table” on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **4** to select Configure SNMPv3 Access Table.

   The SNMPv3 Access Table is shown in Figure 131 on page 341.

   Note
   To display a particular Group Name and its associated parameters from the Configure SNMPv3 Access Table menu, type **N** to display the Next Page and **P** to display the previous page.

3. From the SNMPv3 Access Table, type **2** to select Delete SNMPv3 Table Entry.

   The following prompt is displayed:

   ```
   Enter Group Name:
   ```

4. Enter the Group Name that you want to delete.

Downloaded from www.Manualslib.com manuals search engine

The following prompt is displayed:

```
Enter Security Model [1-v1, 2-v2c, 3-v3]:
```

5. Enter the Security Model of this Group Name.

   Select one of the following security levels:

   1-v1
   Select this value to associate the Group Name with the SNMPv1 protocol.

   2-v2c
   Select this value to associate the Group Name with the SNMPv2c protocol.

   3-v3
   Select this value to associate the Group Name with the SNMPv3 protocol. The following prompt is displayed:

   ```
   Enter the Security Level [N-NoAuthNoPriv,
   A-AuthNoPriv, P-AuthPriv]:
   ```

6. Enter the Security Level of this Group Name.

   Select one of the following Security Levels:

   N-NoAuthNoPriv
   This option represents no authentication and no privacy protocol. Select this security level if you do not want to authenticate SNMP entities and you do not want to encrypt messages using a privacy protocol. This security level provides the least security.

   Note
   If you have selected SNMPv1 or SNMPv2c, N-NoAuthNoPriv is the only security level you can select.

   A-AuthNoPriv
   This option represents authentication, but no privacy protocol. Select this security level if you want to authenticate SNMP users, but you do not want to encrypt messages using a privacy protocol.You can select this value if you configured the Security Model parameter with the SNMPv3 protocol.

   P-AuthPriv
   This option represents authentication and the privacy protocol. Select this security level to encrypt messages using a privacy protocol and authenticate SNMP entities. This level provides the greatest level of security. You can select this value if you configured the Security Model parameter with the SNMPv3 protocol.

   The following prompt is displayed:

Downloaded from www.Manualslib.com manuals search engine

```
Do you want to delete this table entry?(Y/N):[Yes/No]->
```

7. Enter **Y** to delete the view or **N** to save the view.

   The following prompt is displayed:

8. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Modifying an SNMPv3 Access Table Entry

This section describes how to modify parameters in an SNMPv3 Access Table entry. For each entry in the SNMPv3 Access Table, you can modify the following parameters:

- Read View Name
- Write View Name
- Notify View Name
- Storage Type

Configure the values of the Read View Name, Write View Name, and Notify View Name parameters with values previously configured with the View Name parameter in the SNMPv3 View Table. This is the only way to associate a Group Name with these Views. See “Creating an SNMPv3 View Table Entry” on page 331.

See the following procedures:

- “Modifying the Read View Name” on page 346
- “Modifying the Write View Name” on page 349
- “Modifying the Notify View Name” on page 351
- “Modifying the Storage Type” on page 353

Modifying the Read View Name

To modify the Read View Name parameter in an SNMPv3 Access Table entry, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in “Configuring the SNMPv3 User Table” on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **4** to select Configure SNMPv3 Access Table.

   The Configure SNMPv3 Access Table is shown in Figure 131 on page 341.

Downloaded from www.Manualslib.com manuals search engine

3. From the Configure SNMPv3 Access Table, type **3** to select Modify SNMPv3 Table Entry.

   The Modify SNMPv3 Access Table is shown in Figure 132.

```
              Allied Telesis AT-9424T/SP - AT-S63
                           Marketing
User: Manager                                  11:20:02 02-Mar-2005
                    Modify SNMPv3 Access Table
 Group Name .... sales              Security Model . v3
 Context Prefix.                    Security Level . AuthNoPriv
 Read View...... systemmanagers     Context Match .. Exact
 Write View .... salespeople        Storage Type ... Volatile
 Notify View ... salespeople        Row Status ..... Active

 1 - Set Read View Name
 2 - Set Write View Name
 3 - Set Notify View Name
 4 - Set Storage Type

 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 132. Modify SNMPv3 Access Table Menu

4. To modify the Read View Name parameter, type **1** to select Set Read View Name.

   The following prompt is displayed:

   ```
   Enter Group Name:
   ```

5. Enter a Group Name that was previously configured.

   The following prompt is displayed:

   ```
   Enter Security Model [1-v1, 2-v2c, 3-v3]:
   ```

6. Enter the Security Model configured for this Group Name. You cannot change the value of the Security Model parameter.

   Select one of the following SNMP protocols:

   1-v1
   Select this value to associate the Group Name with the SNMPv1 protocol.

   2-v2c
   Select this value to associate the Group Name with the SNMPv2c protocol.

Downloaded from www.Manualslib.com manuals search engine

3-v3
Select this value to associate the Group Name with the SNMPv3 protocol.

The following prompt is displayed:

```
Enter Security Level [N-NoAuthNoPriv, A-AuthNoPriv,
P-AuthPriv]:
```

7. Select one of the following security levels:

N-NoAuthNoPriv
This option represents no authentication and no privacy protocol. Select this security level if you do not want to authenticate SNMP entities and you do not want to encrypt messages using a privacy protocol. This security level provides the least security.

Note
If you have selected SNMPv1 or SNMPv2c, N-NoAuthNoPriv is the only security level you can select.

A-AuthNoPriv
This option represents authentication, but no privacy protocol. Select this security level if you want to authenticate SNMP users, but you do not want to encrypt messages using a privacy protocol.You can select this value if you configured the Security Model parameter with the SNMPv3 protocol.

P-AuthPriv
This option represents authentication and the privacy protocol. Select this security level to encrypt messages using a privacy protocol and authenticate SNMP entities. This level provides the greatest level of security. You can select this value if you configured the Security Model parameter with the SNMPv3 protocol.

The following prompt is displayed:

```
Enter Read View Name:
```

8. Enter a value that you configured with the View Name parameter in the SNMPv3 View Table. See “Creating an SNMPv3 View Table Entry” on page 331.

A Read View Name allows the users assigned to this Security Group to view the information specified in the View Table. This value does not need to be unique.

9. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Modifying the Write View Name

To modify the Write View Name parameter in an SNMPv3 Access Table entry, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in "Configuring the SNMPv3 User Table" on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **4** to select Configure SNMPv3 Access Table.

   The Configure SNMPv3 Access Table is shown in Figure 131 on page 341.

3. From the Configure SNMPv3 Access Table, type **3** to select Modify SNMPv3 Table Entry.

   The Modify SNMPv3 Table menu is shown in Figure 132 on page 347.

4. To modify the Write View Name parameter, type **2** to select Set Write View Name.

   The following prompt is displayed:

   ```
   Enter Group Name:
   ```

5. Enter a Group Name that was previously configured.

   The following prompt is displayed:

   ```
   Enter Security Model[1-v1, 2-v2c, 3-v3]:
   ```

6. Enter the Security Model configured for this Group Name. You cannot change the value of the Security Model parameter.

   Select one of the following SNMP protocols:

   1-v1
   Select this value to associate the Group Name with the SNMPv1 protocol.

   2-v2c
   Select this value to associate the Group Name with the SNMPv2c protocol.

   3-v3
   Select this value to associate the Group Name with the SNMPv3 protocol.

Downloaded from www.Manualslib.com manuals search engine

The following prompt is displayed:

```
Enter Security Level [N-NoAuthNoPriv, A-AuthNoPriv,
P-AuthPriv]:
```

7. Enter the Security Level configured for this Group Name. You cannot change the value of the Security Level parameter.

   Select one of the following security levels:

   N-NoAuthNoPriv
   This option represents no authentication and no privacy protocol. Select this security level if you do not want to authenticate SNMP entities and you do not want to encrypt messages using a privacy protocol. This security level provides the least security.

   Note
   If you have selected SNMPv1 or SNMPv2c, N-NoAuthNoPriv is the only security level you can select.

   A-AuthNoPriv
   This option represents authentication, but no privacy protocol. Select this security level if you want to authenticate SNMP users, but you do not want to encrypt messages using a privacy protocol.You can select this value if you configured the Security Model parameter with the SNMPv3 protocol.

   P-AuthPriv
   This option represents authentication and the privacy protocol. Select this security level to encrypt messages using a privacy protocol and authenticate SNMP entities. This level provides the greatest level of security. You can select this value if you configured the Security Model parameter with the SNMPv3 protocol.

   The following prompt is displayed:

   ```
   Enter Write View Name:
   ```

8. Enter a value that you configured with the View Name parameter in the SNMPv3 View Table.

   A Write View Name allows the people assigned to this Security Group to write, or modify, to the information in the specified View Table. This value does not need to be unique.

9. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Modifying the Notify View Name

To modify the Notify View Name parameter in an SNMPv3 Access Table entry, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in "Configuring the SNMPv3 User Table" on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **4** to select Configure SNMPv3 Access Table.

   The Configure SNMPv3 Access Table is shown in Figure 131 on page 341.

3. From the Configure SNMPv3 Access Table, type **3** to select Modify SNMPv3 Table Entry.

   The Modify SNMPv3 Table menu is shown in Figure 132 on page 347.

4. To modify the Notify View Name parameter, type **3** to select Set Notify View Name.

   The following prompt is displayed:

   ```
   Enter Group Name:
   ```

5. Enter a Group Name that was previously configured.

   The following prompt is displayed:

   ```
   Enter Security Model[1-v1, 2-v2c, 3-v3]:
   ```

6. Enter the Security Model configured for this Group Name. You cannot change the value of the Security Model parameter.

   Select one of the following SNMP protocols:

   1-v1
   Select this value to associate the Group Name with the SNMPv1 protocol.

   2-v2c
   Select this value to associate the Group Name with the SNMPv2c protocol.

   3-v3
   Select this value to associate the Group Name with the SNMPv3 protocol.

Downloaded from www.Manualslib.com manuals search engine

The following prompt is displayed:

```
Enter Security Level [N-NoAuthNoPriv, A-AuthNoPriv,
P-AuthPriv]:
```

7. Enter the Security Level configured for this Group Name. You cannot change the value of the Security Level parameter.

   Select one of the following security levels:

   N-NoAuthNoPriv
   This option represents no authentication and no privacy protocol. Select this security level if you do not want to authenticate SNMP entities and you do not want to encrypt messages using a privacy protocol. This security level provides the least security.

   Note
   If you have selected SNMPv1 or SNMPv2c, N-NoAuthNoPriv is the only security level you can select.

   A-AuthNoPriv
   This option represents authentication, but no privacy protocol. Select this security level if you want to authenticate SNMP users, but you do not want to encrypt messages using a privacy protocol.You can select this value if you configured the Security Model parameter with the SNMPv3 protocol.

   P-AuthPriv
   This option represents authentication and the privacy protocol. Select this security level to encrypt messages using a privacy protocol and authenticate SNMP entities. This level provides the greatest level of security. You can select this value if you configured the Security Model parameter with the SNMPv3 protocol.

   The following prompt is displayed:

   ```
   Enter Notify View Name:
   ```

8. Enter a value that you configured with the View Name parameter in the SNMPv3 View Table.

   A Notify View Name permits the users assigned to this Security Group to send traps specified in this view of the MIB tree. This value does not need to be unique.

9. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Modifying the Storage Type

To modify the Storage Type parameter in an SNMPv3 Access Table entry, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in "Configuring the SNMPv3 User Table" on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **4** to select Configure SNMPv3 Access Table.

   The Configure SNMPv3 Access Table is shown in Figure 131 on page 341.

3. From the Configure SNMPv3 Access Table, type **3** to select Modify SNMPv3 Table Entry.

   The Modify SNMPv3 Table menu is shown in Figure 132 on page 347.

4. To modify the Storage Type parameter, type **4** to select Set Storage Type.

   The following prompt is displayed:

   ```
   Enter Group Name:
   ```

5. Enter a Group Name that was previously configured.

   The following prompt is displayed:

   ```
   Enter Security Model[1-v1, 2-v2c, 3-v3]:
   ```

6. Enter the Security Model configured for this Group Name. You cannot change the value of the Security Model parameter.

   Select one of the following SNMP protocols:

   1-v1
   Select this value to associate the Group Name with the SNMPv1 protocol.

   2-v2c
   Select this value to associate the Group Name with the SNMPv2c protocol.

   3-v3
   Select this value to associate the Group Name with the SNMPv3 protocol.

Downloaded from www.Manualslib.com manuals search engine

The following prompt is displayed:

```
Enter Security Level [N-NoAuthNoPriv, A-AuthNoPriv,
P-AuthPriv]:
```

7. Enter the Security Level configured for this Group Name. You cannot change the value of the Security Level parameter.

   Select one of the following security levels:

   N-NoAuthNoPriv
   This option represents no authentication and no privacy protocol. Select this security level if you do not want to authenticate SNMP entities and you do not want to encrypt messages using a privacy protocol. This security level provides the least security.

   Note
   If you have selected SNMPv1 or SNMPv2c, N-NoAuthNoPriv is the only security level you can select.

   A-AuthNoPriv
   This option represents authentication, but no privacy protocol. Select this security level if you want to authenticate SNMP users, but you do not want to encrypt messages using a privacy protocol.You can select this value if you configured the Security Model parameter with the SNMPv3 protocol.

   P-AuthPriv
   This option represents authentication and the privacy protocol. Select this security level to encrypt messages using a privacy protocol and authenticate SNMP entities. This level provides the greatest level of security. You can select this value if you configured the Security Model parameter with the SNMPv3 protocol. The following prompt is displayed:

```
Enter Storage Type [V-Volatile, N-NonVolatile]:
```

8. Select one of the following storage types for this table entry:

   V - Volatile
   Select this storage type if you do not want the ability to save an entry in the SNMPv3 Access Table to the configuration file. After making changes to an SNMPv3 Access Table entry with a Volatile storage type, the **S** - Save Configuration Changes option does not appear on the Main Menu.

   N-NonVolatile
   Select this storage type if you want the ability to save an entry in the SNMPv3 Access Table to the configuration file. After making changes to an SNMPv3 Access Table entry with a NonVolatile storage type, the **S** - Save Configuration Changes option appears on the Main Menu,

Downloaded from www.Manualslib.com manuals search engine

allowing you to save your changes. Allied Telesis recommends this storage type.

9. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Configuring the SNMPv3 SecurityToGroup Table

This section contains a description of the SNMPv3 SecurityToGroup Table and how to create, delete, and modify table entries. The SNMPv3 SecurityToGroup Table allows you to associate a User Name with a Group Name. The User Name is configured in the Configure SNMPv3 User Table menu while the Group Name is configured in the Configure SNMPv3 Access Table menu. In addition, the configuration in the Configure SNMPv3 Access Table menu defines which MIB views this User can read, write (modify), and send traps from. For each User Name, you can assign:

- A Security Model (SNMPv1, SNMPv2c, SNMPv3)
- A Group Name
- A Storage Type

There are three functions you can perform with the SNMPv3 Access Table.

- "Creating an SNMPv3 SecurityToGroup Table Entry," next
- "Deleting an SNMPv3 SecurityToGroup Table Entry" on page 359
- "Modifying an SNMPv3 SecurityToGroup Table Entry" on page 360

Creating an SNMPv3 SecurityToGroup Table Entry

To create an entry in the SecurityToGroup Table, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in "Configuring the SNMPv3 User Table" on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **5** to select Configure SNMPv3 SecurityToGroup Table.

Downloaded from www.Manualslib.com manuals search engine

The Configure SNMPv3 SecurityToGroup Table menu is shown in Figure 133.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                              11:20:02 02-Mar-2005
          Configure SNMPv3 SecurityToGroup Table
 Security Model................. v3
 Security Name ................. spike
 Group Name .................... marketing
 Storage Type .................. NonVolatile
 Row Status .................... Active

 1 - Create SNMPv3 Table Entry
 2 - Delete SNMPv3 Table Entry
 3 - Modify SNMPv3 Table Entry

 N - Next Page
 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 133. Configure SNMPv3 SecurityToGroup Table Menu

3. To configure a group in the SNMPv3 SecurityToGroup Table, type **1** to select Create SNMPv3 Table Entry.

   The following prompt is displayed:

   ```
   Enter User (Security) Name:
   ```

4. Enter the User Name that you want to associate with a group.

   Enter a User Name that you configured in "Creating an SNMPv3 User Table Entry" on page 321.

   The following prompt is displayed:

   ```
   Enter Security Model [1-v1, 2-v2c, 3-v3]:
   ```

5. Select the SNMP protocol that was configured for this User Name.

   Choose from the following:

   1-v1
   Select this value to associate the Group Name with the SNMPv1 protocol.

   2-v2c
   Select this value to associate the Group Name with the SNMPv2c protocol.

Downloaded from www.Manualslib.com manuals search engine

3-v3
Select this value to associate the Group Name with the SNMPv3 protocol.

The following prompt is displayed:

```
Enter Group Name:
```

6. Enter a Group Name that you configured in the SNMPv3 Access Table. See “Creating an SNMPv3 Access Table Entry” on page 340.

   There are four default values for this field:

   - defaultV1GroupReadOnly
   - defaultV1GroupReadWrite
   - defaultV2cGroupReadOnly
   - defaultV2cGroupReadWrite

   These values are reserved for SNMPv1 and SNMPv2c implementations.

   The following prompt is displayed:

   ```
   Enter Storage Type [V-Volatile, N-NonVolatile]:
   ```

7. Select one of the following storage types for this table entry:

   V - Volatile
   Select this storage type if you do not want the ability to save an entry in the SNMPv3 SecurityToGroup Table to the configuration file. After making changes to an SNMPv3 SecurityToGroup Table entry with a Volatile storage type, the **S** - Save Configuration Changes option does not appear on the Main Menu.

   N-NonVolatile
   Select this storage type if you want the ability to save an entry in the SNMPv3 SecurityToGroup Table to the configuration file. After making changes to an SNMPv3 SecurityToGroup Table entry with a NonVolatile storage type, the **S** - Save Configuration Changes option appears on the Main Menu, allowing you to save your changes. Allied Telesis recommends this storage type.

   Note
   The Row Status parameter is a read-only field. The Active value indicates the SNMPv3 SecurityToGroup Table entry will take effect immediately.

8. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Deleting an SNMPv3 SecurityToGroup Table Entry

You may want to delete an entry from the SNMPv3 SecurityToGroup Table. When you delete an SNMPv3 SecurityToGroup Table entry, there is no way to undelete, or recover, the entry.

To delete an entry in the SNMPv3 SecurityToGroup Table, perform the following procedure:

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in "Configuring the SNMPv3 User Table" on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **5** to select Configure SNMPv3 SecurityToGroup Table.

   The SNMPv3 SecurityToGroup Table is shown in Figure 133 on page 357.

   Note
   To display a Group Name and its associated parameters from the Configure SNMPv3 SecurityToGroup Table menu, type **N** to display the Next Page and **P** to display the previous page.

3. From the SNMPv3 SecurityToGroup Table, type **2** to select Delete SNMPv3 Table Entry.

   The following prompt is displayed:

   ```
   Enter User (Security) Name:
   ```

4. Enter a User Name.

   The following prompt is displayed:

   ```
   Enter Security Model [1-v1, 2-v2c, 3-v3]:
   ```

5. Enter the Security Model of this User Name.

   Choose from the following:

   1-v1
   Select this value to associate the Group Name with the SNMPv1 protocol.

   2-v2c
   Select this value to associate the Group Name with the SNMPv2c protocol.

Downloaded from www.Manualslib.com manuals search engine

3-v3
Select this value to associate the Group Name with the SNMPv3 protocol.

The following prompt is displayed:

```
Do you want to delete this table entry? (Y/N):[Yes/No]->
```

6. Enter **Y** to delete this SecurityToGroup entry or **N** to save the entry.
7. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Modifying an SNMPv3 SecurityToGroup Table Entry

This section describes how to modify parameters in an SNMPv3 SecurityToGroup Table entry. See the following procedures:

- “Modifying the Group Name” on page 360
- “Modifying the Storage Type” on page 362

Modifying the Group Name

To modify the Group Name in an SNMPv3 SecurityToGroup Table entry, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in “Configuring the SNMPv3 User Table” on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.
2. From the Configure SNMPv3 Table menu, type **5** to select Configure SNMPv3 SecurityToGroup Table.

   The Configure SNMPv3 SecurityToGroup Table is shown in Figure 131.
3. From the Configure SNMPv3 SecurityToGroup Table, type **3** to select Modify SNMPv3 Table Entry.

Downloaded from www.Manualslib.com manuals search engine

The Modify SecurityToGroup Table is displayed as shown Figure 133.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing

User: Manager                           11:20:02 02-Oct-2004

            Modify SNMPv3 SecurityToGroup Table
 Security Model................. v3
 Security Name ................. cleo72
 Group Name .................... engineering
 Storage Type .................. Volatile
 Row Status .................... Active

 1 - Set Group Name
 2 - Set Storage Type

 N - Next Page
 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 134. Modify SNMPv3 SecurityToGroup Table Menu

4. To modify the Group Name, type **1** to select Set Group Name.

   The following prompt is displayed:

   ```
   Enter User (Security) Name:
   ```

5. Enter a User Name.

   The User Name must be previously configured in the Configure SNMPv3 User Table menu. See "Creating an SNMPv3 User Table Entry" on page 321.

   The following prompt is displayed:

   ```
   Enter Security Model [1-v1, 2-v2c, 3-v3]:
   ```

6. Enter the Security Model configured for this User Name. You cannot change the value of the Security Model parameter.

   Select one of the following SNMP protocols:

   1-v1
   Select this value if this User Name is configured with the SNMPv1 protocol.

   2-v2c
   Select this value to associate the User Name with the SNMPv2c protocol.

Downloaded from www.Manualslib.com manuals search engine

3-v3
Select this value to associate the User Name with the SNMPv3 protocol.

The following prompt is displayed:

```
Enter Group Name:
```

7. Enter the new Group Name.

   This value must match a value configured in the Group Name parameter in the Configure SNMPv3 Access Table. See “Creating an SNMPv3 Access Table Entry” on page 340.

8. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Modifying the Storage Type

To modify the Storage Type in an SNMPv3 SecurityToGroup Table entry, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in “Configuring the SNMPv3 User Table” on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **5** to select Configure SNMPv3 SecurityToGroup Table.

   The Configure SNMPv3 SecurityToGroup Table is shown in Figure 131 on page 341.

3. From the Configure SNMPv3 SecurityToGroup Table, type **3** to select Modify SNMPv3 Table Entry.

4. To modify the storage type, type **2** to select Set Storage Type.

   The following prompt is displayed:

   ```
   Enter User (Security) Name:
   ```

5. Enter a User Name.

   The User Name must be previously configured in the Configure SNMPv3 User Table menu. See “Creating an SNMPv3 User Table Entry” on page 321.

   The following prompt is displayed:

   ```
   Enter Security Model [1-v1, 2-v2c, 3-v3]:
   ```


Downloaded from www.Manualslib.com manuals search engine

6. Enter the Security Model configured for this User Name. You cannot change the value of the Security Model parameter.

   Select one of the following SNMP protocols:

   1-v1
   Select this value if this User Name is configured with the SNMPv1 protocol.

   2-v2c
   Select this value if this User Name is configured with the SNMPv2c protocol.

   3-v3
   Select this value if this User Name is configured with the SNMPv3 protocol.

   The following prompt is displayed:

   ```
   Enter Storage Type [V-Volatile, N-NonVolatile]:
   ```

7. Select one of the following storage types for this table entry:

   V - Volatile
   Select this storage type if you do not want the ability to save an entry in the SNMPv3 SecurityToGroup Table to the configuration file. After making changes to an SNMPv3 SecurityToGroup Table entry with a Volatile storage type, the **S** - Save Configuration Changes option does not appear on the Main Menu.

   N-NonVolatile
   Select this storage type if you want the ability to save an entry in the SNMPv3 SecurityToGroup Table to the configuration file. After making changes to an SNMPv3 SecurityToGroup Table entry with a NonVolatile storage type, the **S** - Save Configuration Changes option appears on the Main Menu, allowing you to save your changes. Allied Telesis recommends this storage type.

8. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Configuring the SNMPv3 Notify Table

This section contains a description of the SNMPv3 Notify Table menu and how to create, delete, and modify table entries. The Configure SNMPv3 Notify Table menu allows you to define a name for sending traps. For each Notify Name, you define if a trap or inform message ia sent. The two message types, trap and inform, have different packet formats.

For each Notify group, you can configure:

- Notify Name
- Notify Tag
- Notify Type
- Storage Type

The value of the Notify Tag is linked with the Tag List parameter in the Configure SNMPv3 Target Address Table menu. As a result, the Notify Tag parameter assigns a Target IP address to the Notify Table internally.

There are three functions you can perform with the Configure SNMPv3 Notify Table menu.

- “Creating an SNMPv3 Notify Table Entry,” next
- “Deleting an SNMPv3 Notify Table Entry” on page 366
- “Modifying an SNMPv3 Notify Table Entry” on page 367

Creating an SNMPv3 Notify Table Entry

To create an entry in the SNMPv3 Notify Table menu, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in “Configuring the SNMPv3 User Table” on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **6** to select Configure SNMPv3 Notify Table.

Downloaded from www.Manualslib.com manuals search engine

The Configure SNMPv3 Notify Table menu is shown in Figure 135.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                              11:20:02 02-Mar-2005
                Configure SNMPv3 Notify Table
 Notify Name ..................... hardwareengineeringTrap
 Notify Tag ...................... hardwareengineeringtag
 Notify Type ..................... Trap
 Storage Type .................... NonVolatile
 Row Status ...................... Active

 1 - Create SNMPv3 Table Entry
 2 - Delete SNMPv3 Table Entry
 3 - Modify SNMPv3 Table Entry

 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 135. Configure SNMPv3 Notify Table Menu

3. To create an entry in the table, type **1** to select Create SNMPv3 Table Entry.

   The following prompt is displayed:

   ```
   Enter Notify Name:
   ```

4. Enter the name associated with this trap message.

   Enter a name of up to 32 alphanumeric characters. For example, you might want to define a trap message for hardware engineering and enter a value of "hardwareengineeringtrap" for the Notify Name.

   The following prompt is displayed:

   ```
   Enter Notify Tag:
   ```

5. Enter the name of the Notify Tag.

   Enter a name of up to 32 alphanumeric characters.

   The following prompt is displayed:

   ```
   Enter Notify Type [T-Trap, I-Inform]:
   ```

6. Enter one of the following message types:

   T-Trap
   Indicates this notify table is used to send traps. With this message type, the switch does not expects a response from the host.

Downloaded from www.Manualslib.com manuals search engine

I-Inform
Indicates this notify table is used to send inform messages. With this message type, the switch expects a response from the host.

The following prompt is displayed:

```
Enter Storage Type [V-Volatile, N-NonVolatile]:
```

7. Select one of the following storage types for this table entry:

   V - Volatile
   Select this storage type if you do not want the ability to save an entry in the SNMPv3 Notify Table to the configuration file. After making changes to an SNMPv3 Notify Table entry with a Volatile storage type, the
   S - Save Configuration Changes option does not appear on the Main Menu.

   N-NonVolatile
   Select this storage type if you want the ability to save an entry in the SNMPv3 Notify Table to the configuration file. After making changes to an SNMPv3 Notify Table entry with a NonVolatile storage type, the **S** - Save Configuration Changes option appears on the Main Menu, allowing you to save your changes. Allied Telesis recommends this storage type.

   Note
   The Row Status parameter is a read-only field. The Active value indicates the SNMPv3 Notify Table entry takes effect immediately.

8. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Deleting an SNMPv3 Notify Table Entry

You may want to delete an entry from the Configure SNMPv3 Notify Table menu. When you delete a Configure SNMPv3 Notify Table entry, there is no way to undelete, or recover, the entry.

To delete an entry in the Configure SNMPv3 Notify Table menu, perform the following procedure:

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in “Configuring the SNMPv3 User Table” on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **6** to select Configure SNMPv3 Notify Table.

Downloaded from www.Manualslib.com manuals search engine

The Configure SNMPv3 Notify Table menu is shown in Figure 135 on page 365.

Note
To display a Group Name and its associated parameters from the Configure SNMPv3 SecurityToGroup Table menu, type **N** to display the Next Page and **P** to display the previous page.

3. To delete an SNMPv3 Notify Table entry, type **2** to select Delete SNMPv3 Table Entry.

   The following prompt is displayed:

   ```
   Enter Notify Name:
   ```

4. Enter a Notify Name.

   The following prompt is displayed:

   ```
   Do you want to delete this table entry? (Y/N):[Yes/No]->
   ```

5. Enter **Y** to delete the SNMPv3 Notify Table entry or **N** to save the entry.

6. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Modifying an SNMPv3 Notify Table Entry

This section describes how to modify parameters in an SNMPv3 Notify Table entry. See the following procedures:

- "Modifying a Notify Tag" on page 367
- "Modifying a Notify Type" on page 369
- "Modifying a Storage Type" on page 370

Modifying a Notify Tag

To modify the Notify Tag parameter in an SNMPv3 Notify Table entry, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in "Configuring the SNMPv3 User Table" on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **6** to select Configure SNMPv3 Notify Table.

   The Configure SNMPv3 Notify Table menu is shown in Figure 135 on page 365.

Downloaded from www.Manualslib.com manuals search engine

3. From the Configure SNMPv3 Notify Table menu, type **3** to select Modify SNMPv3 Table Entry.

   The Modify SNMPv3 Notify Table menu is shown in Figure 136.

```
            Allied Telesis AT-9424T/SP - AT-S63
                          Marketing
User: Manager                              11:20:02 02-Mar-2005
                  Modify SNMPv3 Notify Table
 Notify Name ..................... softwareeengineering
 Notify Tag....................... softwareeengineeringtag
 Notify Type...................... Inform
 Storage Type .................... NonVolatile
 Row Status ...................... Active

 1 - Set Notify Tag
 2 - Set Notify Type
 3 - Set Storage Type

 N - Next Page
 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 136. Modify SNMPv3 Notify Table Menu

Note
To display a Group Name and its associated parameters from the Configure SNMPv3 SecurityToGroup Table menu, type **N** to display the Next Page and **P** to display the previous page.

4. To modify the Notify Tag, type **1** to select Set Notify Tag.

   The following prompt is displayed:

   ```
   Enter Notify Name:
   ```

5. Enter a Notify Name.

   The following prompt is displayed:

   ```
   Enter Notify Tag:
   ```

6. Enter the new Notify Tag.

   Enter an alphanumeric value of up to 32 characters.

7. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Modifying a Notify Type

To modify the Notify Type parameter in an SNMPv3 Notify Table entry, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in "Configuring the SNMPv3 User Table" on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **6** to select Configure SNMPv3 Notify Table.

   The Configure SNMPv3 Notify Table menu is shown in Figure 135 on page 365.

3. From the Configure SNMPv3 Notify Table menu, type **3** to select Modify SNMPv3 Table Entry.

   The Modify SNMPv3 Notify Table is shown in Figure 136 on page 368.

4. To modify the Notify Type, type **2** to select Set Notify Type.

   The following prompt is displayed:

   ```
   Enter Notify Name:
   ```

5. Enter a Notify Name.

   The following prompt is displayed:

   ```
   Enter Notify Type [T-Trap, I-Inform]:
   ```

6. Enter one of the following message types:

   T-Trap
   Indicates this notify table is used to send traps. With this message type, the switch does not expect a response from the host.

   I-Inform
   Indicates this notify table is used to send inform messages. With this message type, the switch expects a response from the host.

7. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Modifying a Storage Type

To modify the Storage Type parameter in an SNMPv3 Notify Table entry, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in “Configuring the SNMPv3 User Table” on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **6** to select Configure SNMPv3 Notify Table.

   The Configure SNMPv3 Notify Table menu is shown in Figure 135 on page 365.

3. From the Configure SNMPv3 Notify Table menu, type **3** to select Modify SNMPv3 Table Entry.

   The Modify SNMPv3 Notify Table is shown in Figure 136 on page 368.

4. To modify the Storage Type, type **3** to select Set Storage Type.

   The following prompt is displayed:

   ```
   Enter Notify Name:
   ```

5. Enter a Notify Name.

   The following prompt is displayed:

   ```
   Enter Storage type [V-Volatile, N-NonVolatile]:
   ```

6. Select one of the following storage types for this table entry:

   V - Volatile
   Select this storage type if you do not want the ability to save an entry in the SNMPv3 Notify Table to the configuration file. After making changes to an SNMPv3 Notify Table entry with a Volatile storage type, the
   S - Save Configuration Changes option does not appear on the Main Menu.

   N-NonVolatile
   Select this storage type if you want the ability to save an entry in the SNMPv3 Notify Table to the configuration file. After making changes to an SNMPv3 Notify Table entry with a NonVolatile storage type, the **S** - Save Configuration Changes option appears on the Main Menu, allowing you to save your changes. Allied Telesis recommends this storage type.

Downloaded from www.Manualslib.com manuals search engine

7. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Configuring the SNMPv3 Target Address Table

This section contains a description of the SNMPv3 Target Address Table menu and how to create, delete, and modify table entries. You use the SNMPv3 Target Address Table menu to assign the IP address of a host that is used for generating notifications. The Configure SNMPv3 Target Address Table menu is linked internally to the Configure SNMPv3 Notify Table through the Tag List parameter. The Configure SNMPv3 Notify Table menu receives the host IP address through the configuration of the SNMPv3 Target Address Table menu.

For each Target Address Table entry, you can configure the following parameters:

- Target Address Name
- Target IP Address
- UDP Port
- Timeout Value
- Number of Retries
- Tag List
- Target Parameters
- Storage Type

The values for the Tag List parameter are configured with the Notify Tag parameter in the Configure SNMPv3 Notify Table. See “Creating an SNMPv3 Notify Table Entry” on page 364.

There are three functions you can perform with the Configure SNMPv3 Target Address Table menu.

- “Creating an SNMPv3 Target Address Table Entry,” next
- “Deleting an SNMPv3 Target Address Table Entry” on page 375
- “Modifying an SNMPv3 Target Address Table Entry” on page 376

Creating an SNMPv3 Target Address Table Entry

To create an entry in the Configure SNMPv3 Target Address Table menu, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in “Configuring the SNMPv3 User Table” on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **7** to select Configure SNMPv3 Target Address Table.

Downloaded from www.Manualslib.com manuals search engine

The Configure SNMPv3 Target Address Table menu is shown in Figure 137.

```
               Allied Telesis AT-9424T/SP - AT-S63
                            Marketing
User: Manager                                      11:20:02 02-Mar-2005
              Configure SNMPv3 Target Address Table
 Target Addr Name ... host451         Timeout ..... 1500
 Target Parameters .. SNMPmanagerPC   Retries ..... 3
 IP Address ......... 198.35.11.1     UDP Port# ... 162
 Storage Type ....... NonVolatile     Row Status .. Active
 Tag List ........... hwengTrap hwengInform swengTrap swengInform

 1 - Create SNMPv3 Table Entry
 2 - Delete SNMPv3 Table Entry
 3 - Modify SNMPv3 Table Entry

 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 137. Configure SNMPv3 Target Address Table Menu

3. To create an entry in the SNMPv3 Target Address Table, type **1** to select Create SNMPv3 Table Entry.

   The following prompt is displayed:

   ```
   Enter Target Address Name:
   ```

4. Enter the name of the SNMP manager, or host, that manages the SNMP activity on your switch.

   You can enter a name of up to 32 alphanumeric characters.

   The following prompt is displayed:

   ```
   Enter IP Address:
   ```

5. Enter the IP address of the host.

   Use the following format for an IP address:
   XXX.XXX.XXX.XXX

   The following prompt is displayed:

   ```
   Enter UDP Port#: [0 to 65535]-> 162
   ```

6. Enter a UDP port.

   You can enter a UDP port in the range of 0 to 65,535. The default UDP port is 162.

Downloaded from www.Manualslib.com manuals search engine

The following prompt is displayed:

```
Enter Timeout (10mS): [0 to 2147483647]-> 1500
```

7. Enter a timeout value in milliseconds.

   When an Inform message is generated, a response from the switch is required. The timeout value determines how long the switch considers the Inform message an active message. This parameter applies to Inform messages only. The range is from 0 to 2,147,483,647 milliseconds. The default value is 1500 milliseconds.

   The following prompt is displayed:

   ```
   Enter Retries:[0 to 255]-> 3
   ```

8. Enter the number of times the switch will retry, or resend, an Inform message.

   When an Inform message is generated, a response from the switch is required. This parameter determines how many times the switch resends an Inform message. The Retries parameter applies to Inform messages only. The range is 0 to 255 retries. The default is 3 retries.

   The following prompt is displayed:

   ```
   Enter Tag List:
   ```

9. Enter a Tag List.

   This list consists of a tag or list of tags you configured in a Configure SNMPv3 Notify Table entry with the Notify Tag parameter. See “Creating an SNMPv3 Notify Table Entry” on page 364. Enter a Tag List of up to 256 alphanumeric characters. Use a space to separate entries, for example:

   ```
   hwengtag swengtag testengtag
   ```

   The following prompt is displayed:

   ```
   Enter Target Parameters:
   ```

10. Enter a Target Parameters name.

    This name can consist of up to 32 alphanumeric characters. The value configured here must match the value configured with the Target Parameters Name parameter in the Configure SNMPv3 Target Parameters Table.

    The following prompt is displayed:

    ```
    Enter Storage Type [V-Volatile, N-NonVolatile]:
    ```

11. Select one of the following storage types for this table entry:

Downloaded from www.Manualslib.com manuals search engine

V - Volatile
Select this storage type if you do not want the ability to save an entry in the SNMPv3 Target Address Table to the configuration file. After making changes to an SNMPv3 Target Address Table entry with a Volatile storage type, the **S** - Save Configuration Changes option does not appear on the Main Menu.

N-NonVolatile
Select this storage type if you want the ability to save an entry in the SNMPv3 Target Address Table to the configuration file. After making changes to an SNMPv3 Target Address entry with a NonVolatile storage type, the **S** - Save Configuration Changes option appears on the Main Menu, allowing you to save your changes. Allied Telesis recommends this storage type.

Note
The Row Status parameter is a read-only field. The Active value indicates the SNMPv3 Target Address Table entry will take effect immediately.

12. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Deleting an SNMPv3 Target Address Table Entry

You may want to delete an entry from the SNMPv3 Target Address Table. After you delete an SNMPv3 Target Address Table entry, there is no way to undelete, or recover, the entry.

To delete an entry in the SNMPv3 Target Address Table, perform the following procedure:

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in "Configuring the SNMPv3 User Table" on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **7** to select Configure SNMPv3 Target Address Table.

   The Configure SNMPv3 Target Address Table menu is shown in Figure 139 on page 386.

Note
To display a Group Name and its associated parameters from the Configure SNMPv3 SecurityToGroup Table menu, type **N** to display the Next Page and **P** to display the previous page.

Downloaded from www.Manualslib.com manuals search engine

3. To delete an SNMPv3 Target Address Table entry, type **2** to select Delete SNMPv3 Table Entry.

   The following prompt is displayed:

   ```
   Enter Target Address Name:
   ```

4. Enter a Target Address Name.

   The following prompt is displayed:

   ```
   Do you want to delete this table entry?(Y/N):[Yes/No]->
   ```

5. Enter **Y** to delete the SNMPv3 Target Address Table entry or **N** to save the entry.

6. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Modifying an SNMPv3 Target Address Table Entry

This section describes how to modify parameters in an SNMPv3 Target Address Table entry. See the following procedures:

- ❒ “Modifying a Target IP Address” on page 376
- ❒ “Modifying the Target Address UDP Port” on page 378
- ❒ “Modifying the Target Address Timeout” on page 379
- ❒ “Modifying the Target Address Retries” on page 380
- ❒ “Modifying the Target Address Tag List” on page 381
- ❒ “Modifying the Target Parameters Field” on page 382
- ❒ “Modifying the Storage Type” on page 383

Note
You cannot modify the Target Address Name parameter.

Modifying a Target IP Address

To modify the target IP address in an SNMPv3 Target Address Table entry, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in “Configuring the SNMPv3 User Table” on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **7** to select Configure SNMPv3 Target Address Table.

Downloaded from www.Manualslib.com manuals search engine

The Configure SNMPv3 Target Address Table menu is shown in Figure 137 on page 373.

3. From the Configure SNMPv3 Target Address Table menu, type **3** to select Modify SNMPv3 Table Entry.

   The Modify SNMPv3 Target Address Table menu is shown in Figure 138.

```
                Allied Telesis AT-9424T/SP - AT-S63
                             Marketing
User: Manager11:20:02 02-Mar-2005
                 Modify SNMPv3 Target Address Table
 Target Addr Name ... host451         Timeout ..... 1500
 Target Parameters .. SNMPmanagerPC   Retries ..... 3
 IP Address ......... 198.35.11.1     UDP Port# ... 162
 Storage Type ....... NonVolatile     Row Status .. Active
 Tag List ........... hwengTrap hwengInform swengTrap swengInform

 1 - Set Target IP Address
 2 - Set Target Address UDP Port
 3 - Set Target Address Timeout
 4 - Set Target Address Retries
 5 - Set Target Address TagList
 6 - Set Target Parameters
 7 - Set Storage Type

 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 138. Modify SNMPv3 Target Address Table Menu

4. To change the Target IP Address, type **1** to select Set Target IP Address.

   The following prompt is displayed:

   ```
   Enter Target Address Name:
   ```

5. Enter a previously configured Target Address Name.

   This is the name of the SNMP manager, or host, that manages the SNMP activity on your switch. You can enter a name of up to 32 alphanumeric characters.

   The following prompt is displayed:

   ```
   Enter IP Address:
   ```

6. Enter the IP address of the host.

Downloaded from www.Manualslib.com manuals search engine

Use the following format for an IP address:
XXX.XXX.XXX.XXX

7. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Modifying the Target Address UDP Port

To modify the Target Address UDP Port parameter in an SNMPv3 Target Address Table entry, perform the following procedure:

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in “Configuring the SNMPv3 User Table” on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **7** to select Configure SNMPv3 Target Address Table.

   The Configure SNMPv3 Target Address Table menu is shown in Figure 137 on page 373.

3. From the Configure SNMPv3 Target Address Table menu, type **3** to select Modify SNMPv3 Table Entry.

   The Modify SNMPv3 Target Address Table menu is shown in Figure 138 on page 377.

4. To change the Target Address UDP Port, type **2** to select Set Target Address UDP Port.

   The following prompt is displayed:

   ```
   Enter Target Address Name:
   ```

5. Enter a previously configured Target Address Name.

   This is the name of the SNMP manager, or host, that manages the SNMP activity on your switch. You can enter a name of up to 32 alphanumeric characters.

   The following prompt is displayed:

   ```
   Enter UDP Port#: [0 to 65535]-> 162
   ```

6. Enter a UDP port.

   You can enter a UDP port in the range of 0 to 65,535. The default UDP port is 162.

Downloaded from www.Manualslib.com manuals search engine

7. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Modifying the Target Address Timeout

The Target Address Timeout parameter only applies when the message type is an Inform message. To modify the Target Address Timeout parameter in an SNMPv3 Target Address Table entry, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in "Configuring the SNMPv3 User Table" on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **7** to select Configure SNMPv3 Target Address Table.

   The Configure SNMPv3 Target Address Table menu is shown in Figure 137 on page 373.

3. From the Configure SNMPv3 Target Address Table menu, type **3** to select Modify SNMPv3 Table Entry.

   The Modify SNMPv3 Target Address Table menu is shown in Figure 138 on page 377.

4. To modify the Target Address Timeout, type **3** to select Set Target Address Timeout.

   The following prompt is displayed:

   ```
   Enter Target Address Name:
   ```

5. Enter a previously configured Target Address Name.

   This is the name of the SNMP manager, or host, that manages the SNMP activity on your switch. You can enter a name of up to 32 alphanumeric characters.

   The following prompt is displayed:

   ```
   Enter Timeout (10mS): [0 to 2147483647]-> 1500
   ```

6. Enter a timeout value in milliseconds.

   When an Inform message is generated, a response from the switch is required. The timeout value determines how long the switch considers the Inform message an active message. This parameter applies to

Downloaded from www.Manualslib.com manuals search engine

Inform messages only. The range is from 0 to 2,147,483,647 milliseconds. The default value is 1500 milliseconds.

7. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Modifying the Target Address Retries

The Target Address Retries parameter only applies when the message type is an Inform message. To modify the Target Address Retries parameter in an SNMPv3 Target Address Table entry, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in “Configuring the SNMPv3 User Table” on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **7** to select Configure SNMPv3 Target Address Table.

   The Configure SNMPv3 Target Address Table menu is shown in Figure 137 on page 373.

3. From the Configure SNMPv3 Target Address Table menu, type **3** to select Modify SNMPv3 Table Entry.

   The Modify SNMPv3 Target Address Table menu is shown in Figure 138 on page 377.

4. To modify the Target Address Retries, type **4** to select Set Target Address Retries.

   The following prompt is displayed:

   ```
   Enter Target Address Name:
   ```

5. Enter a previously configured Target Address Name.

   This is the name of the SNMP manager, or host, that manages the SNMP activity on your switch. You can enter a name of up to 32 alphanumeric characters.

   The following prompt is displayed:

   ```
   Enter Retries:[0 to 255]-> 3
   ```

6. Enter the number of times the switch will retry, or resend, the Inform message.

Downloaded from www.Manualslib.com manuals search engine

The range is 0 to 255 retries. The default is 3 retries.

7. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Modifying the Target Address Tag List

To modify the Target Address Tag List parameter in an SNMPv3 Target Address Table entry, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in "Configuring the SNMPv3 User Table" on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **7** to select Configure SNMPv3 Target Address Table.

   The Configure SNMPv3 Target Address Table menu is shown in Figure 137 on page 373.

3. From the Configure SNMPv3 Target Address Table menu, type **3** to select Modify SNMPv3 Table Entry.

   The Modify SNMPv3 Target Address Table menu is shown in Figure 138 on page 377.

4. To modify the Target Address Tag List, type **5** to select Set Target Address TagList.

   The following prompt is displayed:

   ```
   Enter Target Address Name:
   ```

5. Enter a previously configured Target Address Name.

   This is the name of the SNMP manager, or host, that manages the SNMP activity on your switch. You can enter a name of up to 32 alphanumeric characters.

   The following prompt is displayed:

   ```
   Enter Tag List:
   ```

   Enter a Tag List of up to 256 alphanumeric characters. Use a space to separate entries. This list consists of a tag or list of tags you configured in a Configure SNMPv3 Notify Table entry with the Notify Tag parameter. See "Creating an SNMPv3 Notify Table Entry" on page 364.

Downloaded from www.Manualslib.com manuals search engine

6. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Modifying the Target Parameters Field

To modify the Target Parameters field in an SNMPv3 Target Address Table entry, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in “Configuring the SNMPv3 User Table” on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **7** to select Configure SNMPv3 Target Address Table.

   The Configure SNMPv3 Target Address Table menu is shown in Figure 137 on page 373.

3. From the Configure SNMPv3 Target Address Table menu, type **3** to select Modify SNMPv3 Table Entry.

   The Modify SNMPv3 Target Address Table menu is shown in Figure 138 on page 377.

4. To modify the Target Parameters field, type **6** to select Set Target Parameters.

   The following prompt is displayed:

   ```
   Enter Target Address Name:
   ```

5. Enter a previously configured Target Address Name.

   This is the name of the SNMP manager, or host, that manages the SNMP activity on your switch. You can enter a name of up to 32 alphanumeric characters.

   The following prompt is displayed:

   ```
   Enter Target Parameters:
   ```

6. Enter a Target Parameters Name.

   The value configured here must match the value configured with the Target Parameters Name parameter in the Configure SNMPv3 Target Parameters Table. This name can consist of up to 32 alphanumeric characters.

Downloaded from www.Manualslib.com manuals search engine

7. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Modifying the Storage Type

To modify the Storage Type parameter in an SNMPv3 Target Address Table entry, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in "Configuring the SNMPv3 User Table" on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **7** to select Configure SNMPv3 Target Address Table.

   The Configure SNMPv3 Target Address Table menu is shown in Figure 137 on page 373.

3. From the Configure SNMPv3 Target Address Table menu, type **3** to select Modify SNMPv3 Table Entry.

   The Modify SNMPv3 Target Address Table menu is shown in Figure 138 on page 377.

4. To modify the Storage Type, type **7** to select Set Storage Type.

   The following prompt is displayed:

   ```
   Enter Target Address Name:
   ```

5. Enter a previously configured Target Address Name.

   This is the name of the SNMP manager, or host, that manages the SNMP activity on your switch. You can enter a name of up to 32 alphanumeric characters.

   The following prompt is displayed:

   ```
   Enter Storage Type [V-Volatile, N-NonVolatile]:
   ```

6. Select one of the following storage types for this table entry:

   V - Volatile
   Select this storage type if you do not want the ability to save an entry in the SNMPv3 Target Address Table to the configuration file. After making changes to an SNMPv3 Target Address Table entry with a Volatile storage type, the **S** - Save Configuration Changes option does not appear on the Main Menu.

Downloaded from www.Manualslib.com manuals search engine

N-NonVolatile
Select this storage type if you want the ability to save an entry in the SNMPv3 Target Address Table to the configuration file. After making changes to an SNMPv3 Target Address entry with a NonVolatile storage type, the **S** - Save Configuration Changes option appears on the Main Menu, allowing you to save your changes. Allied Telesis recommends this storage type.

7. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Configuring the SNMPv3 Target Parameters Table

This section contains a description of the SNMPv3 Target Parameters Table and how to create, delete, and modify table entries. The SNMPv3 Target Parameters Table links the user security information with the message notification information configured in the Configure SNMPv3 Notify Table menu and Configure SNMPv3 Target Address Table menu.

In the SNMPv3 Target Parameters Table, you specify the SNMP parameters that are used when a message is generated to a target, or host, IP address. The SNMPv3 Target Parameters Table also links a User Name and its related security information, called *user security information*, with a host. The user security information consists of the following parameters listed in the SNMPv3 tables where they are configured:

- User Name parameter configured in the SNMPv3 User Table menu
- View Name parameter configured in the SNMPv3 View Table menu
- Group Name, Security Model, and Security Level parameters configured in the SNMPv3 Access Table
- User Name, Security Model, and Group Name configured in the SNMPv3 SecurityToGroup Table

When you enter user security information in an SNMPv3 Target Parameters Table entry, the information must match the configuration in the SNMPv3 tables listed above. If the user security information in the SNMPv3 Target Parameters Table entry does not match the configuration in the tables listed above, messages are not sent on behalf of the user.

Note
In the SNMPv3 Target Parameters Table, the Security Name parameter is the equivalent to the User Name parameter in the SNMPv3 User Table.

For each Target Address Table entry, you can configure:

- Target Parameters Name
- Security Name (User Name)
- Security Model
- Security Level
- Storage Type

There are three functions you can perform with the Configure SNMPv3 Target Parameters Table menu.

- "Creating an SNMPv3 Target Parameters Table Entry," next

Downloaded from www.Manualslib.com manuals search engine

- ❒ “Deleting an SNMPv3 Target Parameters Table Entry” on page 389
- ❒ “Modifying an SNMPv3 Target Parameters Table Entry” on page 390

Creating an SNMPv3 Target Parameters Table Entry

To create an entry in the Configure SNMPv3 Target Parameters Table, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in “Configuring the SNMPv3 User Table” on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **8** to select Configure SNMPv3 Target Parameters Table menu.

   The Configure SNMPv3 Target Parameters Table menu is shown in Figure 139.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                              11:20:02 02-Mar-2005
          Configure SNMPv3 Target Parameters Table
 Target Parameters Name ... host125parm
 Message Processing Model . v3
 Security Model............ v3
 Security Name ............ murthy
 Security Level ........... AuthPriv
 Storage Type ............. NonVolatile
 Row Status ............... Active

 1 - Create SNMPv3 Table Entry
 2 - Delete SNMPv3 Table Entry
 3 - Modify SNMPv3 Table Entry

 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 139. Configure SNMPv3 Target Parameters Table Menu

3. To create an SNMPv3 Target Parameters Table, type **1** to select Create SNMPv3 Table Entry.

   The following prompt is displayed:

   ```
   Enter Target Parameters Name:
   ```

4. Enter a name of the Target Parameters.

   Enter a value of up to 32 alphanumeric characters.

Downloaded from www.Manualslib.com manuals search engine

Note
You are prompted to enter a value for the Message Processing Model parameter only if you select SNMPv1 or SNMPv2c as the Security Model. If you select the SNMPv3 protocol as the Security Model, then the Message Processing Model is automatically assigned to SNMPv3.

The following prompt is displayed:

```
Enter User (Security) Name:
```

5. Enter a User Name.

   The value of this parameter is previously configured with the Configure SNMPv3 User Table. See "Creating an SNMPv3 User Table Entry" on page 321.

   The following prompt is displayed:

   ```
   Enter Security Model [1-v1, 2-v2c, 3-v3]:
   ```

6. Select one of the following SNMP protocols as the Security Model for this Security Name, or User Name.

   1-v1
   Select this value to associate the Security Name, or User Name, with the SNMPv1 protocol.

   2-v2c
   Select this value to associate the Security Name, or User Name, with the SNMPv2c protocol.

   3-v3
   Select this value to associate the Security Name, or User Name, with the SNMPv3 protocol. The SNMPv3 protocol allows you to configure the group to authenticate SNMPv3 entities (users) and to encrypt messages.

   The following prompt is displayed:

   ```
   Enter Security Level [N-NoAuthNoPriv, A-AuthNoPriv,
   P-AuthPriv]:
   ```

7. Select one of the following Security Levels:

Note
The value you configure for the Security Level must match the value configured for the User Name in the Configure SNMPv3 User Table menu. See "Creating an SNMPv3 User Table Entry" on page 321.

Downloaded from www.Manualslib.com manuals search engine

N-NoAuthNoPriv
This option represents no authentication and no privacy protocol. Select this security level if you do not want to authenticate SNMP entities and you do not want to encrypt messages using a privacy protocol. This security level provides the least security.

Note
If you have selected SNMPv1 or SNMPv2c, N-NoAuthNoPriv is the only security level you can select.

A-AuthNoPriv
This option represents authentication, but no privacy protocol. Select this security level if you want to authenticate SNMP users, but you do not want to encrypt messages using a privacy protocol.You can select this value if you configured the Security Model parameter with the SNMPv3 protocol.

P-AuthPriv
This option represents authentication and the privacy protocol. Select this security level to encrypt messages using a privacy protocol and authenticate SNMP entities. This level provides the greatest level of security. You can select this value if you configured the Security Model parameter with the SNMPv3 protocol.

The following prompt is displayed:

```
Enter Storage Type [V-Volatile, N-NonVolatile]:
```

8. Select one of the following storage types for this table entry:

V - Volatile
Select this storage type if you do not want the ability to save an entry in the SNMPv3 Target Parameters Table to the configuration file. After making changes to an SNMPv3 Target Parameters Table entry with a Volatile storage type, the **S** - Save Configuration Changes option does not appear on the Main Menu.

N-NonVolatile
Select this storage type if you want the ability to save an entry in the SNMPv3 Target Parameters Table to the configuration file. After making changes to an SNMPv3 Target Parameters Table entry with a NonVolatile storage type, the **S** - Save Configuration Changes option appears on the Main Menu, allowing you to save your changes. Allied Telesis recommends this storage type.

Note
The Row Status parameter is a read-only field. The Active value indicates the SNMPv3 Target Parameters Table entry will take effect immediately.

Downloaded from www.Manualslib.com manuals search engine

9. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Deleting an SNMPv3 Target Parameters Table Entry

You may want to delete an entry from the SNMPv3 Target Parameters Table. When you delete an SNMPv3 Target Parameters Table entry, there is no way to undelete, or recover, the entry.

To delete an entry in the SNMPv3 Target Parameters Table, perform the following procedure:

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in "Configuring the SNMPv3 User Table" on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **8** to select Configure SNMPv3 Target Parameters Table.

   The Configure SNMPv3 Parameters Table menu is shown in Figure 139 on page 386.

   Note
   To display a Group Name and its associated parameters from the Configure SNMPv3 SecurityToGroup Table menu, type **N** to display the Next Page and **P** to display the previous page.

3. To delete an SNMPv3 Target Parameters Table entry, type **2** to select Delete SNMPv3 Table Entry.

   The following prompt is displayed:

   ```
   Enter Target Parameters Name:
   ```

4. Enter a Target Parameters Name.

   The following prompt is displayed:

   ```
   Do you want to delete this table entry?(Y/N):[Yes/No]->
   ```

5. Enter **Y** to delete the SNMPv3 Target Address Table entry or **N** to save the entry.

6. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Modifying an SNMPv3 Target Parameters Table Entry

This section provides procedures for modifying parameters in an SNMPv3 Target Parameters Table entry. The parameter values configured in the Target Parameters Table must match those configured in the other tables. For a more detailed explanation, see “Creating an SNMPv3 Target Parameters Table Entry” on page 386.

In an SNMPv3 Target Parameters Table entry, the Security Name parameter is linked to the User Name parameter on the SNMPv3 User Table. In an SNMPv3 User Table entry, the User Name parameter is used as an index for the entry. Because the User Name and Security Name parameters are linked, the information you configure that relates to a User Table entry must match the information you configure in the SNMPv3 Target Parameters Table entry. In addition, the values configured for the following parameters in an SNMPv3 Target Parameters Table entry must match those configured in the corresponding table entry:

- User Name parameter in the SNMPv3 User Table
- View Name parameter in the SNMPv3 View Table
- Group Name, Security Model, and Security Level parameters in the SNMPv3 Access Table
- User Name, Security Model, Group Name parameters in the SNMPv3 SecurityToGroup Table

See the following procedures:

- “Modifying the Security Name (User Name)” on page 390
- “Modifying the Security Model” on page 392
- “Modifying the Security Level” on page 393
- “Modifying the Message Process Model” on page 395
- “Modifying the Storage Type” on page 396

Note
You cannot modify the Target Params Name parameter.

Note
You cannot modify an entry in the SNMPv3 Target Parameter Table that contains a value of “default” in the Target Parameters Name field.

Modifying the Security Name (User Name)

In the AT-S63 implementation of the SNMPv3 protocol, the Security Name and the User Name parameters are equivalent. In the SNMPv3 Target Parameters Table menu, the Security Name and the User Name parameters are used interchangeably.

Downloaded from www.Manualslib.com manuals search engine

When you modify the Security Name parameter, you must use a value that you configured with the User Name parameter in the Configure SNMPv3 User Table menu. If you do not use a value configured with the User Name parameter, messages are not sent on behalf of this User Name. See "Creating an SNMPv3 User Table Entry" on page 321.

To modify the Security Name parameter in an SNMPv3 Target Parameter Table entry, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in "Configuring the SNMPv3 User Table" on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **8** to select Configure SNMPv3 Target Address Table.

   The Configure SNMPv3 Target Parameters Table menu is shown in Figure 139.

3. From the Configure SNMPv3 Target Parameters Table menu, type **3** to select Modify SNMPv3 Table Entry.

   The Modify SNMPv3 Target Parameters Table menu is shown in Figure 140.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                              11:20:02 02-Mar-2005
           Modify SNMPv3 Target Parameters Table
 Target Parameters Name ... host27
 Message Processing Model . v3
 Security Model..... v3
 Security Name ..... hoa
 Security Level ..... AuthNoPriv
 Storage Type ..... NonVolatile
 Row Status ..... Active

 1 - Set Security Name
 2 - Set Security Model
 3 - Set Security Level
 4 - Set Message Processing Model
 5 - Set Storage Type

 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 140. Modify SNMPv3 Target Parameters Table Menu

Downloaded from www.Manualslib.com manuals search engine

4. To change the Security Name parameter, type **1** to select Set Security Name.

   The following prompt is displayed:

   ```
   Enter Target Parameters Name:
   ```

5. Enter a previously configured Target Parameters Name.

   Enter a value of up to 32 alphanumeric characters.

   The following prompt is displayed:

   ```
   Enter User (Security) Name:
   ```

6. Enter a User Name.

   Enter a value that you previously configured with the Configure SNMPv3 User Table menu. You can enter a value of up to 32 alphanumeric characters.

7. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Modifying the Security Model

For the Security or User Name you have selected, the value of the Security Model parameter in an SNMPv3 Target Parameter Table entry must match the value of the Security Model parameter in the SNMPv3 Access Table entry.

Caution
If the values of the Security Model parameter in the SNMPv3 User Table and the SNMPv3 Target Parameter Table entry do not match, notification messages are not generated on behalf of this User (Security) Name.

To modify the Security Model parameter in an SNMPv3 Target Parameter Table entry, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in “Configuring the SNMPv3 User Table” on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **8** to select Configure SNMPv3 Target Address Table.

Downloaded from www.Manualslib.com manuals search engine

The Configure SNMPv3 Target Parameters Table menu is shown in Figure 139.

3. From the Configure SNMPv3 Target Parameters Table menu, type **3** to select Modify SNMPv3 Table Entry.

   The Modify SNMPv3 Target Parameters Table menu is shown in Figure 140 on page 391.

4. To change the Security Model, type **2** to select Security Model.

   The following prompt is displayed:

   ```
   Enter Target Parameters Name:
   ```

5. Enter a previously configured Target Parameters Name.

   Enter a value of up to 32 alphanumeric characters.

   The following prompt is displayed:

   ```
   Enter Security Model [1-v1, 2-v2c, 3-v3]:
   ```

6. Select one of the following SNMP protocols that was previously configured as the Security Model for this Security Name, or User Name.

   1-v1
   Select this value if this User Name is associated with the SNMPv1 protocol.

   2-v2c
   Select this value if this User Name is associated with the SNMPv2c protocol.

   3-v3
   Select this value if this User Name is associated with the SNMPv3 protocol.

7. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Modifying the Security Level

For the Security or User Name you have selected, the value of the Security Level parameter in an SNMPv3 Target Parameter Table entry must match the value of the Security Level parameter in the SNMPv3 User Table entry.

To modify the Security Level parameter in an SNMPv3 Target Parameter Table entry, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in "Configuring the SNMPv3 User Table" on page 321. Or,

Downloaded from www.Manualslib.com manuals search engine

from the Main Menu type **5**->**5**->**5**.

The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **8** to select Configure SNMPv3 Target Address Table.

   The Configure SNMPv3 Target Parameters Table menu is shown in Figure 139.

3. From the Configure SNMPv3 Target Parameters Table menu, type **3** to select Modify SNMPv3 Table Entry.

   The Modify SNMPv3 Target Parameters Table menu is shown in Figure 140 on page 391.

4. To modify the Security Level, type **3** to select Set Security Level.

   The following prompt is displayed:

   ```
   Enter Target Parameters Name:
   ```

5. Enter a previously configured Target Parameters Name.

   Enter a value of up to 32 alphanumeric characters.

   The following prompt is displayed:

   ```
   Enter Security Level [N-NoAuthNoPriv, A-AuthNoPriv,
   P-AuthPriv]:
   ```

6. Enter the Security Level.

   Select one of the following Security Levels:

   Note
   The value you configure for the Security Level must match the value configured for the User Name in the Configure SNMPv3 User Table menu. See “Creating an SNMPv3 User Table Entry” on page 321.

   N-NoAuthNoPriv
   This option represents no authentication and no privacy protocol. Select this security level if you do not want to authenticate SNMP entities and you do not want to encrypt messages using a privacy protocol. This security level provides the least security.

   Note
   If you have selected SNMPv1 or SNMPv2c, N-NoAuthNoPriv is the only security level you can select.

Downloaded from www.Manualslib.com manuals search engine

A-AuthNoPriv
This option represents authentication, but no privacy protocol. Select this security level if you want to authenticate SNMP users, but you do not want to encrypt messages using a privacy protocol.You can select this value if you configured the Security Model parameter with the SNMPv3 protocol.

P-AuthPriv
This option represents authentication and the privacy protocol. Select this security level to encrypt messages using a privacy protocol and authenticate SNMP entities. This level provides the greatest level of security. You can select this value if you configured the Security Model parameter with the SNMPv3 protocol.

7. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Modifying the Message Process Model

You can modify the Message Process Model for SNMPv1 and SNMPv2c protocol configurations only. When you configure the SNMPv3 protocol, the Message Process Model is automatically assigned to the SNMPv3 protocol.

To modify the Message Process Model parameter in an SNMPv3 Target Parameter Table entry, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in "Configuring the SNMPv3 User Table" on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **8** to select Configure SNMPv3 Target Address Table.

   The Configure SNMPv3 Target Parameters Table menu is shown in Figure 139.

3. From the Configure SNMPv3 Target Parameters Table menu, type **3** to select Modify SNMPv3 Table Entry.

   The Modify SNMPv3 Target Parameters Table menu is shown in Figure 140 on page 391.

4. To modify the Message Process Model, type **4** to select Set Message Processing Model.

   The following prompt is displayed:

   ```
   Enter Target Parameters Name:
   ```


Downloaded from www.Manualslib.com manuals search engine

5. Enter a previously configured Target Parameters Name.

   Enter a value of up to 32 alphanumeric characters.

   The following prompt is displayed:

   ```
   Enter Message Processing Model[1-v1,2-v2c,3-v3]:
   ```

6. Select one of the following SNMP protocols that is used to process, or send messages:

   1-v1
   Select this value to process messages with the SNMPv1 protocol.

   2-v2c
   Select this value to process messages with the Security Name, or User Name, with the SNMPv2c protocol.

   3-v3
   Select this value to process messages with the SNMPv3 protocol.

7. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Modifying the Storage Type

To modify the Storage Type parameter in an SNMPv3 Target Parameter Table entry, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in “Configuring the SNMPv3 User Table” on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **8** to select Configure SNMPv3 Target Address Table.

   The Configure SNMPv3 Target Parameters Table menu is shown in Figure 139.

3. From the Configure SNMPv3 Target Parameters Table menu, type **3** to select Modify SNMPv3 Table Entry.

   The Modify SNMPv3 Target Parameters Table menu is shown in Figure 140 on page 391.

4. To modify the Storage Type, type **5** to select Storage Type.

   The following prompt is displayed:

   ```
   Enter Target Parameters Name:
   ```


Downloaded from www.Manualslib.com manuals search engine

5. Enter a previously configured Target Parameters Name.

   Enter a value of up to 32 alphanumeric characters.

   The following prompt is displayed:

   ```
   Enter Storage Type [V-Volatile, N-NonVolatile]:
   ```

6. Select one of the following storage types for this table entry:

   V - Volatile
   Select this storage type if you do not want the ability to save an entry in the SNMPv3 Target Parameters Table to the configuration file. After making changes to an SNMPv3 Target Parameters Table entry with a Volatile storage type, the **S** - Save Configuration Changes option does not appear on the Main Menu.

   N-NonVolatile
   Select this storage type if you want the ability to save an entry in the SNMPv3 Target Parameters Table to the configuration file. After making changes to an SNMPv3 Target Parameters Table entry with a NonVolatile storage type, the **S** - Save Configuration Changes option appears on the Main Menu, allowing you to save your changes. Allied Telesis recommends this storage type.

7. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Configuring the SNMPv3 Community Table

This section contains a description of the SNMPv3 Community Table and how to create, delete, and modify table entries. The SNMPv3 Community Table allows you to create SNMPv1 and SNMPv2c Communities using the SNMPv3 Tables.

Allied Telesis does not recommend that you use the menu described in this section to configure SNMPv1 and SNMPv2c communities. Instead, use the procedures described in “Enabling or Disabling SNMP Management” on page 94.

However, if you want to configure SNMPv1 and SNMPv2c with the SNMPv3 Tables you need to start your configuration with the SNMPv3 Community Table and then create entries in the following tables:

- SNMPv3 View Table—See “Creating an SNMPv3 View Table Entry” on page 331.
- SNMPv3 Access Table—See “Creating an SNMPv3 Access Table Entry” on page 340.
- SNMPv3 SecurityToGroup Table—See “Creating an SNMPv3 SecurityToGroup Table Entry” on page 356.
- SNMPv3 Notify Table—See “Configuring the SNMPv3 Notify Table” on page 364.
- SNMPv3 Target Address Table—See “Creating an SNMPv3 Target Address Table Entry” on page 372.
- SNMPv3 Target Parameters Table—See “Creating an SNMPv3 Target Parameters Table Entry” on page 386.

Note that you do not create an entry in the SNMPv3 User Table when you are configuring SNMPv1 and SNMPv2c with the SNMPv3 Tables. When you configure the SNMPv3 protocol, the various tables are linked with the User Name parameter and its related information. With the SNMPv1 and SNMPv2c configuration, the Security Name parameter and its related information (configured in the SNMPv3 Community Table menu) links an SNMPv3 Community Table entry to the other SNMPv3 Table entries.

Note
In the SNMPv3 Community Table entry, the Security Name parameter is not related to the User Name parameter.

For each SNMPv3 Community Table entry, you can configure the following parameters:

- Community Index
- Community Name

Downloaded from www.Manualslib.com manuals search engine

- Security Name
- Transport Tag
- Storage Type

In addition, you can display the entries configured with the Configure SNMPv1 & SNMPv2c Community menu in the Configure SNMPv3 Community Table menu. However, you cannot modify an SNMPv1 & SNMPv2c Community Table entry with the Configure SNMPv3 Community Table menu.

There are three functions you can perform with the Configure SNMPv3 Target Parameters Table menu.

- "Creating an SNMPv3 Community Table Entry," next
- "Deleting an SNMPv3 Community Table Entry" on page 402
- "Modifying an SNMPv3 Community Table Entry" on page 403

Creating an SNMPv3 Community Table Entry

To create an entry in the Configure SNMPv3 Community Table menu, perform the following procedure.

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in "Configuring the SNMPv3 User Table" on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is displayed Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **9** to select Configure SNMPv3 Community Table.

Downloaded from www.Manualslib.com manuals search engine

The Configure SNMPv3 Community Table menu is shown in Figure 141.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
             Configure SNMPv3 Community Table
 Community Index ............... ATIIndex1
 Community Name ................ 451engineering75
 Security Name ................. debashi48
 Transport Tag ................. sampletag
 Storage Type .................. NonVolatile
 Row Status .................... Active

 1 - Create SNMPv3 Table Entry
 2 - Delete SNMPv3 Table Entry
 3 - Modify SNMPv3 Table Entry

 N - Next Page
 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 141. Configure SNMPv3 Community Table Menu

3. To create an entry in the SNMPv3 Community Table, type **1** to select Create SNMPv3 Table Entry.

   The following prompt is displayed:

   ```
   Enter Community Index:
   ```

4. Enter the name of this Community Index.

   This parameter describes the name of this community and is used to index the other parameters in an SNMPv3 Community Table entry. Enter a value of up to 32 alphanumeric characters.

   The following prompt is displayed:

   ```
   Enter Community Name:
   ```

5. Enter a Community Name of up to 64 alphanumeric characters.

   The value of the Community Name parameter acts as a password for the SNMPv3 Community Table entry. This parameter is case sensitive.

Note
Allied Telesis recommends that you select SNMP Community Names carefully to ensure these names are known only to authorized personnel.

Downloaded from www.Manualslib.com manuals search engine

The following prompt is displayed:

```
Enter Security Name:
```

6. Enter the name of an SNMPv1 and SNMPv2c user.

   This name must be unique. Enter a value of up to 32 alphanumeric characters.

   Note
   Do not use a value configured with the User Name parameter in the SNMPv3 User Table.

   The following prompt is displayed:

   ```
   Enter Transport Tag:
   ```

7. Enter a name of up to 32 alphanumeric characters for the Transport Tag.

   The Transport Tag parameter is similar to the Notify Tag parameter in the SNMPv3 Notify Table. Add the value you configure for the Transport Tag parameter to the Tag List parameter in the Target Address Table. In this way, the Transport Tag parameter links an SNMPv3 Community Table entry with an entry in the SNMPv3 Target Address Table.

   The following prompt is displayed:

   ```
   Enter Storage type [V-volatile, N-NonVolatile]:
   ```

8. Select one of the following storage types for this table entry:

   V - Volatile
   Select this storage type if you do not want the ability to save an entry in the SNMPv3 Community Table to the configuration file. After making changes to an SNMPv3 Community Table entry with a Volatile storage type, the **S** - Save Configuration Changes option does not appear on the Main Menu.

   N-NonVolatile
   Select this storage type if you want the ability to save an entry in the SNMPv3 Community Table to the configuration file. After making changes to an SNMPv3 Community Table entry with a NonVolatile storage type, the **S** - Save Configuration Changes option appears on the Main Menu, allowing you to save your changes. Allied Telesis recommends this storage type.

Downloaded from www.Manualslib.com manuals search engine

Note
The Row Status parameter is a read-only field. The Active value indicates the SNMPv3 Community Table entry takes effect immediately.

9. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Deleting an SNMPv3 Community Table Entry

You may want to delete an entry from the SNMPv3 Community Table. When you delete an entry in the SNMPv3 Community Table, there is no way to undelete or recover the entry.

To delete an entry in the SNMPv3 Community Table, perform the following procedure:

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in “Configuring the SNMPv3 User Table” on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is shown in Figure 127 on page 322.

2. From the Configure SNMPv3 Table menu, type **9** to select Configure SNMPv3 Community Table.

   The Configure SNMPv3 Community Table menu is shown in Figure 141 on page 400.

3. To delete an entry in the SNMPv3 Community Table, type **2** to select Delete SNMPv3 Table Entry.

   The following prompt is displayed:

   ```
   Enter Community Index:
   ```

4. Enter the Community Index that you want to delete.

   The following prompt is displayed:

   ```
   Do you want to delete this table entry? (Y/N):[Yes/No]->
   ```

5. Choose one of the following:

   Y
   Type Y to delete an SNMPv3 Community table entry.

   N
   Type N to retain the SNMPv3 Community table entry.

6. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Modifying an SNMPv3 Community Table Entry

For each entry in the SNMPv3 Community Table, you can modify the following parameters:

- Community Name
- Security Name
- Transport Tag
- Storage Type

However, you cannot modify the Community Index parameter.

Although you can display the SNMPv1 and SNMPv2c configuration created with the procedures described in "Creating an SNMP Community String" on page 96, you cannot modify these Community Table entries with the SNMPv3 Tables.

See the following procedures:

- "Modifying the Community Name" on page 403
- "Modifying the Security Name" on page 405
- "Modifying the Transport Tag" on page 405
- "Modifying the Storage Type" on page 406

Modifying the Community Name

To modify the Community Name parameter in an SNMPv3 Community Table entry, perform the following procedure:

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in "Configuring the SNMPv3 User Table" on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is displayed Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **9** to select Configure SNMPv3 Community Table.

   The SNMPv3 Community Table is shown in Figure 141 on page 400.

3. From the Configure SNMPv3 Community Table, type **3** to select Modify SNMPv3 Table Entry.

Downloaded from www.Manualslib.com manuals search engine

The Modify SNMPv3 Community Table menu is shown in Figure 142.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                              11:20:02 02-Mar-2005
                 Modify SNMPv3 Community Table
 Community Index ............... alliedtelesisindex
 Community Name ................. 789bothel23wa
 Security Name .................. buster
 Transport Tag .................. 72
 Storage Type ................... Volatile
 Row Status ..................... Active

 1 - Set Community Name
 2 - Set Security Name
 3 - Set Transport Tag
 4 - Set Storage Type

 N - Next Page
 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 142. Modify SNMPv3 Community Table Menu

4. To change the Community Name, type **1** to select Set Community Name.

   The following prompt is displayed:

   ```
   Enter Community Index:
   ```

5. Enter the Community Index that you want to modify.

   The following prompt is displayed:

   ```
   Enter Community Name:
   ```

6. Enter the new Community Name.

   The value of the Community Name parameter acts as a password for the SNMPv3 Community Table entry. This parameter is case sensitive. Enter a value of up to 64 alphanumeric characters.

   Note
   Allied Telesis recommends that you select SNMP Community Names carefully to ensure these names are known only to authorized personnel.

7. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Modifying the Security Name

To modify the Security Name parameter in an SNMPv3 Community Table entry, perform the following procedure:

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in "Configuring the SNMPv3 User Table" on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is displayed as shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **9** to select Configure SNMPv3 Community Table.

   The Configure SNMPv3 Community Table menu is shown in Figure 141 on page 400.

3. From the Configure SNMPv3 Community Table, type **3** to select Modify SNMPv3 Table Entry.

   The Modify SNMPv3 Community Table menu is shown in Figure 142 on page 404.

4. To change the Security Name, type **2** to select Set Security Name.

   The following prompt is displayed:

   ```
   Enter Community Index:
   ```

5. Enter the Community Index of the Security Name you want to change.

   The following prompt is displayed:

   ```
   Enter Security Name:
   ```

6. Enter the new Security Name.

   Enter a value of up to 32 alphanumeric characters.

7. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Modifying the Transport Tag

To modify the Transport Tag parameter in an SNMPv3 Community Table entry, perform the following procedure:

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in "Configuring the SNMPv3 User Table" on page 321. Or, from the Main Menu type **5**->**5**->**5**.

Downloaded from www.Manualslib.com manuals search engine

The Configure SNMPv3 Table menu is displayed as shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **9** to select Configure SNMPv3 Community Table.

   The Configure SNMPv3 Community Table menu is shown in Figure 141 on page 400.

3. From the Configure SNMPv3 Community Table, type **3** to select Modify SNMPv3 Table Entry.

   The Modify SNMPv3 Community Table menu is shown in Figure 142 on page 404.

4. To change the Transport Tag, type **3** to select Set Transport Tag.

   The following prompt is displayed:

   ```
   Enter Community Index:
   ```

5. Enter the Community Index of the Transport Tag you want to change.

   The following prompt is displayed:

   ```
   Enter Transport Tag:
   ```

6. Enter the new value for the Transport Tag.

   Enter a name of up to 32 alphanumeric characters.

7. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Modifying the Storage Type

To modify the Storage Type parameter in an SNMPv3 Community Table entry, perform the following procedure:

1. Display the Configure SNMPv3 Table menu by performing steps 1 through 3 in “Configuring the SNMPv3 User Table” on page 321. Or, from the Main Menu type **5**->**5**->**5**.

   The Configure SNMPv3 Table menu is displayed as shown in Figure 126 on page 322.

2. From the Configure SNMPv3 Table menu, type **9** to select Configure SNMPv3 Community Table.

   The Configure SNMPv3 Community Table menu is shown in Figure 141 on page 400.

Downloaded from www.Manualslib.com manuals search engine

3. From the Configure SNMPv3 Community Table, type **3** to select Modify SNMPv3 Table Entry.

   The Modify SNMPv3 Community Table Menu is shown in Figure 142 on page 404.

4. To change the Storage Type, type **4** to select Set Storage Type.

   The following prompt is displayed:

   ```
   Enter Community Index:
   ```

5. Enter the Community Index of the Storage Type you want to change.

   The following prompt is displayed:

   ```
   Enter Storage type [V-volatile, N-NonVolatile]:
   ```

6. Select one of the following storage types for this table entry:

   V - Volatile
   Select this storage type if you do not want the ability to an entry in the SNMPv3 Community Table to the configuration file. After making changes to an SNMP Community Table entry with a Volatile storage type, the
   S - Save Configuration Changes option does not appear on the Main Menu.

   N-NonVolatile
   Select this storage type if you want the ability to save an entry in the SNMPv3 Community Table to the configuration file. After making changes to an SNMPv3 Community Table entry with a NonVolatile storage type, the **S** - Save Configuration Changes option appears on the Main Menu, allowing you to save your changes. Allied Telesis recommends this storage type.

7. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Displaying SNMPv3 Table Menus

The procedures in this section describe how to display the SNMPv3 Tables. The following procedures are provided:

- ❒ “Displaying the Display SNMPv3 User Table Menu,” next
- ❒ “Displaying the Display SNMPv3 View Table Menu” on page 410
- ❒ “Displaying the Display SNMPv3 Access Table Menu” on page 411
- ❒ “Displaying the Display SNMPv3 SecurityToGroup Table Menu” on page 411
- ❒ “Displaying the Display SNMPv3 Notify Table Menu” on page 412
- ❒ “Displaying the Display SNMPv3 Target Address Table Menu” on page 413
- ❒ “Displaying the Display SNMPv3 Target Parameters Table Menu” on page 413
- ❒ “Displaying the Display SNMPv3 Community Table Menu” on page 414

Displaying the Display SNMPv3 User Table Menu

This section describes how to display the Display SNMPv3 User Table menu. For information about the SNMPv3 User Table, see “Creating an SNMPv3 User Table Entry” on page 321.

To display the Display SNMPv3 User Table menu, perform the following procedure.

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 6 on page 43.

2. From the System Administration menu, type **5** to select SNMP Configuration.

   The SNMP Configuration menu is shown in Figure 26 on page 94.

3. From the SNMP Configuration menu, type **6** to select Display SNMPv3 Table.

Downloaded from www.Manualslib.com manuals search engine

The Display SNMPv3 Table menu is shown in Figure 143.

```
            Allied Telesis AT-9424T/SP - AT-S63
                          Marketing
User: Manager                              11:20:02 02-Mar-2005
                     Display SNMPv3 Table
 1 - Display SNMPv3 User Table
 2 - Display SNMPv3 View Table
 3 - Display SNMPv3 Access Table
 4 - Display SNMPv3 SecurityToGroup Table
 5 - Display SNMPv3 Notify Table
 6 - Display SNMPv3 Target Address Table
 7 - Display SNMPv3 Target Parameters Table
 8 - Display SNMPv3 Community Table

 R - Return to Previous Menu

 Enter your selection?
```

Figure 143. Display SNMPv3 Table Menu

4. From the Display SNMPv3 Table menu, type **1** to select Display SNMPv3 User Table.

   The Display SNMPv3 User Table is shown in Figure 144.

```
              Allied Telesis AT-9424T/SP - AT-S63
                            Marketing
User: Manager                                11:20:02 02-Mar-2005
                    Display SNMPv3 User Table
 Engine Id ................. 80:00:00:CF:03:00:30:84:FD:57:DA
 User Name ................. spike
 Authentication Protocol ... MD5
 Privacy Protocol .......... DES
 Storage Type .............. NonVolatile
 Row Status ................ Active

 N - Next Page
 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 144. Display SNMPv3 User Table Menu

Downloaded from www.Manualslib.com manuals search engine

Displaying the Display SNMPv3 View Table Menu

This section describes how to display the Display SNMPv3 View Table menu. For information about the SNMPv3 View Table parameters, see “Creating an SNMPv3 View Table Entry” on page 331.

To display the Display SNMPv3 View Table menu, perform the following procedure.

1. Display the Display SNMPv3 Table menu by performing steps 1 through 3 in “Displaying the Display SNMPv3 User Table Menu” on page 408. Or, from the Main menu type **5**->**5**->**6**.

2. From the Display SNMPv3 Table menu, type **2** to select Display SNMPv3 View Table.

   The Display SNMPv3 View Table menu is shown in Figure 145.

```
            Allied Telesis AT-9424T/SP - AT-S63
                         Marketing
User: Manager                              11:20:02 02-Mar-2005
                  Display SNMPv3 View Table

 View Name ..................... tcp
 Subtree OID ................... 1.3.6.1
 Subtree Mask ..................
 View Type ..................... Included
 Storage Type .................. NonVolatile
 Row Status .................... Active

 N - Next Page
 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 145. Display SNMPv3 View Table Menu

Downloaded from www.Manualslib.com manuals search engine

Displaying the Display SNMPv3 Access Table Menu

This section describes how to display the Display SNMPv3 Access Table menu. For information about the SNMPv3 Access Table parameters, see "Creating an SNMPv3 Access Table Entry" on page 340.

To display the Display SNMPv3 Access Table menu, perform the following procedure.

1. Display the Display SNMPv3 Table menu by performing steps 1 through 3 in "Displaying the Display SNMPv3 User Table Menu" on page 408. Or, from the Main menu type **5**->**5**->**6**.

2. From the Display SNMPv3 Table menu, type **3** to select Display SNMPv3 Access Table.

   The Display SNMPv3 Access Table menu is shown in Figure 146.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                                11:20:02 02-Mar-2005
                  Display SNMPv3 Access Table
 Group Name .... technicalsales  Security Model . v3
 Context Prefix.                 Security Level . AuthPriv
 Read View...... internet        Context Match .. Exact
 Write View ....                 Storage Type ... NonVolatile
 Notify View ...                 Row Status ..... Active

 N - Next Page
 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 146. Display SNMPv3 Access Table Menu

Displaying the Display SNMPv3 SecurityToGroup Table Menu

This section describes how to display the Display SNMPv3 SecurityToGroup Table menu. For more information about the parameters in the SNMPv3 SecurityToGroup Table menu, see "Creating an SNMPv3 SecurityToGroup Table Entry" on page 356.

To display the Display SNMPv3 SecurityToGroup Table menu, perform the following procedure.

1. Display the Display SNMPv3 Table menu by performing steps 1 through 3 in "Displaying the Display SNMPv3 User Table Menu" on page 408. Or, from the Main menu type **5**->**5**->**6**.

2. From the Display SNMPv3 Table menu, type **4** to select Display SNMPv3 SecurityToGroup Table.

Downloaded from www.Manualslib.com manuals search engine

The Display SNMPv3 SecurityToGroup Table menu is shown in Figure 147.

```
            Allied Telesis AT-9424T/SP - AT-S63
                         Marketing
User: Manager                              11:20:02 02-Mar-2005
            Display SNMPv3 SecurityToGroup Table
 Security Model................. v3
 Security Name ................. praveen
 Group Name .................... hardwareengineering
 Storage Type .................. NonVolatile
 Row Status .................... Active

 N - Next Page
 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 147. Display SNMPv3 SecurityToGroup Table Menu

Displaying the Display SNMPv3 Notify Table Menu

This section describes how to display the Display SNMPv3 Notify Table menu. For information about the SNMPv3 Notify Table parameters, see “Creating an SNMPv3 Notify Table Entry” on page 364.

To display the Display SNMPv3 Notify Table menu, perform the following procedure.

1. Display the Display SNMPv3 Table menu by performing steps 1 through 3 in “Displaying the Display SNMPv3 User Table Menu” on page 408. Or, from the Main menu type **5**->**5**->**6**.

2. From the Display SNMPv3 Table menu, type **5** to select Display SNMPv3 Notify Table.

   The Display SNMPv3 Notify Table menu is shown in Figure 147.

```
            Allied Telesis AT-9424T/SP - AT-S63
                         Marketing
User: Manager                              11:20:02 02-Mar-2005
                Display SNMPv3 Notify Table
 Notify Name ..................... testengineeringTrap
 Notify Tag ...................... testengineeringtag
 Notify Type ..................... Inform
 Storage Type .................... NonVolatile
 Row Status ...................... Active

 N - Next Page
 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 148. Display SNMPv3 Notify Table Menu

Downloaded from www.Manualslib.com manuals search engine

Displaying the Display SNMPv3 Target Address Table Menu

This section describes how to display the Display SNMPv3 Target Address Table menu. For information about the SNMPv3 Target Address Table parameters, see "Creating an SNMPv3 Target Address Table Entry" on page 372.

To display the Display SNMPv3 Target Address Table menu, perform the following procedure.

1. Display the Display SNMPv3 Table menu by performing steps 1 through 3 in "Displaying the Display SNMPv3 User Table Menu" on page 408. Or, from the Main menu type **5**->**5**->**6**.

2. From the Display SNMPv3 Table menu, type **6** to select Display SNMPv3 Target Address Table.

   The Display SNMPv3 Target Address Table menu is shown in Figure 147.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                            11:20:02 02-Mar-2005
          Display SNMPv3 Target Address Table
 Target Addr Name ... host99          Timeout ..... 1500
 Target Parameters .. SNMPmanagerPC   Retries ..... 5
 IP Address ......... 198.35.11.1     UDP Port# ... 162
 Storage Type ....... NonVolatile     Row Status .. Active
 Tag List ........... engTrap engInform

 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 149. Display SNMPv3 Target Address Table Menu

Displaying the Display SNMPv3 Target Parameters Table Menu

This section describes how to display the Display SNMPv3 Target Parameters Table menu. For information about the SNMPv3 Target Parameters Table parameters, see "Creating an SNMPv3 Target Parameters Table Entry" on page 386.

To display the Display SNMPv3 Target Parameters Table menu, perform the following procedure.

1. Display the Display SNMPv3 Table menu by performing steps 1 through 3 in "Displaying the Display SNMPv3 User Table Menu" on page 408. Or, from the Main menu type **5**->**5**->**6**.

2. From the Display SNMPv3 Table menu, type **7** to select Display SNMPv3 Target Parameters Table.

Downloaded from www.Manualslib.com manuals search engine

The Display SNMPv3 Target Parameters Table menu is shown in Figure 147.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                            11:20:02 02-Mar-2005
          Display SNMPv3 Target Parameters Table
 Target Parameters Name ... TargetIndex21
 Message Processing Model . v3
 Security Model ........... v3
 Security Name ............ wilson
 Security Level ........... AuthPriv
 Storage Type ............. NonVolatile
 Row Status ............... Active

 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 150. Display SNMPv3 Target Parameters Table Menu

Displaying the Display SNMPv3 Community Table Menu

This section describes how to display the Display SNMPv3 Community Table menu. For information about the SNMPv3 Community Table parameters, see “Creating an SNMPv3 Community Table Entry” on page 399.

To display the Display SNMPv3 Community Table menu, perform the following procedure.

1. Display the Display SNMPv3 Table menu by performing steps 1 through 3 in “Displaying the Display SNMPv3 User Table Menu” on page 408. Or, from the Main menu type **5**->**5**->**6**.

2. From the Display SNMPv3 Table menu, type **8** to select Display SNMPv3 Community Table.

Downloaded from www.Manualslib.com manuals search engine

The Display SNMPv3 Community Table menu is shown in Figure 147.

```
            Allied Telesis AT-9424T/SP - AT-S63
                          Marketing
User: Manager                              11:20:02 02-Mar-2005
                Display SNMPv3 Community Table
 Community Index ........ atiindex14
 Community Name ......... sunnyvale
 Security Name .......... hoa
 Transport Tag........... sampletag14
 Storage Type ........... NonVolatile
 Row Status ............. Active

 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 151. Display SNMPv3 Community Table Menu

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Section V

Spanning Tree Protocols

The chapters in this section contain overview information on the different spanning tree protocols supported on the AT-9400 Switch. The chapters also explain how to configure the spanning tree protocols from the menu interface of the AT-S63 Management Software. The chapters include:

- Chapter 22, “Spanning Tree and Rapid Spanning Tree Protocols” on page 419
- Chapter 23, “Multiple Spanning Tree Protocol” on page 439

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Chapter 22

Spanning Tree and Rapid Spanning Tree Protocols

This chapter provides background information on the Spanning Tree Protocol (STP) and Rapid Spanning Tree Protocol (RSTP). The chapter also contains procedures on how to adjust the STP and RSTP bridge and port parameters. The sections in this chapter include:

- ❒ “Enabling or Disabling a Spanning Tree Protocol” on page 420
- ❒ “Configuring STP” on page 422
- ❒ “Configuring RSTP” on page 430

The Multiple Spanning Tree Protocol is described in Chapter 23, “Multiple Spanning Tree Protocol” on page 439.

Downloaded from www.Manualslib.com manuals search engine

Enabling or Disabling a Spanning Tree Protocol

The AT-S63 Management Software supports STP, RSTP, and MSTP. However, only one spanning tree protocol can be active on the switch at a time. Before you can enable a spanning tree protocol, you must first select it as the active spanning tree protocol on the switch. After you have selected it as the active protocol, you can then configure it and enable or disable it.

To select and activate a spanning tree protocol, or to disable spanning tree, perform the following procedure:

1. From the Main Menu, type **3** to select Spanning Tree Configuration.

   The Spanning Tree Configuration menu is shown in Figure 152.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                              11:20:02 02-Mar-2005
                  Spanning Tree Configuration

 1 - Spanning Tree Status ..... Disabled
 2 - Active Protocol Version ... RSTP
 3 - Configure Active Protocol

 R - Return to Previous Menu

 Enter your selection?
```

Figure 152. Spanning Tree Configuration Menu

> **Note**
> Do not enable spanning tree on the switch until after you have selected an activate spanning tree protocol and configured the settings. If you want to disable spanning tree, go to step 5.

2. To change the active version of spanning tree on the switch, type **2** to select Active Protocol Version.

   The following prompt is displayed:

   ```
   Enter new value (S-STP, R-RSTP, M-MSTP):
   ```

3. Type **S** to select STP or **R** to select RSTP, or **M** to select MSTP.

Downloaded from www.Manualslib.com manuals search engine

4. If you selected STP as the active spanning tree protocol, go to "Configuring STP" on page 422 for further instructions. If you selected RSTP, go to "Configuring RSTP" on page 430. Multiple Spanning Tree Protocol (MSTP) is described in Chapter 23, "Multiple Spanning Tree Protocol" on page 439.

   Note
   After you have configured the spanning tree parameters, perform steps 5 through 7 to enable spanning tree.

5. To enable or disable spanning tree, type **1** to select Spanning Tree Status.

   The following prompt is displayed:

   ```
   Enter new value (E-Enable, D-Disable):
   ```

6. Type **E** to enable spanning tree or **D** to disable it. The default is disabled.

7. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Configuring STP

This section contains the following procedures:

- ”Configuring STP Bridge Settings”, next
- “Configuring STP Port Settings” on page 425
- “Displaying STP Port Settings” on page 428
- “Resetting STP to the Default Settings” on page 429

Configuring STP Bridge Settings

This section contains the procedure for configuring a bridge’s STP settings.

Caution
The default STP parameters are adequate for most networks. Changing them without prior experience and an understanding of how STP works might have a negative effect on your network. You should consult the IEEE 802.1d standard before changing any of the STP parameters.

To configure the bridge settings, perform the following procedure:

1. From the Main Menu, type **3** to select Spanning Tree Configuration.

   The Spanning Tree Configuration menu is shown in Figure 152 on page 420.

Downloaded from www.Manualslib.com manuals search engine

2. From the Spanning Tree Configuration menu, type **3** to select Configure Active Protocol. The STP menu is shown in Figure 153.

```
            Allied Telesis AT-9424T/SP - AT-S63
                         Marketing
User: Manager                              11:20:02 02-Mar-2005
                           STP Menu

1 - Bridge Priority ..... 32768
2 - Bridge Hello Time ... 2/2 (Configured/Actual)
3 - Bridge Forwarding ... 15/15 (Configured/Actual)
4 - Bridge Max Age ...... 20/20 (Configured/Actual)
5 - Bridge Identifier ... 32768/00:21:46:A7:B4:11
6 - Root Bridge ......... 00:21:46:A7:B4:11
7 - Root Priority ....... 32768
8 - Root Path Cost ...... 0

P - STP Port Settings
D - Reset STP to Defaults

R - Return to Previous Menu

Enter your selection?
```

Figure 153. STP Menu

The bridge hello time, bridge forwarding, and bridge max age parameters will have two values if STP is enabled on the switch (for example, Bridge Forwarding .. 15/15). The first number is the configured value on the switch for the parameter and the second is the value the switch obtained from the root bridge and is actually using for the parameter. The switch displays only the configured values for these parameters if spanning tree is not activated on the switch.

3. Adjust the following parameters as needed.

1 - Bridge Priority
The priority number for the bridge. This number is used to determine the root bridge for RSTP. The bridge with the lowest priority number is selected as the root bridge. If two or more bridges have the same priority value, the bridge with the numerically lowest MAC address becomes the root bridge. When a root bridge goes offline, the bridge with the next priority number automatically takes over as the root bridge. This parameter can be from 0 (zero) to 61,440 in increments of 4096, with 0 being the highest priority. For a list of the increments, refer to Table 5.

Downloaded from www.Manualslib.com manuals search engine

Table 5. Bridge Priority Value Increments

Increment	Bridge Priority	Increment	Bridge Priority
0	0	8	32768
1	4096	9	36864
2	8192	10	40960
3	12288	11	45056
4	16384	12	49152
5	20480	13	53248
6	24576	14	57344
7	28672	15	61440

2 - Bridge Hello Time
The time interval between generating and sending configuration messages by the bridge. This parameter can be from 1 to 10 seconds. The default is 2 seconds.

3 - Bridge Forwarding
The waiting period in seconds before a bridge changes to a new state, for example, becomes the new root bridge after the topology changes. If the bridge transitions too soon, not all links may have yet adapted to the change, resulting in network loops. The range is 4 to 30 seconds. The default is 15 seconds.

4 - Bridge Max Age
The length of time after which stored bridge protocol data units (BPDUs) are deleted by the bridge. All bridges in a bridged LAN use this aging time to test the age of stored configuration messages called bridge protocol data units (BPDUs). For example, if you use the default value 20, all bridges delete current configuration messages after 20 seconds. This parameter can be from 6 to 40 seconds.

When you select a value for maximum age, observe the following rules:

MaxAge must be greater than (2 x (HelloTime + 1)).

MaxAge must be less than (2 x (ForwardingDelay - 1)).

Note
The aging time for BPDUs is different from the aging time used by the MAC address table.

Downloaded from www.Manualslib.com manuals search engine

5 - Bridge Identifier
The bridge identifier of the switch. The identifier consists of the switch's bridge priority value and MAC address, separated by a slash (/). To change the switch's priority value, use option 1, Bridge Priority. The MAC address of the switch cannot be changed.

6 - Root Bridge
The MAC address of the root bridge of the spanning tree domain. This value cannot be changed and is only displayed when spanning tree is activated on the switch.

7 - Root Priority
The priority value on the root bridge of the spanning tree domain. This parameter is only displayed when spanning tree is enabled on the switch. To change the priority value on the root bridge, you must start a management session on the switch which is functioning as the root bridge and change its bridge priority value.

8 - Root Path Cost
The cost of the path from the current switch to the root switch of the spanning tree domain. If the current switch is the root switch, root path cost will be "0". This value cannot be changed and is only displayed when RSTP is activated on the switch.

4. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

5. To change STP port settings, go to the next procedure.

Configuring STP Port Settings

To adjust STP port parameters, perform the following procedure:

1. From the Main Menu, type **3** to select Spanning Tree Configuration.

   The Spanning Tree Configuration menu is shown in Figure 152 on page 420.

2. From the Spanning Tree Configuration menu, type **3** to select Configure Active Protocol.

   The STP menu is shown in Figure 153 on page 423.

3. From the STP menu, type **P** to select STP Port Parameters.

Downloaded from www.Manualslib.com manuals search engine

The STP Port Parameters menu is shown in Figure 154.

```
            Allied Telesis AT-9424T/SP - AT-S63
                         Marketing
User: Manager                              11:20:02 02-Mar-2005
                     STP Port Parameters

 1 - Configure STP Port Settings
 2 - Display STP Port Configuration

 R - Return to Previous Menu

 Enter your selection?
```

Figure 154. STP Port Parameters Menu

4. Type **1** to select Configure STP Port Settings.

   The following prompt is displayed:

   ```
   Start Port to Configure [1 to 26] ->
   ```

5. Enter the number of the port you want to configure. To configure a range of ports, enter the first port of the range.

   The following prompt is displayed:

   ```
   End Port to Configure [1 to 24] ->
   ```

6. To configure just one port, enter the same port number here as you entered in the previous step. To configure a range of ports, enter the last port of the range.

   The Configure STP Port Settings menu is shown in Figure 155.

```
            Allied Telesis AT-9424T/SP - AT-S63
                         Marketing
User: Manager                              11:20:02 02-Mar-2005
                 Configure STP Port Settings

 Configuring Ports 4-6
 1 - Port Priority ..... 128
 2 - Port Cost ......... Automatic-Update

 R - Return to Previous Menu

 Enter your selection?
```

Figure 155. Configure STP Port Settings Menu

7. Adjust the following parameters as needed.

Downloaded from www.Manualslib.com manuals search engine

1 - Port Priority
This parameter is used as a tie breaker when two or more ports have equal costs to the root bridge. The range is 0 to 240 in increments of 16. The default value is 8 (priority value 128). Table 6 lists the increments.

Table 6. Port Priority Value Increments

Increment	Bridge Priority	Increment	Bridge Priority
0	0	8	128
1	16	9	144
2	32	10	160
3	48	11	176
4	64	12	192
5	80	13	208
6	96	14	224
7	112	15	240

2 - Port Cost
The spanning tree algorithm uses the cost parameter to decide which port provides the lowest cost path to the root bridge for that LAN. The range is 0 to 65,535. The default setting is Automatic Update, which sets port cost depending on the speed of the port. Table 9 lists the STP port costs with Auto-Detect.

Table 7. STP Auto-Detect Port Costs

Port Speed	Port Cost
10 Mbps	100
100 Mbps	10
1000 Mbps	4

Table 8 lists the STP port costs with Auto-Detect when a port is part of a port trunk.

Table 8. STP Auto-Detect Port Trunk Costs

Port Speed	Port Cost
10 Mbps	4
100 Mbps	4

Downloaded from www.Manualslib.com manuals search engine

Table 8. STP Auto-Detect Port Trunk Costs

Port Speed	Port Cost
1000 Mbps	2

8. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Displaying STP Port Settings

To display STP port settings, perform the following procedure:

1. From the Main Menu, type **3** to select Spanning Tree Configuration.

   The Spanning Tree Configuration menu is shown in Figure 152 on page 420.

2. From the Spanning Tree Configuration menu, type **3** to select Configure Active Protocol.

   The STP menu is shown in Figure 153 on page 423.

3. From the STP menu, type **P** to select STP Port Parameters.

   The STP Port Parameters menu is shown in Figure 154 on page 426.

4. From the STP Port Parameters menu, type **2** to select Display STP Port Configuration. The Display STP Port Configuration menu is shown in Figure 156.

```
            Allied Telesis AT-9424T/SP - AT-S63
                         Marketing
User: Manager                          11:20:02 02-Mar-2005
               Display STP Port Configuration

 Port  State           Cost     Priority
 ------------------------------------------------------
 1     Forwarding      4        128
 2     Forwarding      4        128
 3     Forwarding      4        128
 4     Forwarding      4        128
 5     Forwarding      4        128
 6     Forwarding      4        128
 7     Forwarding      4        128
 8     Forwarding      4        128

 N - Next Page
 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 156. Display STP Port Configuration Menu

Downloaded from www.Manualslib.com manuals search engine

The Display STP Port Configuration menu displays a table that contains the following columns of information:

Port
The port number.

State
Current state of a port. The possible states are Listening, Learning, Forwarding, or Blocking when spanning tree is enabled on the switch. When spanning tree is not enabled on the switch or if a port is not being used, its state will be disabled.

Cost
Port cost of the port.

Priority
The port's priority value. The number is used as a tie breaker when two or more ports have equal costs to the root bridge.

Resetting STP to the Default Settings

To reset STP to the default settings, perform the following procedure:

1. From the Main Menu, type **3** to select Spanning Tree Configuration.

   The Spanning Tree Configuration menu is shown in Figure 152 on page 420.

2. From the Spanning Tree Configuration menu, type **3** to select Configure Active Protocol.

   The STP menu is shown in Figure 153 on page 423.

3. From the STP menu, type **D** to select Reset STP to Defaults.

   The following prompt is displayed:

   ```
   Do you want to reset STP configuration to default [Yes/
   No] ->
   ```

4. Enter **Y** for Yes or **N** for No and press Return.

   The STP configuration is reset to the defaults.

Downloaded from www.Manualslib.com manuals search engine

Configuring RSTP

This section contains the following procedures:

- ”Configuring RSTP Bridge Settings”, next
- “Configuring RSTP Port Settings” on page 433
- “Displaying the RSTP Port Configuration” on page 435
- “Displaying the RSTP Port State” on page 437
- “Resetting RSTP to the Default Settings” on page 438

Configuring RSTP Bridge Settings

This section contains the procedure for configuring a bridge’s RSTP settings.

Caution
The default RSTP parameters are adequate for most networks. Changing them without prior experience and an understanding of how RSTP works might have a negative effect on your network. You should consult the IEEE 802.1w standard before changing any of the RSTP parameters.

To configure the RSTP bridge settings, perform the following procedure:

1. From the Main Menu, type **3** to select Spanning Tree Configuration.

   The Spanning Tree Configuration menu is shown in Figure 152 on page 420.

Downloaded from www.Manualslib.com manuals search engine

2. From the Spanning Tree Configuration menu, type **3** to select Configure Active Protocol. The RSTP menu is shown in Figure 157.

```
              Allied Telesis AT-9424T/SP - AT-S63
                           Marketing
User: Manager                                  11:20:02 02-Mar-2005
                           RSTP Menu

 1 - Force Version .......... RSTP
 2 - Bridge Priority ........ 32768 (In multiples of 4096: 8)
 3 - Bridge Hello Time ...... 2/2 (Configured/Actual)
 4 - Bridge Forwarding ...... 15/15 (Configured/Actual)
 5 - Bridge Max Age ......... 20/20 (Configured/Actual)
 6 - Bridge Identifier ...... 32768/00:21:46:A7:B4:11
 7 - Root Bridge ............ 00:21:46:A7:B4:11
 8 - Root Priority .......... 32768
 9 - Root Path Cost ......... 0

 P - RSTP Port Parameters
 D - Reset RSTP to Defaults

 R - Return to Previous Menu

 Enter your selection?
```

Figure 157. RSTP Menu

The bridge hello time, bridge forwarding, and bridge max age parameters will have two values if RSTP is enabled on the switch (for example, Bridge Forwarding..15/15). The first number is the configured value on the switch for the parameter and the second is the value the switch obtained from the root bridge and is currently using for the parameter. The switch displays only the configured values for these parameters if spanning tree is not activated on the switch.

3. Adjust the following parameters as necessary.

1 - Force Version
This selection determines whether the bridge operates with RSTP or in an STP-compatible mode. If you select RSTP, the bridge operates all ports in RSTP, except for those ports that receive STP BPDU packets. If you select Force STP Compatible, the bridge operates in RSTP, using the RSTP parameter settings, but it sends only STP BPDU packets out the ports.

2 - Bridge Priority
The priority number for the bridge. This number is used in determining the root bridge for RSTP. The bridge with the lowest priority number is selected as the root bridge. If two or more bridges have the same priority value, the bridge with the numerically lowest MAC address becomes the root bridge. When a root bridge goes off-line, the bridge with the next priority number automatically takes over as the root bridge. This parameter can be from 0 (zero) to 61,440 in increments of

Downloaded from www.Manualslib.com manuals search engine

4096, with 0 being the highest priority. For a list of the increments, refer to Table 5 on page 424.

3 - Bridge Hello Time
The time interval between generating and sending configuration messages by the bridge. This parameter can be from 1 to 10 seconds. The default is 2 seconds.

4 - Bridge Forwarding
The waiting period before a bridge changes to a new state, for example, becomes the new root bridge after the topology changes. If the bridge transitions too soon, not all links may have yet adapted to the change, possibly resulting in a network loop. The range is 4 to 30 seconds. The default is 15 seconds. This setting applies only to ports running in the STP-compatible mode.

5 - Bridge Max Age
The length of time after which stored bridge protocol data units (BPDUs) are deleted by the bridge. All bridges in a bridged LAN use this aging time to test the age of stored configuration messages called bridge protocol data units (BPDUs). For example, if you use the default 20, all bridges delete current configuration messages after 20 seconds. This parameter can be from 6 to 40 seconds. The default is 20 seconds.

When you select a value for maximum age, observe the following rules:

MaxAge must be greater than (2 x (HelloTime + 1)).

MaxAge must be less than (2 x (ForwardingDelay - 1))

6 - Bridge Identifier
The bridge identifier of the switch. The identifier consists of the switch's bridge priority value and MAC address. The values are separated by a slash (/). To change the switch's priority value, use option 2, Bridge Priority. The MAC address of the switch cannot be changed.

7 - Root Bridge
The MAC address of the root bridge of the spanning tree domain. This value cannot be changed and is only displayed when RSTP is activated on the switch.

8 - Root Priority
The priority value on the root bridge of the spanning tree domain. This parameter is only displayed when RSTP is enabled on the switch. To change the priority value on the root bridge, you must start a management session on the switch functioning as the root bridge and change its bridge priority value.

Downloaded from www.Manualslib.com manuals search engine

9 - Root Path Cost
The cost of the path from the current switch to the root switch of the spanning tree domain. If the current switch is the root switch, root path cost will be "0". This value cannot be changed and is only displayed when RSTP is activated on the switch.

4. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Configuring RSTP Port Settings

To adjust RSTP port parameters, perform the following procedure:

1. From the Main Menu, type **3** to select Spanning Tree Configuration.

   The Spanning Tree Configuration menu is shown in Figure 152 on page 420.

2. From the Spanning Tree Configuration menu, type **3** to select Configure Active Protocol.

   The RSTP menu is shown in Figure 153 on page 423.

3. From the Spanning Tree Configuration menu, type **3** to select STP Configuration.

   The STP menu is shown in Figure 153 on page 423.

4. From the STP menu, type **P** to select RSTP Port Parameters.

   The RSTP Port Parameters menu is shown in Figure 158.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                    RSTP Port Parameters

 1 - Configure RSTP Port Settings
 2 - Display RSTP Port Configuration
 3 - Display RSTP Port State

 R - Return to Previous Menu

 Enter your selection?
```

Figure 158. RSTP Port Parameters Menu

5. Type **1** to select Configure RSTP Port Settings. The following prompt is displayed:

   ```
   Starting Port to Configure [1 to 24] ->
   ```

6. Enter the number of the port you want to configure. To configure a range of ports, enter the first port of the range.

Downloaded from www.Manualslib.com manuals search engine

The following prompt is displayed:

```
Ending Port to Configure [1 to 24] ->
```

7. To configure just one port, enter the same port number here as you entered in the previous step. To configure a range of ports, enter the last port of the range.

   The Configure RSTP Port Settings menu is shown in Figure 159.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
              Configure RSTP Port Settings

 Configuring Ports 4-4
 1 - Port Priority ..... 128
 2 - Port Cost ......... Automatic Update
 3 - Point-to-Point ..... Auto Detect
 4 - Edge Port ......... Yes

 C - Check Migration to RSTP on Selected Ports (MCHECK)
 R - Return to Previous Menu

 Enter your selection?
```

Figure 159. Configure RSTP Port Settings Menu

8. Adjust the following parameters as necessary.

   1 - Port Priority
   This parameter is used as a tie breaker when two or more ports are determined to have equal costs to the root bridge. The range is 0 to 240 in increments of 16. The default value is 8 (priority value 128). For a list of the increments, refer to Table 6 on page 427.

   2 - Port Cost
   The spanning tree algorithm uses the cost parameter to decide which port provides the lowest cost path to the root bridge for that LAN. The range is 0 to 20,000,000. The default setting is Automatic Update, which sets port cost depending on the speed of the port. Table 9 lists the RSTP port costs with Auto-Detect.

Table 9. RSTP Auto-Detect Port Costs

Port Speed	Port Cost
10 Mbps	2,000,000
100 Mbps	200,000
1000 Mbps	20,000

Downloaded from www.Manualslib.com manuals search engine

Table 10 lists the RSTP port costs with Auto-Detect when a port is part of a port trunk.

Table 10. RSTP Auto-Detect Port Trunk Costs

Port Speed	Port Cost
10 Mbps	20,000
100 Mbps	20,000
1000 Mbps	2,000

3 - Point-to-Point
This parameter defines whether the port is functioning as a point-to-point port. The possible settings are Yes, No, and Auto Detect.

4 - Edge Port
This parameter defines whether the port is functioning as an edge port. The possible settings are Yes and No.

C - Check Migration To RSTP on Selected Ports (MCHECK)
The MCHECK parameter is displayed only when RSTP is enabled. This parameter resets an RSTP port, allowing it to send RSTP BPDUs. When an RSTP bridge receives STP BPDUs on an RSTP port, the port transmits STP BPDUs. The RSTP port continues to transmit STP BPDUs indefinitely. Type C to reset the MSTP port to transmit RSTP BPDUs.

9. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Displaying the RSTP Port Configuration

To display the RSTP port configuration, perform the following procedure:

1. From the Main Menu, type **3** to select Spanning Tree Configuration.

   The Spanning Tree Configuration menu is shown in Figure 152 on page 420.

2. From the Spanning Tree Configuration menu, type **3** to select Configure Active Protocol.

   The RSTP menu is shown in Figure 153 on page 423.

3. From the RSTP menu, type **P** to select RSTP Port Parameters.

   The RSTP Port Parameters menu is shown in Figure 158 on page 433.

4. From the RSTP Port Parameters menu, type **2** to select Display RSTP Port Configuration.

Downloaded from www.Manualslib.com manuals search engine

The Display RSTP Port Configuration menu is shown in Figure 160.

```
                Allied Telesis AT-9424T/SP - AT-S63
                          Marketing
User: Manager                                  11:20:02 02-Mar-2005
                  Display RSTP Port Configuration
   Port | Edge-Port |Point-to-Point |    Cost      |  Priority
 ------------------------------------------------------------------
     1      Yes         Auto Detect     Auto Update     128
     2      Yes         Auto Detect     Auto Update     128
     3      Yes         Auto Detect     Auto Update     128
     4      Yes         Auto Detect     Auto Update     128
     5      Yes         Auto Detect     Auto Update     128
     6      Yes         Auto Detect     Auto Update     128
     7      Yes         Auto Detect     Auto Update     128
     8      Yes         Auto Detect     Auto Update     128
     1      Yes         Auto Detect     Auto Update     128

 N - Next Page
 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 160. Display RSTP Port Configuration Menu

The Display RSTP Port Configuration menu displays a table that contains the following columns of information:

Port
The port number.

Edge-Port
Whether or not the port is operating as an edge port. The possible settings are Yes and No.

Point-to-Point
Whether or not the port is functioning as a point-to-point port. The possible settings are Yes, No, and Auto Detect.

Cost
Port cost of the port. The default is Auto Update.

Priority
The number used as a tie breaker when two or more ports have equal costs to the root bridge.

Downloaded from www.Manualslib.com manuals search engine

Displaying the RSTP Port State

To display the RSTP port state, perform the following procedure:

1. From the Main Menu, type **3** to select Spanning Tree Configuration.

   The Spanning Tree Configuration menu is shown in Figure 152 on page 420.

2. From the Spanning Tree Configuration menu, type **3** to select Configure Active Protocol.

   The RSTP menu is shown in Figure 153 on page 423.

3. From the RSTP menu, type **P** to select RSTP Port Parameters.

   The RSTP Port Parameters menu is shown in Figure 158 on page 433.

4. From the RSTP Port Parameters menu, type **3** to select Display RSTP Port State.

   The Display RSTP Port State menu is shown in Figure 161.

```
                Allied Telesis AT-9424T/SP - AT-S63
                           Marketing
User: Manager                                  11:20:02 02-Mar-2005
                       Display RSTP Port State
   Port  State         Role         Edge   P2P   Version   Port-Cost
 ------------------------------------------------------------------
   1     Disabled      ------------------------------------
   2     Forwarding    Designated   No     Yes   RSTP      200000
   3     Forwarding    Designated   No     Yes   RSTP      200000
   4     Forwarding    Designated   No     Yes   RSTP      200000
   5     Forwarding    Designated   No     Yes   RSTP      200000
   6     Forwarding    Designated   No     Yes   RSTP      200000
   7     Forwarding    Designated   No     Yes   RSTP      200000
   8     Forwarding    Designated   No     Yes   RSTP      200000

 N - Next Page
 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 161. Display RSTP Port State Menu

The Display RSTP Port State menu displays a table that contains the following information:

Port
The port number.

State
The RSTP state of the port. The possible states for a port connected to another device running RSTP are Discarding and Forwarding.

Downloaded from www.Manualslib.com manuals search engine

The possible states for a port connected to a device running STP are Listening, Learning, Forwarding, and Blocking.

The possible states for a port not being used or where spanning tree is not activated is Disabled.

Role
The RSTP role of the port. Possible roles are:

Root - The port that is connected to the root switch, directly or through other switches, with the least path cost.

Alternate - The port offers an alternate path in the direction of the root switch.

Backup - The port on a designated switch that provides a backup for the path provided by the designated port.

Designated - The port on the designated switch for a LAN that has the least cost path to the root switch. This port connects the LAN to the root switch.

P2P
Whether or not the port is functioning as a point-to-point port. The possible settings are Yes and No.

Version
Whether the port is operating in RSTP mode or STP-compatible mode.

Port Cost
The port cost of the port.

Resetting RSTP to the Default Settings

To reset RSTP to the default settings, perform the following procedure:

1. From the Main Menu, type **3** to select Spanning Tree Configuration.

   The Spanning Tree Configuration menu is shown in Figure 152 on page 420.

2. From the Spanning Tree Configuration menu, type **3** to select Configure Active Protocol.

   The RSTP menu is shown in Figure 157 on page 431.

3. From the RSTP Menu, type **D** to select Reset RSTP to Defaults.

   The following prompt is displayed:

   ```
   Do you want to reset RSTP configuration to default [Yes/
   No] ->
   ```

4. Type **Y** for Yes or **N** for No and press Return.

   The RSTP configuration is reset to the defaults.

Downloaded from www.Manualslib.com manuals search engine

Chapter 23

Multiple Spanning Tree Protocol

This chapter contains the procedures for configuring the Multiple Spanning Tree Protocol (MSTP). The sections in this chapter include:

- ❒ “Selecting MSTP as the Active Spanning Tree Protocol” on page 440
- ❒ “Configuring MSTP Bridge Settings” on page 441
- ❒ “Configuring the CIST Priority” on page 445
- ❒ “Displaying the CIST Priority” on page 447
- ❒ “Creating, Deleting, and Modifying MSTI IDs” on page 449
- ❒ “Adding, Removing, and Modifying VLAN Associations to MSTI IDs” on page 452
- ❒ “Configuring MSTP Port Settings” on page 457
- ❒ “Displaying the MSTP Port Configuration” on page 463
- ❒ “Displaying the MSTP Port State” on page 465
- ❒ “Resetting MSTP to the Defaults” on page 468

Spanning Tree Protocol (STP) and Rapid Spanning Tree Protocol (RSTP) are described in Chapter 22, “Spanning Tree and Rapid Spanning Tree Protocols” on page 419.

Downloaded from www.Manualslib.com manuals search engine

Selecting MSTP as the Active Spanning Tree Protocol

To select and activate MSTP as the active spanning tree protocol on the switch, or to disable spanning tree, perform the following procedure:

1. From the Main Menu, type **3** to select Spanning Tree Configuration.

   The Spanning Tree Configuration menu is shown in Figure 152 on page 420.

2. To change the active version of spanning tree on the switch, type **2** to select Active Protocol Version.

   The following prompt is displayed:

   ```
   Enter new value (S-STP, R-RSTP, M-MSTP):
   ```

3. Type **M** to select MSTP.

   Note
   A change to the active spanning tree is automatically saved on the switch.

4. To enable or disable spanning tree, type **1** to select Spanning Tree Status.

   The following prompt is displayed:

   ```
   Enter new value (E-Enable, D-Disable):
   ```

5. Type **E** to enable spanning tree or **D** to disable it. The default is disabled.

6. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Configuring MSTP Bridge Settings

To configure a bridge's MSTP settings, perform the following procedure:

1. From the Main Menu, type **3** to select Spanning Tree Configuration.

   The Spanning Tree Configuration menu is shown in Figure 152 on page 420.

2. From the Spanning Tree menu, type **3** to select Configure Active Protocol.

   The MSTP menu is shown in Figure 162.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                              11:20:02 02-Mar-2005
                     MSTP Configuration

1 - Force Version .......... MSTP
2 - Hello Time ............. 2/2 (Configured/Actual)
3 - Forwarding Delay ....... 15/15 (Configured/Actual)
4 - Max Age ................ 20/20 (Configured/Actual)
5 - Max Hops ............... 20
6 - Configuration Name .....
7 - Revision Level ......... 0
8 - Bridge Identifier ...... 32768/00:30:24:1E:EE:11
9 - Root Identifier ........ 32768/00:30:84:EF:CC:DD

C - CIST Menu
M - MSTI Menu
V - VLAN-MSTI Association Menu
P - MSTP Port Parameters
D - Reset MSTP to Defaults

R - Return to Previous Menu

Enter your selection?
```

Figure 162. MSTP Configuration Menu

The hello time, forwarding delay, and max age parameters have two values when MSTP is enabled on the switch (for example, Forwarding Delay .. 15/15). The first number is the configured value on the switch for the parameter and the second is the value the switch obtained from the root bridge and is actually using for the parameter. The switch displays only the configured values for these parameters if multiple spanning tree is not enabled on the switch.

Downloaded from www.Manualslib.com manuals search engine

3. Configure the following parameters as necessary.

1 - Force Version
This selection determines whether the bridge operates with MSTP or in an STP-compatible mode. If you select MSTP, the bridge operates all ports in MSTP, except for those ports that receive STP or RSTP BPDU packets. If you select Force STP Compatible, the bridge uses its MSTP parameter settings, but sends only STP BPDU packets from the ports.

Note
Selecting the STP-compatible mode deletes all spanning tree instances on the switch.

2 - Hello Time
The time interval between generating and sending configuration messages by the bridge. The range of this parameter is 1 to 10 seconds. The default is 2 seconds. This value is active only if the bridge is selected as the root bridge of the network.

3 - Forwarding Delay
The waiting period before a bridge changes to a new state, for example, becomes the new root bridge after the topology changes. If the bridge transitions too soon, not all links may have yet adapted to the change, possibly resulting in a network loop. The range is 4 to 30 seconds. The default is 15 seconds. This setting applies only to ports running in the STP-compatible mode.

4 - Max Age
The length of time after which stored bridge protocol data units (BPDUs) are deleted by the bridge. This parameter applies only if the bridged network contains an STP or RSTP single-instance spanning tree. Otherwise, the bridges use the Max Hop counter to delete BPDUs.

All bridges in a single-instance bridged LAN use this aging time to test the age of stored configuration messages called bridge protocol data units (BPDUs). For example, if you use the default of 20, all bridges delete current configuration messages after 20 seconds. The range of this parameter is 6 to 40 seconds. The default is 20 seconds.

When you select a value for maximum age, observer the following rules:

MaxAge must be greater than (2 x (HelloTime + 1)).

MaxAge must be less than (2 x (ForwardingDelay - 1))

5 - Max Hops
MSTP regions use this parameter to discard BPDUs. The Max Hop counter in a BPDU is decremented every time the BPDU crosses a

Downloaded from www.Manualslib.com manuals search engine

bridge within a MSTP region. After the counter reaches zero, the BPDU is deleted. The counter is reset to its original value if a BPDU crosses a MSTP regional boundary.

6 - Configuration Name
The name of the MSTP region. The range is 0 (zero) to 32 alphanumeric characters in length. The name, which is case sensitive, must be the same on all bridges in a region. Examples include Sales Region and Production Region.

7 - Revision Level
The revision level of an MSTP region. The range is 0 (zero) to 255. This is an arbitrary number that you assign to a region. The revision level must be the same on all bridges in a region. Different regions can have the same revision level without conflict.

8 - Bridge Identifier
The bridge identifier of the switch. The identifier consists of the switch's CIST priority value and MAC address, separated by a slash (/). To change the switch's priority value, refer to "Configuring the CIST Priority" on page 445. The MAC address of the switch cannot be changed.

9 - Root Identifier
The bridge identifier of the root bridge of the CIST spanning tree domain. The identifier consists of the root switch's bridge or CIST priority value and MAC address, separated by a slash (/). If this MAC address is the same as the current bridge's MAC address, then the switch is functioning as a root bridge. If the two MAC addresses are different, then a different switch is functioning as the root bridge. This parameter is only displayed with MSTP is enabled.

Note
Selection C, CIST menu, is described in "Configuring the CIST Priority," next.

Selection M, MSTI menu, is described in "Creating, Deleting, and Modifying MSTI IDs" on page 449.

Selection V, VLAN-MSTI Association menu, is described in "Adding, Removing, and Modifying VLAN Associations to MSTI IDs" on page 452.

Selection P, MSTP Port Parameters, is described in "Configuring MSTP Port Settings" on page 457.

Selection D, Reset MSTP to Defaults, is described in "Resetting MSTP to the Defaults" on page 468.

Downloaded from www.Manualslib.com manuals search engine

4. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Configuring the CIST Priority

This procedure explains how to adjust the bridge's CIST priority.

To change the CIST priority, perform the following procedure:

1. From the Main Menu, type **3** to select Spanning Tree Configuration.

   The Spanning Tree Configuration menu is shown in Figure 152 on page 420.

2. From the Spanning Tree Configuration menu, type **3** to select Configure Active Protocol.

   The MSTP menu is shown in Figure 162 on page 441.

3. From the MSTP menu, type **C** to select CIST menu.

   The CIST menu is shown in Figure 163.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                            11:20:02 02-Mar-2005
                         CIST Menu

CIST Priority ............. 32768
Associated VLANs .......... 1,2,4,11

1 - Modify CIST Priority

R - Return to Previous Menu
Enter your selection?
```

Figure 163. CIST Menu

   The CIST Priority field in the menu displays the current value for this MSTP parameter. This number is used in determining the root bridge of the network spanning tree. This number is analogous to the RSTP bridge priority value. The bridge in the network with the lowest priority number is selected as the root bridge. If two or more bridges have the same bridge or CIST priority values, the bridge with the numerically lowest MAC address becomes the root bridge.

   The Associated VLANs field displays the VIDs of the VLANs that are currently associated with CIST and have not been assigned to a MSTI.

4. From the CIST menu, type **1** to select Modify CIST Priority.

Downloaded from www.Manualslib.com manuals search engine

The following prompt is displayed:

```
Enter new priority [the value will be multiplied by
4096]: [0 to 15] ->
```

5. Enter the increment that represents the new CIST priority value. The range is 0 (zero) to 61,440 in increments of 4,096, with 0 being the highest priority. For a list of the increments, refer to Table 6, “Port Priority Value Increments” on page 427.

6. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Displaying the CIST Priority

To change the CIST priority, perform the following procedure:

1. From the Main Menu, type **3** to select Spanning Tree Configuration.

   The Spanning Tree Configuration menu is shown in Figure 152 on page 420.

2. From the Spanning Tree Configuration menu, type **3** to select Configure Active Protocol.

   The MSTP menu is shown in Figure 162 on page 441.

3. From the MSTP menu, type **M** to select MSTI menu.

   The MSTI menu is shown in Figure 164.

```
               Allied Telesis AT-9424T/SP - AT-S63
                            Marketing
User: Manager                                      11:20:02 02-Mar-2005
                              MSTI Menu

 MSTI | Priority | Regional Root ID | Path Cost | Associated VLANs
 ------------------------------------------------------------------

 1       32768     00A0D2 1454B3       0          1,2
 2       32768     00A0D2 1454B3       0          4,11

 1 - Create MSTI
 2 - Delete MSTI
 3 - Modify MSTI

 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 164. MSTI Menu

The MSTI menu displays a table that contains the following columns of information:

MSTI
Lists the MSTI IDs existing on the switch.

Priority
Specifies the MSTI priority value for the MSTI. The steps in this procedure explain how you can assign this value when you create an MSTI ID and how to modify the value for an existing MSTI ID.

Regional Root ID
Identifies the regional root for the MSTI by its MAC address.

Downloaded from www.Manualslib.com manuals search engine

Path Cost
Specifies the path cost from the bridge to the regional root. If the bridge is the regional root, the value is 0.

Associated VLANs
Specifies the VIDs of the VLANs that have been associated with the MSTI ID.

The table does not include the CIST. The table is empty if no MSTI IDs have been created.

Downloaded from www.Manualslib.com manuals search engine

Creating, Deleting, and Modifying MSTI IDs

The following sections contain procedures for working with MSTI IDs:

- "Creating an MSTI ID" next
- "Deleting an MSTI ID" on page 450
- "Modifying an MSTI ID" on page 450

Creating an MSTI ID

To create an MSTI ID, perform the following procedure:

1. From the Main Menu, type **3** to select Spanning Tree Configuration.

   The Spanning Tree Configuration menu is shown in Figure 152 on page 420.

2. From the Spanning Tree Configuration menu, type **3** to select Configure Active Protocol.

   The MSTP menu is shown in Figure 162 on page 441.

3. From the MSTP menu, type **M** to select MSTI menu.

   The MSTI menu is shown in Figure 164 on page 447.

4. Type **1** to select Create MSTI.

   The following prompt is displayed:

   ```
   Enter the MSTI ID to be created: [1 to 15] ->
   ```

5. Enter the new MSTP ID. The MSTI ID range is from 1 to 15. You can specify only one MSTI ID at a time.

   The following prompt is displayed:

   ```
   Success...Do you want to associate VLANs with this MSTI
   ID: [Yes/No] ->
   ```

6. If you want to associate VLANs to the MSTI now, type **Y** for yes. If you want to do it later, type **N** for no. (To add or remove VLANs from an existing MSTI, go to "Adding, Removing, and Modifying VLAN Associations to MSTI IDs" on page 452.)

   If you respond with yes, this prompt appears:

   ```
   Enter the list of VLANs:
   ```

7. Enter the VIDs of the VLANs that you want to associate with the MSTI ID. You can specify more than one VLAN at a time (for example, 4,6,11) To view VIDs, refer to "Displaying VLANs" on page 485.

Downloaded from www.Manualslib.com manuals search engine

8. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Deleting an MSTI ID

To delete an MSTI ID, perform the following procedure:

1. From the Main Menu, type **3** to select Spanning Tree Configuration.

   The Spanning Tree Configuration menu is shown in Figure 152 on page 420.

2. From the Spanning Tree Configuration menu, type **3** to select Configure Active Protocol.

   The MSTP menu is shown in Figure 162 on page 441.

3. From the MSTP menu, type **M** to select MSTI menu.

   The MSTI menu is shown in Figure 164 on page 447.

4. Type **2** to select Delete MSTI.

   The following prompt is displayed:

   ```
   Enter the MSTI ID to be deleted: [1 to 15] ->
   ```

5. Enter the MSTP IDs that you want to delete. The range is 1 to 15. (You cannot delete CIST, which has a value of 0.)

   All VLANs associated with a deleted MSTP ID are returned to CIST.

6. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Modifying an MSTI ID

To change the MSTI priority value for an MSTI, perform the following procedure:

1. From the Main Menu, type **3** to select Spanning Tree Configuration.

   The Spanning Tree Configuration menu is shown in Figure 152 on page 420.

2. From the Spanning Tree Configuration menu, type **3** to select Configure Active Protocol.

   The MSTP menu is shown in Figure 162 on page 441.

3. From the MSTP menu, type **M** to select MSTI menu.

   The MSTI menu is shown in Figure 164 on page 447

4. Type **3** to select Modify MSTI.

Downloaded from www.Manualslib.com manuals search engine

The following prompt is displayed:

```
Enter the MSTI ID to be modified: [1 to 15] ->
```

5. Enter the MSTP IDs that you want to modify. The range is 1 to 15. You can specify only one MSTI ID at a time.

   The following prompt is displayed:

   ```
   Enter new priority [the value will be multiplied by 4096]
   [0 to 15] -> 8
   ```

6. Enter a new MSTI priority number for this MSTI on the bridge. This parameter is used in selecting a regional root for the MSTI. The range is 0 (zero) to 61,440 in increments of 4,096, with 0 being the highest priority. This parameter is used in selecting a regional root for the MSTI. For a list of the increments, refer to Table 5, "Bridge Priority Value Increments" on page 424.

7. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Adding, Removing, and Modifying VLAN Associations to MSTI IDs

When you create a new MSTI ID, you are given the opportunity of associating VLANs to it. But after an MSTI ID is created, you may want to add more VLANs to it, or perhaps remove VLANs. This procedure explains how to associate VLANs on the switch to an existing MSTI ID and also how to remove VLANs. Before performing this procedure, note the following:

- You must create a MSTI ID before you can assign VLANs to it. To create a MSTI ID, refer to “Creating, Deleting, and Modifying MSTI IDs” on page 449.
- You can assign a VLAN to only one MSTI. By default, a VLAN, when created, is associated with the CIST instance, which has a MSTI ID of 0.
- An MSTI can contain any number of VLANs.

This section contains the following procedures:

- ”Adding or Removing a VLAN from an MSTI ID” next
- “Associating a VLAN to an MSTI ID” on page 453
- “Removing a VLAN from an MSTI ID” on page 454
- “Associating VLANs to an MSTI ID and Deleting All Associated VLANs” on page 455
- “Clearing VLAN to MSTI Associations” on page 456

Adding or Removing a VLAN from an MSTI ID

To add or remove a VLAN from an MSTI ID, perform the following procedure:

1. From the Main Menu, type **3** to select Spanning Tree Configuration.

   The Spanning Tree Configuration menu is shown in Figure 152 on page 420.

2. From the Spanning Tree Configuration menu, type **3** to select Configure Active Protocol.

   The MSTP menu is shown in Figure 162 on page 441.

3. From the MSTP menu, type **M** to select MSTI menu.

   The MSTI menu is shown in Figure 164 on page 447.

4. From the MSTP menu, type **V** to select VLAN-MSTI Association menu.

Downloaded from www.Manualslib.com manuals search engine

The VLAN-MSTI Association menu is shown in Figure 165.

```
            Allied Telesis AT-9424T/SP - AT-S63
                          Marketing
User: Manager                              11:20:02 02-Mar-2005
                  VLAN-MSTI Association Menu

MSTI/CIST    Associated VLANs
-------------------------------------------------------
0
4            1,2
5            6
7            7,22

1 - Add VLANs to MSTI
2 - Delete VLANs from MSTI
3 - Set VLAN to MSTI Association
4 - Clear VLAN to MSTI Association

U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 165. VLAN-MSTI Association Menu

The VLAN-MSTI Association menu displays a table that contains the following columns of information:

MSTI / CIST
Lists the CIST and current MSTI IDs on the switch.

Associated VLANs
Specifies the VIDs of the VLANs associated with the CIST and MSTI IDs. For instance, referring to Figure 165, the VLANs with the VIDs 7 and 22 are assigned to MSTI 7.

Associating a VLAN to an MSTI ID

To associate a VLAN to an MSTP ID, perform the following procedure:

1. From the Main Menu, type **3** to select Spanning Tree Configuration.

   The Spanning Tree Configuration menu is shown in Figure 152 on page 420.

2. From the Spanning Tree Configuration menu, type **3** to select Configure Active Protocol.

   The MSTP menu is shown in Figure 162 on page 441.

3. From the MSTP menu, type **M** to select MSTI menu.

   The MSTI menu is shown in Figure 164 on page 447.

Downloaded from www.Manualslib.com manuals search engine

4. From the MSTP menu, type **V** to select VLAN-MSTI Association menu.

   The VLAN-MSTI Association menu is shown in Figure 165 on page 453.

5. From the VLAN-MSTI Association menu, type **1** to select Add VLANs to MSTI.

   The following prompt is displayed:

   ```
   Enter the MSTI ID <enter 0 for CIST> [0 to 15] ->
   ```

6. Enter the MSTI ID to which you want to associate a VLAN.

   A prompt similar to the following is displayed:

   ```
   Enter the list of VLANs:
   ```

7. Enter the VLAN ID of the virtual LAN you want to associate with the MSTI ID. You can enter more than one VLAN at a time (for example, 2,4,7). To view VIDs, refer to “Displaying VLANs” on page 485.

   The MSTI ID retains any VLANs already associated with it when new VLANs are added.

8. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Removing a VLAN from an MSTI ID

To remove a VLAN from an MSTP ID, perform the following procedure:

1. From the Main Menu, type **3** to select Spanning Tree Configuration.

   The Spanning Tree Configuration menu is shown in Figure 152 on page 420.

2. From the Spanning Tree Configuration menu, type **3** to select Configure Active Protocol.

   The MSTP menu is shown in Figure 162 on page 441.

3. From the MSTP menu, type **M** to select MSTI menu.

   The MSTI menu is shown in Figure 164 on page 447

4. From the MSTP menu, type **V** to select VLAN-MSTI Association menu.

   The VLAN-MSTI Association menu is shown in Figure 165 on page 453.

5. From the VLAN-MSTI Association menu, type **2** to select Delete VLANs from MSTI.

Downloaded from www.Manualslib.com manuals search engine

The following prompt is displayed:

```
Enter the MSTI ID <enter 0 for CIST> [0 to 15] ->
```

6. Enter the MSTI ID to which you want to associate a VLAN.

   A prompt similar to the following is displayed:

   ```
   Enter the list of VLANs:
   ```

7. Enter the VLAN ID of the virtual LAN that you want to remove from the MSTI ID. You can enter more than one VLAN at a time (for example, 2,4,7) To view VIDs, refer to "Displaying VLANs" on page 485.

   A removed VLAN is returned to CIST.

8. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Associating VLANs to an MSTI ID and Deleting All Associated VLANs

To associate VLANs to an MSTP ID while deleting all VLANs that are already associated with it, perform the following procedure:

1. From the Main Menu, type **3** to select Spanning Tree Configuration.

   The Spanning Tree Configuration menu is shown in Figure 152 on page 420.

2. From the Spanning Tree Configuration menu, type **3** to select Configure Active Protocol.

   The MSTP menu is shown in Figure 162 on page 441.

3. From the MSTP menu, type **M** to select MSTI menu.

   The MSTI menu is shown in Figure 164 on page 447

4. From the MSTP menu, type **V** to select VLAN-MSTI Association menu.

   The VLAN-MSTI Association menu is shown in Figure 165 on page 453.

5. From the VLAN-MSTI Association menu, type **1** to select Add VLANs to MSTI.

   The following prompt is displayed:

   ```
   Enter the MSTI ID <enter 0 for CIST> [0 to 15] ->
   ```

6. Enter the MSTI ID to which you want to associate a VLAN.

7. A prompt similar to the following is displayed:

   ```
   Enter the list of VLANs:
   ```


Downloaded from www.Manualslib.com manuals search engine

8. Enter the VLAN ID of the virtual LAN that you want to associate with the MSTI ID. You can enter more than one VLAN at a time (for example, 2,4,7) (To view VIDs, refer to “Displaying VLANs” on page 485.)

   The VLANs already associated with the MSTI ID are removed when the new VLANs are added. The removed VLANs are returned to CIST.

9. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Clearing VLAN to MSTI Associations

To clear VLAN to MSTI associations, perform the following procedure:

1. From the Main Menu, type **3** to select Spanning Tree Configuration.

   The Spanning Tree Configuration menu is shown in Figure 152 on page 420.

2. From the Spanning Tree Configuration menu, type **3** to select Configure Active Protocol.

   The MSTP menu is shown in Figure 162 on page 441.

3. From the MSTP menu, type **M** to select MSTI menu.

   The MSTI menu is shown in Figure 164 on page 447

4. From the MSTP menu, type **V** to select VLAN-MSTI Association menu.

   The VLAN-MSTI Association menu is shown in Figure 165 on page 453.

5. From the VLAN-MSTI Association menu, type **4** to select Clear VLAN to MSTI Association.

   The following prompt is displayed:

   ```
   Enter the MSTI ID: [1 to 15] ->
   ```

6. Type the MSTI ID number and press Return.

Downloaded from www.Manualslib.com manuals search engine

Configuring MSTP Port Settings

The MSTP port settings are divided into two groups. The parameters in the first group are set just once on a port, regardless of the number of MSTIs in which a port is a member. These settings are:

- External path cost
- Point-to-point designation
- Edge port designation

The procedure for setting these parameters is in "Configuring Generic MSTP Port Settings," next.

The second group of port parameters can be set independently for each MSTI where a port is a member. These parameters are:

- Internal path cost
- Priority

To set these parameters, refer to "Configuring MSTI-specific Port Parameters" on page 460.

Configuring Generic MSTP Port Settings

To configure the external path cost of a port or to designate whether the port is an edge or point-to-point port, perform the following procedure:

1. From the Main Menu, type **3** to select Spanning Tree Configuration.

   The Spanning Tree Configuration menu is shown in Figure 152 on page 420.

2. From the Spanning Tree Configuration menu, type **3** to select Configure Active Protocol.

   The MSTP menu is shown in Figure 162 on page 441.

3. From the MSTP menu, type **P** to select MSTP Port Parameters.

Downloaded from www.Manualslib.com manuals search engine

The MSTP Port Parameters menu is shown in Figure 166.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                   MSTP Port Parameters


1 - Configure Generic Port Settings
2 - Configure Per Spanning Tree Port Settings
3 - Display MSTP Port Configuration
4 - Display MSTP Port State

R - Return to Previous Menu

Enter your selection?
```

Figure 166. MSTP Port Parameters Menu

4. From the MSTP Port Parameters menu, type **1** to select Configure Generic Port Settings.

   The following prompt is displayed:

   ```
   Start port to configure: [1 to 26] ->
   ```

5. Enter the number of the port you want to configure. To configure a range of ports, enter the first port of the range.

   The following prompt is displayed:

   ```
   End port to configure: [1 to 26] -> 4
   ```

6. Enter the last port of the range. To configure just one port, enter the same port here as in Step 5.

   The Configure MSTP Port Settings menu is shown in Figure 167.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
              Configure Generic Port Settings


1 - Port External Path Cost ..... Auto
2 - Point-to-Point ............... Auto Detect
3 - Edge Port ................... Yes

R - Return to Previous Menu

Enter your selection?
```

Figure 167. Configure MSTP Port Settings Menu

Downloaded from www.Manualslib.com manuals search engine

7. Adjust the following parameters as necessary:

   1- Port External Path Cost
   The port cost of the port if the port is connected to a bridge which is a member of another MSTP region or is running STP or RSTP. The range is 0 to 200,000,000. The default setting is Auto, which sets port cost depending on the speed of the port. Table 11 lists the MSTP port costs with the Auto setting when the port is not a member of a trunk.

   Table 11 Auto External Path Costs

Port Speed	Port Cost
10 Mbps	2,000,000
100 Mbps	200,000
1000 Mbps	20,000

   Table 12 lists the MSTP port costs with the Auto setting when the port is part of a port trunk.

   Table 12. Auto External Path Trunk Costs

Port Speed	Port Cost
10 Mbps	20,000
100 Mbps	20,000
1000 Mbps	2,000

   2 - Point-to-Point
   This parameter defines whether the port is functioning as a point-to-point port.

   3 - Edge Port
   This parameter defines whether the port is functioning as an edge port.

8. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Configuring MSTI-specific Port Parameters

This procedure explains how to set a port's priority and internal path cost. These parameters can be set independently on a port for each MSTI in which a port is a member. To configure the parameters, perform the following procedure:

1. From the Main Menu, type **3** to select Spanning Tree Configuration.

   The Spanning Tree Configuration menu is shown in Figure 152 on page 420.

2. From the Spanning Tree Configuration menu, type **3** to select Configure Active Protocol.

   The MSTP menu is shown in Figure 162 on page 441.

3. From the MSTP menu, type **P** to select MSTP Port Parameters.

   The MSTP Port Parameters menu is shown in Figure 166 on page 458.

4. Type **2** to select Configure Per Spanning Tree Port Settings.

   The following prompt is displayed:

   ```
   Enter Spanning Tree (CIST/MSTI) List :
   ```

5. Enter the ID number of the CIST or MSTI where the VLAN containing the port whose settings you want to configure has been assigned. You can specify more than one ID number.

   The following prompt is displayed:

   ```
   Start port to configure: [1 to 26] -> 1
   ```

6. Enter the number of the port you want to configure. To configure a range of ports, enter the first port of the range.

   The following prompt is displayed:

   ```
   End port to configure: [1 to 26] -> 1
   ```

7. Enter the last port of the range. To configure just one port, enter the same port here as in Step 6.

Downloaded from www.Manualslib.com manuals search engine

Configure Per Spanning Tree Port Settings Menu is shown in Figure 168.

```
              Allied Telesis AT-9424T/SP - AT-S63
                           Marketing
 User: Manager                                  11:20:02 02-Mar-2005
           Configure Per Spanning Tree Port Settings

Spanning Tree List: 4
Configuring Ports: 7-7

1 - Port Priority ............... 128
2 - Port Internal Path Cost ..... Auto Update

R - Return to Previous Menu

Enter your selection?
```

Figure 168. Configure Per Spanning Tree Port Settings Menu

The Spanning Tree List displays the ID numbers of the MSTIs you specified.

8. Adjust the following parameters as necessary:

   1 - Port Priority
   This parameter is used as a tie breaker when two or more ports are determined to have equal costs to the regional root bridge. The range is 0 to 240 in increments of 16. The default value is 8 (priority value 128). For a list of the increments, refer to Table 6, "Port Priority Value Increments" on page 427.

   2- Port Internal Path Cost
   The port cost of the port if the port is connected to a bridge which is part of the same MSTP region. The range is 0 to 200,000,000. The default setting is 0, Auto Update, which sets port cost depending on the speed of the port. Default values are 2,000,000 for 10 Mbps ports, 200,000 for a 100 Mbps ports, and 20,000 for one gigabit ports.

   Table 13 lists the RSTP port costs with Auto-Detect.

Table 13. RSTP Auto-Detect Port Costs

Port Speed	Port Cost
10 Mbps	2,000,000
100 Mbps	200,000
1000 Mbps	20,000

Downloaded from www.Manualslib.com manuals search engine

Table 14 lists the RSTP port costs with Auto-Detect when the port is part of a port trunk.

Table 14. RSTP Auto-Detect Port Trunk Costs

Port Speed	Port Cost
10 Mbps	20,000
100 Mbps	20,000
1000 Mbps	2,000

9. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Displaying the MSTP Port Configuration

To display the MSTP port configuration, perform the following procedure:

1. From the Main Menu, type **3** to select Spanning Tree Configuration.

   The Spanning Tree Configuration menu is shown in Figure 152 on page 420.

2. From the Spanning Tree Configuration menu, type **3** to select Configure Active Protocol.

   The MSTP menu is shown in Figure 162 on page 441.

3. From the MSTP menu, type **P** to select MSTP Port Parameters.

   The MSTP Port Parameters menu is shown in Figure 166 on page 458.

4. From the MSTP Port Parameters menu, type **3** to select Display MSTP Port Configuration.

   The Display MSTP Port Configuration menu is shown in Figure 169.

```
                Allied Telesis AT-9424T/SP - AT-S63
                             Marketing
User: Manager                                        11:20:02 02-Mar-2005
                  Display MSTP Port Configuration

                                        |      Cost         |
   Port | Edge-Port |Point-to-Point | External Internal|Priority
 ------------------------------------------------------------
     1      Yes         Auto-Detect     200000     Auto      128
     2      Yes         Auto-Detect     200000     Auto      128
     3      Yes         Auto-Detect     200000     Auto      128
     4      Yes         Auto-Detect     200000     Auto      128
     5      Yes         Auto-Detect     200000     Auto      128
     6      Yes         Auto-Detect     200000     Auto      128
     7      Yes         Auto-Detect     200000     Auto      128
     8      Yes         Auto-Detect     200000     Auto      128

 N - Next Page
 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 169. Display MSTP Port Configuration Menu

Downloaded from www.Manualslib.com manuals search engine

The Display MSTP Port Configuration menu displays a table that contains the following columns of information:

Port
The port number.

Edge-Port
Whether or not the port is functioning as an edge port. The possible settings are Yes and No.

Point-to-Point
Whether or not the port is functioning as a point-to-point port. The possible settings are Yes, No, and Auto-Detect.

External or Internal Port Cost
External Port Cost
The port cost of the port if the port is connected to a bridge which is a member of another MSTP region or is running STP or RSTP.

Internal Port Cost
The port cost of the port if the port is connected to a bridge which is part of the same MSTP region. If the setting is Auto Update, the port cost is set automatically depending on the speed of the port. Default values are 2,000,000 for 10 Mbps ports, 200,000 for a 100 Mbps ports, and 20,000 for one gigabit ports.

Priority
This parameter is used as a tie breaker when two or more ports are determined to have equal costs to the regional root bridge.

Downloaded from www.Manualslib.com manuals search engine

Displaying the MSTP Port State

To display the MSTP port state, perform the following procedure:

1. From the Main Menu, type **3** to select Spanning Tree Configuration.

   The Spanning Tree Configuration menu is shown in Figure 152 on page 420.

2. From the Spanning Tree Configuration menu, type **3** to select Configure Active Protocol.

   The MSTP menu is shown in Figure 162 on page 441.

3. From the MSTP menu, type **P** to select MSTP Port Parameters.

   The MSTP Port Parameters menu is shown in Figure 166 on page 458.

4. From the MSTP Port Parameters menu, type **4** to select Display MSTP Port State.

   The following prompt is displayed:

   ```
   Enter Spanning Tree (CIST/MSTI) ID to display port state:
   [0 to 15} ->
   ```

5. Enter an MSTI ID.

Downloaded from www.Manualslib.com manuals search engine

The Display MSTP Port State menu is shown in Figure 170.

```
                Allied Telesis AT-9424T/SP - AT-S63
                          Marketing
User: Manager                                    11:20:02 02-Mar-2005
                      Display MSTP Port State

 Spanning Tree Instance: 0 (CIST)
 Port State       Role         P2P   Version  Internal Port-Cost
 ------------------------------------------------------------------

 1    Forwarding   Root         Yes   MSTP     200000
 2    Disabled
 3    Discarding   Alternate    Yes   MSTP     200000
 4    Discarding   Alternate    Yes   MSTP     200000
 5    Disabled
 6    Disabled
 7    Forwarding   Designated   Yes   MSTP     200000
 8    Disabled

 N - Next Page
 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 170. Display MSTP Port State Menu

The MSTP Port State menu displays a table that contains the following columns of information:

Port
The port number.

State
The MSTP state of the port. The possible states are:

Discarding - The port is discarding received packets and is not submitting forwarded packets for transmission.

Learning - The port is learning the MAC address from the received packet, but does not process or forward the packet.

Forwarding - Normal operation.

Disabled - The port has been disabled.

Role
The MSTP role of the port. The possible roles are:

Root - The port that is connected to the root switch, directly or through other switches, with the least path cost.

Alternate - The port offers an alternate path in the direction of the root switch.

Downloaded from www.Manualslib.com manuals search engine

Backup - The port on a designated switch that provides a backup for the path provided by the designated port.

Designated - The port on the designated switch for a LAN that has the least cost path to the root switch. This port connects the LAN to the root switch.

Master - Similar to the root port. When the port is a boundary port, the MSTI port roles follow the CIST port roles. The MSTI port role is called "master" when the CIST role is "root."

P2P
Whether or not the port is functioning as a point-to-point port. The possible settings are Yes, No, and Auto-Detect.

Version
Whether the port is operating in MSTP mode or STP-compatible mode.

Internal Port-Cost
The port cost when the port is connected to a bridge in the same MSTP region.

Downloaded from www.Manualslib.com manuals search engine

Resetting MSTP to the Defaults

To reset MSTP to the defaults, perform the following procedure:

1. From the Main Menu, type **3** to select Spanning Tree Configuration.

   The Spanning Tree Configuration menu is shown in Figure 152 on page 420.

2. From the Spanning Tree Configuration menu, type **3** to select Configure Active Protocol.

   The MSTP menu is shown in Figure 162 on page 441.

3. From the MSTP menu, type **D** to select Reset MSTP to Defaults.

   The following message is displayed:

   ```
   Do you want to reset MSTP configuration to default? [Yes/
   No] ->
   ```

4. Enter **Y** for Yes or **N** for No and press Return.

   The MSTP configuration is reset to the defaults.

Downloaded from www.Manualslib.com manuals search engine

Section VI

Virtual LANs

The chapters in this section contain overview information on the different types of virtual LANs supported by the AT-9400 Switch. The chapters also explain how to configure these features from the menu interface of the AT-S63 Management Software. The chapters include:

- Chapter 24, “Port-based and Tagged VLANs” on page 471
- Chapter 25, “GARP VLAN Registration Protocol” on page 495
- Chapter 26, “Multiple VLAN Modes” on page 515
- Chapter 27, “Protected Ports VLANs” on page 521
- Chapter 28, “MAC Address-based VLANs” on page 533

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Chapter 24

Port-based and Tagged VLANs

This chapter contains basic information about virtual LANs (VLANs) and procedures for creating, modifying, and deleting VLANs from a local or Telnet management session.

This chapter contains the following sections:

- “Creating a Port-based or Tagged VLAN” on page 472
- “Example of Creating a Port-based VLAN” on page 477
- “Example of Creating a Tagged VLAN” on page 479
- “Modifying a Port-based or Tagged VLAN” on page 481
- “Displaying VLANs” on page 485
- “Deleting a Port-based or Tagged VLAN” on page 487
- “Deleting All VLANs” on page 490
- “Displaying PVIDs” on page 492
- “Enabling or Disabling Ingress Filtering” on page 493

Downloaded from www.Manualslib.com manuals search engine

Creating a Port-based or Tagged VLAN

To create a port-based or tagged VLAN, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.

   The VLAN Configuration menu is shown in Figure 171.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                              11:20:02 02-Mar-2005
                     VLAN Configuration

 1 - Ingress Filtering Status ........ Disabled
 2 - VLANs Mode ..................... User Configured VLANs
 3 - Configure VLANs
 4 - Show VLANs
 5 - Show PVIDs
 6 - Configure GARP-GVRP

 R - Return to Previous Menu

 Enter your selection?
```

Figure 171. VLAN Configuration Menu

2. From the VLAN Configuration menu, type **3** to select Configure VLANs.

Note
The switch must be operating in the user-configured VLAN mode to support port-based and tagged VLANs. To change a switch's VLAN mode, refer to "Selecting a VLAN Mode" on page 516.

Selection 6, Configure GARP-GVRP, is described in Chapter 25, "GARP VLAN Registration Protocol" on page 495.

Downloaded from www.Manualslib.com manuals search engine

The Configure VLANs menu is shown in Figure 172.

```
          Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                            11:20:02 02-Mar-2005
                      Configure VLANs

1 - Create VLAN
2 - Modify VLAN
3 - Delete VLAN
4 - Reset to Default VLAN

R - Return to Previous Menu

Enter your selection?
```

Figure 172. Configure VLANs Menu

3. From the Configure VLANs menu, type **1** to select Create VLAN.

   The Create VLAN menu is shown in Figure 173.

```
          Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                            11:20:02 02-Mar-2005
                       Create VLAN

1 - VLAN Name ............
2 - VLAN ID (VID) ........ 2
3 - VLAN Type ............ Port Based
4 - Tagged Ports .........
5 - Untagged Ports .......
6 - Protected Ports ...... No

C - Create VLAN
R - Return to Previous Menu

Enter your selection?
```

Figure 173. Create VLAN Menu

4. Type **1** to select VLAN Name.

   The following prompt is displayed:

   ```
   Enter new value ->
   ```

5. Type a name for the new VLAN.

   The name can be from one to fifteen alphanumeric characters in length. The name should reflect the function of the nodes that will be a part of the VLAN (for example, Sales or Accounting). The name cannot

Downloaded from www.Manualslib.com manuals search engine

contain spaces or special characters, such as asterisks (*) or exclamation points (!).

If the VLAN will be unique in your network, then the name should be unique as well. If the VLAN will be part of a larger VLAN that spans multiple switches, then the name for the VLAN should be the same on each switch where nodes of the VLAN are connected.

Note
A VLAN must be assigned a name.

6. Type **2** to select VLAN ID (VID.

   The following prompt is displayed:

   ```
   Enter new value -> [2 to 4094] ->
   ```

7. Type a VID value for the new VLAN. The range for the VID value is 1 to 4094.

   The AT-S63 Management Software uses the next available VID number on the switch as the default value. If this VLAN is unique in your network, then its VID should also be unique. If this VLAN is part of a larger VLAN that spans multiple switches, than the VID value for the VLAN should be the same on each switch. For example, if you are creating a VLAN called Sales that spans three switches, you should assign the Sales VLAN on each switch the same VID value.

   Note
   A VLAN must have a VID.

   It is important to note that the switch is only aware of the VIDs of the VLANs that exist on the device, and not those that might already be in use in the network. For example, if you add a new AT-9400 Switch to a network that already contains VLANs that use VIDs 2 through 24, the AT-S63 Management Software still uses VID 2 as the default value when you create the first VLAN on the new switch, even though that VID number is already being used by another VLAN on the network. To prevent inadvertently using the same VID for two different VLANs, you should keep a list of all your network VLANs and their VID values.

8. Type **3** to toggle VLAN Type so that it displays Port Based, the default setting. This is the correct setting when creating a port-based or tagged VLAN.

Downloaded from www.Manualslib.com manuals search engine

Note
The MAC Based setting for option 3 is used to create MAC address-based VLANs. For instructions, refer to Chapter 28, "MAC Address-based VLANs" on page 533.

9. If the VLAN will contain tagged ports, type **4** to select Tagged Ports and specify the ports. If this VLAN will not contain any tagged ports, leave this field empty.

   You can specify the ports individually (e.g., 2,3,5), as a range (e.g., 7-9), or both (e.g., 2,5,7-9).

10. Type **5** to select Untagged Ports and specify the ports on the switch to function as untagged ports in the VLAN. If this VLAN will not contain any untagged ports, leave this field empty.

    You can specify the ports individually (e.g., 2,3,5), as a range (e.g., 7-9), or both (e.g., 2,5,7-9).

Note
Option 6, Protected Ports, in the Create VLAN menu is not used to create port-based or tagged VLANs. It should be left in the "No" default setting. This option is used to create protected ports VLANs, as explained in Chapter 27, "Protected Ports VLANs" on page 521.

11. Type **C** to select Create VLAN. The following message is displayed:

    ```
    SUCCESS - Press any key to continue.
    ```

    The AT-S63 Management Software creates the new port-based or tagged VLAN. The new VLAN is now ready for network use.

12. Press any key.

    The VLAN Configuration menu in Figure 171 on page 472 is redisplayed.

13. To verify that the VLAN was created correctly, type **6** to select Show VLANs.

14. Check to see that the VLAN contains the appropriate ports.

15. To permanently save your changes, return to the Main Menu and type **S** to select Save Configuration Changes.

16. Repeat this procedure to create additional VLANs.

Downloaded from www.Manualslib.com manuals search engine

Note
Untagged ports of a new VLAN are automatically removed from their current untagged VLAN assignment. For example, if you are creating a new VLAN on a switch that contains only the Default_VLAN, the untagged ports of the new VLAN are automatically removed from the Default_VLAN.

Note
Tagged ports are not removed from any current VLAN assignments because tagged ports can belong to more than one VLAN at a time.

Downloaded from www.Manualslib.com manuals search engine

Example of Creating a Port-based VLAN

This procedure is an example of how to create an untagged VLAN. The specifications of the VLAN are:

Name: Sales

VID: 2

Untagged ports, 1, 3 to 5

To create this VLAN, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.

   The VLAN Configuration menu is shown in Figure 171 on page 472.

2. From the VLAN Configuration menu, type **3** to select Configure VLANs.

   The Configure VLANs menu is shown in Figure 172 on page 473.

3. From the Configure VLANs menu, type **1** to select Create VLAN.

   The Create VLAN menu is shown in Figure 173 on page 473.

4. From the Create VLAN menu, type **1** to select VLAN Name and enter "Sales".

5. Type **2** to select VLAN ID (VID) and enter "2". This is the VID value for the new VLAN.

6. Type **3** to toggle VLAN Type to Port Based.

   Note
   Option 4, Tagged Ports, is left empty because this VLAN will not contain any tagged ports.

7. Type **5** to select Untagged Ports and enter "1,3-5". These are the untagged ports of the VLAN. Press Return.

   Note
   Option 6, Protected Ports, must be left in the "No" default setting when creating a port-based or tagged VLAN. This option is explained in Chapter 27, "Protected Ports VLANs" on page 521.

8. Type **C** to select Create VLAN.

9. When you see the confirmation prompt, press any key.

Downloaded from www.Manualslib.com manuals search engine

The new Sales VLAN has now been created.

Downloaded from www.Manualslib.com manuals search engine

Example of Creating a Tagged VLAN

This procedure is an example of how to create a tagged VLAN. The specifications of the example VLAN are:

Name: Engineering

VID: 3

Tagged ports: 2, 10

Untagged ports, 9, 11 to 13

To create the Engineering VLAN, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.

   The VLAN Configuration menu is shown in Figure 171 on page 472.

2. From the VLAN Configuration menu, type **3** to select Configure VLANs.

   The Configure VLANs menu is shown in Figure 172 on page 473.

3. From the Configure VLANs menu, type **1** to select Create VLAN.

   The Create VLAN menu is shown in Figure 173 on page 473.

4. From the Create VLAN menu, type **1** to select VLAN Name and enter "Engineering".

5. Type **2** to select VLAN ID (VID) and enter "3". This is the VID value for the new VLAN.

6. Type **3** to toggle VLAN Type to Port Based.

7. Type **4** to select Tagged Ports and enter "2,10". These are the tagged ports of the VLAN on the switch.

8. Type **5** to select Untagged Ports and enter "9,11-13". These are the untagged ports of the VLAN.

   Note
   Option 6, Protected Ports, must be left in the "No" default setting when creating a port-based or tagged VLAN. This option is explained in Chapter 27, "Protected Ports VLANs" on page 521.

9. Type **C** to select Create VLAN.

10. When you see the confirmation prompt, press any key.

Downloaded from www.Manualslib.com manuals search engine

The new Engineering VLAN has now been created.

Downloaded from www.Manualslib.com manuals search engine

Modifying a Port-based or Tagged VLAN

Note
To modify a VLAN, you need to know its VID. To view VLAN VIDs, refer to "Displaying VLANs" on page 485.

To modify a VLAN, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.

   The VLAN Configuration menu is shown in Figure 171 on page 472.

2. From the VLAN Configuration menu, type **3** to select Configure VLANs.

   The Configure VLANs menu is shown in Figure 172 on page 473.

3. From the Configure VLANs menu, type **2** to select Modify VLAN.

   The Modify VLAN menu is shown in Figure 174.

```
            Allied Telesis AT-9424T/SP - AT-S63
                          Marketing
User: Manager                              11:20:02 02-Mar-2005
                         Modify VLAN

1 - VLAN ID (VID) ........
2 - Change GARP VLAN
3 - Change MAC Associations

R - Return to Previous Menu

Enter your selection?
```

Figure 174. Modify VLAN Menu

Note
Selection 2, Change GARP VLAN, is described in Chapter 25, "GARP VLAN Registration Protocol" on page 495. Selection 3, Change MAC Associations, is explained in Chapter 28, "MAC Address-based VLANs" on page 533.

4. From the Modify VLAN menu, type **1** to select VLAN ID (VID).

   The following prompt is displayed:

   ```
   Enter new value -> [1 to 4096] ->
   ```


Downloaded from www.Manualslib.com manuals search engine

5. Enter the VID of the port-based or tagged VLAN you want to modify.

   The Modify VLAN menu expands to contain all relevant information about the VLAN, as shown in Figure 175.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                          11:20:02 02-Mar-2005
                         Modify VLAN

 1 - VLAN Name ............... Sales
 2 - VLAN ID (VID) ........... 3
 3 - VLAN Type ............... Port Based
 4 - Tagged Ports ............ 7,9
 5 - Untagged Ports .......... 20-24
 6 - Protected Ports ......... No

 M - Modify VLAN
 R - Return to Previous Menu

 Enter your selection?
```

Figure 175. Expanded Modify VLAN Menu

6. Adjust the following parameters as necessary.

   1 - VLAN Name
   This parameter changes the name of a VLAN. The name can be from one to fifteen alphanumeric characters in length. The name should reflect the function of the nodes that will be a part of the VLAN (for example, Sales or Accounting). The name cannot contain spaces or special characters, such as asterisks (*) or exclamation points (!).

   When you change a VLAN's name, observe the following guidelines:

   - A VLAN's new name cannot be the same as the name of another VLAN on the same switch. For example, if the switch already contains a VLAN called Sales, you cannot change an existing VLAN's name to Sales.
   - You cannot change the name of the Default_VLAN.

   Note
   A VLAN must have a name.

   2 - VLAN ID (VID)
   This is the VLAN's VID value. You cannot change this value.

   3 - VLAN Type
   VLAN type should be Port Based for a port-based or tagged VLAN. You cannot change this value.

Downloaded from www.Manualslib.com manuals search engine

4 - Tagged Ports
Use this selection to add or remove tagged ports from the VLAN. You can specify the ports individually (e.g., 2,3,5), as a range (e.g., 7-9), or both (e.g., 2,5,7-9).

When you add or remove tagged ports, observe the following guidelines:

- The new list of tagged ports will replace the existing tagged ports.
- If the VLAN contains tagged ports and you want to remove them all, enter 0 (zero) for this value.

5 - Untagged Ports
Use this selection to add or remove untagged ports from the VLAN. You can specify the ports individually (e.g., 2,3,5), as a range (e.g., 7-9), or both (e.g., 2,5,7-9).

When you add or remove untagged ports, observe the following guidelines:

- The new list of untagged ports will replace the existing untagged ports.
- If you want to remove all untagged ports from the VLAN, enter 0 (zero) for this value.
- You cannot change the name of the Default_VLAN, nor can you directly remove untagged ports from the Default_VLAN. Instead, you must assign the port as an untagged port to another VLAN.

An untagged port removed from a VLAN is automatically returned to the Default_VLAN as an untagged port.

Note
Selection 6, Protected Ports, should be left in the "No" default setting when modifying a port-based or tagged VLAN. This option is explained in Chapter 27, "Protected Ports VLANs" on page 521.

7. After making the desired changes, type **M** to select Modify VLAN.

   The following message is displayed:

```
SUCCESS
Please make sure to manually update any static
multicast MAC address(es) entries for this VLAN.
Press any key to continue...
```

   The VLAN has been modified and is now ready for network operations.

   Any untagged ports removed from a VLAN are automatically returned to the Default_VLAN as untagged ports.

Downloaded from www.Manualslib.com manuals search engine

If you added or removed from the VLAN a port with one or more static MAC addresses assigned to it, you must update the static addresses by deleting their entries from the MAC address table and reentering them again using the VID of the VLAN to which the port has been moved to. For information on how to add static MAC addresses, refer to “Adding Static Unicast and Multicast MAC Addresses” on page 110. For instructions on how to delete addresses, refer to “Deleting Unicast and Multicast MAC Addresses” on page 112.

8. Press any key.

   The Modify VLAN menu in Figure 174 on page 481 is displayed again.

9. Repeat this procedure starting with Step 4 to modify other VLANs.

10. To permanently save your changes, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Displaying VLANs

To view the name, VID number, and member ports of all the VLANs on a switch, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.

   The VLAN Configuration menu is shown in Figure 171 on page 472.

2. From the VLAN Configuration menu, type **4** to select Show VLANs.

   The Show VLANs menu is shown in Figure 176.

```
                Allied Telesis AT-9424T/SP - AT-S63
                             Marketing
User: Manager                                      11:20:02 02-Mar-2005
                             Show VLANs


VID   VLAN Name     VLAN Type      Protocol    Member Port(s)
-------------------------------------------------------------------

1     Default_VLAN  Port Based                 Untagged
                                                  Configured: 20-24
                                                  Actual: 20-24
                                               Tagged: 7,9
2     Sales         Port Based                 Untagged
                                                  Configured: 1-7
                                                  Actual: 1-7
                                               Tagged: 9
3     Production    Port Based                 Untagged
                                                  Configured: 8-19
                                                  Actual: 8-19
                                               Tagged: 7

U - Update Display
D - Detail Information Display
R - Return to Previous Menu

Enter your selection?
```

Figure 176. Show VLANs Menu

Note
Selection D, Detail Information Display, only applies to MAC address-based VLANs.

The Show VLANs menu displays a table that contains the following columns of information:

VID
The VLAN ID.

Downloaded from www.Manualslib.com manuals search engine

VLAN Name
Name of the VLAN.

VLAN Type
The VLAN type. The possible settings are:

Port Based - The VLAN is a port-based or tagged VLAN.

MAC Based - The VLAN is a MAC address-based VLAN.

Protected - The VLAN is a protected ports VLAN.

GARP - The VLAN was automatically created by GARP.

Protocol
The protocol associated with this VLAN. The possible settings are:

Blank - The VLAN is a port-based, tagged, or MAC address-based VLAN.

GARP - The VLAN is a dynamic GVRP VLAN or the port is a dynamic GVRP port of a static VLAN.

Member Port(s)
The untagged and tagged ports of a VLAN. (These fields are blank for a MAC address-based VLAN.) The untagged ports of a VLAN are listed as follows.

- Configured: The untagged ports assigned to the VLAN when the VLAN was created or modified.
- Actual: The current untagged ports of the VLAN. If you are not using 802.1x Port-based Network Access Control, both the Configured and Actual untagged ports of a VLAN will always be the same.

  If you are using 802.1x and you assigned a Guest VLAN to an authenticator port or you associated an 802.1x supplicant to a VLAN on the authentication server, it is possible for a port to be in different VLAN than the virtual LAN where it was originally assigned as an untagged port. In these situations, the Configured and Actual port lists can differ, with the Actual list detailing the ports that are currently functioning as untagged ports of the VLAN.

  For example, if a particular port is listed as a Configured member of a VLAN, but not as an Actual member, that would mean either the port is currently a part of a Guest VLAN or the supplicant who logged on the port was associated with a VLAN assignment on the authentication server.

Downloaded from www.Manualslib.com manuals search engine

Deleting a Port-based or Tagged VLAN

This procedure deletes port-based and tagged VLANs from the switch. Note the following before performing this procedure:

- You cannot delete the Default_VLAN.
- You cannot delete a VLAN if it has a routing interface. The interface must be deleted first. For instructions, refer to "Deleting a Routing Interface" on page 554.
- All untagged ports in a deleted VLAN are returned to the Default_VLAN as untagged ports.
- Static addresses assigned to the ports of a deleted VLAN become obsolete and should be deleted from the MAC address table. For instructions, refer to "Deleting Unicast and Multicast MAC Addresses" on page 112.

Note
To delete a VLAN, you need to know its VID. To view VLAN VIDs, refer to "Displaying VLANs" on page 485.

To delete a VLAN, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.

   The VLAN Configuration menu is shown in Figure 171 on page 472.

2. From the VLAN Configuration menu, type **3** to select Configure VLANs.

   The Configure VLANs menu is shown in Figure 172 on page 473.

3. From the Configure VLANs menu, type **3** to select Delete VLAN.

   The Delete VLAN menu is shown in Figure 177.

```
            Allied Telesis AT-9424T/SP - AT-S63
                         Marketing
User: Manager                              11:20:02 02-Mar-2005
                          Delete VLAN

1 - VLAN ID (VID) ........

R - Return to Previous Menu

Enter your selection?
```

Figure 177. Delete VLAN Menu

Downloaded from www.Manualslib.com manuals search engine

4. From the Delete VLAN menu, type **1** to select VLAN ID (VID).

   The following prompt is displayed:

   ```
   Enter new value -> [2 to 4094] ->
   ```

5. Enter the VID of the VLAN you want to delete. You can specify only one VID at a time.

   Note
   You cannot delete the Default_VLAN, which has a VID of 1.

   The Delete VLAN menu expands to contain all relevant information about the VLAN, as shown in Figure 178. You can use this menu to confirm that you are deleting the correct VLAN.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                      Delete VLAN

1 - VLAN Name ............... Sales
2 - VLAN ID (VID) ........... 3
3 - VLAN Type ............... Port Based
4 - Tagged Ports ............ 7,9
5 - Untagged Ports .......... 20-24
6 - Protected Ports ......... No

D - Delete VLAN
R - Return to Previous Menu

Enter your selection?
```

Figure 178. Expanded Delete VLAN Menu

6. Type **D** to delete the VLAN or **R** to cancel the procedure.

   If you select to delete the VLAN, the following confirmation prompt is displayed:

   ```
   Are you sure you want to delete this VLAN [Yes/No] ->
   ```

7. Type **Y** to delete the VLAN or **N** to cancel the procedure. Press Return.

   If you select Yes, the VLAN is deleted and the following message is displayed:

   ```
   SUCCESS
   Please make sure to manually delete any static multicast
   MAC address(es) entries for this VLAN
   Press any key to continue ...
   ```


Downloaded from www.Manualslib.com manuals search engine

8. Press any key.
9. Repeat this procedure starting with Step 4 to delete other VLANs.
10. To permanently save your changes, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Deleting All VLANs

The following procedure deletes all port-based, tagged, protected ports, and MAC address-based VLANs on a switch. To delete selected VLANs, perform the procedure in “Deleting a Port-based or Tagged VLAN” on page 487.

Note the following before performing this procedure:

- You cannot delete the Default_VLAN.
- You cannot delete a VLAN if it has a routing interface. The interface must be deleted first. For instructions, refer to “Deleting a Routing Interface” on page 554.
- All ports on the switch are returned to the Default_VLAN as untagged ports.
- Static addresses assigned to the ports of the deleted VLANs become obsolete and should be deleted from the MAC address table. For instructions, refer to “Deleting Unicast and Multicast MAC Addresses” on page 112.

To return all ports to the default VLAN, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.

   The VLAN Configuration menu is shown in Figure 171 on page 472.

2. From the VLAN Configuration menu, type **3** to select Configure VLANs.

   The Configure VLANs menu is shown in Figure 172 on page 473.

3. From the Configure VLANs menu, type **4** to select Reset to Default VLAN.

   The following prompt is displayed:

   ```
   This operation deletes ALL user created VLANs!
   Do you want to continue [Yes/No] ->
   ```

4. Type **Y** to delete all VLANs or **N** to cancel the procedure. Press Return.

   If you select Yes, all VLANs are deleted and the following message is displayed:

   ```
   SUCCESS
   Please make sure to manually update any static
   multicast MAC address(es) entries.
   Press any key to continue...
   ```

   All tagged and untagged ports are returned to the Default_VLAN as untagged ports.

Downloaded from www.Manualslib.com manuals search engine

Any static addresses assigned to the ports of the VLANs are now obsolete, except for the Default_VLAN, because the VLANs have been deleted. Those addresses should be deleted from the MAC address table. For instructions on how to delete addresses, refer to "Deleting All Dynamic MAC Addresses" on page 113.

5. Press any key.

6. To permanently save your changes, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Displaying PVIDs

The following procedure displays a menu that lists the PVIDs for all the ports on the switch.

To display the PVID settings on the switch, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.

   The VLAN Configuration menu is shown in Figure 171 on page 472.

2. From the VLAN Configuration menu, type **5** to select Show PVIDs.

   The Show PVIDs menu is shown in Figure 179.

```
            Allied Telesis AT-9424T/SP - AT-S63
                          Marketing
User: Manager                              11:20:02 02-Mar-2005
                         Show PVIDs

Port    PVID
-----------------------------------------------------------
01      22
02      22
03      1
04      1
05      1
06      1
07      24
08      24

N - Next Page
U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 179. Show PVIDs Menu

The PVID column displays the current PVID value for each switch port.

Downloaded from www.Manualslib.com manuals search engine

Enabling or Disabling Ingress Filtering

There are rules a switch follows when it receives and forwards an Ethernet frame. There are rules for frames as they enter a port (called *ingress rules*) and rules for when a frame is transmitted out a port (called *egress rules*). A switch does not accept and forward a frame unless the frame passes the ingress and egress rules.

There are many ingress and egress rules for Gigabit Ethernet switches. This discussion reviews only the rules as they apply to tagged frames, because ingress filtering does not apply to untagged frames.

First, as a reminder, a tagged frame is an Ethernet frame that contains a tagged header. The header contains the VID of the VLAN to which the frame originated.

The ingress rules are applied to tagged frames when ingress filtering is activated. The switch examines the tagged header of each tagged frame that enters a port and determines whether the tagged frame and the port that received the frame are members of the same VLAN. If they belong to the same VLAN, the port accepts the frame. If they belong to different VLANs, the port discards the frame.

As an example, assume that a tagged frame with a VID of 4 is received on a port that is a member of a VLAN also with a VID of 4. In this case, the port accepts the frame, because both the frame and the port belong to the same VLAN. If the frame and port belong to different VLANs, the frame is discarded.

How do the egress rules apply when ingress filtering is disabled? First, any tagged frame is accepted on any port on the switch. It does not matter whether the frame and the port belong to the same or different VLANs.

After the tagged frame is received, the switch examines the tagged header and determines if the VID in the header corresponds to any VLANs on the switch. If there is no corresponding VLAN, the switch discards the frame. If there is, the switch transmits the frame out the port to the destination node, assuming that the destination node's MAC address is in the MAC address table, or floods the port to all ports on the VLAN if the MAC address is not in the table.

In addition, each tagged frame contains a priority tag that informs the switch about the importance of the frame. Frames with a high priority are handled ahead of frames with a low priority.

Activating or deactivating ingress filtering has no effect on the switch's handling of priority tags. A switch will always examines a priority tag in a tagged frame, without regard to the status of ingress filtering.

Downloaded from www.Manualslib.com manuals search engine

In most cases, you will probably want to leave ingress filtering activated on the switch, which is the default. You can enable or disable ingress filtering on a per switch basis. You cannot set this per port.

To enable or disable ingress filtering, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.

   The VLAN Configuration menu is shown in Figure 171 on page 472.

2. From the VLAN Configuration menu, type **1** to select Ingress Filtering Status.

   The following prompt is displayed:

   ```
   Enter Ingress Filtering Status (E-Enable, D-Disable) ->
   ```

3. Type **E** to activate ingress filtering or **D** to disable the feature on the switch.

   A change to the status of ingress filtering is immediately activated on the switch.

4. To permanently save your changes, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Chapter 25

GARP VLAN Registration Protocol

This chapter describes the GARP VLAN Registration Protocol (GVRP) and contains the following sections:

- ❒ “Configuring GVRP” on page 496
- ❒ “Enabling or Disabling GVRP on a Port” on page 498
- ❒ “Converting a Dynamic GVRP VLAN” on page 500
- ❒ “Displaying the GVRP Port Configuration” on page 501
- ❒ “Displaying GVRP Counters” on page 502
- ❒ “Displaying the GVRP Database” on page 507
- ❒ “Displaying the GIP Connected Ports Ring” on page 509
- ❒ “Displaying the GVRP State Machine” on page 511

Downloaded from www.Manualslib.com manuals search engine

Configuring GVRP

To configure GVRP, perform the following procedure:

> **Note**
> The timers in the following menus are in increments of centi seconds which is one hundredth of a second.

To configure GVRP, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.

   The VLAN Configuration menu is shown in Figure 171 on page 472.

2. From the VLAN Configuration menu, type **6** to select Configure GARP-GVRP.

   The GARP-GVRP menu is shown in Figure 180.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing

User: Manager                          11:20:02 02-Mar-2005

                          GARP-GVRP

1 - GVRP Status ............ Disabled
2 - GVRP GIP Status ........ Enabled
3 - GVRP Join Timer ........ 20
4 - GVRP Leave Timer ....... 60
5 - GVRP Leave All Timer .. 1000

P - GVRP Port Parameters
O - Other GVRP Parameters
D - Reset GVRP to Defaults

R - Return to Previous Menu

Enter your selection?
```

Figure 180. GARP-GVRP Menu

> **Note**
> Selection 8, Configure GARP-GVRP, is not shown in the VLAN Configuration menu when the VLAN mode is multiple VLANs.

3. From the GARP-GVRP menu, type **1** to select GVRP Status.

   The following prompt is displayed:

   ```
   Enter your new value (E-Enabled, D-Disabled):
   ```


Downloaded from www.Manualslib.com manuals search engine

4. Type **E** to enable GVRP or **D** to disable GVRP. The default setting is disabled.

5. Type **2** to select GVRP GIP Status.

   The following prompt is displayed:

   ```
   Enter your new value (E-Enabled, D-Disabled):
   ```

6. Type **E** to enable GIP or **D** to disable GIP.

   Note
   Do not disable GIP if you intend to use GVRP. GIP is required to propagate VLAN information among the ports of the switch.

   Caution
   The following steps change the three GVRP timers. Please note that the settings for these timers must be the same on all GVRP-active network devices.

7. Type **3** to select GVRP Join Timer.

   The following prompt is displayed:

   ```
   Enter new value (in centi seconds): [10 to 60] -> 20
   ```

8. Enter a new value for the Join Timer field in centi seconds which are one hundredths of a second. The default is 20 centiseconds.

   If you change this field, it must be in relation to the GVRP Leave Timer according to the following equation:

   Join Timer <= (2 x (GVRP Leave Timer))

9. Type **4** to select GVRP Leave Timer.

   The following prompt is displayed:

   ```
   Enter new value (in centi seconds): [30 to 180] -> 60
   ```

10. Type **5** to select GVRP Leave All Timer. The default is 60 centiseconds.

    The following prompt is displayed:

    ```
    Enter new value (in centi seconds): [500 to 3000] -> 1000
    ```

11. Enter a value in centiseconds. The default is 1000 centiseconds.

12. To permanently save your changes, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Enabling or Disabling GVRP on a Port

This procedure enables and disables GVRP on a switch port. The default setting for GVRP on a port is enabled. Only those ports where GVRP is enabled transmit PDUs.

> **Note**
> Allied Telesis recommends disabling GVRP on unused ports and those ports connected to GVRP-inactive devices for protection against unauthorized access to restricted areas of your network.

To enable or disable GVRP on a port, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.

   The VLAN Configuration menu is shown in Figure 171 on page 472.

2. From the VLAN Configuration menu, type **6** to select Configure GARP-GVRP.

   The GARP-GVRP menu is shown in Figure 180 on page 496.

3. From the GARP-GVRP menu, type **P** to select GVRP Port Parameters.

   The GVRP Port Parameters menu is shown in Figure 181.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing

User: Manager                              11:20:02 02-Mar-2005

                     GVRP Port Parameters

1 - Configure GVRP Port Settings
2 - Display GVRP Port Configuration

R - Return to Previous Menu

Enter your selection?
```

Figure 181. GVRP Port Parameters Menu

4. From the GVRP Port Parameters menu, type **1** to select Configure GVRP Port Settings.

Downloaded from www.Manualslib.com manuals search engine

The following prompt is displayed:

```
Enter port-list:
```

5. Enter a port or a list of ports.

   The Configure GVRP Port Settings menu is shown in Figure 182.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing

User: Manager                            11:20:02 02-Mar-2005

                Configure GVRP Port Settings

Configuring Port 1-8
1 - Port Mode ............. Normal

R - Return to Previous Menu

Enter your selection?
```

Figure 182. Configure GVRP Port Settings Menu

6. Type **1** to select Port Mode.

   The following prompt is displayed:

   ```
   Enter mode (0-Normal, 1-None): [0 to 1] -> 0
   ```

7. Type **0** to select Normal or **1** to select None. A setting of Normal means the port processes and propagates GVRP information. This is the default setting. A setting of None prevents the port from processing GVRP information and from transmitting PDUs.

8. To permanently save your changes, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Converting a Dynamic GVRP VLAN

This procedure converts a dynamic GVRP VLAN into a static VLAN. You can perform this procedure to permanently retain the VLANs the switch learned through GVRP.

> **Note**
> This procedure cannot convert a dynamic GVRP port in a static VLAN into a static port. For that you must manually modify the static VLAN by specifying the dynamic port as either a tagged or untagged member of the VLAN.

To convert a dynamic GVRP VLAN to a static VLAN, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.

   The VLAN Configuration menu is shown in Figure 171 on page 472.

2. From the VLAN Configuration menu, type **4** to select Configure VLANs.

   > **Note**
   > If selection 4, Configure VLANs, is not displayed in the menu, the switch is running a multiple VLAN mode. To change a switch's VLAN mode, refer to "Selecting a VLAN Mode" on page 516.

   The Configure VLAN menu is shown in Figure 172 on page 473.

3. From the Configure VLAN menu, type **2** to select Modify VLAN.

   The Modify VLAN menu is shown in Figure 174 on page 481.

4. From the Modify VLAN menu, type **2** to select Change GARP VLAN.

   The following prompt is displayed:

   ```
   Enter VLAN ID: [1 to 4096] ->
   ```

5. Enter the VID of the dynamic GVRP VLAN you want to convert into a static VLAN. You can specify only one GVRP VLAN at a time.

   The dynamic GVRP VLAN is changed to a static VLAN. To confirm this, refer to "Displaying VLANs" on page 485.

6. To permanently save your changes, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Displaying the GVRP Port Configuration

To display the GVRP port configuration, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.

   The VLAN Configuration menu is shown in Figure 171 on page 472.

2. From the VLAN Configuration menu, type **6** to select Configure GARP-GVRP.

   The GARP-GVRP menu is shown in Figure 180 on page 496.

3. From the GVRP Port Parameters menu, type **2** to select Display GVRP Port Configuration.

   The Display GVRP Port Configuration menu is shown in Figure 183.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing

User: Manager                              11:20:02 02-Mar-2005

                Display GVRP Port Configuration

GARP Port Parameters
Mode Normal ............. 1-8
Mode None ............... 12,15,21

U - Update
R - Return to Previous Menu

Enter your selection?
```

Figure 183. Display GVRP Port Configuration Menu

The Display GVRP Port Configuration menu provides the following information:

Mode Normal
A list of ports that process and propagate GVRP information.

Mode None
A list of ports that do not process GVRP information or transmit PDUs.

Downloaded from www.Manualslib.com manuals search engine

Displaying GVRP Counters

To display GVRP counters, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.

   The VLAN Configuration menu is shown in Figure 171 on page 472.

2. From the VLAN Configuration menu, type **6** to select Configure GARP-GVRP.

   The GARP-GVRP menu is shown in Figure 180 on page 496.

3. From the GARP-GVRP menu, type **O** to select Other GVRP Parameters.

   The Other GVRP Parameters menu is shown in Figure 184.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing

User: Manager                              11:20:02 02-Mar-2005

                    Other GVRP Parameters

1 - Display GVRP Counters
2 - Display GVRP Database
3 - Display GIP Connected Ports Ring
4 - Display GVRP State Machine

R - Return to Previous Menu

Enter your selection?
```

Figure 184. Other GVRP Parameters Menu

4. From the Other GARP Port Parameters menu, type 1 to select Display GVRP Counters.

Downloaded from www.Manualslib.com manuals search engine

The GVRP Counters menu (page 1) is shown in Figure 185.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing

User: Manager                            11:20:02 02-Mar-2005

                        GVRP Counters

Receive:                      Transmit:
--------                      ---------
Total GARP Packets    41      Total GARP Packets  166
Invalid GARP Packets  0


Discarded:
-----------
GARP Disabled         0       GARP Disabled       0
Port Not Listening    0       Port Not Sending    3117
Invalid Port          0
Invalid Protocol      0
Invalid Format        0
Database Full         0

N - Next Page
U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 185. GVRP Counters Menu (page 1)

The statistics span two menus. To display the second menu, type **N** to select Next Page. The second menu is shown in Figure 186. The information in both menus is for display purposes only.

Downloaded from www.Manualslib.com manuals search engine

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing

User: Manager                            11:20:02 02-Mar-2005

                        GVRP Counters

Receive:                          Transmit:
--------                          ---------
GARP Messages:
---------------
LeaveAll            7             LeaveAll        77
JoinEmpty           0             JoinEmpty       58
JoinIn              68            JoinIn          285
LeaveEmpty          0             LeaveEmpty      1
LeaveIn             0             LeaveIn         0
Empty               5             Empty           21
Bad Message         0
Bad Attribute       0

P - Previous Page
U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 186. GVRP Counters Menu (page 2)

The GVRP counters in the menus are described in Table 15.

Table 15. GVRP Counters

Parameter	Meaning
Receive: Total GARP Packets	Total number of GARP PDUs received by this GARP application.
Transmit: Total GARP Packets	Total number of GARP PDUs transmitted by this GARP application.
Receive: Invalid GARP Packets	Number of invalid GARP PDUs received by this GARP application.
Receive Discarded: GARP Disabled	Number of received GARP PDUs discarded because the GARP application was disabled.
Transmit Discarded: GARP Disabled	Number of GARP PDUs discarded because the GARP application was disabled. This counter is incremented when ports are added to or deleted from the GARP application arising from port movements in the underlying VLAN or STP.

Downloaded from www.Manualslib.com manuals search engine

Table 15. GVRP Counters (Continued)

Parameter	Meaning
Receive Discarded: Port Not Listening	Number of GARP PDUs discarded because the port that received the PDUs was not listening, that is, MODE=NONE was set on the port.
Transmit Discarded: Port Not Sending	Number of GARP PDUs discarded because the port that the PDUs were to be transmitted on was not sending, that is, MODE=NONE was set on the port.
Receive Discarded: Invalid Port	Number of GARP PDUs discarded because the port that received the PDU does not belong to the GARP application.
Receive Discarded: Invalid Protocol	Number of GARP PDUs discarded because the GARP PDU contained an invalid protocol.
Receive Discarded: Invalid Format	Number of GARP PDUs discarded because the format of the GARP PDU was not recognized.
Receive Discarded: Database Full	Number of GARP PDUs discarded because the database for the GARP application was full, that is, the maximum number of attributes for the GARP application is in use.
Receive GARP Messages: LeaveAll	Number of GARP LeaveAll messages received by the GARP application.
Transmit: GARP Messages: LeaveAll	Number of GARP LeaveAll messages transmitted by the GARP application.
Receive GARP Messages: JoinEmpty	Total number of GARP JoinEmpty messages received for all attributes in the GARP application.
Transmit GARP Messages: JoinEmpty	Total number of GARP JoinEmpty messages transmitted for all attributes in the GARP application.
Receive GARP Messages: JoinIn	Total number of GARP JoinIn messages received for all attributes in the GARP application.
Transmit GARP Messages: JoinIn	Total number of GARP JoinIn messages transmitted for all attributes in the GARP application.
Receive GARP Messages: LeaveEmpty	Total number of GARP LeaveEmpty messages received for all attributes in the GARP application.

Downloaded from www.Manualslib.com manuals search engine

Table 15. GVRP Counters (Continued)

Parameter	Meaning
Transmit GARP Messages: LeaveEmpty	Total number of GARP LeaveEmpty messages transmitted for all attributes in the GARP application.
Receive GARP Messages: LeaveIn	Total number of GARP LeaveIn messages received for all attributes in the GARP application.
Transmit GARP Messages: LeaveIn	Total number of GARP LeaveIn messages transmitted for all attributes in the GARP application.
Receive GARP Messages: Empty	Total number of GARP Empty messages received for all attributes in the GARP application.
Transmit GARP Messages: Empty	Total number of GARP Empty messages transmitted for all attributes in the GARP application.
Receive GARP Messages: Bad Message	Number of GARP messages that had an invalid Attribute Type value, an invalid Attribute Length value or an invalid Attribute Event value.
Receive GARP Messages: Bad Attribute	Number of GARP messages that had an invalid Attribute Value value.

Downloaded from www.Manualslib.com manuals search engine

Displaying the GVRP Database

To display GVRP database, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.

   The VLAN Configuration menu is shown in Figure 171 on page 472.

2. From the VLAN Configuration menu, type **6** to select Configure GARP-GVRP.

   The GARP-GVRP menu is shown in Figure 180 on page 496.

3. From the GARP-GVRP menu, type **O** to select Other GVRP Parameters menu.

   The Other GARP Port Parameters menu is shown in Figure 184 on page 502.

4. From the Other GARP Port Parameters menu, type **2** to select Display GVRP Database

   The GVRP Database menu is shown in Figure 187.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing

User: Manager                              11:20:02 02-Mar-2005

                          GVRP Database

GARP Application: GVRP
GID index   VLAN ID  Used  GID index   VLAN ID   Used
------------------------ ------------------------------
0           1        Yes   1           3         Yes
2           2        Yes

U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 187. GVRP Database Menu

The GVRP Database menu displays a table that contains the following columns of information:

GARP Application
Identifies the GARP application, that is, "GVRP".

GID index
Value of the GID index corresponding to the attribute. GID indexes

Downloaded from www.Manualslib.com manuals search engine

begin at 0. If the GARP application has no attributes presently registered, “No attributes have been registered” is displayed.

VLAN ID
The VLAN ID.

Used
Indicates whether the GID index is currently being used by any port in the GARP application. The definition of “used” is whether the Applicant and Registrar state machine for the GID index are in a non-initialized state, that is, not in {Vo, Mt} state. The value of this parameter is either “Yes” or “No”.

Downloaded from www.Manualslib.com manuals search engine

Displaying the GIP Connected Ports Ring

To display the GIP connected ports ring, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.

   The VLAN Configuration menu is shown in Figure 171 on page 472.

2. From the VLAN Configuration menu, type **6** to select Configure GARP-GVRP.

   The GARP-GVRP menu is shown in Figure 180 on page 496.

3. From the GARP-GVRP menu, type **O** to select Other GVRP Parameters menu.

   The Other GARP Parameters menu is shown in Figure 184 on page 502.

4. From the Other GARP Port Parameters menu, type **3** to select Display GIP Connected Ports Ring.

   The GIP Connected Ports Ring menu is shown in Figure 188.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing

User: Manager                           11:20:02 02-Mar-2005

                    GIP Connected Ports Ring

GARP Application: GVRP
GIP Context ID: 0, STP ID: 0
-------------------------------------------------------

4 -> 12 -> 18

U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 188. GIP Connected Ports Ring Menu

The GIP Connected Ports Ring menu displays the following information:

GARP Application
Identifies the GARP application, that is, "GVRP."

GIP Context ID
A number assigned to the instance for the GIP context.

Downloaded from www.Manualslib.com manuals search engine

STP ID
Present if the GARP application is GVRP; identifies the spanning tree instance associated with the GIP context.

Connected Ring
The ring of connected ports. Only ports presently in the spanning tree Forwarding state are eligible for membership in the GIP connected ring. If no ports exist in the GIP connected ring, “No ports are connected” is displayed. If the GARP application has no ports, “No ports have been assigned” is displayed.

Downloaded from www.Manualslib.com manuals search engine

Displaying the GVRP State Machine

To display the GVRP state machine, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.

   The VLAN Configuration menu is shown in Figure 171 on page 472.

2. From the VLAN Configuration menu, type **6** to select Configure GARP-GVRP.

   The GARP-GVRP menu is shown in Figure 180 on page 496.

3. From the GARP-GVRP menu, type **O** to select Other GVRP Parameters menu.

   The Other GVRP Parameters menu is shown in Figure 184 on page 502.

4. From the Other GVRP Parameters menu, type **4** to Display GVRP State Machine.

   The GVRP State Machine menu (page 1) is shown in Figure 189.

```
                Allied Telesis AT-9424T/SP - AT-S63
                             Marketing

User: Manager                                      11:20:02 02-Mar-2005

                          GVRP State Machine

Enter a VLAN ID for displaying the state machine: [1 to 4094] -> 1
```

Figure 189. GVRP State Machine Menu (page 1)

5. Enter a VLAN ID.

Downloaded from www.Manualslib.com manuals search engine

The GVRP State Machine menu (page 2) is displayed, as shown in Figure 190.

```
                Allied Telesis AT-9424T/SP - AT-S63
                          Marketing

User: Manager                                    11:20:02 02-Mar-2005

                          GVRP State Machine

State Machine for VLAN: 1
 Port  App   Reg  | Port  App Reg  | Port App  Reg  | Port  App  Reg |
-------------------------------------------------------------------
 1     Aa    Fix  | 2     Aa  Fix  | 3    Vo   Mt   | 4     Vo   Fix |
 5     VO    Fix  | 6     Vo  Fix  | 7    VO   Mt   | 8     Vo   Fix |
 9     Vo    Fix  | 10    Vo  Fix  | 11   Vo   Mt   | 12    Vo   Fix |
 13    Vo    Fix  | 14    Vo  Fix  | 15   Vo   Mt   | 16    Vo   Fix |
 17    Aa    Fix  | 18    Vo  Fix  | 19   Vo   Mt   | 20    Vo   Fix |
 21    Vo    Mt   | 22    Vo  Mt   | 23   Aa   FIx  | 24    Aa   Fix |
-------------------------------------------------------------------

U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 190. Display GVRP State Machine Menu (page 2)

The information in the menu is defined in Table 16. This information is for viewing purposes only.

Table 16. GVRP State Machine Parameters

Parameter	Meaning
Port	Port number on the switch; this port belongs to the GARP application. If the GARP application has no ports, “No ports have been assigned” is displayed.

Downloaded from www.Manualslib.com manuals search engine

Table 16. GVRP State Machine Parameters (Continued)

Parameter	Meaning
App	Applicant state machine for the GID index on that particular port. One of:
	Normal Participant Management state:
	"Vo" Very Anxious Observer
	"Ao" Anxious Observer
	"Qo" Quiet Observer
	"Lo" Leaving Observer
	"Vp" Very Anxious Passive Member
	"Ap" Anxious Passive Member
	"Qp" Quiet Passive Member
	"Va" Very Anxious Active Member
	"Aa" Anxious Active Member
	"Qa" Quiet Active Member
	"La" Leaving Active Member
App (*Continued*)	*Non-Participant Management state:*
	"Von" Very Anxious Observer
	"Aon" Anxious Observer
	"Qon" Quiet Observer
	"Lon" Leaving Observer
	"Vpn" Very Anxious Passive Member
	"Apn" Anxious Passive Member
	"Qpn" Quiet Passive Member
	"Van" Very Anxious Active Member
	"Aan" Anxious Active Member
	"Qan" Quiet Active Member
	"Lan" Leaving Active Member
	The initialized state for the Applicant is Vo.

Downloaded from www.Manualslib.com manuals search engine

Table 16. GVRP State Machine Parameters (Continued)

Parameter	Meaning	
Reg	Registrar state machine for the GID index on that particular port. One of:	
	“Mt”	Empty
	“Lv3”	Leaving substate 3 (final Leaving substate)
	“Lv2”	Leaving substate 2
	“Lv1”	Leaving substate 1
	“Lv”	Leaving substate (initial Leaving substate)
	“In”	In
	“Fix”	Registration Fixed
	“For”	Registration Forbidden
	The initialized state for the Registrar is Mt.	

Downloaded from www.Manualslib.com manuals search engine

Chapter 26

Multiple VLAN Modes

This chapter contains the following sections:

- “Selecting a VLAN Mode” on page 516
- “Displaying VLAN Information” on page 518

Downloaded from www.Manualslib.com manuals search engine

Selecting a VLAN Mode

The following procedure explains how to select a VLAN mode. Available modes are:

- ❒ User-configured VLAN mode (port-based, tagged, MAC address-based, and protected ports VLANs)
- ❒ IEEE 802.1Q Compliant Multiple VLAN mode
- ❒ Non-IEEE 802.1Q Compliant Multiple VLAN mode

Note
All current VLANs on the switch are delete when the VLAN mode is changed from the user-configured mode to a multiple VLAN mode and, at some point, the switch is reset. The VLANs must be recreated if you later return the switch to the user- configured VLAN mode.

To select a VLAN mode, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.

   The VLAN Configuration menu is shown in Figure 171 on page 472.

2. From the VLAN Configuration menu, type **2** to select VLANs Mode.

   The following prompt is displayed:

   ```
   Enter VLAN Mode (U-UserConfig, M-Multiple, Q-802.1Q
   Multiple VLANs) ->
   ```

3. Select one of the following VLAN modes:

   Q - 802.1Q Multiple VLAN mode

   M - Non-802.1Q compliant multiple VLAN mode

   U - User-configured VLAN mode. Supports port-based, tagged, MAC address-based, and protected ports VLANs. This is the default setting.

   If you enter **Q** or **M**, the following prompt is displayed:

   ```
   Enter Uplink VLAN Port number -> [1 to 24] ->
   ```

4. Enter the port number on the switch that will function as the uplink port for the other ports. You can specify only one port.

   The following prompt is displayed:

   ```
   SUCCESS
   Press any key to continue ...
   ```


Downloaded from www.Manualslib.com manuals search engine

The new VLAN mode is now active on the switch.

5. To permanently save your changes, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Displaying VLAN Information

To view the VLANs on the switch while the unit is operating in a multiple VLAN mode, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.

   The VLAN Configuration menu (multiple VLAN mode) is shown in Figure 191.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                              11:20:02 02-Mar-2005
                     VLAN Configuration

1 - Ingress Filtering Status ........ Enabled
2 - VLANs Mode ...................... Multiple VLANs
3 - Management VLAN ................. 1 (Default_VLAN)
4 - Configure VLANs
5 - Show Multiple VLANs
6 - Show PVIDs

R - Return to Previous Menu

 Enter your selection?
```

Figure 191. VLAN Configuration Menu (Multiple VLAN Mode)

2. From the VLAN Configuration menu, type **5** to select Show Multiple VLANs.

Downloaded from www.Manualslib.com manuals search engine

The Show Multiple VLANs menu is shown in Figure 192.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing

User: Manager                          11:20:02 02-Mar-2005

                    Show Multiple VLANs

Name         Untagged Port   Uplink Port   VLAN ID
-------------------------------------------------------
Client_1     1               24            1
Client_2     1               24            1
Client_3     1               24            1
Client_4     1               24            1
Client_5     1               24            1
Client_6     1               24            1
Client_7     1               24            1
Client_8     1               24            1

N - Next Page
U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 192. Show VLANs Menu, Multiple VLANS

The Show Multiple VLANs menu displays a table that contains the following columns of information:

Name
Name of the VLAN.

Untagged Port
The untagged ports that are part of the VLAN.

Uplink Port
The uplink port for the VLAN.

VLAN ID
The VLAN ID.

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Chapter 27

Protected Ports VLANs

This chapter explains protected ports VLANs. It contains the following sections:

- ❒ “Creating a Protected Ports VLAN” on page 522
- ❒ “Modifying a Protected Ports VLAN” on page 525
- ❒ “Displaying a Protected Ports VLAN” on page 528
- ❒ “Deleting a Protected Ports VLAN” on page 530

Downloaded from www.Manualslib.com manuals search engine

Creating a Protected Ports VLAN

To create a new protected ports VLAN, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.
2. From the VLAN Configuration menu, type **3** to select Configure VLANs.
3. From the Configure VLANs menu, type **1** to select Create VLAN.

   The Create VLAN menu is shown in Figure 193.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                            11:20:02 02-Mar-2005
                          Create VLAN

1 - VLAN Name .............
2 - VLAN ID (VID) ........ 2
3 - VLAN Type ............. Port Based
4 - Tagged Ports .........
5 - Untagged Ports .......
6 - Protected Ports ...... No

C - Create VLAN
R - Return to Previous Menu

Enter your selection?
```

Figure 193. Create VLAN Menu

Note
The appropriate setting for Option 3, VLAN Type, for a protected ports VLAN is the default setting, Port Based.

4. Type **1** to select VLAN Name.

   The following prompt is displayed:

   ```
   Enter new value ->
   ```

5. Type a name for the new protected ports VLAN.

   The name can be from one to fifteen alphanumeric characters in length. The name should reflect the function of the nodes that will be a part of the protected ports VLAN (for example, InternetGroups). The name cannot contain spaces or special characters, such as asterisks (*) or exclamation points (!).

Downloaded from www.Manualslib.com manuals search engine

Note
A VLAN must be assigned a name.

6. Type **2** to select VLAN ID (VID.

   The following prompt is displayed:

   ```
   Enter new value -> [2 to 4094] ->
   ```

7. Type a VID value for the new VLAN. The range for the VID value is 1 to 4094.

   The AT-S63 Management Software uses the next available VID number on the switch as the default value. It is important to note that the switch is only aware of the VIDs of the VLANs that exist on the device, and not those that might already be in use in the network. For example, if you add a new AT-9400 Switch to a network that already contains VLANs that use VIDs 2 through 24, the AT-S63 Management Software still uses VID 2 as the default value when you create the first VLAN on the new switch, even though that VID number is already being used by another VLAN on the network. To prevent inadvertently using the same VID for two different VLANs, you should keep a list of all your network VLANs and their VID values.

   Note
   A VLAN must have a VID.

8. If the VLAN will contain tagged ports, type **4** to select Tagged Ports and specify the ports. You can specify the ports individually (e.g., 2,3,5), as a range (e.g., 7-9), or both (e.g., 2,5,7-9). If this VLAN will not contain any tagged ports, leave this field empty.

9. Type **5** to select Untagged Ports and specify the ports on the switch to function as untagged ports in the VLAN. You can specify the ports individually (e.g., 2,3,5), as a range (e.g., 7-9), or both (e.g., 2,5,7-9). If this VLAN will not contain any untagged ports, leave this field empty.

10. Type **6** to select Protected Ports**.**

    The following prompt is displayed:

    ```
    Enter New Value [Yes/No] ->
    ```

11. To make this a protected ports VLAN, type **Y**.

12. Type **C** to select Create VLAN**.**

    The following prompt is displayed:

    ```
    Enter Uplink Ports (4 - 12) ->
    ```


Downloaded from www.Manualslib.com manuals search engine

The prompt displays the ports of the VLAN.

13. Enter the port in the VLAN to function as the uplink port for the groups in the VLAN. You can specify more than one uplink port.

    The following prompt is displayed:

    ```
    Enter Group Ports (4 - 11) ->
    ```

    The prompt includes the ports in the VLAN, minus the uplink port specified in the previous step.

14. Specify the ports of one of the groups of the protected ports VLAN. This can be a few as one port or as many as all the remaining ports of the VLAN. You can specify the ports individually (e.g., 2,3,5), as a range (e.g., 7-9), or both (e.g., 2,5,7-9).

    The following prompt is displayed:

    ```
    Enter Group Number ->
    ```

15. Enter a group number for the port(s). Each group on a switch must be given a unique group number. The range is 1 to 256.

16. If there are unassigned ports in the VLAN, the prompt in Step 13 is displayed again, showing the unassigned ports. You must repeat Steps 14 and 15, creating additional groups, until all of the ports in the VLAN have been assigned to a group.

    After creating all of the groups, the following prompt is displayed:

    ```
    SUCCESS - Press any key to continue.
    Press any key to continue.
    ```

    The new protected ports VLAN and its groups are now active on the switch.

17. Press any key to return to the Configure VLANs menu.

18. To permanently save your changes, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Modifying a Protected Ports VLAN

Note the following before performing this procedure:

- To modify a protected ports VLAN, you have to recreate it. You must reselect the uplink port(s) and reassign the ports to the groups. To make the process easier, Allied Telesis recommends displaying the details of the VLAN before performing this procedure, and writing down on paper the current configuration (i.e., uplink port and port to group assignments). This information will make it easier for you to recreate the VLAN, with the necessary modifications, when you perform the procedure. To display a VLAN's configuration, refer to "Displaying a Protected Ports VLAN" on page 528.
- To add untagged ports, the ports must be untagged members of the Default_VLAN or a port-based or tagged VLAN. They can not be members of another protected ports VLAN.
- An untagged port removed from a VLAN is automatically returned to the Default_VLAN.

> **Note**
> You need to know the VID of a VLAN to modify it. To view VLAN VIDs, refer to "Displaying a Protected Ports VLAN" on page 528.

To modify a protected ports VLAN, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.

   The VLAN Configuration menu is shown in Figure 171 on page 472.

2. From the VLAN Configuration menu, type **3** to select Configure VLANs.

   The Configure VLANs menu is shown in Figure 172 on page 473.

3. From the Configure VLANs menu, type **2** to select Modify VLAN.

   The Modify VLAN menu is shown in Figure 174 on page 481.

4. Type **1** to select VLAN ID (VID).

   The following prompt is displayed:

   ```
   Enter new value -> [1 to 4096] ->
   ```

5. Enter the VID of the VLAN to be modified.

Downloaded from www.Manualslib.com manuals search engine

The Modify VLAN menu expands to contain all relevant information about the VLAN, as shown in Figure 194.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing

User: Manager                            11:20:02 02-Mar-2005

                          Modify VLAN

1 - VLAN Name ............... Internet_1
2 - VLAN ID (VID) ........... 3
3 - VLAN Type ............... Protected
4 - Tagged Ports ............ 7,9
5 - Untagged Ports ......... 20-24
6 - Protected Ports ........ Yes

M - Modify VLAN
R - Return to Previous Menu

Enter your selection?
```

Figure 194. Expanded Modify VLAN Menu

6. Adjust the following parameters as necessary.

1 - VLAN Name
Use this selection to change the name of a VLAN. The name can be from one to fifteen alphanumeric characters in length. The name cannot contain spaces or special characters, such as asterisks (*) or exclamation points (!).

Note
A VLAN must have a name.

---

2 - VLAN ID (VID)
This is the VLAN's VID value. You cannot change this value.

3- VLAN Type
This identifies the VLAN as a protected ports VLAN. This option can not be changed.

4 - Tagged Ports
Use this selection to specify the tagged ports of the VLAN. You can specify the ports individually (e.g., 2,3,5), as a range (e.g., 7-9), or both (e.g., 2,5,7-9). The new list of tagged ports replaces the existing list. To retain tagged ports, you must include them in the new list.

5 - Untagged Ports
Use this selection to specify the untagged ports of the VLAN. You can specify the ports individually (e.g., 2,3,5), as a range (e.g., 7-9), or both (e.g., 2,5,7-9). The new list of untagged ports replaces the existing list. To retain untagged ports, you must include them in the new list.

Downloaded from www.Manualslib.com manuals search engine

6 - Protected Ports
This identifies the VLAN as a protected ports VLAN. This option can not be changed. To convert a protected ports VLAN into a tagged or port-based VLAN, you must delete it and recreate it as a tagged or port-based VLAN.

7. After making the desired changes, type **M** to select Modify VLAN.

   The following prompt is displayed:

   ```
   Enter Uplink Ports (4 - 12) ->
   ```

   This prompt lists the ports of the VLAN.

8. Enter the port to function as the uplink port for the VLAN groups. You can select more than one uplink port.

   The following prompt is displayed:

   ```
   Enter Group Ports (4 - 11) ->
   ```

   The prompt lists the ports in the VLAN, minus the uplink port specified in the previous step.

9. Specify the ports of one of the groups of the VLAN. This can be a small as one port or as many as all the remaining ports of the VLAN. You can specify the ports of the group individually (e.g., 2,3,5), as a range (e.g., 7-9), or both (e.g., 2,5,7-9).

   The following prompt is displayed:

   ```
   Enter Group Number ->
   ```

10. Enter a group number for the port(s). Each group on a switch must be given a unique group number. The range is 1 to 256.

11. If there are unassigned ports in the VLAN, the prompt in Step 8 is displayed again, showing the unassigned ports. You must repeat Steps 9 and 10, creating additional groups, until all the ports in the VLAN are assigned to a group.

    This prompt is displayed after all the ports of the VLAN are assigned to a group:

    ```
    SUCCESS - Press any key to continue.
    Press any key to continue.
    ```

    The modified protected ports VLAN and its groups are now active on the switch.

12. Press any key to return to the Configure VLANs menu.

13. To permanently save your changes, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Displaying a Protected Ports VLAN

To view the name, VID number, and member ports of all the VLANs on a switch, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.

   The VLAN Configuration menu is shown in Figure 171 on page 472.

2. From the VLAN Configuration menu, type **4** to select Show VLANs.

   The Show VLANs menu is shown in Figure 195.

```
                    Allied Telesis AT-9424T/SP - AT-S63
                                 Marketing

User: Manager                                          11:20:02 02-Mar-2005

                                 Show VLANs


VID   VLAN Name     VLAN Type      Protocol    Member Port(s)
-------------------------------------------------------------------

1     Default_VLAN  Port Based                 Untagged
                                                  Configured: 20-24
                                                  Actual: 20-24
                                               Tagged:
2     Sales         Port Based                 Untagged
                                                  Configured: 1-7
                                                  Actual: 1-7
                                               Tagged: 23
3     Production    Protected                  Untagged: 8-19
                                               Tagged: 24

U - Update Display
D - Detail Information Display
R - Return to Previous Menu

Enter your selection?
```

Figure 195. Show VLANs Menu

3. To view additional information about a protected ports VLAN, type **D** to select Detail Information Display.

   The following prompt is displayed:

   ```
   Enter new value ->
   ```

4. Enter the VID of a protected ports VLAN.

Downloaded from www.Manualslib.com manuals search engine

An example of the Show VLANs window is shown in Figure 196.



Figure 196. Show VLANs Menu

Section 1 lists all the tagged and untagged ports in the protected ports VLAN. Section 2 lists the groups in the VLAN, starting with the uplink port(s). The groups are listed by group number followed by the port numbers. For example, in Figure 196 the uplink port for the VLAN is port 24 and Group 1 consists of ports 8 and 11.

Downloaded from www.Manualslib.com manuals search engine

Deleting a Protected Ports VLAN

To delete a protected ports VLAN, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.
2. From the VLAN Configuration menu, type **3** to select Configure VLANs.

   The Configure VLANs menu is shown in Figure 172 on page 473.
3. From the Configure VLANs menu, type **3** to select Delete VLAN.

   The Delete VLAN menu is shown in Figure 197.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing

User: Manager                              11:20:02 02-Mar-2005

                           Delete VLAN

1 - VLAN ID (VID) ........

R - Return to Previous Menu

Enter your selection?
```

Figure 197. Delete VLAN Menu

4. Type **1** to select VLAN ID (VID).

   The following prompt is displayed:

   ```
   Enter new value -> [2 to 4094] ->
   ```
5. Enter the VID of the VLAN to be deleted. You can specify only one VID at a time.

> **Note**
> You cannot delete the Default_VLAN, which has a VID of 1.

Downloaded from www.Manualslib.com manuals search engine

The Delete VLAN menu expands to contain the relevant information about the VLAN. You can use the information to confirm that you are deleting the correct VLAN. An example is shown in Figure 198.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing

User: Manager                           11:20:02 02-Mar-2005

                          Delete VLAN

1 - VLAN Name ............... Sales
2 - VLAN ID (VID) .......... 3
3 - VLAN Type ............... Protected
4 - Tagged Ports ............ 7,9
5 - Untagged Ports .......... 20-24
6 - Protected Ports ......... Yes

D - Delete VLAN
R - Return to Previous Menu

Enter your selection?
```

Figure 198. Expanded Delete VLAN Menu

6. Type **D** to delete the VLAN or **R** to cancel the procedure.

   If you select to delete the VLAN, the following confirmation prompt is displayed:

   ```
   Are you sure you want to delete this VLAN [Yes/No] ->
   ```

7. Type **Y** to delete the VLAN or **N** to cancel the procedure. Press Return.

   If you select Yes, the VLAN is deleted and the following message is displayed:

   ```
   SUCCESS
   Please make sure to manually delete any static multicast
   MAC address(es) entries for this VLAN
   Press any key to continue ...
   ```

   All untagged ports in the deleted VLAN are returned to the Default_VLAN as untagged ports. Any static addresses assigned to the ports of the VLAN are now obsolete. Those addresses should be deleted from the MAC address table. For instructions on how to delete addresses, refer to "Deleting Unicast and Multicast MAC Addresses" on page 112.

8. Press any key.

9. Repeat this procedure starting with Step 4 to delete other VLANs.

10. To permanently save your changes, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Chapter 28

MAC Address-based VLANs

This chapter contains the procedures for creating MAC address-based VLANs. Sections in the chapter include:

- ❒ “Creating a MAC Address-based VLAN” on page 534
- ❒ “Adding and Deleting MAC Addresses” on page 536
- ❒ “Adding and Deleting Egress Ports” on page 538
- ❒ “Deleting a MAC Address-based VLAN” on page 540
- ❒ “Displaying MAC Address-based VLANs” on page 542

Downloaded from www.Manualslib.com manuals search engine

Creating a MAC Address-based VLAN

This is the first stage to creating a MAC address-based VLAN. This procedure assigns the VLAN a name and a VID and sets the VLAN type. After completing this procedure you can add the source MAC addresses to the VLAN, as explained in “Adding and Deleting MAC Addresses” on page 536 and, finally, the egress ports, as explained in “Adding and Deleting Egress Ports” on page 538.

To create a new MAC address-based VLAN, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.

   The VLAN Configuration menu is shown in Figure 171 on page 472.

2. From the VLAN Configuration menu, type **3** to select Configure VLANs.

   The Configure VLANs menu is shown in Figure 172 on page 473.

3. From the Configure VLANs menu, type **1** to select Create VLAN.

   The Create VLAN menu is shown in Figure 173 on page 473.

4. Type **1** to select VLAN Name.

   The following prompt is displayed:

   ```
   Enter new value ->
   ```

5. Type a name for the new VLAN.

   The name can be from one to fifteen alphanumeric characters in length. The name should reflect the function of the nodes that will be a part of the VLAN (for example, Sales or Accounting). The name cannot contain spaces or special characters, such as asterisks (*) or exclamation points (!).

   If the VLAN will be unique in your network, then the name should be unique as well. If the VLAN will be part of a larger VLAN that spans multiple switches, then the name for the VLAN should be the same on each switch where nodes of the VLAN are connected.

   Note
   A VLAN must be assigned a name.

6. Type **2** to select VLAN ID (VID.

Downloaded from www.Manualslib.com manuals search engine

The following prompt is displayed:

```
Enter new value -> [2 to 4094] ->
```

7. Type a VID value for the new VLAN. The range for the VID value is 1 to 4094.

   The AT-S63 Management Software uses the next available VID number on the switch as the default value. If this VLAN is unique in your network, then its VID should also be unique. If this VLAN is part of a larger VLAN that spans multiple switches, than the VID value for the VLAN should be the same on each switch. For example, if you are creating a VLAN called Sales that spans three switches, you should assign the Sales VLAN on each switch the same VID value.

   Note
   A VLAN must have a VID.

   The switch is only aware of the VIDs of the VLANs on the device and not those that might already exist in the network. For example, if you add a new AT-9400 Switch to a network where there are VLANs that use VIDs 2 through 24, the AT-S63 Management Software still uses VID 2 as the default value when you create the first VLAN on the new switch, even though that VID number is already being used by another VLAN on the network. You should keep a list of all your network VLANs and their VID values to prevent inadvertently using the same VID for two different VLANs.

8. Type **3** to toggle VLAN Type to display MAC Based. This is the correct setting for a MAC address-based VLAN.

   Note
   The Port Based setting for VLAN type is used to create port-based and tagged VLANs, as explained to Chapter 24, "Port-based and Tagged VLANs" on page 471.

   Note
   Do not specify any tagged or untagged ports. Additionally, leave the Protected Ports selection at the default setting of No.

9. Type **C** to select Create VLAN.

10. To permanently save your changes, return to the Main Menu and type **S** to select Save Configuration Changes. This completes the first phase to creating a new MAC address-based VLAN. You assigned it a name, gave it a VID, and set the VLAN type. You are now ready to assign the MAC addresses, as explained in "Adding and Deleting MAC Addresses" on page 536.

Downloaded from www.Manualslib.com manuals search engine

Adding and Deleting MAC Addresses

This procedure explains how to add and delete MAC addresses from a MAC address-based VLAN. If you are creating a new VLAN, you perform this procedure after you initially create the VLAN by giving it a name and a VID and setting the VLAN type, as explained in “Creating a MAC Address-based VLAN” on page 534. After you assign the MAC addresses to the VLAN, you must specify the egress ports, as described in “Adding and Deleting Egress Ports” on page 538.

You cannot remove a MAC address from a VLAN if the address has been assigned egress ports. You must first remove the ports from the MAC address before you can delete it. For instructions, refer to “Adding and Deleting Egress Ports” on page 538.

To add or delete MAC addresses from a MAC address-based VLAN, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.

   The VLAN Configuration menu is shown in Figure 171 on page 472.

2. From the VLAN Configuration menu, type **3** to select Configure VLANs.

   The Configure VLANs menu is shown in Figure 172 on page 473.

3. From the Configure VLANs menu, type **2** to select Modify VLAN.

   The Modify VLAN menu is shown in Figure 174 on page 481.

4. From the Modify VLAN menu, type **3** to select Configure MAC Associations.

   The MAC Based VLANs menu is shown in Figure 199.

```
          Allied Telesis AT-9448T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                     MAC Based VLANs

1 - Add MAC Address
2 - Delete MAC Address
3 - Add Ports
4 - Delete Ports

R - Return to Previous Menu

Enter your selection?
```

Figure 199. MAC Based VLANs Menu

Downloaded from www.Manualslib.com manuals search engine

5. To add a MAC address to a MAC address-based VLAN, type **1** to select Add MAC Address. To delete an address, type **2** to select Delete MAC Address.

   The following prompt is displayed:

   ```
   Please enter VLAN ID -> [1 to 4094] -> 2
   ```

6. Enter the VID of the MAC address-based VLAN where you want to add or delete a MAC address. You can enter only one VID. To display the VIDs, refer to "Displaying MAC Address-based VLANs" on page 542.

   The following prompt is displayed:

   ```
   Please enter MAC address ->
   ```

7. Enter the MAC address to add to or delete from the VLAN. You can enter the address in either of the following formats:

   xx:xx:xx:xx:xx:xx or xxxxxxxxxxxx

   The MAC address is added to or deleted from the VLAN.

8. To add or delete more MAC addresses, repeat this procedure starting with step 5.

9. To permanently save your changes, return to the Main Menu and type **S** to select Save Configuration Changes.

   If you added a new MAC address to a new or existing VLAN, perform the procedure "Adding and Deleting Egress Ports" on page 538 to assign egress ports to the address.

Downloaded from www.Manualslib.com manuals search engine

Adding and Deleting Egress Ports

This procedure explains how to add and delete egress ports from the MAC addresses in a MAC address-based VLAN.

Before adding egress ports to a MAC address, review the following:

- The egress ports of a MAC address-based VLAN are considered as a community. Assigning a port to one address makes it an egress port for all the addresses in the same VLAN.
- A MAC address must have at least one egress port. Otherwise, the address is not considered a part of the VLAN and the PVID of the port where the packet's of the node are received determines VLAN membership.
- A MAC address must be added to a VLAN before you can assign it an egress port. For instructions, refer to "Adding and Deleting MAC Addresses" on page 536.

To add or delete egress ports from a MAC address, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.

   The VLAN Configuration menu is shown in Figure 171 on page 472.

2. From the VLAN Configuration menu, type **3** to select Configure VLANs.

   The Configure VLANs menu is shown in Figure 172 on page 473.

3. From the Configure VLANs menu, type **2** to select Modify VLAN.

   The Modify VLAN menu is shown in Figure 174 on page 481.

4. From the Modify VLAN menu, type **3** to select Configure MAC Associations.

   The MAC Based VLANs menu is shown in Figure 199 on page 536.

5. To add an egress port to a MAC address, type **3** to select Add Ports. To delete an address, type **4** to select Delete Ports.

   The following prompt is displayed:

   ```
   Please enter VLAN ID -> [1 to 4094] -> 2
   ```

6. Enter the VID of the MAC address-based VLAN where you want to add or delete an egress port. You can enter only one VID. To display the VIDs, refer to "Displaying MAC Address-based VLANs" on page 542.

Downloaded from www.Manualslib.com manuals search engine

The following prompt is displayed:

```
Please enter MAC address ->
```

7. Enter the MAC address where you want to add or delete an egress port. You can specify only one address and the address must already exist in the VLAN. For instructions on how to add an address to a VLAN, refer to "Adding and Deleting MAC Addresses" on page 536. You can enter the address in either of the following formats:

   xx:xx:xx:xx:xx:xx or xxxxxxxxxxxx

   The following prompt is displayed:

   ```
   Please enter port number(s):
   ```

8. Enter the egress port for the address. You can specify more than one port. You can specify the ports individually (e.g., 2,4,15), as a range (e.g., 11-15), or both (e.g., 2,4,11-17).

   If you are adding an egress port, the port is immediately added to the MAC address. If you are deleting an egress port, the port is deleted from the address.

9. To add or delete more egress ports, repeat this procedure starting with step 5.

10. To permanently save your changes, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Deleting a MAC Address-based VLAN

Note
To delete a VLAN, you need to know its VID. To view VLAN VIDs, refer to “Displaying MAC Address-based VLANs” on page 542.

To delete a VLAN, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.

   The VLAN Configuration menu is shown in Figure 171 on page 472.

2. From the VLAN Configuration menu, type **3** to select Configure VLANs.

   The Configure VLANs menu is shown in Figure 172 on page 473.

3. From the Configure VLANs menu, type **3** to select Delete VLAN.

   The Delete VLAN menu is shown in Figure 200.

```
            Allied Telesis AT-9448T/SP - AT-S63
                          Marketing
User: Manager                              11:20:02 02-Mar-2005
                         Delete VLAN

1 - VLAN ID (VID) ........

R - Return to Previous Menu

Enter your selection?
```

Figure 200. Delete VLAN Menu

4. From the Delete VLAN menu, type **1** to select VLAN ID (VID).

   The following prompt is displayed:

   ```
   Enter new value -> [2 to 4094] ->
   ```

5. Enter the VID of the VLAN you want to delete. You can specify only one VID at a time.

Note
You cannot delete the Default_VLAN, which has a VID of 1.

Downloaded from www.Manualslib.com manuals search engine

The Delete VLAN menu expands to contain all relevant information about the VLAN, as shown in Figure 201. You can use this menu to confirm that you are deleting the correct VLAN.

```
          Allied Telesis AT-9448T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                        Delete VLAN

1 - VLAN Name ............... Sales
2 - VLAN ID (VID) ........... 2
3 - VLAN Type ............... MAC Based
4 - Tagged Ports ............
5 - Untagged Ports .........
6 - Protected Ports ........ No

D - Delete VLAN
R - Return to Previous Menu

Enter your selection?
```

Figure 201. Expanded Delete VLAN Menu

6. Type **D** to delete the VLAN or **R** to cancel the procedure.

   If you select to delete the VLAN, the following confirmation prompt is displayed:

   ```
   Are you sure you want to delete this VLAN [Yes/No] ->
   ```

7. Type **Y** to delete the VLAN or **N** to cancel the procedure. Press Return.

   If you select Yes, the VLAN is deleted and the following message is displayed:

   ```
   SUCCESS
   Please make sure to manually delete any static multicast
   MAC address(es) entries for this VLAN
   Press any key to continue ...
   ```

8. Press any key.

9. Repeat this procedure starting with Step 4 to delete other VLANs.

10. To permanently save your changes, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Displaying MAC Address-based VLANs

To view the details of a MAC address-based VLAN, perform the following procedure:

1. From the Main Menu, type **2** to select VLAN Configuration.

   The VLAN Configuration menu is shown in Figure 171 on page 472.

2. From the VLAN Configuration menu, type **4** to select Show VLANs.

   The Show VLANs menu is shown in Figure 202.

```
                    Allied Telesis AT-9448T/SP - AT-S63
                                Marketing
User: Manager                                        11:20:02 02-Mar-2005
                                Show VLANs


VID   VLAN Name      VLAN Type    Protocol    Member Port(s)
-------------------------------------------------------------------

1     Default_VLAN   Port Based               Untagged
                                                 Configured: 20-48
                                                 Actual: 20-24
                                               Tagged: 7,9
11    Sales          Port Based               Untagged
                                                 Configured: 1-5
                                                 Actual: 1-5
                                               Tagged: 9
15    Engineering    MAC Based                U:
                                               T:
16    Production     MAC Based                U:
                                               T:

N - Next Page
U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 202. Show VLANs Menu with MAC Address-based VLANs

The Show VLANs menu displays a table that contains the following columns of information:

VID
The VLAN ID.

VLAN Name
Name of the VLAN.

VLAN Type
The VLAN type. The possible settings are:

Port Based - The VLAN is a port-based or tagged VLAN.

Downloaded from www.Manualslib.com manuals search engine

MAC Based - The VLAN is a MAC address-based VLAN.

GARP - The VLAN was automatically created by GARP.

Protocol
The protocol associated with this VLAN. The possible settings are:

Blank - The VLAN is a port-based, tagged, or MAC address-based VLAN.

GARP - The VLAN is a dynamic GVRP VLAN or the port is a dynamic GVRP port of a static VLAN.

Member Port(s)
The untagged and tagged ports of a VLAN. These are empty for a MAC address-based VLAN.

3. To view the MAC addresses and egress ports of a MAC address-based VLAN, type **D** to select Detail Information Display.

   The following prompt is displayed:

   ```
   Enter VLAN ID [2 to 4094] -> 2
   ```

4. Enter the VID of the VLAN. The Detail Information Display menu is shown in Figure 203.

```
                  Allied Telesis AT-9448T/SP - AT-S63
                               Marketing
User: Manager                                      11:20:02 02-Mar-2005
                       Detail Information Display

VID   VLAN Name      VLAN Type    Protocol    Untagged (U) / Tagged (T)
-------------------------------------------------------------------------

15    Engineering    MAC Based                U:
                                              T:

MAC Associations:
   Total number of associated MAC addresses: 5
   ------------------------------------------------
   MAC Address         Ports
   ------------------------------------------------
   00:0A:22:22:22:22   12-20,22
   00:0A:44:44:44:44   12
   00:0A:66:66:66:66   12
   00:0A:77:77:77:77   12
   00:0A:88:88:88:88   12

U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 203. Detail Information Display

Downloaded from www.Manualslib.com manuals search engine

The lower portion of the display lists the MAC addresses of the VLAN and the egress ports.

Downloaded from www.Manualslib.com manuals search engine

Section VII

Internet Protocol Routing

The chapter in this section contains the procedures for managing routing interfaces of the Internet Protocol version 4 (IPv4) packet routing feature. The chapter is:

- Chapter 29, “Internet Protocol Version 4 Routing Interfaces” on page 547

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Chapter 29

Internet Protocol Version 4 Routing Interfaces

This chapter contains the following procedures for managing Internet Protocol Version 4 (IPv4) routing interfaces:

- ❒ “Creating a New Routing Interface” on page 548
- ❒ “Modifying a Routing Interface” on page 551
- ❒ “Deleting a Routing Interface” on page 554
- ❒ “Displaying the IP Address of the Local Interface” on page 555
- ❒ “Setting the Default Route or Default Gateway” on page 556
- ❒ “Setting the Local Interface” on page 557
- ❒ “Setting the ARP Cache Timeout” on page 558

Note
The IPv4 packet routing feature consists of three components — routing interfaces, static routes, and the Router Information Protocol (RIP). The menus interface supports just routing interfaces. To configure all of the routing components, you must use the command line interface.

Downloaded from www.Manualslib.com manuals search engine

Creating a New Routing Interface

A routing interface is a logical connection to a local network or subnet for routing IPv4 packets. Interfaces route packets between the local networks and subnets directly connected to the switch and also function as anchor points for static routes and RIP.

To create a new routing interface, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.
2. From the System Administration menu, type **2** to select System Configuration.
3. From the System Configuration menu, type **I** to select Configure Interface.

   The Configure Interface menu lists the current routing interfaces on the switch. An example is shown in Figure 204.

```
                  Allied Telesis AT-9424Ts - AT-S63
                              Marketing

User: Manager                                    11:20:02 02-Jun-2006

                           Configure Interface

Interface           IPAddress            NetMask             Status
-------------------------------------------------------------------
vlan2-0             149.123.11.21        255.255.255.0       UP
vlan5-0             149.55.12.15         255.255.255.0       DOWN
vlan8-0             149.55.13.2          255.255.255.0       UP
vlan8-1[eth0]       149.55.14.8          255.255.255.0       UP

C - Create Interface
D - Delete Interface
M - Modify Interface
E - Set eth0 Interface

R - Return to Previous Menu

Enter your selection?
```

Figure 204. Configure Interface Menu

The columns in the table are:

Interface
The name of an interface. An interface name consists of “VLAN” followed the ID number (VID) of its VLAN assignment and an interface number, separated by a dash.

Downloaded from www.Manualslib.com manuals search engine

If a routing interface has been designated as the local interface of a switch, its name is followed by "eth0". The local interface is used for enhanced stacking and remote Telnet, SSH, and web browser management.

IPAddress
The IP address of the interface.

NetMask
The subnet mask of the interface.

Status
The status of the interface. The status "UP" means the VLAN of the interface has at least one active port. The status "DOWN" means the VLAN has no active ports.

4. To create a new interface, type **C** to select Create Interface.

   The Create Interface menu is shown in Figure 205.

```
            Allied Telesis AT-9424Ts - AT-S63
                        Marketing

User: Manager                        11:20:02 02-Jun-2006

                     Create Interface

1 - Interface Name ...................
2 - IP Address ...................... 0.0.0.0
3 - Subnet Mask ..................... 0.0.0.0

C - Create Interface
R - Return to Previous Menu

Enter your selection?
```

Figure 205. Create Interface Menu

5. Type **1** to select Interface Name.

   The following prompt is displayed:

   ```
   Enter Interface Name:
   ```

6. Enter a name for the new interface. An interface name consists of "VLAN" followed by the ID (VID) of the VLAN where the interface is to be assigned and an interface number, separated by a dash (e.g., vlan4-0). The VLAN must already exist on the switch. When there are multiple interfaces within a VLAN, each must be assigned a unique interface number. The range of the interface number is 0 to 15.

7. Type **2** to select IP address.

Downloaded from www.Manualslib.com manuals search engine

The following prompt is displayed:

```
Enter IP Address [STATIC IP|DHCP|BOOTP]:
```

8. Enter a static IP address for the new interface or enter “DHCP” or “BOOTP” to activate the DHCP or BOOTP client.

Note
Skip steps 9 and 10 if you selected DHCP or BOOTP in step 8.

9. To change the default subnet mask for a static IP address, type **3** to select Subnet Mask.

   The following prompt is displayed:

   ```
   Enter Subnet Mask:
   ```

10. Enter a subnet mask for the static address of the interface. The default values are:

    Class A address - 255.0.0.0

    Class B address - 255.255.0.0

    Class C address - 255.255.255.0

    The three values listed above are the only supported values because the value of a byte in a mask must be either 255 or 0.

11. Type **C** to select Create Interface.

    The following prompt is displayed:

    ```
    Interface Created Successfully?
    Press any key to continue...
    ```

12. Press any key.

    The new interface is added to the Configure Interface menu and immediately activated on the switch.

13. To create additional interfaces, repeat this procedure starting with step 4.

14. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Modifying a Routing Interface

This procedure modifies the IP address and subnet mask of a routing interface. Note the following before performing this procedure:

- Modifying the IP address of a routing interface deletes all static routes assigned to the interface.
- Modifying the IP address of a routing interface that has RIP removes the routing protocol from the interface and deletes all RIP routes learned on the interface from the routing table.
- You cannot modify the RIP metric of a routing interface from the menus interface. That task must be performed from the command line interface using the SET IP INTERFACE command.
- You cannot change the name of a routing interface. The only way to change the VID or interface number of an interface is to delete the interface and recreate it.

To modify a routing interface, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.
2. From the System Administration menu, type **2** to select System Configuration.
3. From the System Configuration menu, type **I** to select Configure Interface.

   The Configure Interface menu is shown in Figure 204 on page 548.
4. From the Configure Interface menu, type **M** to select Modify Interface.

   The following prompt is displayed:

   ```
   Enter Interface Name:
   ```
5. Enter the name of the interface (e.g., vlan2-1) to be modified.

Downloaded from www.Manualslib.com manuals search engine

The specifications of the interface are displayed in the Modify Interface menu. An example is shown in Figure 205.

```
            Allied Telesis AT-9424Ts - AT-S63
                        Marketing

User: Manager                        11:20:02 02-Jun-2006

                      Modify Interface

1 - Interface Name ................... VLAN2-0
2 - IP Address ....................... 149.55.22.21
3 - Subnet Mask ...................... 255.255.255.0

M - Modify Interface
R - Return to Previous Menu

Enter your selection?
```

Figure 206. Modify Interface Menu

6. To change the IP address of the interface, type **2** to select IP address.

   The following prompt is displayed:

   ```
   Enter IP Address [STATIC IP|DHCP|BOOTP]:
   ```

7. Enter a new static IP address for the interface or enter “DHCP” or “BOOTP” to activate the DHCP or BOOTP client.

   Note
   Skip steps 8 and 9 if you selected DHCP or BOOTP in step 7.

8. To change the subnet mask of a static IP address, type **3** to select Subnet Mask.

   The following prompt is displayed:

   ```
   Enter Subnet Mask:
   ```

9. Enter a new subnet mask for the static address of the interface. The default values are:

   Class A address - 255.0.0.0

   Class B address - 255.255.0.0

   Class C address - 255.255.255.0

   The three values listed above are the only supported values because the value of a byte in a mask must be either 255 or 0.

Downloaded from www.Manualslib.com manuals search engine

10. Type **M** to select Modify Interface.

    The following prompt is displayed:

    ```
    Interface Modified Successfully?
    Press any key to continue...
    ```

11. Press any key.

    The modifications are immediately implemented on the routing interface.

12. To modify another routing interface, repeat this procedure starting with step 4.

13. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Deleting a Routing Interface

This procedure deletes a routing interface from the switch. Note the following before performing this command:

- All IPv4 packet routing to and from the local network or subnet of a deleted interface ceases.
- All static routes assigned to the interface are deleted from the routing table.
- If RIP was assigned to the interface, all dynamic routes learned by the interface are deleted from the routing table.
- Deleting an interface used by the AT-S63 Management Software to communicate with a network device for management purposes (e.g., a RADIUS or syslog server) causes the switch to stop performing those management functions.
- Deleting the local interface on a master switch of an enhanced stack disables the device's ability to function as the master switch.
- Deleting the local interface of a switch during a remote Telnet or SSH management session immediately ends the session if you accessed the switch directly (i.e., not through enhanced stacking). To continue managing the switch, you must start a local management session using the Terminal Port on the unit.

To delete a routing interface, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.
2. From the System Administration menu, type **2** to select System Configuration.
3. From the System Configuration menu, type **I** to select Configure Interface.

   The Configure Interface menu is shown in Figure 204 on page 548.
4. From the Configure Interface menu, type **D** to select Delete Interface.

   The following prompt is displayed:

   ```
   Enter Interface Name:
   ```
5. Enter the name of the interface (e.g., vlan2-1) to be deleted.

   The interface is immediately deleted from the switch.
6. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Displaying the IP Address of the Local Interface

This procedure displays the IP address and subnet mask of the local interface on the switch. The local interface is used for remote Telnet, SSH, and web browser management of the switch. On the master switch of an enhanced stack, the local interface also designates the common VLAN of the switches.

To view the IP address and subnet mask of the local interface, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.
2. From the System Administration menu, type **2** to select System Configuration.

   The System Configuration menu is shown in Figure 2 on page 33.

> **Note**
> Selections 5 to 7 in the System Configuration menu are described in "Configuring the Switch's Name, Location, and Contact" on page 32. Selection 8, ARP Cache Timeout, is described in "Setting the ARP Cache Timeout" on page 558. Selection T, Configure System Time, is described in "Setting the System Time" on page 38.

Items 1 through 4 in the menu display the IP settings for the routing interface designated as the local interface on the switch. There will be no IP settings if no interface has been designated as the local interface.

1 - Eth0 Interface
This parameter displays the name of the local interface. An interface name consists of "VLAN" followed the ID number (VID) of the VLAN where the interface is assigned and the interface number, separated by a dash (e.g., VLAN2-0).

2 - IP Address
This parameter displays the IP address and source of the address for the local interface. The source is STATIC for a manually assigned address or DHCP or BOOTP for an address supplied by a DHCP or BOOTP server.

3 - Subnet Mask
This parameter specifies the subnet mask of the local interface.

4 - Default Gateway
This parameter specifies the IP address of the default route or default gateway for the switch. For instructions, refer to "Setting the Default Route or Default Gateway" on page 556.

Downloaded from www.Manualslib.com manuals search engine

Setting the Default Route or Default Gateway

If you are configuring an AT-9400 Switch that supports IPv4 packet routing, such as the AT-9424Ts and AT-9448Ts/XP switches, you can configure the default route from the menus interface. The default route is used by the switch when it receives a network packet for routing, but cannot find a route for it. To create a default route, you specify the IP address of the next hop for those packets without a route in the switch's routing table.

For an AT-9400 Switch that does not support the IPv4 packet routing feature, such as the AT-9424T/GB and AT-9424T/SP switches, you can define the default gateway from the menus interface. The default gateway is the IP address of a router interface on your network. The switch's management software uses this address as the next hop to reaching a remote network device, such as a remote management workstation or a syslog server, when the switch's local interface and the remote device are on different subnets.

To set the default route or default gateway of the switch, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.
2. From the System Administration menu, type **2** to select System Configuration.

   The System Configuration menu is shown in Figure 2 on page 33. The current default route or default gateway is displayed in Selection 4, Default Gateway. This selection contains 0.0.0.0 if no default route or default gateway is defined on the switch.
3. In the System Configuration menu, type **4** to select Default Gateway.

   The following prompt is displayed:

   ```
   Enter IP Address:
   ```
4. Enter the IP address of the next hop for the default route or default gateway.

   The IP address must be a member of a subnet on the switch that has a routing interface.
5. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Setting the Local Interface

This procedure designates the local interface of a switch. The local interface is used for remote Telnet, SSH, and web browser management of the switch. On the master switch of an enhanced stack, the local interface also designates the common VLAN of the switches.

A switch can have only one local interface. The current local interface is indication in the Create Interface menu with "eth0" following its name.

To select a local interface, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.
2. From the System Administration menu, type **2** to select System Configuration.
3. From the System Configuration menu, type **I** to select Configure Interface.

   The Configure Interface menu is shown in Figure 204 on page 548.
4. From the Configure Interface menu, type **E** to select Set eth0 Interface.

   The following prompt is displayed:

   ```
   Enter Interface Name:
   ```
5. Enter the name of the interface (e.g., vlan2-1) to be the local interface on the switch. To remove the current local interface assignment without assigning a new local interface, enter "none".

   The name of the selected interface in the Create Interface menu should now include "eth0" to indicate that the interface is now functioning as the local interface on the switch.
6. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Setting the ARP Cache Timeout

The ARP cache contains mappings of IP addresses to physical addresses for hosts where the switch has recently routed packets. To have an entry in the ARP cache, a host must have attempted to access another host, and it must have found the physical address by using the ARP protocol. (You must use the command line interface to view the ARP cache.)

This procedure sets the ARP cache timeout value. The timer prevents the ARP table from becoming full with inactive entries. An entry that is not used for the length of the timeout period is designated as inactive and is deleted from the table.

To set the ARP cache timeout value, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.
2. From the System Administration menu, type **2** to select System Configuration.
3. Type **8** to select ARP Cache Timeout.

   The following prompt is displayed:

   ```
   Enter your new value -> [1 to 260000] 150
   ```

4. Enter a new value for the ARP cache timeout value. The range is 1 to 260000 seconds. The default is 150 seconds.
5. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Section VIII

Port Security

The chapters in this section contain overview information on the port security features of the AT-9400 Switch. The chapters also explain how to configure these features from the menu interface of the AT-S63 Management Software. The chapters include:

- Chapter 30, “MAC Address-based Port Security” on page 561
- Chapter 31, “802.1x Port-based Network Access Control” on page 569

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Chapter 30

MAC Address-based Port Security

This chapter explains how you can use the dynamic and static MAC addresses learned or manually added to the switch's MAC address table to control which end nodes can forward packets through the device. The sections in this chapter include:

- ❒ "Configuring MAC Address Port Security" on page 562
- ❒ "Displaying Port Security Levels" on page 566

Note
This type of port security does not apply to ports located on optional GBIC, SFP, or XFP modules.

Downloaded from www.Manualslib.com manuals search engine

Configuring MAC Address Port Security

To set the port security level on a port, perform the following procedure:

1. From the Main Menu, type **1** to select Port Configuration.
2. From the Port Configuration menu, type **5** to select Port Security.

   The Port Security menu is shown in Figure 207.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                     Port Security

1 - Configure Port Security
2 - Display Port Security

R - Return to Previous Menu

Enter your selection?
```

Figure 207. Port Security Menu

3. From the Port Security menu, type **1** to select Configure Port Security.

   The following prompt is displayed:

   ```
   Enter Port-List:
   ```

4. Enter the port where you want to set MAC address port security. You can specify one port or a range or ports (for example, 4-8).

   The Configure Port Security menu is shown in Figure 208.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                Configure Port Security

 Configuring Port Security 4
1 - Security Mode ..................... Automatic

D - Set Default Port Security
R - Return to Previous Menu

Enter your selection?
```

Figure 208. Configure Port Security Menu #1

Downloaded from www.Manualslib.com manuals search engine

The menu displays the current security level on the selected port. If you are configuring a range of ports and the ports have different security levels, the menu displays the security level of the lowest number port.

Note
Option D, Select Default Port Security, sets the security mode for the port to the default value of Automatic.

5. From the Configure Port Security menu, type **1** to select Security Mode.

   The following prompt is displayed:

   ```
   Enter new mode (A-Automatic, L-Limited, S-Secured, K-
   locKed):
   ```

6. Select the desired security level.

   - automatic - Disables security on the port. This is the default setting.
   - limited - Sets the port to the Limited security mode. The port learns a limited number of dynamic MAC addresses.
   - secured - Sets the port to the Secured security mode. The port accepts frames based on static MAC addresses. You must enter the static MAC addresses of the nodes with frames the port is to accept after you have activated this security mode on a port.
   - locked - Sets the switch to the Locked security mode. The port stops learning new dynamic MAC addresses. The port forwards frames based on static MAC addresses and those dynamic addresses it has already learned.

7. Do one of the following:

   - If you selected Automatic, which disables port security on the port, no further steps are required. Return to the Main Menu to save your change.
   - If you selected the Secure security level, remember to enter the static MAC addresses of the end nodes that can send packets through the port. For instructions on how to add static MAC addresses, refer to "Adding Static Unicast and Multicast MAC Addresses" on page 110.
   - If you selected Locked, no further steps are required. Return to the Main Menu to save your change. You can, if desired, add static addresses to a port operating in the Locked security mode. For instructions, refer to "Adding Static Unicast and Multicast MAC Addresses" on page 110.

Downloaded from www.Manualslib.com manuals search engine

- If you selected Limited, several new menu options are added to the Configure Port Security menu, as shown in Figure 209. Continue with Step 8 for instructions on configuring a port operating under the Limited security level.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                            11:20:02 02-Mar-2005
                   Configure Port Security
 Configuring Port Security 4
1 - Security Mode ..................... Limited
2 - Intruder Action ................... No Action
3 - Port Participating ................ No
4 - Threshold ......................... 100

D - Set Default Port Security
R - Return to Previous Menu

Enter your selection?
```

Figure 209. Configure Port Security Menu #2

8. To specify the maximum number of dynamic MAC addresses you want the port to be able to learn, do the following:

   a. Type **2** to select Threshold.

      The following prompt is displayed:

      ```
      Enter port security threshold: [1 to 255] -> 100
      ```

   b. Enter the maximum number of dynamic MAC addresses you want the port to be able to learn. The range is 1 to 255. The default is 100.

9. To set the intrusion action for the port, do the following:

   a. Type **3** to select Intruder Action.

      The following prompt is displayed:

      ```
      Enter intrusion action: (N-Discard, T-Trap, D-
      Disable):
      ```

   b. Select the desired intrusion action:

      N - Discard: The port discards invalid frames. This is the default.

      T - Trap: The port discards invalid frames and sends an SNMP trap.

      D - Disable: The port discards invalid frames, sends an SNMP trap, and disables the port.

Downloaded from www.Manualslib.com manuals search engine

10. If you selected the trap or disable intrusion action, type **4** to toggle the Port Participating option to Yes.

    Option 3, Port Participating, only applies when the intrusion action is set to trap or disable. This option does not apply when intrusion action is set to discard. If this option is set to No when intrusion action is set to trap or disable, the port discards invalid packets, but it does not send an SNMP trap or disable the port. If you want the switch to send a trap and/or disable the port, be sure to sent this option to Yes.

11. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Displaying Port Security Levels

To view the current security levels and intrusion actions for the ports on the switch, perform the following procedure:

1. From the Main Menu, type **1** to select Port Configuration.
2. From the Port Configuration menu, type **5** to select Port Security.

   The Port Security menu is shown in Figure 207 on page 562.
3. From the Port Security menu, type **2** to select Display Port Security.

   The Display Port Security menu is shown in Figure 210.

```
               Allied Telesis AT-9424T/SP - AT-S63
                            Marketing
User: Manager                                    11:20:02 02-Mar-2005
                        Display Port Security

Port  Security Mode  Threshold   Intruder Action  Participating
-------------------------------------------------------------------
1     Limited       6           Trap             Yes
2     Limited       10          Trap             Yes
3     Automatic     ---         ------           ---
4     Locked        ---         ------           ---
5     Automatic     ---         ------           ---
6     Automatic     ---         ------           ---
7     Automatic     ---         ------           ---
8     Secured       ---         ------           ---

N - Next Page
U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 210. Display Port Security Menu

The Display Port Security menu displays a table that contains the following columns of information:

Port
The number of the port.

Security Mode
The active security mode on the port.

Threshold
The maximum number of dynamic MAC addresses the port learns. It only applies when a port is operating in the Limited security mode.

Downloaded from www.Manualslib.com manuals search engine

Intruder Action
The action taken by a port if it receives an invalid frame while operating in the Limited security mode. The possible settings are:

- Discard - The port discards invalid frames. This is the default.
- Trap - The port discards invalid frames and sends a trap.
- Trap/Disable - The port discards invalid frames, sends a trap, and disables the port.

Note
Though this is not reflected in the Display Port Security menu, ports operating in the Secure or Locked security mode discard all invalid frames.

Participating
This column applies only when the intrusion action for a port operating in the Limited security mode is set to trap or disable. This option does not apply when intrusion action is set to No Action (discard). If this option is set to No when intrusion action is set to trap or disable, the port discards invalid packets, but it does not send a trap or disable the port.

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Chapter 31

802.1x Port-based Network Access Control

This chapter explains 802.1x Port-based Network Access Control and how this feature can increase network security by restricting access to the network ports on the switch. Sections are as follows:

- ❒ “Setting Port Roles” on page 570
- ❒ “Enabling or Disabling 802.1x Port-based Network Access Control” on page 572
- ❒ “Configuring Authenticator Port Parameters” on page 573
- ❒ “Configuring Supplicant Port Parameters” on page 579
- ❒ “Displaying the Port Access Parameters” on page 582
- ❒ “Configuring RADIUS Accounting” on page 584

Downloaded from www.Manualslib.com manuals search engine

Setting Port Roles

This procedure sets the role of a port to authenticator or supplicant. You must set the role of a port before you can configure its settings.

To set port roles, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.

   The Security and Services menu is shown in Figure 71 on page 220.

2. From the Security and Services menu, type **2** to select Port Access Control (802.1X).

   The Port Access Control (802.1X) menu is shown in Figure 211.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                            11:20:02 02-Mar-2005
                Port Access Control (802.1X)

1 - Port Access Control ............... Enabled
2 - Authentication Method ............. RADIUS EAP
3 - Configure Port Access Role
4 - Configure Authenticator
5 - Configure Supplicant
6 - Display Port Access Status
7 - Configure Accounting

R - Return to Previous Menu

Enter your selection?
```

Figure 211. Port Access Control (802.1X) Menu

3. From the Port Access Control menu, type **3** to select Configure Port Access Role.

   The following prompt is displayed:

   ```
   Enter port list ->
   ```

4. Enter the port whose role you want to change. You can configure more than one port at a time. You can specify ports individually (for example, 5,7,22), as a range (for example, 18-23), or both (for example 1,5,14-22).

Downloaded from www.Manualslib.com manuals search engine

The Configure Port Access Role menu is shown in Figure 212.

```
          Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                          11:20:02 02-Mar-2005
                Configure Port Access Role

Configuring Port 3
1 - Port Role ......... None

R - Return to Previous Menu

Enter your selection?
```

Figure 212. Configure Port Access Role Menu

5. Type **1** to select Port Role.

   The following prompt is displayed:

   ```
   Enter new Port Role [N-None, A-Authenticator,
   S-Supplicant] ->
   ```

6. If you type **N** for None, the port does not participate in port access control. This is the default setting. If the port is connected to a supplicant, type **A** to set the port's role to Authenticator. If the port is connected to an authenticator, type **S** to set the port's roles to Supplicant.

7. Repeat this procedure starting with Step 3 to configure the role of the other ports on the switch.

   After you have set port roles, go to "Configuring Authenticator Port Parameters" on page 573 and "Configuring Supplicant Port Parameters" on page 579 to configure the port settings.

Downloaded from www.Manualslib.com manuals search engine

Enabling or Disabling 802.1x Port-based Network Access Control

This procedure explains how to enable and disable port-based access control on the switch. If you have not assigned port roles and configured the parameter settings, you should skip this procedure and go first to “Setting Port Roles” on page 570. To configure the port settings, refer to “Configuring Authenticator Port Parameters” on page 573 and “Configuring Supplicant Port Parameters” on page 579.

To enable or disable 802.1x Port-based Network Access Control, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.

   The Security and Services menu is shown in Figure 71 on page 220.

2. From the Security and Services menu, type **2** to select Port Access Control (802.1X).

   The Port Access Control (802.1X) menu is shown in Figure 211 on page 570.

3. From the Port Access Control menu, type **1** to select Port Access Control.

   The following prompt is displayed:

   ```
   Port Access Control (E-Enable, D-Disable):
   ```

4. Type **E** to enable port access control, or **D** to disable port access control.

5. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Configuring Authenticator Port Parameters

Note
A port must already be set to the authenticator role before you can configure its settings. For instructions on how to change the role of a port, refer to "Setting Port Roles" on page 570.

To configure the parameters of an authenticator port, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.

   The Security and Services menu is shown in Figure 71 on page 220.

2. From the Security and Services menu, type **2** to select Port Access Control (802.1X).

   The Port Access Control (802.1X) menu is shown in Figure 211 on page 570.

3. From the Port Access Control menu, type **4** to select Configure Authenticator.

   The Configure Authenticator menu is shown in Figure 213.

```
            Allied Telesis AT-9424T/SP - AT-S63
                         Marketing
User: Manager                              11:20:02 02-Mar-2005
                   Configure Authenticator

 1 - Configure Authenticator Port Access Parameters
 2 - Display Authenticator Port Access Parameters

 R - Return to Previous Menu

 Enter your selection?
```

Figure 213. Configure Authenticator Menu

4. From the Configure Authenticator menu, type **1** to select Configure Authenticator Port Access Parameters.

   The following prompt is displayed:

   ```
   Enter port list ->
   ```

5. Enter the authenticator port number whose parameters you want to change. You can configure more than one port at a time.

Downloaded from www.Manualslib.com manuals search engine

The Configure Authenticator Port Access Parameters menu is shown in Figure 214.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                            11:20:02 02-Mar-2005
      Configure Authenticator Port Access Parameters

 Configuring Port 3
0 - Authentication Mode ..... 802.1x
1 - Supplicant Mode ......... Single
2 - Port Control ............ Auto
3 - Quiet Period ............ 60 Seconds
4 - TX Period ............... 30 Seconds
5 - Reauth Enabled .......... Enabled
6 - Reauth Period ........... 3600 Seconds
7 - Supplicant Timeout ...... 30 Seconds
8 - Server Timeout .......... 30 Seconds
9 - Max Requests ............ 2
A - VLAN Assignment ......... Enabled
B - Secure VLAN ............. On
C - Control Direction ....... Both
D - Piggyback Mode .......... Disabled
E - Guest VLAN .............. None

R - Return to Previous Menu

Enter your selection?
```

Figure 214. Configure Authenticator Port Access Parameters Menu

6. Adjust the following parameters as necessary.

   0 - Authentication Mode
   This parameter can take the following values on an authenticator port:

   - **802.1x**: Specifies 802.1x username and password authentication. With this authentication method the supplicant must provide, either manually or automatically, a username and password. This authentication method requires 802.1x client software on the supplicant nodes.
   - **MAC based**: Specifies MAC address-based authentication. The authenticator port extracts the source MAC address from the initial frames received from a supplicant and automatically sends the address as both the username and password of the supplicant to the authentication server. Supplicant nodes must have 802.1x client software for this authentication method.

Downloaded from www.Manualslib.com manuals search engine

1 - Supplicant Mode
This parameter can take the following values on an authenticator port:

- **Single**: Configures the authenticator port to accept only one authentication. This supplicant mode should be used together with the piggy-back mode. When an authenticator port is set to the Single mode and the piggy-back mode is disabled, only the one client who is authenticated can use the port. Packets from or to other clients on the port are discarded. If piggy-back mode is enabled, other clients can piggy-back onto another client's authentication and so be able to use the port.
- **Multiple**: Configures the authenticator port to accept up to 320 authentications. Every client using an authenticator port in this mode must have a username and password combination.

2 - Port Control
The possible settings for this parameter are:

Auto - Enables 802.1x port-based authentication and causes the port to begin in the unauthorized state, allowing only EAPOL frames to be sent and received through the port. The authentication process begins when the link state of the port changes or the port receives an EAPOL-Start packet from a supplicant. The switch requests the identity of the client and begins relaying authentication messages between the client and the authentication server. Each client that attempts to access the network is uniquely identified by the switch using the client's MAC address. This is the default setting.

Force-authorized - Disables IEEE 802.1X port-based authentication and causes the port to transition to the authorized state without any authentication exchange required. The port transmits and receives normal traffic without 802.1x-based authentication of the client.

Force-unauthorized - Causes the port to remain in the unauthorized state, ignoring all attempts by the client to authenticate. The switch cannot provide authentication services to the client through the port.

3 - Quiet Period
The quiet period is the number of seconds that the port remains in the quiet state following a failed authentication exchange with the client. The default value is 60 seconds. The range is 0 to 65,535 seconds.

4 - TX Period
This parameter sets the number of seconds that the switch waits for a response to an EAP-request/identity frame from the client before retransmitting the request. The default value is 30 seconds. The range is 1 to 65,535 seconds.

5 - Reauth Enabled
Specifies if reauthentication should occur according to the reauthentication period. The options are Enabled or Disabled. If

Downloaded from www.Manualslib.com manuals search engine

disabled, the supplicant is not require to reauthenticate after the initial authentication.

6 - Reauth Period
Specifies the time period in seconds between reauthentications of the client when the Reauth. Enabled option is set to Enabled. The default value is 3600 seconds. The range is 1 to 65,535 seconds.

7 - Supplicant Timeout
This parameter sets the switch-to-client retransmission time for the EAP-request frame. The default value for this parameter is 30 seconds. The range is 1 to 600 seconds.

8 - Server Timeout
This parameter sets the timer used by the switch to determine authentication server timeout conditions. The default value for this parameter is 30 seconds. The range is 1 to 600 seconds.

9 - Max Requests
This parameter specifies the maximum number of times that the switch retransmits an EAP Request packet to the client before it times out the authentication session. The default value for this parameter is 2 retransmissions. The range is 1 to 10 retransmissions.

A - VLAN Assignment
This parameter controls whether an authenticator port uses the VLAN assignments returned by a RADIUS server. Options are:

- **Enabled**: Specifies that the authenticator port is to use the VLAN assignment returned by the RADIUS server when a supplicant logs on. This is the default setting. The port automatically moves to the designated VLAN after the supplicant successfully logs on.
- **Disabled**: Specifies that the authenticator port ignore any VLAN assignment information returned by the RADIUS server when a supplicant logs on. The authenticator port remains in its predefined VLAN assignment even if the RADIUS server returns a VLAN assignment when a supplicant logs on. This is the default setting.

B - Secure VLAN
This parameter controls the action of an authenticator port to subsequent authentications after the initial authentication where VLAN assignments have been added to the user accounts on the RADIUS server. This parameter only applies when the port is operating in the Multiple operating mode. Possible settings are:

- **On**: Specifies that only those supplicants with the same VLAN assignment as the initial supplicant are authenticated. Supplicants with a different or no VLAN assignment are denied entry to the port. This is the default setting.
- **Off**: Specifies that all supplicants, regardless of their assigned VLANs, are authenticated. However, the port remains in the VLAN

Downloaded from www.Manualslib.com manuals search engine

specified in the initial authentication, regardless of the VLAN assignments of subsequent authentications.

C - Control Direction
This parameter specifies how the port handles ingress and egress broadcast and multicast packets when in the unauthorized state. When a port is set to the authenticator role, it remains in the unauthorized state until a client logs on by providing a username and password combination. In the unauthorized state, the port only accepts EAP packets from the client. All other ingress packets that the port might receive from the client, including multicast and broadcast traffic, is discarded until the supplicant has logged in. The options are:

- **Ingress**: A port, when in the unauthorized state, discards all ingress broadcast and multicast packets from the client, but forwards all egress broadcast and multicast traffic to the same client.
- **Both**: A port, when in the unauthorized state, does not forward ingress or egress broadcast and multicast packets from or to the same client until the client logs in. This is the default.

Note
This parameter is only available when the authenticator's mode is set to Single. When set to Multiple, a port does not forward ingress or egress broadcast or multicast packets until at least one client has logged on.

D - Piggyback Mode
This parameter controls who can use the switch port in cases where there are multiple clients using the port (e.g., the switch port is connected to an Ethernet hub). If set to enabled, the port allows all clients on the port to piggy-back onto the initial client's authentication, forwarding all packets after one client is authenticated. If set to Disabled, the switch port forwards only those packets from the client who is authenticated and discards packets from all other users.

Note
This parameter is only available when the authenticator's mode is set to Single.

E - Guest VLAN
This parameter specifies the name or VID of a Guest VLAN. The authenticator port is a member of a Guest VLAN when no supplicant is logged on. Clients do not log on to access a Guest VLAN. To remove a Guest VLAN without assigning a new one, enter "none".

7. Repeat this procedure starting with Step 4 to configure additional authenticator ports on the switch.

Downloaded from www.Manualslib.com manuals search engine

8. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Configuring Supplicant Port Parameters

Note
A port must already be set to the supplicant role before you can configure its settings. For instructions on how to change the role of a port, refer to "Setting Port Roles" on page 570.

To configure supplicant port parameters, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.

   The Security and Services menu is shown in Figure 71 on page 220.

2. From the Security and Services menu, type **2** to select Port Access Control (802.1X).

   The Port Access Control (802.1X) menu is shown in Figure 211 on page 570.

3. From the Port Access Control menu, type **5** to select Configure Supplicant.

   The Configure Supplicant menu is shown in Figure 213.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                  Configure Supplicant

 1 - Configure Supplicant Port Access Parameters
 2 - Display Supplicant Port Access Parameters

 R - Return to Previous Menu

 Enter your selection?
```

Figure 215. Configure Supplicant Menu

4. From the Configure Supplicant menu, type **1** to select Configure Authenticator Port Access Parameters.

   The following prompt is displayed:

   ```
   Enter port list ->
   ```

5. Enter the supplicant port number whose parameters you want to change. You can specify one port or a range of ports (for example, 4-8), but not multiple individual ports (for example, 4,6,11).

Downloaded from www.Manualslib.com manuals search engine

The Configure Supplicant Port Access Parameters menu is shown in Figure 214.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                              11:20:02 02-Mar-2005
        Configure Supplicant Port Access Parameters

 Configuring Port 5-8
 1 - Auth Period........... 30 Seconds
 2 - Held Period........... 60 Seconds
 3 - Max Start  ........... 3
 4 - Start Period.......... 30 Seconds
 5 - User Name: ...........
 6 - User Password: .......

 R - Return to Previous Menu

 Enter your selection?
```

Figure 216. Configure Supplicant Port Access Parameters Menu

6. Adjust the following parameters as necessary.

1 - Auth Period
This parameter specifies the period of time in seconds that the supplicant waits for a reply from the authenticator after sending an EAP-Response frame. The range is 1 to 300 seconds. The default is 30 seconds.

2 - Held Period
The held period specifies the amount of time in seconds the supplicant is to refrain from retrying to re-contact the authenticator in the event the end user provides an invalid username and/or password. After the time period has expired, the supplicant can attempt to log on again. The range is 0 to 65,535. The default value is 60.

3 - Max Start
Max start is the maximum number of times the supplicant sends EAPOL-Start frames before assuming that there is no authenticator present. The range is 1 to 10. The default is 3.

4 - Start Period
The start period is the time period in seconds between successive attempts by the supplicant to establish contact with an authenticator when there is no reply. The range is 1 to 60. The default is 30.

5 - User Name
The user name is the username for the switch port. The port sends the name to the authentication server for verification when the port logs on to the network. The username can be from 1 to 16 alphanumeric characters (A to Z, a to z, 1 to 9). Do not use spaces or special

Downloaded from www.Manualslib.com manuals search engine

characters, such as asterisks or exclamation points. The username is case sensitive.

6 - User Password
This parameter specifies the password for the switch port. The port sends the password to the authentication server for verification when the port logs on to the network. The password can be from 1 to 16 alphanumeric characters (A to Z, a to z, 1 to 9). Do not use spaces or special characters, such as asterisks or exclamation points. The password is case sensitive.

7. Repeat this procedure starting with Step 4 to configure additional supplicant ports on the switch.

8. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Displaying the Port Access Parameters

To display the port access parameters for the ports on the switch, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.

   The Security and Services menu is shown in Figure 71 on page 220.

2. From the Security and Services menu, type **2** to select Port Access Control (802.1X).

   The Port Access Control (802.1X) menu is shown in Figure 211 on page 570.

3. From the Port Access Control menu, type **6** to select Display Port Access status.

   The Display Port Access Status menu is shown in Figure 217.

```
                    Allied Telesis AT-9424T/SP - AT-S63
                                Marketing
User: Manager                                          11:20:02 02-Mar-2006
                         Display Port Access Status

Port  PortRole        AuthMode      State           Additional Info
-------------------------------------------------------------------------
1     None                          ------          ------------------
2     Authenticator   802.1x        Connecting      ------------------
3     Authenticator   802.1x        Authenticated   00:a0:d2:18:1a:c8
4     Authenticator   MAC Based     Connecting      ------------------
5     None                          ------          ------------------
6     None                          ------          ------------------
7     None                          ------          ------------------
8     Supplicant                    Disabled        ------------------

N - Next Page
U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 217. Display Port Access Status Menu

The Display Port Access Status menu displays a table that contains the following columns of information:

Port
Port number.

Downloaded from www.Manualslib.com manuals search engine

Port Role
Port access role configured for the port. The possible settings are None, Authenticator, or Supplicant.

AuthMode
The port's authentication mode: 802.1x or MAC Based.

State
State of the port. The state field is dependent on whether a port is configured as an authenticator or a supplicant. The State field can have the following values for an authenticator port:

Aborting
Authenticated
Authenticating
Connecting
Disconnected
Force_Auth
Force_Unauth
Held
Initialize

The State field can have the following values for a supplicant port:

Acquired
Authenticated
Authenticating
Connecting
Disconnected
Held
Logoff

Additional Info
This field displays the MAC address of an authenticated node for authenticator ports with a status of Authenticated.

Downloaded from www.Manualslib.com manuals search engine

Configuring RADIUS Accounting

The AT-S63 Management Software supports RADIUS accounting for ports operating in the Authenticator role. The accounting information sent by the switch to a RADIUS server includes the date and time when clients log on and log off, as well as the number of packets sent and received by a switch port during a client session. The default setting for this feature on the switch is disabled.

To configure this feature, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.

   The Security and Services menu is shown in Figure 71 on page 220.

2. From the Security and Services menu, type **2** to select Port Access Control (802.1X).

   The Port Access Control (802.1X) menu is shown in Figure 211 on page 570.

3. From the Port Access Control (802.1X) menu, type **7** to select Configure Accounting.

   The RADIUS Accounting menu is shown in Figure 218.

```
            Allied Telesis AT-9424T/SP - AT-S63
                         Marketing
User: Manager                              11:20:02 02-Mar-2005
                      RADIUS Accounting

1 - Status............ Disabled
2 - Port.............. 1813
3 - Type.............. Network
4 - Trigger Type...... Start_Stop
5 - Update Status..... Disabled
6 - Update Interval... 60

R - Return to Previous Menu

Enter your selection?
```

Figure 218. Radius Accounting Menu

Downloaded from www.Manualslib.com manuals search engine

4. Adjust the following parameters as necessary.

   1 - Status
   This parameter activates or deactivates RADIUS accounting on the switch. Select Enabled to activate the feature or Disabled to deactivate it. The default is Disabled.

   2 - Port
   This parameter specifies the UDP port for RADIUS accounting. The default is port 1813.

   3 - Type
   This parameter specifies the type of RADIUS accounting. The default is Network. This value cannot be changed.

   4 - Trigger Type
   This parameter specifies the action that causes the switch to send accounting information to the RADIUS server. The options are:

   Start_Stop
   The switch sends accounting information whenever a client logs on or logs off the network. This is the default.

   Stop
   The switch sends accounting information only when a client logs off.

   5 - Update Status
   This parameter controls whether the switch is to send interim accounting updates to the RADIUS server. The default is disabled. If you enable this feature, use the next option in the menu to specify the intervals at which the switch is to send the accounting updates.

   6 - Update Interval
   This parameter specifies the intervals at which the switch sends interim accounting updates to the RADIUS server. The range is 30 to 300 seconds. The default is 60 seconds.

5. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Section IX

Management Security

The chapters in this section contain overview information on the management security features of the AT-9400 Switch. The chapters also explain how to configure these features from the menu interface of the AT-S63 Management Software. The chapters include:

- Chapter 32, “Web Server” on page 589
- Chapter 33, “Encryption Keys” on page 595
- Chapter 34, “PKI Certificates and SSL” on page 611
- Chapter 35, “Secure Shell (SSH)” on page 633
- Chapter 36, “TACACS+ and RADIUS Protocols” on page 639
- Chapter 37, “Management Access Control List” on page 651

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Chapter 32

Web Server

The chapter provides an overview of the web server feature and procedures for configuring the server. It contains the following sections:

- “Configuring the Web Server” on page 590
- “General Steps for Configuring the Web Server for Encryption” on page 593

Downloaded from www.Manualslib.com manuals search engine

Configuring the Web Server

This procedure explains how to enable and disable the web server and how to configure the HTTP and HTTPS settings from a local or Telnet management session. The default setting for the web server is enabled, with the non-secure HTTP mode as the active web server mode.

Before you configure the web server, note the following:

- You cannot make any changes to the HTTP or HTTPS settings while the web server is enabled. You must first disable the web server before making changes.
- To configure the web server for the HTTPS secure mode, you must first create an encryption key and a certificate, and add the certificate to the certificate database. The AT-S63 Management Software does not allow you to configure the web server for the HTTPS secure mode until those steps have been completed. For instructions, refer to Chapter 33, “Encryption Keys” on page 595, and Chapter 34, “PKI Certificates and SSL” on page 611. For an overview of all the steps, see “General Steps for Configuring the Web Server for Encryption” on page 593.
- To change an HTTP or HTTPS setting, you must perform the entire procedure. For example, to change the port number for HTTP, you must first disable the web server and then reselect HTTP.

To configure the web server, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **4** to select Web Server Configuration.

   The Web Server Configuration menu is shown in Figure 219.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                           11:20:02 02-Mar-2005
                   Web Server Configuration

1 - Status ............................ Disabled
2 - Mode .............................. HTTP
3 - Port Number ....................... 80

R - Return to Previous Menu

Enter your selection?
```

Figure 219. Web Server Configuration Menu

Downloaded from www.Manualslib.com manuals search engine

3. Type **1** to select Status to enable or disable the web server. To configure the web server, you must first disable it. Possible settings are:

   Enabled - Enables the web server. This is the default setting.

   Disabled - Disables the web server. (To change any of the web server settings, you must first disable it.)

4. Type **2** to select Mode to set the mode of the web server. The following prompt is displayed:

   ```
   Enter Web Server Mode (1 - HTTP, 2 - HTTPS):
   [1 to 2] ->
   ```

1. Choose one of the following:

   1 - HTTP to select the non-secure HTTP mode for the web server. This is the default value.

   2 - HTTPS to select the secure HTTPS mode. This setting activates the SSL protocol on the web server.

   When you choose HTTPS, the following prompt is displayed:

   ```
   Enter SSL Key ID ->
   ```

2. Enter an SSL Key ID.

   Enter the ID number of an encryption key on the switch. (To view the encryption key IDs, refer to "Creating an Encryption Key" on page 596.) The encryption key and its certificate must already exist on the switch and the certificate must be in the certificate database.

3. To enable the web server, type **1** to toggle Status to **Enabled**.

   The Web Server Configuration menu is redisplayed. Figure 220 shows an example of the menu configured for HTTPS.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                          11:20:02 02-Mar-2005
                Web Server Configuration

1 - Status ............................ Enabled
2 - Mode .............................. HTTPS
3 - Port Number ....................... 443
4 - SSL Key ID ........................ 243

R - Return to Previous Menu

Enter your selection?
```

Figure 220. Web Server Configuration Menu Configured for HTTPS

Downloaded from www.Manualslib.com manuals search engine

The default port number for HTTP is 80. The default port number for HTTPS is 443.

1. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

General Steps for Configuring the Web Server for Encryption

There are several procedures you need to perform in order to implement HTTPS and web browser encryption on the switch. This section is here to provide you with the general steps you need to do and the procedures for performing them. There is a section for configuring the web server with a self-signed certificate and another for a public or private CA certificate.

General Steps for a Self-signed Certificate

Below are the general steps for setting up the web server with a self-signed certificate.

1. Set the switch's date and time. You must do this before you create a certificate because the date and time are stamped in the digital document. For instructions, refer to "Setting the System Time" on page 38.
2. Create a public and private key pair, as explained in "Creating an Encryption Key" on page 596.
3. Create a self-signed certificate using the key pair, as explained in "Creating a Self-signed Certificate" on page 612.
4. Add the certificate to the certificate database, as explained in "Adding a Certificate to the Database" on page 616.
5. Configure the web server on the switch by activating HTTPS and specifying the key pair used to create the certificate as the active key. This step is explained in "Configuring the Web Server" on page 590.

General Steps for a Public or Private CA Certificate

Below are the steps for setting up the web server with a public or private CA certificate. This requires generating an enrollment request.

1. Set the switch's date and time. You must do this before you create the enrollment request. The date and time at stamped in the request. The instructions for this are in "Setting the System Time" on page 38.
2. Create a public and private key pair, as explained in "Creating an Encryption Key" on page 596.
3. Generate an enrollment request, as explained in "Generating an Enrollment Request" on page 627.
4. Upload the enrollment request from the switch's file system onto your management station or a TFTP server, as explained in "Uploading a System File" on page 190.
5. Submit the enrollment request to the public or private CA.

Downloaded from www.Manualslib.com manuals search engine

6. After you have received the appropriate certificates from the CA, download them into the switch's file system from your management station or a TFTP server, as explained in "Downloading a System File" on page 182.

7. Add the certificates to the certificate database, as explained in "Adding a Certificate to the Database" on page 616.

8. Configure the web server on the switch by activating HTTPS and specifying the key pair used to create the enrollment request as the active key. This step is explained in "Configuring the Web Server" on page 590.

Downloaded from www.Manualslib.com manuals search engine

Chapter 33

Encryption Keys

This chapter describes encryption keys and how you can use keys to improve the security of your switches. Because of the complexity of the feature, this chapter contains two overview sections. The Basic Overview section offers a general review of the purpose of this feature along with relevant guidelines. For additional information, refer to the Technical Overview section. The sections in this chapter include:

- ❒ “Creating an Encryption Key” on page 596
- ❒ “Deleting an Encryption Key” on page 600
- ❒ “Modifying an Encryption Key” on page 601
- ❒ “Exporting an Encryption Key” on page 602
- ❒ “Importing an Encryption Key” on page 605
- ❒ “Displaying the Encryption Keys” on page 608

For an overview of the procedures to configuring the switch’s web server for encryption, refer to “General Steps for Configuring the Web Server for Encryption” on page 593.

Downloaded from www.Manualslib.com manuals search engine

Creating an Encryption Key

This section contains the procedure for creating an encryption key pair.

Caution
Key generation is a CPU-intensive process. Because this process may affect switch behavior, Allied Telesis recommends creating keys when the switch is not connected to a network or during periods of low network activity.

To create an encryption key, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.

   The Security and Services menu is shown in Figure 71 on page 220.

2. From the Security and Services menu, type **7** to select Keys/Certificate Configuration.

   The Keys/Certificate Configuration menu is shown in Figure 221.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                           11:20:02 02-Mar-2005
              Keys/Certificates Configuration

 1 - Switch Distinguished Name (DN)
 2 - Key Management
 3 - Public Key Infrastructure (PKI) Configuration

 R - Return to Previous Menu

 Enter your selection?
```

Figure 221. Keys/Certificate Configuration Menu

3. From the Keys/Certificates Configuration menu, type **2** to select Key Management.

Downloaded from www.Manualslib.com manuals search engine

The Key Management menu is shown in Figure 222.

```
            Allied Telesis AT-9424T/SP - AT-S63
                          Marketing
User: Manager                              11:20:02 02-Mar-2005
                        Key Management

 ID  Algorithm    Length  Digest    Description
 ------------------------------------------------------------
 1   RSA-Private  512     642C6FC8  Marketing Switch key 1
 2   RSA-Private  512     5333E64F  Marketing Switch key 2

 1 - Create Key
 2 - Delete Key
 3 - Modify Key
 4 - Export Key to File
 5 - Import Key from File

 N - Next Page
 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 222. Key Management Menu

4. Type **1** to select Create Key.

   The Create Key menu is shown in Figure 223.

```
            Allied Telesis AT-9424T/SP - AT-S63
                          Marketing
User: Manager                              11:20:02 02-Mar-2005
                         Create Key

1 - Key ID ..............  0
2 - Key Type ............  RSA-Private
3 - Key Length ..........  512
4 - Key Description ....
5 - Generate Key

U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 223. Create Key Menu

5. From the Create Key menu, type **1** to select Key ID.

   The following prompt is displayed:

   ```
   Enter Key Id -> [0 to 65535] -> 0
   ```


Downloaded from www.Manualslib.com manuals search engine

6. Enter an identification number for the key. This number can be from 0 to 65,535. This number is used only for identification purposes and not in generating the actual encryption key. The ID for each key on the switch must be unique.

   Note
   You cannot change the value for option 2, Key Type. This value is always RSA - Private.

7. Type **3** to select Key Length.

   The following prompt is displayed:

   ```
   Enter Key Length ->[512 to 1536] -> 512
   ```

8. Enter a key length. The range is 512 to 1,536 bits, in increments of 256 bits (for example, 512, 768, 1024, etc). Before selecting a key length, note the following

   - For SSL and web browser encryption, key length can be any valid value within the range.
   - For SSH host and server key pairs, the two keys must be created separately and be of different lengths of at least one increment (256 bits) apart. The recommended length is 768 bits for the server key and 1024 bits for the host key.

9. Type **4** to select Key Description.

   The following prompt is displayed:

   ```
   Enter new Description ->
   ```

10. Enter a description for the key. For instance, the description could reflect the name of the switch (for example, Production switch web server key). You can enter up to 40 alphanumeric values including spaces.

11. Type **5** to select Generate Key.

    The following message is displayed:

    ```
    Key generation will take some time. Please wait...
    ```

    The AT-S63 Management Software begins to create the key. This process can take over a minute if you specified a long key length. After the key is created, you will see this message:

    ```
    Press any key to continue ...
    ```

12. Press any key.

Downloaded from www.Manualslib.com manuals search engine

The new key is added to the list of keys in the Key Management menu.

Returning to the Main Menu to save your changes is not necessary with this procedure. This type of change is automatically saved by the management software.

To create a self-signed certificate using the new encryption key, go to "Creating a Self-signed Certificate" on page 612. To create an enrollment request, go to "Generating an Enrollment Request" on page 627.

If you created server and host keys for SSH encryption, go to "Configuring SSH" on page 634 to configure the SSH server software on the switch.

Downloaded from www.Manualslib.com manuals search engine

Deleting an Encryption Key

This section contains the procedure for deleting an encryption key pair from the switch. Note the following before performing this procedure.

- Deleting a key pair from the key management database also deletes the key's corresponding ".ukf" file from the AT-S63 file system.
- You cannot delete a key pair if it is being used by SSL or SSH. You must either disable the SSL or SSH server software or reconfigure the software by specifying another key.
- Deleting a key pair used in creating an SSL certificate voids the certificate.

To delete a public and private key pair, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.

   The Security and Services menu is shown in Figure 71 on page 220.

2. From the Security and Services menu, type **7** to select Keys/Certificate Configuration.

   The Keys/Certificate Configuration menu is shown in Figure 221 on page 596.

3. From the Keys/Certificates Configuration menu, type **2** to select Key Management.

   The Key Management menu is shown in Figure 222 on page 597.

4. From the Key Management menu, type **2** to select Delete Key.

   The following prompt is displayed:

   ```
   Enter Key Id to delete -> [0 to 65535] -> 0
   ```

5. Enter the ID number of the key you want to delete.

   The key pair is deleted from the key database and its corresponding ".UKF" file is deleted from the file system.

   Returning to the Main Menu to save your changes is not necessary with this procedure. This type of change is automatically saved by the management software.

Downloaded from www.Manualslib.com manuals search engine

Modifying an Encryption Key

The Key Management menu has a selection for modifying the description of an encryption key. This is the only item of a key that you can modify. You cannot change a key's ID, type, or length.

To change the description of a key, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.

   The Security and Services menu is shown in Figure 71 on page 220.

2. From the Security and Services menu, type **7** to select Keys/Certificate Configuration.

   The Keys/Certificate Configuration menu is shown in Figure 221 on page 596.

3. From the Keys/Certificates Configuration menu, type **2** to select Key Management.

   The Key Management menu is shown in Figure 222 on page 597.

4. From the Key Management menu, type, type **3** to select Modify Key.

   The following prompt is displayed:

   ```
   Enter Key Id to modify -> [0 to 65535] -> 0
   ```

5. Enter the ID of the key whose description you want to modify.

   The following prompt is displayed.

   ```
   Enter new Description ->
   ```

6. Enter the new description for the key. The description can be up to 40 alphanumeric characters including spaces. To help identify the key, you might make the description the name of the web server the key will be used to protect (for example, Production switch web server).

   The following prompt is displayed:

   ```
   Press any key to continue ...
   ```

   The key has been modified.

7. Press any key to return to the Key Management menu.

   Returning to the Main Menu to save your changes is not necessary with this procedure. This type of change is automatically saved by the management software.

Downloaded from www.Manualslib.com manuals search engine

Exporting an Encryption Key

The following procedure exports the public key of a key pair into the AT-S63 file system. (The management software does not allow you to export a private key.) Before performing this procedure, please note the following:

- The only circumstance in which you are likely to perform this procedure is if you are using an SSH client that does not download the key automatically when you start an SSH management session. In that situation, you can use this procedure to export the SSH client key from the key database into the AT-S62 file system, from where you can upload it onto the SSH management session for incorporation in your SSH client software.
- You should not use this procedure to export a public key being used for SSL. Typically, an SSL public key only has value when incorporated into a certificate or enrollment request.

To export a public key into the file system, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.

   The Security and Services menu is shown in Figure 71 on page 220.

2. From the Security and Services menu, type **7** to select Keys/Certificate Configuration.

   The Keys/Certificate Configuration menu is shown in Figure 221 on page 596.

3. From the Keys/Certificates Configuration menu, type **2** to select Key Management.

   The Key Management menu is shown in Figure 222 on page 597.

4. From the Key Management menu, type, type **4** to select Export Key to File.

Downloaded from www.Manualslib.com manuals search engine

The Export Key to File menu is shown in Figure 224.

```
            Allied Telesis AT-9424T/SP - AT-S63
                          Marketing
User: Manager                            11:20:02 02-Mar-2005
                      Export Key to File

1 - Key ID ............. 0
2 - Key Type ........... RSA-Public
3 - Key File Format ... HEX
4 - Key File Name
5 - Export Key to File

R - Return to Previous Menu

Enter your selection?
```

Figure 224. Export Key to File Menu

5. From the Export Key to File menu, type **1** to select Key ID.

   The following prompt is displayed:

   ```
   Enter Key ID -> [0 to 65535] ->
   ```

6. Enter the key ID of the public key you want to export into the file system.

   Note
   Key Type is a read-only field. You cannot change this value.

7. Type **3** to toggle Key File Format to specify the format of the key. Possible options are:

   HEX - An internal format for storing files. Select this option for SSL configuration. This is the default.

   SSH - A format for a Secure Shell (SSH) environment. Select this option for a SSH server or client.

8. Type **4** to select Key File Name.

   The following prompt is displayed:

   ```
   Enter filename (*.key) ->
   ```

9. Specify the file name of the key. The file name can be from one to eight alphanumeric characters, not including the extension. Spaces are allowed. The file name must include the extension ".key".

10. Type **5** to select Export Key to File to export the key to a file.

Downloaded from www.Manualslib.com manuals search engine

The following message is displayed:

```
Key Export in Progress. Please wait...Done
```

11. Press any key to return to the Key Management menu.

To view the public key in the switch's file system, refer to "Displaying System Files" on page 159.

Returning to the Main Menu to save your changes is not necessary with this procedure. This type of change is automatically saved by the management software.

Downloaded from www.Manualslib.com manuals search engine

Importing an Encryption Key

Use the following procedure to import a public key from the AT-S63 file system into the key management database. If a file contains both public and private keys, only the public key is imported. The private key is ignored.

> **Note**
> It is unlikely that you will ever need to perform this procedure. A switch can only use those public keys that it has generated itself.

This procedure starts from the Key Management menu. If you are unsure how to display the menu, perform steps 1 to 3 in "Creating an Encryption Key" on page 596.

To import a public key, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.

   The Security and Services menu is shown in Figure 71 on page 220.

2. From the Security and Services menu, type **7** to select Keys/Certificate Configuration.

   The Keys/Certificate Configuration menu is shown in Figure 221 on page 596.

3. From the Keys/Certificates Configuration menu, type **2** to select Key Management.

   The Key Management menu is shown in Figure 222 on page 597.

4. From the Key Management menu, type **5** to select Import Key From File to import an RSA - Public key.

Downloaded from www.Manualslib.com manuals search engine

The Import Key from File menu is shown in Figure 225.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                          11:20:02 02-Mar-2005
                    Import Key from File

1 - Key ID ............ 0
2 - Key Type .......... RSA-Public
3 - Key File Format ... HEX
4 - Key File Name .....
5 - Import Key from File

R - Return to Previous Menu

Enter your selection?
```

Figure 225. Import Key from File Menu

5. From the Import Key from File menu, type **1** to select Key ID.

   The following prompt is displayed:

   ```
   Enter Key ID -> [0 to 65535] ->
   ```

6. Enter a key ID for the public key.

   This must be an unused key ID. It cannot match any of the key IDs that are already in use on the switch.

   Note
   You cannot change Option 2, Key Type.

7. Type **3** to select Key File Format to choose the format of the key. The possible options are:

   HEX - An internal format for storing files. Select this option for SSL configuration. This is the default.

   SSH - A format for a Secure Shell (SSH) environment. Select this option for a SSH server or client.

8. Type **4** to select Key File Name.

   The following prompt is displayed:

   ```
   Enter filename (*.key) ->
   ```

9. Specify the file name of the key.

Downloaded from www.Manualslib.com manuals search engine

The key file name must include the ".key" extension. If you are unsure of the file name, display the files in the switch's file system by referring to "Displaying System Files" on page 159.

10. Type **5** to select Import Key From File to import a key to the switch from an external file.

    The following message is displayed:

    ```
    Key Import in Progress. Please wait...Done
    ```

    After you receive this message, the key is added to the Key Management database. See the Key Management menu in Figure 222 on page 597.

    Returning to the Main Menu to save your changes is not necessary with this procedure. This type of change is automatically saved by the management software.

Downloaded from www.Manualslib.com manuals search engine

Displaying the Encryption Keys

To display the encryption keys, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.

   The Security and Services menu is shown in Figure 71 on page 220.

2. From the Security and Services menu, type **7** to select Keys/Certificate Configuration.

   The Keys/Certificate Configuration menu is shown in Figure 221 on page 596.

3. From the Keys/Certificates Configuration menu, type **2** to select Key Management.

   The Key Management Menu is shown in Figure 226.

```
              Allied Telesis AT-9424T/SP - AT-S63
                          Marketing
User: Manager                                 11:20:02 02-Mar-2005
                        Key Management

ID  Algorithm    Length  Digest    Description
------------------------------------------------------------
1   RSA-Private  512     642C6FC8  Marketing Switch key 1
2   RSA-Private  512     5333E64F  Marketing Switch key 2

1 - Create Key
2 - Delete Key
3 - Modify Key
4 - Export Key to File
5 - Import Key to File

N - Next Page
U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 226. Key Management Menu

The Key Management menu displays a table that contains the following columns of information:

ID
The identification number of the key.

Algorithm
The algorithm used in creating the encryption. This is always RSA-Private.

Downloaded from www.Manualslib.com manuals search engine

Length
The length of the key in bits.

Digest
The CRC32 value of the MD5 digest of the public key.

Description
The key's description.

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Chapter 34

PKI Certificates and SSL

This chapter contains the procedures for creating public key infrastructure (PKI) certificates for web server security. Because of the complexity of this feature, two overview sections are provided. The Basic Overview section offers a general review of the purpose of certificates along with relevant guidelines. For additional information refer to the Technical Overview section. This chapter contains the following sections:

- ❒ “Creating a Self-signed Certificate” on page 612
- ❒ “Adding a Certificate to the Database” on page 616
- ❒ “Modifying a Certificate” on page 619
- ❒ “Deleting a Certificate” on page 622
- ❒ “Viewing a Certificate” on page 624
- ❒ “Generating an Enrollment Request” on page 627
- ❒ “Installing CA Certificates onto a Switch” on page 630
- ❒ “Viewing and Configuring the Maximum Number of Certificates” on page 631
- ❒ “Configuring SSL” on page 632

Downloaded from www.Manualslib.com manuals search engine

Creating a Self-signed Certificate

This section contains the procedure for creating a self-signed certificate. Please review the following before you perform the procedure:

- For a general review of all the steps to configuring the switch for a self-signed certificate, refer to “General Steps for a Self-signed Certificate” on page 593.)
- The switch’s time and date must be set before you create a certificate. You can set this manually or you can configure the switch to obtain the date and time from an SNTP server on your network. For instructions, refer to “Setting the System Time” on page 38.
- You must generate an encryption key pair before creating a certificate. For instructions, refer to “Creating an Encryption Key” on page 596.
- During this procedure you are prompted to enter the ID number of the encryption key pair to be used to create the certificate. If you have forgotten the ID number of the key, refer to “Creating an Encryption Key” on page 596 to view key ID numbers.

To create a self-signed certificate, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.
2. From the Security and Services menu, type **7** to select Keys/Certificates Configuration.

   The Keys/Certificates Configuration menu is shown in Figure 221 on page 596.

   Note
   You can specify the distinguished name for the certificate from this menu by selecting option 1, Distinguished Name, in the Keys/Certificates Configuration menu and entering the name. Or, you can wait and specify the distinguished name later in this procedure.

3. From the Keys/Certificate menu, type **3** to select Public Key Infrastructure (PKI) Configuration.

Downloaded from www.Manualslib.com manuals search engine

The Public Key Infrastructure (PKI) Configuration menu is shown in Figure 227.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                            11:20:02 02-Mar-2005
       Public Key Infrastructure (PKI) Configuration

 1 - Maximum Number of Certificates....... 256
 2 - X509 Certificate Management
 3 - Generate Enrollment Request

 R - Return to Previous Menu

 Enter your selection?
```

Figure 227. Public Key Infrastructure (PKI) Configuration Menu

4. From the Public Key Infrastructure (PKI) Configuration menu, type **2** to select X509 Certificate Management.

   The X509 Certificate Management menu is shown in Figure 228.

```
          Allied Telesis AT-9424T/SP - AT-S63
                       Marketing
User: Manager                            11:20:02 02-Mar-2005
              X509 Certificate Management

 Certificate Database:
 Name          State    MTrust  Type   Source
 ------------------------------------------------------
 Switch43cert  Trusted  False   Self   Command

 1 - Create Self-Signed Certificate
 2 - Add Certificate
 3 - Delete Certificate
 4 - Modify Certificate
 5 - View Certificate Details

 U - Update Display
 R - Return to Previous Menu

 Enter your selection?
```

Figure 228. X509 Certificate Management Menu

The Certificate Database portion of the menu lists the certificates that you created (or had a CA create) and added to the database. The switch's web server can only use a certificate if it is in the database.

Downloaded from www.Manualslib.com manuals search engine

Note
In the X509 Certificate Management menu, MTrust means manually trusted. This field indicates that you verified the certificate. The Source field indicates the certificate was generated on the switch. Both MTrust and Source are read-only fields.

5. Type **1** to select Create Self-Signed Certificate.

   The Create Self-Signed Certificate menu is shown in Figure 229.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                            11:20:02 02-Mar-2005
                Create Self-Signed Certificate

 1 - Certificate Name.............
 2 - Key Pair ID.................. 0
 3 - Format....................... DER
 4 - Serial Number................ 0
 5 - Subject DN...................
 6 - Create Self-Signed Certificate

 R - Return to Previous Menu

 Enter your selection?
```

Figure 229. Create Self-Signed Certificate Menu

6. Type **1** to select Certificate Name to enter a file name for the certificate.

   The following prompt is displayed:

   ```
   Enter certificate name (24 char max) ->
   ```

7. Enter a file name for the certificate. This is the file name under which the certificate will be stored in the AT-S63 file system. The name can be up to 24 alphanumeric characters. Spaces are allowed.

   Note
   The AT-S63 Management Software automatically adds a ".cer" extension to the filename.

8. Type **2** to select Key Pair ID.

   The following prompt is displayed:

   ```
   Enter certificate Key Pair ID -> [0 to 65535] ->
   ```


Downloaded from www.Manualslib.com manuals search engine

9. Enter the ID number of the encryption key that you want to use to create this certificate. The encryption key must already exist on the switch. (If you have forgotten the key ID number, return to the Key Management menu to view the keys on the switch.) The value can be from 0 to 65,535.

10. Type **3** to select Format to choose the encoding format for the certificate. The possible options are:

    DER - Indicates the certificate contents are in a binary format. This is the default.

    PEM - Indicates the certificate are in the Privacy Enhanced Mail (PEM) format which is an ASCII format.

11. Type **4** to select Serial Number.

    The following prompt is displayed:

    ```
    Enter certificate serial number->[0 to 2147483647] -> 0
    ```

12. Enter a value between 0 and 2,147,483,647.

    Self-signed certificates are usually assigned a serial number of 0.

13. Type **5** to select Subject DN and enter a distinguished name for the certificate. (Do not enclose the distinguished name in quotes.)

    Note
    If you did not enter a distinguished name in step 2, then you need to enter one here. A certificate must have a distinguished name. If you enter a name both here and in Step 2, the certificate will contain the name entered here.

14. Type **6** to select Create Self-Signed Certificate.

    The following prompt is displayed:

    ```
    Please wait while certificate is generated...Done!
    ```

15. Press any key.

    The X509 Certificate Management menu is displayed again.

    The certificate is automatically saved in the AT-S63 file system. You do not need to return to the Main Menu to permanently save the new certificate.

16. Go to the next procedure to add the certificate to the certificate database.

Downloaded from www.Manualslib.com manuals search engine

Adding a Certificate to the Database

After creating a certificate or receiving a certificate from a public or private CA, you need to add it to the certificate database. This makes it available to the switch's web server. A certificate in the certificate database appears in the X509 Certificate Management menu.

To add a certificate to the certificate database, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.
2. From the Security and Services menu, type **7** to select Keys/ Certificates Configuration.

   The Keys/Certificates Configuration menu is shown in Figure 221 on page 596.
3. From the Keys/Certificate menu, type **3** to select Public Key Infrastructure (PKI) Configuration.

   The Public Key Infrastructure (PKI) Configuration menu is shown in Figure 227 on page 613.
4. From the Public Key Infrastructure (PKI) Configuration menu, type **2** to select X509 Certificate Management.

   The X509 Certificate Management menu is shown in Figure 228 on page 613.
5. From the X509 Certificate Management menu, type **2** to select Add Certificate. The Add Certificate menu is shown in Figure 230.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                           11:20:02 02-Mar-2005
                      Add Certificate

 1 - Certificate Name .............
 2 - State ......................... Trusted
 3 - Type .......................... EE
 4 - File Name ....................
 5 - Add Certificate

 R - Return to Previous Menu

 Enter your selection?
```

Figure 230. Add Certificate Menu

6. Type **1** to select Certificate Name.

Downloaded from www.Manualslib.com manuals search engine

The following prompt is displayed:

```
Enter file name (*.key) ->
```

7. Enter a name for the certificate.

   This is the name for the certificate as it will appear in the certificate database list. You can enter up to 24 alphanumeric characters. Spaces are allowed. No extension is needed.

   You might want the name to include the filename of the certificate in the file system. This will make it easier for you to correlate a certificate in the database with its corresponding file in the file system. Here is an example:

   ```
   Switch 12 - sw12.cer
   ```

8. Type **2** to select (certificate) State. The possible settings are:

   Trusted
   This value indicates you have verified the certificate is from a trusted CA. This is the default.

   Untrusted
   This value indicates the certificate is from an untrusted CA either because you have not verified the CA or have verified the CA is untrusted.

   Note
   This parameter has no affect on the operation of a certificate. The parameter is included only for informational purposes when the certificate is displayed in the certificate database.

9. Type **3** to select Type (of certificate). The possible settings are:

   EE
   The certificate was issued by a CA, such as VeriSign. This is the default.

   CA
   The certificate belongs to a CA.

   Self
   This certificate is a self-signed certificate. The switch treats this type of certificate as its own.

   Note
   This parameter has no affect on the operation of a certificate. The parameter is included only for informational purposes when the certificate is displayed in the certificate database.

Downloaded from www.Manualslib.com manuals search engine

10. Type **4** to select File Name.

    The following prompt is displayed:

    ```
    Enter file name (*.key) ->
    ```

11. Specify the filename of the certificate.

    This is the filename of the certificate in the AT-S63 file system. The filename has a ".cer" extension. For example, if you created a self-signed certificate and gave it the name "webserver127", the filename of the certificate would be "webserver127.cer". If you have forgotten the filename of the certificate, refer to "Displaying System Files" on page 159.

12. Type **5** to select Add Certificate to add the certificate to the certificate database.

    The AT-S63 Management Software adds the certificate to the database, a process that requires only a few seconds.

13. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Modifying a Certificate

The procedure in this section modifies a certificate in the certificate database. Here are the certificate items you can modify:

- State - trusted or untrusted
- Type - EE, CA, or Self

> **Note**
> These parameters have no affect on the operation of a certificate. They are included only for informational purposes when the certificate is displayed in the certificate database.

To modify a certificate, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.
2. From the Security and Services menu, type **7** to select Keys/ Certificates Configuration.

   The Keys/Certificates Configuration menu is shown in Figure 221 on page 596.
3. From the Keys/Certificate menu, type **3** to select Public Key Infrastructure (PKI) Configuration.

   The Public Key Infrastructure (PKI) Configuration menu is shown in Figure 227 on page 613.
4. From the Public Key Infrastructure (PKI) Configuration menu, type **2** to select X509 Certificate Management.

   The X509 Certificate Management menu is shown in Figure 228 on page 613.
5. From the X509 Certificate Management menu, type **4** to select Modify Certificate.

   The following prompt is displayed:

   ```
   Enter a certificate name ->
   ```
6. Enter the name of the certificate you want to modify. (This field is case sensitive.)

Downloaded from www.Manualslib.com manuals search engine

The Modify Certificate menu is shown in Figure 231.

```
          Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                          11:20:02 02-Mar-2005
                    Modify Certificate

 1 - Certificate Name.................. Switch12
 2 - State ............................ Trusted
 3 - Type ............................. Self
 4 - Modify Certificate

 R - Return to Previous Menu

 Enter your selection?
```

Figure 231. Modify Certificate Menu

Note
You cannot change selection 1, Certificate Name.

7. Type **2** to select State. The possible settings are:

   Trusted
   This value indicates you have verified that the certificate is from a trusted CA. This is the default.

   Untrusted
   This value indicates the certificate is from an untrusted CA either because you have not verified the CA or you have verified the CA is untrusted.

8. Type **3** to select Type. The possible settings are:

   EE
   The certificate was issued by a CA, such as VeriSign. This is the default.

   CA
   The certificate belongs to a CA.

   Self
   This certificate is a self-signed certificate. The switch treats this type of certificate as its own.

9. Type **4** to select Modify Certificate.

   Your changes are implement in the certificate.

   The following message is displayed:

   ```
   Please wait while certificate is updated...Done.
   ```


Downloaded from www.Manualslib.com manuals search engine

10. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Deleting a Certificate

The procedure in this section deletes a certificate from the certificate database. Please note the following before performing this procedure:

- Deleting a certificate from the database does not delete it from the switch. It continues to reside in the AT-S63 file system. To completely remove a certificate from the switch, you must also delete it from the file system. For instructions, refer to “Deleting a System File” on page 158.
- You cannot delete a certificate from the database if its corresponding encryption key is the active key in the web server configuration. The switch will consider the certificate as in use and will not allow you to delete it. You must first configure the web server with another encryption key pair for a different certificate. For instructions, refer to “Configuring the Web Server” on page 590.

To delete a certificate from the certificate database, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.
2. From the Security and Services menu, type **7** to select Keys/Certificates Configuration.

   The Keys/Certificates Configuration menu is shown in Figure 221 on page 596.
3. From the Keys/Certificate menu, type **3** to select Public Key Infrastructure (PKI) Configuration.

   The Public Key Infrastructure (PKI) Configuration menu is shown in Figure 227 on page 613.
4. From the Public Key Infrastructure (PKI) Configuration menu, type **2** to select X509 Certificate Management.

   The X509 Certificate Management menu is shown in Figure 228 on page 613.
5. From the X509 Certificate Management menu, type **3** to select Delete Certificate.

   The following prompt is displayed:

   ```
   Enter certificate name (ALL - delete all) ->
   ```
6. Enter the name of the certificate you want to delete. (This field is case sensitive.) To delete all the certificates, enter ALL.

Downloaded from www.Manualslib.com manuals search engine

7. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Viewing a Certificate

This procedure displays information about a certificate, such as its distinguished name and serial number.

To view the details of a certificate, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.
2. From the Security and Services menu, type **7** to select Keys/ Certificates Configuration.
3. From the Keys/Certificate menu, type **3** to select Public Key Infrastructure (PKI) Configuration.

   The Public Key Infrastructure (PKI) Configuration menu is shown in Figure 227 on page 613.
4. From the Public Key Infrastructure (PKI) Configuration menu, type **2** to select X509 Certificate Management.

   The X509 Certificate Management menu is shown in Figure 228 on page 613.
5. From the X509 Certificate Management menu, type **5** to select View Certificate Details.

   The following prompt is displayed:

   ```
   Enter certificate name ->
   ```
6. Enter a name of the certificate you want to view. (This field is case sensitive.)

Downloaded from www.Manualslib.com manuals search engine

The View Certificate Details menu (page 1) is shown in Figure 232.

```
          Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                            11:20:02 02-Mar-2005
                  View Certificate Details

 Certificate Details:
   Name ................ Switch12
   State ............... Trusted
   Manually Trusted ... True
   Type ................ Self
   Source .............. Command

   Version ............. V3 (0X2)
   Serial Number ...... 0 (0X0)
   Signature Alg ...... md5WithRSAEncryption
   Public Key Alg ..... rsaEncryption
   Not Valid Before ... Jan 9 01:28:18 2004 GMT
   Not Valid After .... Jan 8 01:28:18 2006 GMT

 N - Next Page
 R - Return to Previous Menu

 Enter your selection?
```

Figure 232. View Certificate Details Menu (page 1)

The following information is displayed in page 1:

Name
The name of the certificate.

State
Whether the certificate is Trusted or Untrusted.

Manually Trusted
Whether the certificate was manually trusted.

Type
The type of the certificate. The options are EE, SELF, and CA.

Source
The source of the certificate. The source for self-signed certificates created by the switch is COMMAND.

Version
The version of X.509 that the certificate complies with.

Serial Number
The certificate's serial number.

Signature Alg
The signature algorithm of the certificate.

Downloaded from www.Manualslib.com manuals search engine

Public Key Alg
The public key algorithm.

Not Valid Before
The date the certificate became active.

Not Valid After
The date the certificate expires. Self-signed certificates are valid for two years.

7. Type **N** to see the second page of certificate details.

   The View Certificate Details menu (page 2) is shown in Figure 233.

```
                    Allied Telesis AT-9424T/SP - AT-S63
                                Marketing
User: Manager                                              11:20:02 02-Mar-2005
                           View Certificate Details

 Subject ......... CN=149.44.44.44
 Issuer .......... CN=149.44.44.44
 MD5 Fingerprint...4E:76:06:FA:F6:C1:DA:FF:4D:E9:76:02:1D:8F:DA:CB
 SHA1 Fingerprint..F8:43:CB:E2:0A:BF:4A:02:CA:C6:B0:47:DF:74:1E:D3:A8:A3:F0:00

 N - Previous Page
 R - Return to Previous Menu

 Enter your selection?
```

Figure 233. View Certificate Details Menu (page 2)

The following information is displayed in page 2:

Subject
The distinguished name of the subject of the certificate.

Issuer
The distinguished name of the issuer of the certificate.

MD5 Fingerprint
The MD5 algorithm. This value provides a unique sequence for each certificate consisting of 16 bytes.

SHA1 Fingerprint
The Secure Hash Algorithm. This value provides a unique sequence for each certificate consisting of 20 bytes.

Downloaded from www.Manualslib.com manuals search engine

Generating an Enrollment Request

To request a certificate from a CA, you must generate an enrollment request. The request contains the public key for the certificate, a distinguished name, and other information. The request is stored as a file with a ".csr" extension in the AT-S63 file system and must be uploaded onto your management station or TFTP server for submission to the CA.

- This procedure prompts you for the ID number of the encryption key pair to be used to create the enrollment request. If you have forgotten the ID number, refer to "Displaying the Encryption Keys" on page 608 to view key ID numbers.
- You must create the key pair before performing this procedure. For instructions, refer to "Creating an Encryption Key" on page 596.
- For a review of all the steps to creating an enrollment request and downloading a certificate from a CA onto a switch, refer to "General Steps for a Public or Private CA Certificate" on page 593.

To generate an enrollment request, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.
2. From the Security and Services menu, type **7** to select Keys/Certificates Configuration.

   The Keys/Certificates Configuration menu is shown in Figure 221 on page 596.
3. From the Keys/Certificates Configuration menu, type **1** to select Switch Distinguished Name (DN).

   The following prompt is displayed:

   ```
   Enter new DN (128 chars max) ->
   ```
4. Enter a name. An enrollment request must have a distinguished name.
5. Type **3** to select Public Key Infrastructure (PKI) Configuration.

   The Public Key Infrastructure (PKI) Configuration menu is shown in Figure 227 on page 613.
6. From the Public Key Infrastructure (PKI) Configuration menu, type **3** to select Generate Enrollment Request.

Downloaded from www.Manualslib.com manuals search engine

The Generate Enrollment Request menu is shown in Figure 234.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                            11:20:02 02-Mar-2005
                 Generate Enrollment Request

 1 - Request Name.....................
 2 - KeyPair ID ..................... 0
 3 - Format ......................... PEM
 4 - Type ........................... PKCS10
 5 - Generate Enrollment Request

 R - Return to Previous Menu

 Enter your selection?
```

Figure 234. Generate Enrollment Request Menu

7. Type **1** to select Request Name.

   The following prompt is displayed:

   ```
   Enter enrollment request name (24 chars max) ->
   ```

8. Enter a name of up to 24 alphanumeric characters for the enrollment request. Spaces are allowed.

   The enrollment request is stored in the AT-S63 file system using the enrollment request name as the filename. The full filename consists of the enrollment request name followed by ".csr" extension, which the management software adds automatically. For example, if you enter "certificate75" as the enrollment request name, the enrollment request's filename will be "certificate75.csr".

9. Type **2** to select KeyPair ID.

   The following prompt is displayed:

   ```
   Enter keypair ID -> [0 to 65535] -> 0
   ```

10. Enter a KeyPair ID between 0 and 65,535.
11. Type **3** to toggle the Format selection between the following options:

    DER - Creates the certificate in a binary format. This is the default.

    PEM - Creates the certificate in the Privacy Enhanced Mail (PEM) format which is an ASCII format.

> **Note**
> You cannot change option 4, Type. The PKCS10 value indicates the internal format of an enrollment request.

Downloaded from www.Manualslib.com manuals search engine

12. Type **5** to select Generate Enrollment Request.

    After the switch has finished generating the request, a message similar to the following is displayed:

    ```
    Enrollment request is being generated. Please wait
    ...Done.
    Enrollment Request available in file [Switch 12.csr].
    Press any key to continue ...
    ```

    The enrollment request is now stored in the AT-S63 file system. To see the file, refer to "Displaying System Files" on page 159.

13. Press any key to return to the Public Key Infrastructure (PKI) Configuration menu.

14. To submit the request to a CA, upload it from the file system on the switch to your management station or to an FTP server on your network. For instructions, refer to "Uploading a System File" on page 190.

    Be sure to follow the rules and guidelines of the CA when submitting an enrollment request. Failure to follow their guidelines may delay the issuing of the certificate.

Downloaded from www.Manualslib.com manuals search engine

Installing CA Certificates onto a Switch

This section lists the procedures to perform for a certificate from a public or private CA. It should be noted that a CA generated certificate will consist of several certificates, with a minimum of two. All the certificates from the CA must be installed on the switch and loaded into the certificate database.

Note
A certificate from a CA can only be used on the switch where you created the encryption key pair and enrollment request. Do not install the certificate on any other switch.

To install CA certificates on a switch, perform the following procedure:

1. Download the certificates from your management station or FTP server to the AT-S63 file system on the switch. For instructions, refer to “Downloading a System File” on page 182.

2. Load the certificates into the certificate database. For instructions, refer to “Adding a Certificate to the Database” on page 616.

3. Activate HTTPS on the switch by configuring the web server and specifying the key pair used to create the enrollment request as the active key pair. For instructions, refer to “Configuring the Web Server” on page 590.

Downloaded from www.Manualslib.com manuals search engine

Viewing and Configuring the Maximum Number of Certificates

You can specify the maximum number of certificates the certificate database can store. The range is a maximum of 12 to 256. The default value is 256. You should never need to adjust this value.

To view or change the maximum number of certificates the certificate database can store, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.
2. From the Security Configuration menu, type **7** to select Keys/ Certificates Configuration.

   The Keys/Certificates Configuration menu is shown in Figure 221 on page 596. Selection 1, Maximum Number of Certificates, shows the current setting.
3. To change the maximum number of certificates, type **1** to select Maximum Number of Certificates.

   The following prompt is displayed:

   ```
   Enter certificate limit -> [12 to 256] 256
   ```
4. Enter a new number and press Return.
5. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Configuring SSL

To configure the SSL protocol, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.
2. From the Security and Services menu, type **9** to select Secure Socket Layer (SSL).

   The Secure Socket Layer (SSL) menu is shown in Figure 235.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                              11:20:02 02-Mar-2005
                  Secure Socket Layer (SSL)

 1 - Maximum Number of Sessions......... 50
 2 - Session Cache Timeout.............. 300 seconds

 R - Return to Previous Menu

 Enter your selection?
```

Figure 235. Secure Socket Layer (SSL) Menu

3. Type **1** to select Maximum Number of Sessions to increase the number of sessions.

   The following prompt is displayed:

   ```
   Enter maximum SSL sessions value -> [1 to 100] 50
   ```

   Enter a value from 1 to 100. The maximum number of sessions is used to speed up a connection. By increasing the number of sessions, you increase HTTPS performance. However, increasing the number of sessions also increases the memory requirements. The default is 50.

4. Type **2** to select Session Cache Timeout to increase or decrease the timer that determines when the session cache times out.

   The following prompt is displayed:

   ```
   Enter Cache timeout value -> [1 to 600] 300
   ```

   Enter a value, in seconds, from 1 to 600. The default is 300 seconds.

5. To permanently save your change, return to the Main Menu and type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Chapter 35

Secure Shell (SSH)

The chapter contains overview information about the Secure Shell (SSH) protocol as well a procedure for configuring this protocol on a switch using a local or Telnet management session. It contains the following sections:

- ❒ “Configuring SSH” on page 634
- ❒ “Displaying SSH Information” on page 637

Downloaded from www.Manualslib.com manuals search engine

Configuring SSH

This section describes how to configure the switch as an SSH server.

Before you begin this procedure, you need to configure a host and server keys for SSH. See Chapter 33, “Encryption Keys” on page 595. The minimum bit size of the server key is 512 bits. The recommended bit size for a server key is 768 bits. The recommended size for the host key is 1024 bits. In addition, the bit size of the host and server keys must differ by 128 bits.

While you are configuring the SSH feature, you must disable the SSH server. When you have completed your configuration changes, enable the SSH server to permit SSH client connections.

> **Note**
> Allied Telesis recommends disabling the Telnet server before you enable SSH. Otherwise, the security functions provided by SSH are lost. See “Configuring the Telnet Server” on page 47.

To configure the SSH protocol, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.

   The Security and Services menu is shown in Figure 71 on page 220.

2. From the Security and Services menu, type **8** to select Secure Shell (SSH).

   The Secure Shell (SSH) menu is shown in Figure 236.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                          11:20:02 02-Mar-2005
                    Secure Shell (SSH)

1 - SSH Server Status ....... Disabled
2 - Host Key ID.............. <Not Defined>
3 - Server Key ID ........... <Not Defined>
4 - Server Key Expiry Time .. 0 hours
5 - Login Timeout ........... 180 seconds
6 - Show Server Information
R - Return to Previous Menu

Enter your selection?
```

Figure 236. Secure Shell (SSH) Menu

Downloaded from www.Manualslib.com manuals search engine

3. Type **2** to select Host Key ID.

   The following prompt is displayed:

   ```
   Enter Host Key ID [0 to 65535] -> 0
   ```

   Enter the ID number of the encryption key that will function as the host key. The default is Not Defined. For instructions on creating encryption keys, see Chapter 33, "Encryption Keys" on page 595.

4. Type **3** to select Server Key ID.

   The following prompt is displayed:

   ```
   Enter Server Key ID [0 to 65535 -> 0
   ```

   Enter the ID number of the encryption key that will function as the server key. The default is Not Defined. For instructions on creating encryption keys, see Chapter 33, "Encryption Keys" on page 595.

5. Type **4** to select Server Key Expiry Time to set the time, in hours, for the server key to expire.

   The following prompt is displayed:

   ```
   Enter Server Key Expiry Time [0 to 5] -> 0
   ```

   This timer determines how often the server key is regenerated. A server key is regenerated for security purposes. A server key is only valid for the time period configured in the Server Key Expiry (Expiration) Time timer. Allied Telesis recommends you set this field to 1. With this setting, a new key is generated every hour.

   The default is 0 hours which means the server key never expires. The range is 0 to 5 hours.

6. Type **5** to select Login Timeout.

   The following prompt is displayed:

   ```
   Enter Login Timeout [60 to 600] -> 180
   ```

   This is the time it takes to release the SSH server from an incomplete SSH client connection. Enter a time in seconds. The default is 180 seconds (3 minutes). The range is 60 to 600 seconds.

7. Type **1** to select SSH Server Status to enable or disable the SSH server.

   The following prompt is displayed:

   ```
   SSH Server Status [E-Enabled, D-Disabled] ->
   ```


Downloaded from www.Manualslib.com manuals search engine

Type **E** to enable the SSH server. Select this value after you have finished configuring SSH and want to log on to the server. Or, type D to disable SSH while you are configuring the protocol. SSH must be disabled while you are configuring the protocol. This is the default.

Note
When there are active SSH connections, you cannot disable the SSH server. If you attempt to disable the SSH server when it is in this state, you receive a warning message.

Note
Allied Telesis recommends disabling the Telnet server before you enable SSH. Otherwise, the security provided by SSH is lost.

8. After making changes, type **R** to until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Displaying SSH Information

To display SSH server information, perform the following procedure:

1. From the Main Menu, type **7** to select Security and Services.

   The Security and Services menu is shown in Figure 71 on page 220.

2. From the Security and Services menu, type **8** to select Secure Shell (SSH).

   The Secure Shell (SSH) menu is shown in Figure 236 on page 634.

3. From the Secure Shell (SSH) menu, type **6** to select Show Server Information.

   The Show Server Information menu is shown in Figure 237.

```
                  Allied Telesis AT-9424T/SP - AT-S63
                                Marketing
User: Manager                                        11:20:02 02-Mar-2005
                          Show Server Information

 Versions Supported ....... 1.3, 1.5, 2.0
 Server Status ............ Enabled
 Server Port .............. 22
 Host Key ID .............. 200
 Host Key Bits ............ 1024
 Server Key ID ............ 250
 Server Key Expiry ........ 0 hours
 Login Timeout ............ 180 seconds
 Authentication Available . Password
 Ciphers Available ........ 3DES, 128 bit AES, 192 bit AES,256 bit AES,
 Arcfour (RC4)
 MACs Available ........... hmac-sha1, hmac-md5
 Data Compression ......... Available

 R - Return to Previous Menu

 Enter your selection?
```

Figure 237. Show Server Information Menu

The Show Server Information menu provides the following information:

Versions Supported
The versions of SSH which are supported by the AT-S63 Management Software.

Server Status
Whether or not the SSH server is enabled or disabled.

Server Port
The well-known port for SSH. The default is port 22.

Downloaded from www.Manualslib.com manuals search engine

Host Key ID
The host key ID defined for SSH.

Host Key Bits
Number of bits in the host key.

Server Key ID
Server key ID defined for SSH.

Server Key Expiry
Length of time, in hours, until the server key is regenerated. The default is 0 hours which means the server key is not regenerated.

Login Timeout
Time, in seconds, until a SSH server is released from an incomplete connection with a SSH client.

Authentication Available
Authentication method available. Currently, password authentication is the only supported method.

Ciphers Available
SSH ciphers that are available on the switch.

MACs Available
Message Authorization Code (MAC) that is used to validate incoming SSH messages to the server. Two algorithms are supported.

Data Compression
Whether or not data compression is available on the switch. Data compression is useful for networks that have a slow throughput speed.

Downloaded from www.Manualslib.com manuals search engine

Chapter 36

TACACS+ and RADIUS Protocols

This chapter describes how to configure the parameter settings for the two authentication protocols TACACS+ and RADIUS. Sections in the chapter include:

- ❒ “Enabling or Disabling Server-based Management Authentication” on page 640
- ❒ “Configuring the TACACS+ Client” on page 642
- ❒ “Displaying the TACACS+ Settings” on page 644
- ❒ “Configuring the RADIUS Client” on page 645
- ❒ “Displaying RADIUS Status and Settings” on page 648

Downloaded from www.Manualslib.com manuals search engine

Enabling or Disabling Server-based Management Authentication

This procedure explains how to enable or disable server-based management authentication on the switch. When the feature is enabled, the switch seek its valid manager accounts from an authentication server. When disabled, the switch uses its standard Manager and Operator accounts.

Note the following before performing this procedure:

- You should create the manager accounts (i.e., username and password combinations) on the TACACS+ or RADIUS server before activating server-based authentication. Otherwise, you may not be able to initiate future management sessions with the switch.
- This procedure does not affect 802.1x port-based access control. To control that feature, refer to “Enabling or Disabling 802.1x Port-based Network Access Control” on page 572.

To enable or disable server-based management authentication, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **6** to select Authentication Configuration.

   The Authentication Configuration menu is shown in Figure 238.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                          11:20:02 02-Mar-2005
                 Authentication Configuration

1 - Server-based Authentication ..... Disabled
2 - Authentication Method ........... TACACS+
3 - TACACS+ Configuration
4 - RADIUS Configuration
5 - Passwords Configuration

R - Return to Previous Menu

Enter your selection?
```

Figure 238. Authentication Configuration Menu

Downloaded from www.Manualslib.com manuals search engine

Note
Selection 5, Passwords Configuration, is described in "Changing the Manager and Operator Passwords" on page 35.

3. To select the active authentication protocol, type **2** to select Authentication Method.

   The following prompt is displayed:

   ```
   Enter T-TACACS+, R-RADIUS ->
   ```

4. Type **T** to select TACACS+ or **R** for RADIUS. The default is TACACS+. Only one protocol can be active on the switch at a time.

5. To activate or deactivate the feature, type **1** to select Server-based Authentication from the Authentication Configuration menu.

   Note
   Option 1 - Server-based Authentication in the menu applies only to the manager accounts feature described in this chapter. This menu selection has no affect on the 802.1x port-based access control feature described in Chapter 31, "802.1x Port-based Network Access Control" on page 569. When Option 1 is set to disabled, the default setting, the switch uses the default manager and operator accounts. When set to enabled, the switch seeks its manager accounts from a TACACS+ or RADIUS authentication server.

   The following prompt is displayed:

   ```
   Server Based User Authentication (E-Enabled,
   D-Disabled) ->
   ```

6. Type **E** to enable or **D** to disable server-based authentication on the switch.

   If you activate the feature, you must enter the manager username and password accounts that you defined on the TACACS+ or RADIUS authentication server when you initiate future management sessions on the switch.

   If you deactivate the feature, future management sessions with the switch are initiated with the standard manager and operator accounts.

7. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Configuring the TACACS+ Client

To configure the TACACS+ client on the switch, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **6** to select Authentication Configuration.

   The Authentication Configuration menu is shown in Figure 238 on page 640.

3. From the Authentication Configuration menu, type **3** to select TACACS+ Configuration.

   The TACACS+ Client Configuration menu is shown in Figure 239.

```
            Allied Telesis AT-9424T/SP - AT-S63
                         Marketing
User: Manager                           11:20:02 02-Mar-2005
                 TACACS+ Client Configuration

1 - TAC Server 1 ................... 0.0.0.0
2 - TAC Server 2 ................... 0.0.0.0
3 - TAC Server 3 ................... 0.0.0.0
4 - TAC Global Secret ..............
5 - TAC Timeout ..................... 30 seconds

R - Return to Previous Menu

Enter your selection?
```

Figure 239. TACACS+ Client Configuration Menu

4. Adjust the following parameters as necessary.

   1 - TAC Server 1
   2 - TAC Server 2
   3 - TAC Server 3
   Use these parameters to specify the IP addresses of up to three network servers containing TACACS+ server software. After you have entered an IP address, you will see the following prompt:

   ```
   Use per-server secret [Y/N] ->
   ```


Downloaded from www.Manualslib.com manuals search engine

If you will be specifying more than one TACACS+ server and if all of the servers use the same encryption secret, you can answer No to this prompt and enter the encryption secret using the TAC Global Secret parameter.

However, if you are specifying only one TACACS+ server or if the servers have difference encryption secrets, then respond with Yes to this prompt. You will see:

```
Enter per-server secret [max 40 characters] ->
```

Use this prompt to enter the encryption secret for the TACACS+ server whose IP address you are specifying. The maximum length is 39 characters.

4 - TAC Global Secret
If all of the TACACS+ servers have the same encryption secret, rather then entering the same secret when you enter the IP addresses, you can use this option to enter the secret just once. The maximum length is 39 characters.

5 - TAC Timeout
This parameter specifies the maximum amount of time the switch waits for a response from a TACACS+ server before assuming the server is not responding. If the timeout expires and the server has not responded, the switch queries the next TACACS+ server in the list. If there are no more servers, the switch defaults to the standard Manager and Operator accounts. The default is 30 seconds. The range is 1 to 300 seconds.

5. After you have finished configuring the parameters in the TACACS+ Client Configuration menu, type **R** to return to the Authentication Configuration menu, shown in Figure 238 on page 640.

6. To activate the feature, perform the procedure "Enabling or Disabling Server-based Management Authentication" on page 640.

Downloaded from www.Manualslib.com manuals search engine

Displaying the TACACS+ Settings

To display the TACACS+ settings, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **6** to select Authentication Configuration.

   The Authentication Configuration menu is shown in Figure 238 on page 640.

3. Type **3** to select TACACS+ Configuration.

   The TACACS+ Client Configuration menu is shown in Figure 240.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                              11:20:02 02-Mar-2005
                TACACS+ Client Configuration

1 - TAC Server 1 ................... 142.34.56.102
2 - TAC Server 2 ................... 0.0.0.0
3 - TAC Server 3 ................... 0.0.0.0
4 - TAC Global Secret .............. tech
5 - TAC Timeout .................... 30 seconds

R - Return to Previous Menu

Enter your selection?
```

Figure 240. TACACS+ Client Configuration Menu

The TACACS+ Client Configuration menu provides the following information:

TAC Server 1
TAC Server 2
TAC Server 3
The IP addresses of the TACACS+ servers.

TAC Global Secret
Global encryption secret if all the servers use the same one. The maximum length is 39 characters.

TAC Timeout
The maximum amount of time the switch waits for a response from a TACACS+ server before assuming the server is not responding.

Downloaded from www.Manualslib.com manuals search engine

Configuring the RADIUS Client

To configure the RADIUS client, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **6** to select Authentication Configuration.

   The Authentication Configuration menu is shown in Figure 238 on page 640.

3. Type **4** to select RADIUS Configuration.

   The RADIUS Client Configuration menu is shown in Figure 241.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                           11:20:02 02-Mar-2005
                 RADIUS Client Configuration

1 - Global Encryption Key .............. ATI
2 - Global Server Timeout period....... 10 second(s)
3 - RADIUS Server 1 Configuration ..... 0.0.0.0
4 - RADIUS Server 2 Configuration ..... 0.0.0.0
5 - RADIUS Server 3 Configuration ..... 0.0.0.0
6 - Show Status

R - Return to Previous Menu

Enter your selection?
```

Figure 241. RADIUS Client Configuration

4. Adjust the following parameters as necessary.

   Global Encryption Key
   This parameter specifies the encryption key for the RADIUS servers. This option is useful if you will be entering more than one RADIUS server and all the servers share the same encryption key. The maximum length is 39 characters. The default is ATI.

   Global Server Timeout period
   This parameter specifies the maximum amount of time the switch waits for a response from a RADIUS server before assuming that the server does not respond. If the timeout expires and the server has not responded, the switch queries the next RADIUS server in the list. If there are no more servers, then the switch defaults to the standard

Downloaded from www.Manualslib.com manuals search engine

Manager and Operator accounts. The default is 10 seconds. The range is 1 to 60 seconds.

3 - RADIUS Server 1 Configuration
4 - RADIUS Server 1 Configuration
5 - RADIUS Server 1 Configuration
Use these parameters to specify the IP addresses of up to three network servers containing the RADIUS server software. Selecting one of the options displays the RADIUS Server Configuration menu, shown in Figure 242.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                            11:20:02 02-Mar-2005
                RADIUS Server 1 Configuration

1 - Server IP Address ................. 0.0.0.0
2 - Server Authentication UDP Port .... 1812
3 - Server Encryption Key ............. <Not Defined>

R - Return to Previous Menu

Enter your selection?
```

Figure 242. RADIUS Server Configuration

Adjust the following parameters as necessary:

1 - Server IP Address
Use this option to specify the IP address of the RADIUS server.

2 - Server Authentication UDP Port
Use this option to specify the UDP port of the RADIUS protocol.

3 - Server Encryption Key
Use this option to specify the encryption key for the RADIUS server.

If you are using the RADIUS client software to support 802.1x port-based network access control, but not new manager accounts, no further steps are required after you configure the parameters in the RADIUS Server Configuration menu. You can return to the main menu and type **S** to select Save Configuration Changes.

However, if you are using the RADIUS client software to support new manager accounts, you must perform steps 5 to 7 to activate the feature.

5. After you finish configuring the parameters in the RADIUS Client Configuration menu, type **R** to return to the Authentication Configuration menu, shown in Figure 238 on page 640.

Downloaded from www.Manualslib.com manuals search engine

6. To activate the feature, perform the procedure "Enabling or Disabling Server-based Management Authentication" on page 640.

Downloaded from www.Manualslib.com manuals search engine

Displaying RADIUS Status and Settings

To display the RADIUS status and settings, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **6** to select Authentication Configuration.

   The Authentication Configuration menu is shown in Figure 238 on page 640.

3. From the Authentication Configuration menu, type **4** to select RADIUS Configuration.

   The RADIUS Client Configuration menu is shown in Figure 241 on page 645.

4. From the RADIUS Client Configuration menu, type **6** to select Show Status.

   The Show Status menu is shown in Figure 243.

```
               Allied Telesis AT-9424T/SP - AT-S63
                            Marketing
User: Manager                                    11:20:02 02-Mar-2005
                           Show Status
Global Configuration
--------------------
Encryption Key : ATI
Server Timeout: 30 second(s)

Server IP Address  Auth Port  Encryption Key  Auth Req Auth Resp
-------------------------------------------------------------
149.11.11.11       1812       WRRT            100      96
149.22.22.22       1812       LLST            4        4
149.22.22.22       1812       OORT            0        0

U - Update Display
R - Return to Previous Menu

Enter your selection?
```

Figure 243. Show Status Menu

Downloaded from www.Manualslib.com manuals search engine

The Show Status menu displays a table that contains the following columns of information:

Server IP Address
IP address of the RADIUS server.

Auth Port
UDP port of the RADIUS protocol.

Encryption Key
Encryption key for the RADIUS server.

Auth Req
Number of authentication requests the switch has made to the RADIUS server.

Auth Resp
Number of responses that the switch has received back from the server.

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Chapter 37

Management Access Control List

Sections in this chapter include:

- “Enabling or Disabling the Management ACL” on page 652
- “Creating an ACE” on page 654
- “Deleting an ACE” on page 658
- “Displaying the ACEs” on page 659

Downloaded from www.Manualslib.com manuals search engine

Enabling or Disabling the Management ACL

This procedure enables and disables the management ACL. When enabled, only those management stations specified in the ACL are allowed to manage the switch remotely using the Telnet application protocol or a web browser. When the feature is disabled, the management software on the switch can be accessed remotely from any management workstation.

Note
Do not activate the management ACL until you have specified the access control entries (ACEs). Otherwise, the switch will discard all remote management packets, making it impossible for you to remotely manage the unit from a Telnet or web browser management session. For instructions on how to add ACEs, refer to “Creating an ACE” on page 654.

To enable or disable the Management ACL, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **7** to select Management ACL.

   The Management ACL Configuration menu is shown in Figure 244.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                           11:20:02 02-Mar-2005
                Management ACL Configuration

Configuring Management ACL
1 - Management ACL Status ..... Disabled
2 - Create Management ACL Entry
3 - Modify Management ACL Entry
4 - Delete Management ACL Entry
5 - Display All Management ACL Entries

R - Return to Previous Menu

Enter your selection?
```

Figure 244. Management ACL Configuration Menu

3. Type **1** to select Management ACL Status and toggle the selection to either Enabled or Disabled. The default setting is disabled.

Downloaded from www.Manualslib.com manuals search engine

A change to the status of the management ACL is immediately activated on the switch.

Note
If you activate the feature while managing the switch from a Telnet management session, your management session will end and you will not be able to reestablish it if the management ACL does not contain an ACE that specifies your management workstation.

4. After making changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Creating an ACE

To create a new ACE in the management ACL, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **7** to select Management ACL.

   The Management ACL Configuration menu is shown in Figure 244 on page 652.

3. From the Management ACL Configuration menu, type **2** to select Create Management ACL Entry.

   The following prompt is displayed:

   ```
   Enter the entry ID :  [1 to 256] -> 1
   ```

4. Enter an identification number for the access control entry. Every ACE must have a unique number. The range is 1 to 256.

   The following prompt is displayed:

   ```
   Enter the IP address:
   ```

5. Enter the IP address of a specific management station (for example, 149.11.11.11) or a subnet (for example, 149.11.11.0).

   The following prompt is displayed:

   ```
   Enter the Mask:
   ```

6. Enter a mask that indicates the parts of the IP address the switch should filter on. A binary “1” indicates the switch should filter on the corresponding bit of the address, while a “0” indicates that it should not. If you are filtering on a specific IP address, enter the mask 255.255.255.255. If you are filtering on a subnet, the mask will depend on the subnet. For example, to allow all management stations in the subnet 149.11.11.0 to manage the switch, you would enter the mask 255.255.255.0.

   The following prompt is displayed:

   ```
   Enter the Application Type [TELNET, WEB, PING, ALL]:
   ```


Downloaded from www.Manualslib.com manuals search engine

7. Specify the applications that the management station can use to manage the switch. The options are:

   - Telnet - Permits Telnet management.
   - Web - Permits web browser management.
   - Ping - Permits the management workstation to ping the switch.
   - All - Permits all of the above.

   You can specify more than one by separating the selections with a comma (for example, "Telnet,Ping").

   The new ACE is added to the ACL.

8. After making your changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Modifying an ACE

To modify an ACE, you need to know its identification number. To view the identification numbers of the ACEs, refer to “Displaying the ACEs” on page 659.

To modify an ACE, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **7** to select Management ACL.

   The Management ACL Configuration menu is shown in Figure 244 on page 652.

3. From the Management ACL Configuration menu, type **3** to select Modify Management ACL Entry.

   The following prompt is displayed:

   ```
   Enter the entry ID :  [1 to 256] -> 1
   ```

4. Enter the identification number of the ACE you want to modify. You can modify one ACE at a time.

   The specifications of the selected ACE are displayed in the Modify Management ACL Entry window. An example of the window is shown in Figure 245.

```
            Allied Telesis AT-9424T/SP - AT-S63
                        Marketing
User: Manager                           11:20:02 02-Mar-2005
                  Modify Management ACL Entry
Configuring Management ACL
1 - ID ........................... 11
2 - IP Address ................... 149.44.44.44
3 - Network Mask ................. 255.255.255.255
4 - Application(s) ............... Telnet,Ping

M - Modify Management ACL Entry

R - Return to Previous Menu

Enter your selection?
```

Figure 245. Modify Management ACL Entry

Downloaded from www.Manualslib.com manuals search engine

5. Make the desired changes to the entry by selecting the corresponding option and entering a new value. You cannot change an entry's ID number. For information on an entry's IP address, network mask, and applications, refer to steps 5, 6, and 7 in the procedure "Creating an ACE" on page 654.

6. After entering your changes, type **M** to select Modify Management ACL Entry.

   Your changes are immediately implemented on the switch.

7. After making your changes, type **R** until you return to the Main Menu. Then type **S** to select Save Configuration Changes.

Downloaded from www.Manualslib.com manuals search engine

Deleting an ACE

To delete an ACE, you need to know its identification number. To view the identification numbers of the ACEs, refer to “Displaying the ACEs” on page 659.

Note
If you are managing the switch from a Telnet management session and the management ACL is active, your management session will end and you will be unable to reestablish it if you delete the ACE that specifies your management workstation.

To delete an ACE, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **7** to select Management ACL.

   The Management ACL Configuration menu is shown in Figure 244 on page 652.

3. From the Management ACL Configuration menu, type **4** to select Delete Management ACL Entry.

   The following prompt is displayed:

   ```
   Enter the entry ID :  [1 to 256] -> 1
   ```

4. Enter the identification number of the ACE to be deleted.

   The ACE is immediately deleted from the management ACL.

5. If desired, repeat this procedure starting with Step 3 to delete more ACEs from the Management ACL.

Downloaded from www.Manualslib.com manuals search engine

Displaying the ACEs

To display the ACEs in the management ACL, perform the following procedure:

1. From the Main Menu, type **5** to select System Administration.

   The System Administration menu is shown in Figure 1 on page 32.

2. From the System Administration menu, type **7** to select Management ACL.

   The Management ACL Configuration menu is shown in Figure 244 on page 652.

3. From the Management ACL Configuration menu, type **5** to select Display All Management ACL Entries.

   The Display All Management ACL Entries menu is shown in Figure 246.

```
            Allied Telesis AT-9424T/SP - AT-S63
                         Marketing
User: Manager                           11:20:02 02-Mar-2005
              Display All Management ACL Entries
ID    IP Address         Mask                 Application
-----------------------------------------------------------
1     133.22.145.18      255.255.255.255      All
2     133.22.146.0       255.255.255.0        Web

U - Update display
R - Return to Previous Menu

Enter your selection?
```

Figure 246. Display All Management ACL Entries Menu

The menu provides the following information about the ACEs:

ID
The entry's identification number.

IP Address
The IP address of a management station or a subnet.

Mask
The parts of the IP address the switch is filtering on.

Application
The application that the management station is permitted to use to manage the switch. The options are Telnet, Web, Ping and All.

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine

Index

Numerics

802.1Q-compliant VLAN mode
  displaying 518
  selecting 516
802.1x Port-based Network Access Control
  access role, configuring 570
  authenticator port 573
  configuring 570
  disabling 572
  enabling 572
  port parameters, displaying 582
  port role, configuring 570
  supplicant port 579

A

access control entry (ACE)
  adding 654, 656
  deleting 658
  displaying 659
access control list (ACL)
  creating 232
  deleting 237
  deleting all 239
  displaying 240
  modifying 235
Address Resolution Protocol (ARP) table
  configuring timeout value 558
administrator name 33
adminkey parameter 130
aggregator
  creating 129
  deleting 134
  displaying status 135
  modifying 132
aging time
  changing 114
associated VLANs parameter 448
associations, VLANs to MSTI IDs 452
AT-9400 Switch, hardware information 52
AT-S63 software
  resetting to factory defaults 50
AT-S63 software updates
  downloading from a local session 168
authentication failure trap
  disabling 95
  enabling 95
Auto-Negotiation
  configuring 66
  forcing 78

B

back pressure 71
baud rate, terminal port 48
boot configuration file. *See* configuration file
bridge forwarding delay
  Multiple Spanning Tree Protocol (MSTP) 442
  Rapid Spanning Tree Protocol (RSTP) 432
  Spanning Tree Protocol (STP) 424
bridge hello time
  Multiple Spanning Tree Protocol (MSTP) 442
  Rapid Spanning Tree Protocol (RSTP) 432
  Spanning Tree Protocol (STP) 424
bridge identifier
  Multiple Spanning Tree Protocol (MSTP) 443
  Rapid Spanning Tree Protocol (RSTP) 432
  Spanning Tree Protocol (STP) 425
bridge max age
  Multiple Spanning Tree Protocol (MSTP) 442
  Rapid Spanning Tree Protocol (RSTP) 432
  Spanning Tree Protocol (STP) 424
bridge priority
  Rapid Spanning Tree Protocol (RSTP) 431
  Spanning Tree Protocol (STP) 423
bridge protocol data unit (BPDU) 424, 432
broadcast frame control
  configuring, 283

C

CA certificate, steps for 593
certificate database
  adding certificates 616
  deleting certificates 622
  modifying certificates 619
  specifying maximum number of certificates 631
  viewing certificates 624
certificate enrollment request
  creating 627
  steps for 593
  uploading from switch 190
certificate format 628
certificates
  adding to database 616
  creating
    enrollment requests 627
    self-signed 612
  deleting 622
  displaying 624
  format 615
  installing CA 630

Downloaded from www.Manualslib.com manuals search engine

maximum number in database, configuring 631
modifying 619
type, configuring 617
ciphers available parameter 638
CIST priority parameter 445
Class of Service (CoS)
configuring 244
displaying port priorities 250
mapping priorities to egress queues 247
scheduling
configuring 248
classifier
creating 220
deleting 226, 227
displaying 228
modifying 224
Common and Internal Spanning Tree (CIST)
configuring 445
priority, displaying 447
compact flash card
changing directory on 166
configuration file on 150
listing files on 161
configuration file
creating 146
displaying 151
downloading switch to switch 179
downloading to switch 182
editing 152
overview 146
selecting active 149
uploading from switch 190
configuration name 443
console disconnect interval 46
console startup mode 45
console timer 46

D

data compression parameter 638
daylight savings time (DST) 41
default gateway, setting 556
default route, setting 556
default values
resetting to 50
Denial of Service (DoS) defense
configuring 280
mirror port 282
DER certificate format 628
DER certificates format 615
distinguished name
configuring 612, 615
document conventions 25
DoS. *See* Denial of Service (DoS) defense
downloading files 168, 182
duplex mode 68
dynamic GVRP VLAN
converting 500

E

edge port
Multiple Spanning Tree Protocol (MSTP) 459
Rapid Spanning Tree Protocol (RSTP) 435
edge port parameter 459
egress ports
adding 538
deleting 538
encryption key
creating 596
deleting 600
displaying 608
exporting 602
importing 605
modifying 601
enhanced stacking
configuring 86
returning to master switch 91
selecting switch 88
setting switch status 86
Ethernet port statistics
clearing 83
displaying 80
event log
clearing 206
disabling 198
displaying 199
enabling 198
saving to a file 206
severity codes 203
software module list 201

F

facility levels 212
factory defaults
resetting 50
fan speed 56
files. *See* system files
filtering, configuring 73
flash memory
configuration file in 150
displaying information about 162
formatting 163
flow control 71
flow group
creating 252
deleting 256
displaying 257
modifying 255
force version
Multiple Spanning Tree Protocol (MSTP) 442
Rapid Spanning Tree Protocol (RSTP) 431

Downloaded from www.Manualslib.com manuals search engine

G

GARP VLAN Registration Protocol (GVRP)
- configuring 496
- disabling 496
- disabling on a port 498
- displaying
  - counters 502
  - database 507
  - GIP connected ports ring 509
  - GVRP state machine 511
  - port configuration 501
- dynamic VLAN, converting 500
- enabling 496
- enabling on a port 498
- port mode, configuring 499

GBIC transceiver, displaying information about 57
GID index parameter 507
global encryption key 645
global secret
- configuring 643
- displaying 644

global server timeout 645
GVRP database 507
GVRP join timer 497
GVRP leave all timer 497
GVRP leave timer 497

H

hardware information 52
hello time
- Multiple Spanning Tree Protocol (MSTP) 442
- Rapid Spanning Tree Protocol (RSTP) 432
- Spanning Tree Protocol (STP) 424

HOL blocking 69
host key ID parameter 635
host topology
- IGMP snooping 297
- MLD snooping 306

host/router timeout interval
- IGMP snooping 298
- MLD snooping 307

I

IEEE 802.1w standard 430
image file, downloading 174
ingress filtering 493
ingress filtering, enabling or disabling 494
ingress packet threshold 75
Internet Group Management Protocol (IGMP) snooping
- configuring 296
- disabling 300
- displaying
  - host nodes 301
  - multicast routers 303
- enabling 300
- host topology 297
- host/router timeout value 298
- maximum multicast groups 298
- router ports 298

intrusion action
- displaying 566
- selecting 564

IP Options attack 280

L

Land attack 280
Link Aggregation Control Protocol (LACP) port trunk
- adminkey parameter 130
- aggregator
  - creating 129
  - deleting 134
  - modifying 132
- displaying status 135
- enabling or disabling protocol 126
- load distribution method
  - changing 133
  - selecting 131
- ports
  - changing 133
  - specifying 131
- system priority 128

load distribution methods
- setting in LACP trunk 131, 133
- setting in static port trunk 118, 121

local interface 557
local management interface
- displaying IP address 555

log output definition
- creating 210
- deleting 216
- described 209
- displaying 217
- facility levels 212
- modifying 215

login timeout parameter 635

M

MAC address table
- adding a static address 110
- aging time
  - changing 114
- deleting all dynamic addresses 113
- deleting an address 112
- displaying 106

MAC address-based port security
- configuring 562
- displaying 566
- intrusion action
  - displaying 566
  - selecting 564

MAC address-based VLAN
- adding egress ports 538
- adding MAC addresses 536
- creating 534
- deleting 540
- deleting egress ports 538
- deleting MAC addresses 536

Downloaded from www.Manualslib.com manuals search engine

displaying 542
MACs available parameter 638
management access control list
adding an access control entry 654, 656
deleting an access control entry 658
disabling 652
displaying access control entries 659
enabling 652
management access levels 35
manager access 35
manager password 35
master switch
assigning 86
defined 86
returning to 91
max age
Multiple Spanning Tree Protocol (MSTP) 442
Rapid Spanning Tree Protocol (RSTP) 432
Spanning Tree Protocol (STP) 424
max hops, Multiple Spanning Tree Protocol (MSTP) 442
maximum multicast groups
IGMP snooping 298
MLD snooping 307
maximum number of sessions
configuring 632
MCHECK 435
MDI/MDI-X 68
MSTI association to a VLAN
creating 453
removing 454
MSTI ID
associating to VLANs 455
creating 449
deleting 450
list 447
modifying 450
removing a VLAN association 455
MSTP. *See* Multiple Spanning Tree Protocol (MSTP)
Multicast Listener Discovery (MLD) snooping
configuring 306
disabling 309
displaying
host nodes 310
multicast routers 312
enabling 309
host topology 306
host/router timeout value 307
maximum multicast groups 307
router ports 307
Multiple Spanning Tree Instance (MSTI)
MSTI ID
associating to VLANs 455
creating 449
deleting 450
list 447
modifying 450
removing a VLAN association 455
port priority 447
Multiple Spanning Tree Protocol (MSTP)
activating 440
associating VLANs to MSTI IDs 452
bridge forwarding delay 442
bridge hello time 442
bridge identifier 443
bridge max age 442
bridge settings, configuring 441
configuration name 443
edge port 459
force version 442
max hops 442
MSTI ID, modifying 450
point-to-point port 459
port configuration, displaying 463
port external path cost 459
port internal path cost 461
port parameters, configuring 457
port priority 461
port status, displaying 465
resetting to defaults 468
revision level 443
multiple VLAN modes
displaying VLANs 518
selecting 516
selecting uplink port 516

N

non-802.1Q compliant VLAN mode
displaying 518
selecting 516
NULL character, Telnet server 47

O

operator access 35
operator password 35

P

packet filtering, configuring 73
path cost 448
PEM 615
PEM certificate format 628
Ping of Death attack 280
pinging 49
point-to-point (port) parameter 459
point-to-point port
Multiple Spanning Tree Protocol (MSTP) 459
Rapid Spanning Tree Protocol (RSTP) 435
policy
creating 271
deleting 275
displaying 276
modifying 274
poll interval 41
port
Auto-Negotiation 66
back pressure 71
description 66
disabling 66

Downloaded from www.Manualslib.com manuals search engine

displaying settings 62
duplex mode 68
enabling 66
flow control 71
forcing Auto-Negotiation 78
MDI/MDI-X 68
resetting 77
resetting to default settings 79
speed 66, 67
port cost
Rapid Spanning Tree Protocol (RSTP) 434
Spanning Tree Protocol (STP) 427
port external path cost parameter, Multiple Spanning Tree Protocol (MSTP) 459
port internal path cost, Multiple Spanning Tree Protocol (MSTP) 461
port mirror
creating 138
deleting 140
displaying 142
modifying 141
port parameters, configuring
Multiple Spanning Tree Protocol (MSTP) 457
Rapid Spanning Tree Protocol (RSTP) 433
Spanning Tree Protocol (STP) 425
port priority
Multiple Spanning Tree Instance (MSTI) 447
Multiple Spanning Tree Protocol (MSTP) 461
Rapid Spanning Tree Protocol (RSTP) 434
Spanning Tree Protocol (STP) 427
port statistics
clearing 83
displaying 80
port VLAN identifier (PVID) 492
port-based VLAN
creating 472
deleting 487, 490
displaying 485
modifying 481
Power over Ethernet (PoE)
configuring port settings 286
displaying status 288
setting threshold 284
power supply status 56
protected ports VLAN
creating 522
deleting 530
displaying 528
modifying 525

R

RADIUS
configuring 645
displaying settings 648
enabling 640
settings, displaying 648
status, displaying 648
RADIUS accounting, configuring 584
Rapid Spanning Tree Protocol (RSTP)
bridge forwarding delay 432
bridge hello time 432
bridge max age 432
bridge parameters, configuring 430
bridge priority 431
disabling 420
edge port, configuring 435
enabling 420
force version 431
MCHECK 435
point-to-point port, configuring 435
port configuration, displaying 435
port cost 434
port parameters, configuring 433
port priority 434
port state, displaying 437
resetting to defaults 438
rate limit, setting 75
redundant power supply (RPS) status 56
regional root ID 447
regional root path cost 448
revision level 443
router ports
IGMP snooping 298
MLD snooping 307
Router Redundancy Protocol (RRP) snooping
disabling 316
enabling 316
routing interface
creating 548
deleting 554
modifying 551
setting the local interface 557
RSTP. *See* Rapid Spanning Tree Protocol (RSTP)

S

scheduling, CoS
configuring 248
strict priority 248
weighted round robin 248
Secure Shell (SSH)
server
configuring 634
displaying information 637
Secure Sockets Layer (SSL) 632
self-signed certificate 593
server authentication UDP port 646
server encryption key 646
server IP address 646
server key expiry time parameter 635
server key ID parameter 635
session cache timeout
configuring 632
SFP transceiver, displaying information about 57
Simple Network Management Protocol. *See* SNMP
Simple Network Time Protocol (SNTP)
configuring 38
servers 38

Downloaded from www.Manualslib.com manuals search engine

slave switch
assigning 86
defined 86
SMURF attack 280
SNMP community string
creating 96
disabling 94
displaying 104
enabling 94
modifying 99
SNMP management
disabling 94
enabling 94
SNMPv3 Access Table entry
creating 340
deleting 344
displaying 411
modifying
notify view 351
read view 346
storage type 353
write view name 349
SNMPv3 community 398
SNMPv3 Community Table entry
creating 399
deleting 402
displaying 414
modifying
community name 403
security name 405
storage type 406
transport tag 405
SNMPv3 Notify Table entry
creating 364
deleting 366
displaying 412
modifying
notify tag 367
storage type 370
SNMPv3 protocol
community name parameter 400
SNMPv3 SecurityToGroup Table entry
creating 356
deleting 359
displaying 411
modifying
group name 360
storage type 362
SNMPv3 Target Address Table entry
creating 372
deleting 375
displaying 413
modifying
storage type 383
target address retries 380
target address tag list 381
target address timeout 379
target address UDP port 378
target IP address 376
target parameters 382
SNMPv3 Target Parameters Table entry
creating 386
deleting 389
displaying 413
modifying
message process model 395
security level 393
security model 392
storage type 396
user name 390
SNMPv3 User Table entry
creating 321
deleting 325
displaying 408
modifying
authentication protocol 326
authentication protocol password 326
privacy protocol 328
privacy protocol password 328
SNMPv3 View Table entry 337
creating 331
deleting 334
displaying 410
storage type, modifying 338
subtree mask, modifying 335
SNTP. *See* Simple Network Time Protocol (SNTP)
software updates
downloading from a local session 168
downloading switch to switch 176
Spanning Tree Protocol (STP)
bridge forwarding delay 424
bridge hello time 424
bridge identifier 425
bridge max age 424
bridge parameters, configuring 422
bridge priority 423
disabling 420
enabling 420
forwarding delay 424
port cost 427
port settings, configuring 425
port settings, displaying 428
resetting to defaults 429
SSH server status parameter 635
SSH. *See* Secure Shell (SSH)
SSL key ID 591
static port trunk
creating 116
deleting 123
modifying 120
STP. *See* Spanning Tree Protocol (STP)
switch
hardware information, displaying 55
rebooting 43
switch name, configuring 32
SYN Flood attack 280
syslog server 209
system date 38

Downloaded from www.Manualslib.com manuals search engine

system files
    copying 154
    deleting 158
    display on compact flash card 161
    displaying 159
    downloading to switch 182
    renaming 156
    uploading from switch 190
system hardware information, displaying 55
system information 52
system name 33
system temperature 56
system time 38

T

TACACS+
    configuring 642
    displaying settings 644
    enabling 640
    server IP address 642
    server timeout
        configuring 643
        displaying 644
tagged ports
    adding to VLAN 475, 483
    deleting from VLAN 483
tagged VLAN
    creating 472
    creating, example 479
    deleting 487, 490
    displaying 485
    modifying 481
target IP address 364
Teardrop attack 280
Telnet server
    enabling or disabling 47
    NULL character 47
terminal port baud rate, setting 48
TFTP, downloading and uploading files 168
traffic class
    creating 261
    deleting 267
    displaying 268
    modifying 265

U

unavailable status, defined 86
untagged ports
    adding to VLAN 475, 483
    deleting from VLAN 483
uploading files 190
user-configured VLAN mode, selecting 516
UTC offset 40

V

view type, modifying 337

W

web server
    configuring 590
    disabling 591
    enabling 591
web server mode 591

Downloaded from www.Manualslib.com manuals search engine

Downloaded from www.Manualslib.com manuals search engine